

PIC18FXX8 Data Sheet

28/40-Pin High-Performance, Enhanced Flash Microcontrollers with CAN Module

 $[\]ensuremath{\textcircled{}^{\circ}}$ 2006 Microchip Technology Inc.

Note the following details of the code protection feature on Microchip devices:

- Microchip products meet the specification contained in their particular Microchip Data Sheet.
- Microchip believes that its family of products is one of the most secure families of its kind on the market today, when used in the intended manner and under normal conditions.
- There are dishonest and possibly illegal methods used to breach the code protection feature. All of these methods, to our knowledge, require using the Microchip products in a manner outside the operating specifications contained in Microchip's Data Sheets. Most likely, the person doing so is engaged in theft of intellectual property.
- Microchip is willing to work with the customer who is concerned about the integrity of their code.
- Neither Microchip nor any other semiconductor manufacturer can guarantee the security of their code. Code protection does not mean that we are guaranteeing the product as "unbreakable."

Code protection is constantly evolving. We at Microchip are committed to continuously improving the code protection features of our products. Attempts to break Microchip's code protection feature may be a violation of the Digital Millennium Copyright Act. If such acts allow unauthorized access to your software or other copyrighted work, you may have a right to sue for relief under that Act.

Information contained in this publication regarding device applications and the like is provided only for your convenience and may be superseded by updates. It is your responsibility to ensure that your application meets with your specifications. MICROCHIP MAKES NO REPRESENTATIONS OR WARRANTIES OF ANY KIND WHETHER EXPRESS OR IMPLIED, WRITTEN OR ORAL, STATUTORY OR OTHERWISE, RELATED TO THE INFORMATION, INCLUDING BUT NOT LIMITED TO ITS CONDITION, QUALITY, PERFORMANCE, MERCHANTABILITY OR FITNESS FOR PURPOSE. Microchip disclaims all liability arising from this information and its use. Use of Microchip devices in life support and/or safety applications is entirely at the buyer's risk, and the buyer agrees to defend, indemnify and hold harmless Microchip from any and all damages, claims, suits, or expenses resulting from such use. No licenses are conveyed, implicitly or otherwise, under any Microchip intellectual property rights.

QUALITY MANAGEMENT SYSTEM CERTIFIED BY DNV ISO/TS 16949:2002

Trademarks

The Microchip name and logo, the Microchip logo, Accuron, dsPIC, KEELOQ, microID, MPLAB, PIC, PICmicro, PICSTART, PRO MATE, PowerSmart, rfPIC and SmartShunt are registered trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

AmpLab, FilterLab, Migratable Memory, MXDEV, MXLAB, SEEVAL, SmartSensor and The Embedded Control Solutions Company are registered trademarks of Microchip Technology Incorporated in the U.S.A.

Analog-for-the-Digital Age, Application Maestro, CodeGuard, dsPICDEM, dsPICDEM.net, dsPICworks, ECAN, ECONOMONITOR, FanSense, FlexROM, fuzzyLAB, In-Circuit Serial Programming, ICSP, ICEPIC, Linear Active Thermistor, Mindi, MiWi, MPASM, MPLIB, MPLINK, PICkit, PICDEM, PICDEM.net, PICLAB, PICtail, PowerCal, PowerInfo, PowerMate, PowerTool, REAL ICE, rfLAB, rfPICDEM, Select Mode, Smart Serial, SmartTel, Total Endurance, UNI/O, WiperLock and ZENA are trademarks of Microchip Technology Incorporated in the U.S.A. and other countries.

SQTP is a service mark of Microchip Technology Incorporated in the U.S.A.

All other trademarks mentioned herein are property of their respective companies.

© 2006, Microchip Technology Incorporated, Printed in the U.S.A., All Rights Reserved.

Printed on recycled paper.

Microchip received ISO/TS-16949:2002 certification for its worldwide headquarters, design and wafer fabrication facilities in Chandler and Tempe, Arizona, Gresham, Oregon and Mountain View, California. The Company's quality system processes and procedures are for its PICmicro® 8-bit MCUs, KEELOQ® code hopping devices, Serial EEPROMs, microperipherals, nonvolatile memory and analog products. In addition, Microchip's quality system for the design and manufacture of development systems is ISO 9001:2000 certified.

DS41159E-page ii



28/40-Pin High-Performance, Enhanced Flash Microcontrollers with CAN

High-Performance RISC CPU:

- Linear program memory addressing up to 2 Mbytes
- · Linear data memory addressing to 4 Kbytes
- Up to 10 MIPS operation
- DC 40 MHz clock input
- 4 MHz-10 MHz oscillator/clock input with PLL active
- 16-bit wide instructions, 8-bit wide data path
- · Priority levels for interrupts
- 8 x 8 Single-Cycle Hardware Multiplier

Peripheral Features:

- High current sink/source 25 mA/25 mA
- Three external interrupt pins
- Timer0 module: 8-bit/16-bit timer/counter with 8-bit programmable prescaler
- Timer1 module: 16-bit timer/counter
- Timer2 module: 8-bit timer/counter with 8-bit period register (time base for PWM)
- Timer3 module: 16-bit timer/counter
- Secondary oscillator clock option Timer1/Timer3
- Capture/Compare/PWM (CCP) modules; CCP pins can be configured as:
 - Capture input: 16-bit, max resolution 6.25 ns
 - Compare: 16-bit, max resolution 100 ns (TCY)
 - PWM output: PWM resolution is 1 to 10-bit Max. PWM freq. @:8-bit resolution = 156 kHz 10-bit resolution = 39 kHz
- Enhanced CCP module which has all the features of the standard CCP module, but also has the following features for advanced motor control:
 - 1, 2 or 4 PWM outputs
 - Selectable PWM polarity
 - Programmable PWM dead time
- Master Synchronous Serial Port (MSSP) with two modes of operation:
 - 3-wire SPI™ (Supports all 4 SPI modes)
 - I²C[™] Master and Slave mode
- Addressable USART module:
 - Supports interrupt-on-address bit

Advanced Analog Features:

- 10-bit, up to 8-channel Analog-to-Digital Converter module (A/D) with:
 - Conversion available during Sleep
- Up to 8 channels available
- Analog Comparator module:
 - Programmable input and output multiplexing
- Comparator Voltage Reference module
- Programmable Low-Voltage Detection (LVD) module:
 Supports interrupt-on-Low-Voltage Detection
- Programmable Brown-out Reset (BOR)

CAN bus Module Features:

- · Complies with ISO CAN Conformance Test
- Message bit rates up to 1 Mbps
- Conforms to CAN 2.0B Active Spec with:
 - 29-bit Identifier Fields
 - 8-byte message length
 - 3 Transmit Message Buffers with prioritization
 - 2 Receive Message Buffers
 - 6 full, 29-bit Acceptance Filters
 - Prioritization of Acceptance Filters
 - Multiple Receive Buffers for High Priority Messages to prevent loss due to overflow
 - Advanced Error Management Features

Special Microcontroller Features:


- Power-on Reset (POR), Power-up Timer (PWRT) and Oscillator Start-up Timer (OST)
- Watchdog Timer (WDT) with its own on-chip RC oscillator
- Programmable code protection
- Power-saving Sleep mode
- Selectable oscillator options, including:
 - 4x Phase Lock Loop (PLL) of primary oscillator
 Secondary Oscillator (32 kHz) clock input
- In-Circuit Serial Programming[™] (ICSP[™]) via two pins

Flash Technology:

- · Low-power, high-speed Enhanced Flash technology
- · Fully static design
- Wide operating voltage range (2.0V to 5.5V)
- Industrial and Extended temperature ranges

	Prog	ram Memory	Data	Memory			ors		MSS			
Device	Flash (bytes)	# Single-Word Instructions	SRAM (bytes)	EEPROM (bytes)	I/O	10-bit A/D (ch)	Comparators	CCP/ ECCP (PWM)	SPI™	Master I ² C™	USART	Timers 8/16-bit
PIC18F248	16K	8192	768	256	22	5	_	1/0	Y	Y	Y	1/3
PIC18F258	32K	16384	1536	256	22	5	_	1/0	Y	Y	Y	1/3
PIC18F448	16K	8192	768	256	33	8	2	1/1	Y	Y	Y	1/3
PIC18F458	32K	16384	1536	256	33	8	2	1/1	Y	Y	Y	1/3

Pin Diagrams



Pin Diagrams (Continued)




Table of Contents

1.0	Device Overview	
2.0	Oscillator Configurations	17
3.0	Reset	25
4.0	Memory Organization	37
5.0	Data EEPROM Memory	59
6.0	Flash Program Memory	65
7.0	8 x 8 Hardware Multiplier	75
8.0	Interrupts	77
9.0	I/O Ports	93
10.0	Parallel Slave Port	107
11.0	Timer0 Module	109
12.0	Timer1 Module	113
13.0	Timer2 Module	117
14.0	Timer3 Module	119
15.0	Capture/Compare/PWM (CCP) Modules	123
16.0	Enhanced Capture/Compare/PWM (ECCP) Module	131
17.0	Master Synchronous Serial Port (MSSP) Module	143
18.0	Addressable Universal Synchronous Asynchronous Receiver Transmitter (USART)	183
19.0	CAN Module	199
20.0	Compatible 10-Bit Analog-to-Digital Converter (A/D) Module	241
	Comparator Module	
22.0	Comparator Voltage Reference Module	255
23.0	Low-Voltage Detect	259
24.0	Special Features of the CPU	265
25.0	Instruction Set Summary	281
26.0	Development Support	323
27.0	Electrical Characteristics	
28.0	DC and AC Characteristics Graphs and Tables	361
29.0	Packaging Information	377
Appe	ndix A: Data Sheet Revision History	385
Appe	ndix B: Device Differences	385
Appe	ndix C: Device Migrations	386
Appe	ndix D: Migrating From Other PICmicro [®] Devices	386
Index	· · · · · · · · · · · · · · · · · · ·	387
On-L	ne Support	397
Syste	ms Information and Upgrade Hot Line	397
Read	er Response	398
PIC1	BFXX8 Product Identification System	399

TO OUR VALUED CUSTOMERS

It is our intention to provide our valued customers with the best documentation possible to ensure successful use of your Microchip products. To this end, we will continue to improve our publications to better suit your needs. Our publications will be refined and enhanced as new volumes and updates are introduced.

If you have any questions or comments regarding this publication, please contact the Marketing Communications Department via E-mail at **docerrors@microchip.com** or fax the **Reader Response Form** in the back of this data sheet to (480) 792-4150. We welcome your feedback.

Most Current Data Sheet

To obtain the most up-to-date version of this data sheet, please register at our Worldwide Web site at:

http://www.microchip.com

You can determine the version of a data sheet by examining its literature number found on the bottom outside corner of any page. The last character of the literature number is the version number, (e.g., DS30000A is version A of document DS30000).

Errata

An errata sheet, describing minor operational differences from the data sheet and recommended workarounds, may exist for current devices. As device/documentation issues become known to us, we will publish an errata sheet. The errata will specify the revision of silicon and revision of document to which it applies.

To determine if an errata sheet exists for a particular device, please check with one of the following:

- Microchip's Worldwide Web site; http://www.microchip.com
- Your local Microchip sales office (see last page)

When contacting a sales office, please specify which device, revision of silicon and data sheet (include literature number) you are using.

Customer Notification System

Register on our web site at www.microchip.com to receive the most current information on all of our products.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 6

1.0 DEVICE OVERVIEW

This document contains device specific information for the following devices:

- PIC18F248
- PIC18F258
- PIC18F448
- PIC18F458

These devices are available in 28-pin, 40-pin and 44-pin packages. They are differentiated from each other in four ways:

1. PIC18FX58 devices have twice the Flash program memory and data RAM of PIC18FX48 devices (32 Kbytes and 1536 bytes vs. 16 Kbytes and 768 bytes, respectively).

- 2. PIC18F2X8 devices implement 5 A/D channels, as opposed to 8 for PIC18F4X8 devices.
- 3. PIC18F2X8 devices implement 3 I/O ports, while PIC18F4X8 devices implement 5.
- 4. Only PIC18F4X8 devices implement the Enhanced CCP module, analog comparators and the Parallel Slave Port.


All other features for devices in the PIC18FXX8 family, including the serial communications modules, are identical. These are summarized in Table 1-1.

Block diagrams of the PIC18F2X8 and PIC18F4X8 devices are provided in Figure 1-1 and Figure 1-2, respectively. The pinouts for these device families are listed in Table 1-2.

Fe	eatures	PIC18F248	PIC18F258	PIC18F448	PIC18F458	
Operating Fre	quency	DC – 40 MHz				
Internal	Bytes	16K	32K	16K	32K	
Program Memory	# of Single-Word Instructions	8192	16384	8192	16384	
Data Memory	(Bytes)	768	1536	768	1536	
Data EEPRON	M Memory (Bytes)	256	256	256	256	
Interrupt Sour	ces	17	17	21	21	
I/O Ports		Ports A, B, C	Ports A, B, C	Ports A, B, C, D, E	Ports A, B, C, D, E	
Timers		4	4	4	4	
Capture/Comp	are/PWM Modules	1	1	1	1	
Enhanced Capture/Compare/ PWM Modules		—	—	1	1	
Serial Communications		MSSP, CAN, Addressable USART			MSSP, CAN, Addressable USART	
Parallel Communications (PSP)		No	No	Yes	Yes	
10-bit Analog-to-Digital Converter		5 input channels	5 input channels 8 input channels		8 input channels	
Analog Compa	arators	No	No	2	2	
Analog Compa	arators VREF Output	N/A	N/A	Yes	Yes	
Resets (and Delays)		POR, BOR, RESET Instruction, Stack Full, Stack Underflow (PWRT, OST)				
Programmable	e Low-Voltage Detect	Yes	Yes	Yes	Yes	
Programmable	e Brown-out Reset	Yes	Yes	Yes	Yes	
CAN Module		Yes	Yes	Yes	Yes	
In-Circuit Serial Programming™ (ICSP™)		Yes	Yes	Yes	Yes	
Instruction Set	t	75 Instructions	75 Instructions	75 Instructions	75 Instructions	
Packages		28-pin SPDIP 28-pin SOIC	28-pin SPDIP 28-pin SOIC	40-pin PDIP 44-pin PLCC 44-pin TQFP	40-pin PDIP 44-pin PLCC 44-pin TQFP	


TABLE 1-1: PIC18FXX8 DEVICE FEATURES





DS41159E-page 8





^{© 2006} Microchip Technology Inc.

	Pi	in Numb	er					
Pin Name	PIC18F248/258	PIC	:18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP	TQFP	PLCC		- 76 -		
MCLR/Vpp MCLR	1	1	18	2	I	ST	Master Clear (input) or programming voltage (output). Master Clear (Reset) input. This pin is an active low Reset	
Vpp					Р	—	to the device. Programming voltage input.	
NC	—	_	12, 13, 33, 34	1, 17, 28, 40	—	—	These pins should be left unconnected.	
OSC1/CLKI OSC1 CLKI	9	13	30	14	I	CMOS/ST CMOS	Oscillator crystal or external clock input. Oscillator crystal input or external clock source input. ST buffer when configured in RC mode; otherwise, CMOS. External clock source input. Always associated with pin function OSC1 (see OSC1/ CLKI, OSC2/CLKO pins).	
OSC2/CLKO/RA6 OSC2	10	14	31	15	0		Oscillator crystal or clock output. Oscillator crystal output. Connects to crystal or resonator in Crystal Oscillator mode.	
CLKO					Ο		In RC mode, OSC2 pin outputs CLKO, which has 1/4 the frequency of OSC1 and denotes the instruction cycle rate.	
RA6					I/O	TTL	General purpose I/O pin.	
Legend:TTL = TTL compatible inputCMOS = CMOS compatible input or outputST = Schmitt Trigger input with CMOS levelsAnalog = Analog inputI = InputO = OutputP = PowerOD = Open-Drain (no P diode to VDD)						g input It		

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS

	Pi	n Numb	er					
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	PDIP TQFP		PLCC	туре	туре		
							PORTA is a bidirectional I/O port.	
RA0/AN0/CVREF RA0 AN0 CVREF	2	2	19	3	I/O I O	TTL Analog Analog	Digital I/O. Analog input 0. Comparator voltage reference output.	
RA1/AN1 RA1 AN1	3	3	20	4	I/O I	TTL Analog	Digital I/O. Analog input 1.	
RA2/AN2/VREF- RA2 AN2 VREF-	4	4	21	5	I/O I I	TTL Analog Analog	Digital I/O. Analog input 2. A/D reference voltage (Low) input.	
RA3/AN3/VREF+ RA3 AN3 VREF+	5	5	22	6	I/O I I	TTL Analog Analog	Digital I/O. Analog input 3. A/D reference voltage (High) input.	
RA4/T0CKI RA4 T0CKI	6	6	23	7	I/O I	TTL/OD ST	Digital I/O – open-drain when configured as output. Timer0 external clock input.	
RA5/AN4/SS/LVDIN RA5 AN4 SS LVDIN	7	7	24	8	I/O 	TTL Analog ST Analog	Digital I/O. Analog input 4. SPI™ slave select input. Low-Voltage Detect input.	
RA6							See the OSC2/CLKO/RA6 pir	
Legend: TTL = TT			MOS leve	els		og = Analo = Outpu	S compatible input or output g input	

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pi	in Numb	er		Pin	Buffer	
Pin Name	PIC18F248/258	PIC	18F448/	458	Туре	Туре	Description
	SPDIP, SOIC	PDIP	TQFP	PLCC			
			_				PORTB is a bidirectional I/O port PORTB can be software programmed for internal weak pull-ups on all inputs.
RB0/INT0 RB0 INT0	21	33	8	36	I/O I	TTL ST	Digital I/O. External interrupt 0.
RB1/INT1 RB1 INT1	22	34	9	37	I/O I	TTL ST	Digital I/O. External interrupt 1.
RB2/CANTX/INT2 RB2 CANTX INT2	23	35	10	38	I/O O I	TTL TTL ST	Digital I/O. Transmit signal for CAN bus. External interrupt 2.
RB3/CANRX RB3 CANRX	24	36	11	39	I/O I	TTL TTL	Digital I/O. Receive signal for CAN bus.
RB4	25	37	14	41	I/O	TTL	Digital I/O. Interrupt-on-change pin.
RB5/PGM RB5	26	38	15	42	I/O	TTL	Digital I/O.
PGM					I	ST	Interrupt-on-change pin. Low-voltage ICSP™ programming enable.
RB6/PGC RB6	27	39	16	43	I/O	TTL	Digital I/O. In-Circuit Debugger pin.
PGC					I	ST	Interrupt-on-change pin. ICSP programming clock.
RB7/PGD RB7	28	40	17	44	I/O	TTL	Digital I/O. In-Circuit Debugger pin.
PGD					I/O	ST	Interrupt-on-change pin. ICSP programming data.
-			MOS leve	els		og = Analo = Outpu	

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pi	n Numb	er		D'	Duffer	
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description
	SPDIP, SOIC	PDIP	TQFP	PLCC	71.5		
RC0/T1OSO/T1CKI RC0 T1OSO	11	15	32	16	I/O O	ST	PORTC is a bidirectional I/O port Digital I/O. Timer1 oscillator output.
T1CKI					I	ST	Timer1/Timer3 external clock input.
RC1/T1OSI RC1 T1OSI	12	16	35	18	I/O I	ST CMOS	Digital I/O. Timer1 oscillator input.
RC2/CCP1 RC2 CCP1	13	17	36	19	I/O I/O	ST ST	Digital I/O. Capture 1 input/Compare 1 output/PWM1 output.
RC3/SCK/SCL RC3 SCK	14	18	37	20	I/O I/O	ST ST	Digital I/O. Synchronous serial clock input/output for SPI™ mode.
SCL					I/O	ST	Synchronous serial clock input/output for I ² C™ mode.
RC4/SDI/SDA RC4 SDI SDA	15	23	42	25	I/O I I/O	ST ST ST	Digital I/O. SPI data in. I ² C data I/O.
RC5/SDO RC5 SDO	16	24	43	26	I/O O	ST —	Digital I/O. SPI data out.
RC6/TX/CK RC6 TX	17	25	44	27	I/O O	ST —	Digital I/O. USART asynchronous transmit.
СК					I/O	ST	USART synchronous clock (see RX/DT).
RC7/RX/DT RC7 RX DT	18	26	1	29	I/O I I/O	ST ST ST	Digital I/O. USART asynchronous receiv USART synchronous data (see TX/CK).
			MOS leve	els		g = Analo = Outpu	

_. _ . _ - . . - -.....

C18F248/258 PDIP, SOIC —	PIC PDIP 19 20	18F448/ TQFP 38	458 PLCC 21	Pin Type I/O I/O	Buffer Type	Description PORTD is a bidirectional I/O port These pins have TTL input buffer when external memory is enabled
PDIP, SOIC	19	38		I/O		These pins have TTL input buffer when external memory is enable
_			21		ST	These pins have TTL input buffer when external memory is enable
_			21		ST	
_	20	00		I/O	TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 1 input.
		39	22	I/O I/O I	ST TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 1 input.
_	21	40	23	I/O I/O I	ST TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 2 input.
_	22	41	24	I/O I/O I	ST TTL Analog	Digital I/O. Parallel Slave Port data. Comparator 2 input.
_	27	2	30			
				I/O I/O I/O O	ST TTL ST	Digital I/O. Parallel Slave Port data. ECCP1 capture/compare. ECCP1 PWM output A.
_	28	3	31	I/O I/O O	ST TTL —	Digital I/O. Parallel Slave Port data. ECCP1 PWM output B.
_	29	4	32	I/O I/O O	ST TTL	Digital I/O. Parallel Slave Port data. ECCP1 PWM output C.
_	30	5	33	I/O I/O O	ST TTL	Digital I/O. Parallel Slave Port data. ECCP1 PWM output D.
	t Trigger inpu	 27 28 29 30 ompatible input tt Trigger input with CM 	-272-283-294-305ompatible input tt Trigger input with CMOS level	- 27 2 30 - 28 3 31 - 29 4 32 - 30 5 33 ompatible input tringger input with CMOS levels 30 5	- 22 41 24 I/O - 27 2 30 I/O - 27 2 30 I/O - 28 3 31 I/O - 28 3 31 I/O - 29 4 32 I/O - 30 5 33 I/O ompatible input tTrigger input with CMOS levels CMOS	$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$

TABLE 1-2: PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)

	Pi	n Numb	er					
Pin Name	PIC18F248/258	PIC	18F448/	458	Pin Type	Buffer Type	Description	
	SPDIP, SOIC	SPDIP, SOIC PDIP T		PLCC	-71	- 71		
							PORTE is a bidirectional I/O port	
RE0/AN5/RD	—	8	25	9		0T		
RE0					I/O	ST	Digital I/O.	
AN5						Analog	Analog input 5.	
RD					I	TTL	Read control for Parallel Slav Port (see WR and CS pins).	
RE1/AN6/WR/C1OUT	_	9	26	10				
RE1					I/O	ST	Digital I/O.	
AN6					I	Analog	Analog input 6.	
WR					I	TTL	Write control for Parallel Slav	
							Port (see \overline{CS} and \overline{RD} pins).	
C1OUT					0	Analog	Comparator 1 output.	
RE2/AN7/CS/C2OUT	_	10	27	11				
RE2					I/O	ST	Digital I/O.	
<u>AN</u> 7					I	Analog	Analog input 7.	
CS					I	TTL	Chip select control for Paralle	
							Slave Port (see RD and WR	
							pins).	
C2OUT					0	Analog	Comparator 2 output.	
Vss	19, 8	12, 31	6, 29	13, 34	—	—	Ground reference for logic and I/O pins.	
Vdd	20	11, 32	7, 28	12, 35	_	_	Positive supply for logic and I/O	
		-					pins.	
Legend: TTL = TTI	compatible inpu	ıt			CMO	S = CMO	S compatible input or output	

TABLE 1-2:	PIC18FXX8 PINOUT I/O DESCRIPTIONS (CONTINUED)
IADLL I-2.	

TTL = TTL compatible input ST = Schmitt Trigger input with CMOS levels

Analog = Analog input

0 = Output

= Open-Drain (no P diode to VDD) OD

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 16

2.0 OSCILLATOR CONFIGURATIONS

2.1 Oscillator Types

The PIC18FXX8 can be operated in one of eight oscillator modes, programmable by three configuration bits (FOSC2, FOSC1 and FOSC0).

- 1. LP Low-Power Crystal
- 2. XT Crystal/Resonator
- 3. HS High-Speed Crystal/Resonator
- 4. HS4 High-Speed Crystal/Resonator with PLL enabled
- 5. RC External Resistor/Capacitor
- 6. RCIO External Resistor/Capacitor with I/O pin enabled
- 7. EC External Clock
- 8. ECIO External Clock with I/O pin enabled

2.2 Crystal Oscillator/Ceramic Resonators

In XT, LP, HS or HS4 (PLL) Oscillator modes, a crystal or ceramic resonator is connected to the OSC1 and OSC2 pins to establish oscillation. Figure 2-1 shows the pin connections. An external clock source may also be connected to the OSC1 pin, as shown in Figure 2-3 and Figure 2-4.

The PIC18FXX8 oscillator design requires the use of a parallel cut crystal.

Note: Use of a series cut crystal may give a frequency out of the crystal manufacturer's specifications.

FIGURE 2-1:

CRYSTAL/CERAMIC RESONATOR OPERATION (HS, XT OR LP OSC CONFIGURATION)




TABLE 2-1: CERAMIC RESONATORS

Ranges Tested:								
Mode	Freq	OSC1	OSC2					
XT	455 kHz 2.0 MHz 4.0 MHz	68-100 pF 15-68 pF 15-68 pF	68-100 pF 15-68 pF 15-68 pF					
HS	8.0 MHz 16.0 MHz	10-68 pF 10-22 pF	10-68 pF 10-22 pF					
	These values are for design guidance only. See notes following Table 2-2.							
Resonators Used:								
455 kHz	Panasonic EFO-A455K04B ±0.3%							

455 kHz	Panasonic EFO-A455K04B	±0.3%					
2.0 MHz	2.0 MHz Murata Erie CSA2.00MG						
4.0 MHz	Murata Erie CSA4.00MG	±0.5%					
8.0 MHz	Murata Erie CSA8.00MT	±0.5%					
16.0 MHz Murata Erie CSA16.00MX ±0.5%							
All resonators used did not have built-in capacitors.							

TABLE 2-2:CAPACITOR SELECTION FOR
CRYSTAL OSCILLATOR

Osc Type	Crystal Freq	Cap. Range C1	Cap. Range C2
LP	32.0 kHz	33 pF	33 pF
	200 kHz	15 pF	15 pF
XT	200 kHz	47-68 pF	47-68 pF
	1.0 MHz	15 pF	15 pF
	4.0 MHz	15 pF	15 pF
HS	4.0 MHz	15 pF	15 pF
	8.0 MHz	15-33 pF	15-33 pF
	20.0 MHz	15-33 pF	15-33 pF
	25.0 MHz	15-33 pF	15-33 pF
These yelu	aa ara far de	olan auldonoo	anly

These values are for design guidance only. See notes on this page.

Crystals Used

	-	
32.0 kHz	Epson C-001R32.768K-A	±20 PPM
200 kHz	STD XTL 200.000KHz	±20 PPM
1.0 MHz	ECS ECS-10-13-1	±50 PPM
4.0 MHz	ECS ECS-40-20-1	±50 PPM
8.0 MHz	EPSON CA-301 8.000M-C	±30 PPM
20.0 MHz	EPSON CA-301 20.000M-C	±30 PPM

- Note 1: Recommended values of C1 and C2 are identical to the ranges tested (Table 2-1).
 - 2: Higher capacitance increases the stability of the oscillator but also increases the start-up time.
 - 3: Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
 - 4: Rs may be required in HS mode, as well as XT mode, to avoid overdriving crystals with low drive level specification.


2.3 RC Oscillator

For timing insensitive applications, the "RC" and "RCIO" device options offer additional cost savings. The RC oscillator frequency is a function of the supply voltage, the resistor (REXT) and capacitor (CEXT) values and the operating temperature. In addition to this, the oscillator frequency will vary from unit to unit due to normal process parameter variation. Furthermore, the difference in lead frame capacitance between package types will also affect the oscillation frequency, especially for low CEXT values. The user also needs to take into account variation due to tolerance of external R and C components used. Figure 2-2 shows how the RC combination is connected.

In the RC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic.

Note:	If the oscillator frequency divided by 4
	signal is not required in the application, it
	is recommended to use RCIO mode to
	save current.

FIGURE 2-2: RC OSCILLATOR MODE




The RCIO Oscillator mode functions like the RC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. The I/O pin becomes bit 6 of PORTA (RA6).

2.4 **External Clock Input**

The EC and ECIO Oscillator modes require an external clock source to be connected to the OSC1 pin. The feedback device between OSC1 and OSC2 is turned off in these modes to save current. There is no oscillator start-up time required after a Power-on Reset or after a recovery from Sleep mode.

In the EC Oscillator mode, the oscillator frequency divided by 4 is available on the OSC2 pin. This signal may be used for test purposes or to synchronize other logic. Figure 2-3 shows the pin connections for the EC Oscillator mode.

FIGURE 2-3: **EXTERNAL CLOCK INPUT OPERATION (EC OSC CONFIGURATION**)




The ECIO Oscillator mode functions like the EC mode, except that the OSC2 pin becomes an additional general purpose I/O pin. Figure 2-4 shows the pin connections for the ECIO Oscillator mode.

FIGURE 2-4:

OPERATION (ECIO CONFIGURATION)

EXTERNAL CLOCK INPUT




HS4 (PLL) 2.5

A Phase Locked Loop circuit is provided as a programmable option for users that want to multiply the frequency of the incoming crystal oscillator signal by 4. For an input clock frequency of 10 MHz, the internal clock frequency will be multiplied to 40 MHz. This is useful for customers who are concerned with EMI due to high-frequency crystals.

The PLL can only be enabled when the oscillator configuration bits are programmed for HS mode. If they are programmed for any other mode, the PLL is not enabled and the system clock will come directly from OSC1.

The PLL is one of the modes of the FOSC2:FOSC0 configuration bits. The oscillator mode is specified during device programming.

A PLL lock timer is used to ensure that the PLL has locked before device execution starts. The PLL lock timer has a time-out referred to as TPLL.



PLL BLOCK DIAGRAM

^{© 2006} Microchip Technology Inc.


2.6 Oscillator Switching Feature

The PIC18FXX8 devices include a feature that allows the system clock source to be switched from the main oscillator to an alternate low-frequency clock source. For the PIC18FXX8 devices, this alternate clock source is the Timer1 oscillator. If a low-frequency crystal (32 kHz, for example) has been attached to the Timer1 oscillator pins and the Timer1 oscillator has been enabled, the device can switch to a Low-Power Execution mode. Figure 2-6 shows a block diagram of the system clock sources. The clock switching feature is enabled by programming the Oscillator Switching Enable (OSCSEN) bit in Configuration register, CONFIG1H, to a '0'. Clock switching is disabled in an erased device. See Section 12.2 "Timer1 Oscillator" for further details of the Timer1 oscillator and Section 24.1 "Configuration Bits" for Configuration register details.

2.6.1 SYSTEM CLOCK SWITCH BIT

The system clock source switching is performed under software control. The system clock switch bit, SCS (OSCCON register), controls the clock switching. When the SCS bit is '0', the system clock source comes from the main oscillator selected by the FOSC2:FOSC0 configuration bits. When the SCS bit is set, the system clock source comes from the Timer1 oscillator. The SCS bit is cleared on all forms of Reset.

Note: The Timer1 oscillator must be enabled to switch the system clock source. The Timer1 oscillator is enabled by setting the T1OSCEN bit in the Timer1 Control register (T1CON). If the Timer1 oscillator is not enabled, any write to the SCS bit will be ignored (SCS bit forced cleared) and the main oscillator continues to be the system clock source.



REGISTER 2-1: OSCCON: OSCILLATOR CONTROL REGISTER

	U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-1
	—	—	_	_	_	-	—	SCS
	bit 7							bit 0
oit 7-1	Unimpleme	ented: Read	d as '0'					
oit 0	SCS: Syste	m Clock Sv	vitch bit					
	When OSC	SEN config	uration bit =	<u>0 and T108</u>	SCEN bit is s	set:		
	1 = Switch	to Timer1 o	scillator/cloo	k pin				
	0 = Use pri	mary oscilla	ator/clock inp	out pin				
	When OSC	SEN is clea	r or T1OSC	EN is clear:				
	Bit is forced	clear.						
	Legend:							
	R = Readab	ole bit	W = W	ritable bit	U = Unim	plemented	bit, read as '	'O'
	II – Houduc							•

2.6.2 OSCILLATOR TRANSITIONS

The PIC18FXX8 devices contain circuitry to prevent "glitches" when switching between oscillator sources. Essentially, the circuitry waits for eight rising edges of the clock source that the processor is switching to. This ensures that the new clock source is stable and that its pulse width will not be less than the shortest pulse width of the two clock sources.

Figure 2-7 shows a timing diagram indicating the transition from the main oscillator to the Timer1 oscillator. The Timer1 oscillator is assumed to be running all the time. After the SCS bit is set, the processor is frozen at the next occurring Q1 cycle. After eight synchronization cycles are counted from the Timer1 oscillator, operation resumes. No additional delays are required after the synchronization cycles. The sequence of events that takes place when switching from the Timer1 oscillator to the main oscillator will depend on the mode of the main oscillator. In addition to eight clock cycles of the main oscillator, additional delays may take place.

If the main oscillator is configured for an external crystal (HS, XT, LP), the transition will take place after an oscillator start-up time (Tost) has occurred. A timing diagram indicating the transition from the Timer1 oscillator to the main oscillator for HS, XT and LP modes is shown in Figure 2-8.






FIGURE 2-7: TIMING DIAGRAM FOR TRANSITION FROM OSC1 TO TIMER1 OSCILLATOR

FIGURE 2-8: TIMING DIAGRAM FOR TRANSITION BETWEEN TIMER1 AND OSC1 (HS, XT, LP)



^{© 2006} Microchip Technology Inc.

If the main oscillator is configured for HS4 (PLL) mode, an oscillator start-up time (TOST) plus an additional PLL time-out (TPLL) will occur. The PLL time-out is typically 2 ms and allows the PLL to lock to the main oscillator frequency. A timing diagram indicating the transition from the Timer1 oscillator to the main oscillator for HS4 mode is shown in Figure 2-9. If the main oscillator is configured in the RC, RCIO, EC or ECIO modes, there is no oscillator start-up time-out. Operation will resume after eight cycles of the main oscillator have been counted. A timing diagram indicating the transition from the Timer1 oscillator to the main oscillator for RC, RCIO, EC and ECIO modes is shown in Figure 2-10.



Q1 Q2 Q3 Q4 Q1 Q2 Q3 Q4 Q3 Q4 Q1 TT1P T1OSI Tosc /1_/2_/3_/4_/5_/6_/7_/8\ OSC1 OSC2 Internal System Clock SCS (OSCCON<0>) Tscs Program PC + 4PC PC + 2Counter Note 1: RC Oscillator mode assumed.

FIGURE 2-10: TIMING FOR TRANSITION BETWEEN TIMER1 AND OSC1 (RC, EC)

2.7 Effects of Sleep Mode on the On-Chip Oscillator

When the device executes a SLEEP instruction, the on-chip clocks and oscillator are turned off and the device is held at the beginning of an instruction cycle (Q1 state). With the oscillator off, the OSC1 and OSC2 signals will stop oscillating. Since all the transistor switching currents have been removed, Sleep mode achieves the lowest current consumption of the device (only leakage currents). Enabling any on-chip feature that will operate during Sleep will increase the current consumed during Sleep. The user can wake from Sleep through external Reset, Watchdog Timer Reset or through an interrupt.

2.8 Power-up Delays

Power-up delays are controlled by two timers so that no external Reset circuitry is required for most applications. The delays ensure that the device is kept in Reset until the device power supply and clock are stable. For additional information on Reset operation, see **Section 3.0 "Reset"**.

The first timer is the Power-up Timer (PWRT), which optionally provides a fixed delay of TPWRT (parameter #D033) on power-up only (POR and BOR). The second timer is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable.

With the PLL enabled (HS4 Oscillator mode), the timeout sequence following a Power-on Reset is different from other oscillator modes. The time-out sequence is as follows: the PWRT time-out is invoked after a POR time delay has expired, then the Oscillator Start-up Timer (OST) is invoked. However, this is still not a sufficient amount of time to allow the PLL to lock at high frequencies. The PWRT timer is used to provide an additional fixed 2 ms (nominal) to allow the PLL ample time to lock to the incoming clock frequency.

TABLE 2-3: OSC1 AND OSC2 PIN STATES IN SLEEP MODE

OSC Mode	OSC1 Pin	OSC2 Pin
RC	Floating, external resistor should pull high	At logic low
RCIO	Floating, external resistor should pull high	Configured as PORTA, bit 6
ECIO	Floating	Configured as PORTA, bit 6
EC	Floating	At logic low
LP, XT and HS	Feedback inverter disabled at quiescent voltage level	Feedback inverter disabled at quiescent voltage level

Note: See Table 3-1 in Section 3.0 "Reset" for time-outs due to Sleep and MCLR Reset.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 24

3.0 RESET

The PIC18FXX8 differentiates between various kinds of RESET:

- a) Power-on Reset (POR)
- b) MCLR Reset during normal operation
- c) MCLR Reset during Sleep
- d) Watchdog Timer (WDT) Reset during normal operation
- e) Programmable Brown-out Reset (PBOR)
- f) RESET Instruction
- g) Stack Full Reset
- h) Stack Underflow Reset

Most registers are unaffected by a Reset. Their status is unknown on POR and unchanged by all other Resets. The other registers are forced to a "Reset" state on Power-on Reset, MCLR, WDT Reset, Brownout Reset, MCLR Reset during Sleep and by the RESET instruction.


Most registers are not affected by a WDT wake-up, since this is viewed as the resumption of normal operation. Status bits from the RCON register, RI, TO, PD, POR and BOR are set or cleared differently in different Reset situations, as indicated in Table 3-2. These bits are used in software to determine the nature of the Reset. See Table 3-3 for a full description of the Reset states of all registers.

A simplified block diagram of the On-Chip Reset Circuit is shown in Figure 3-1.

The Enhanced MCU devices have a $\overline{\text{MCLR}}$ noise filter in the $\overline{\text{MCLR}}$ Reset path. The filter will detect and ignore small pulses.

A WDT Reset does not drive MCLR pin low.

FIGURE 3-1: SIMPLIFIED BLOCK DIAGRAM OF ON-CHIP RESET CIRCUIT



^{© 2006} Microchip Technology Inc.

3.1 Power-on Reset (POR)

A Power-on Reset pulse is generated on-chip when a VDD rise is detected. To take advantage of the POR circuitry, connect the MCLR pin directly (or through a resistor) to VDD. This eliminates external RC components usually needed to create a Power-on Reset delay. A minimum rise rate for VDD is specified (refer to parameter D004). For a slow rise time, see Figure 3-2.

When the device starts normal operation (exits the Reset condition), device operating parameters (voltage, frequency, temperature, etc.) must be met to ensure operation. If these conditions are not met, the device must be held in Reset until the operating conditions are met. Brown-out Reset may be used to meet the voltage start-up condition.


3.2 MCLR

PIC18FXX8 devices have a noise filter in the MCLR Reset path. The filter will detect and ignore small pulses.

It should be noted that a WDT Reset does not drive MCLR pin low.

The behavior of the ESD protection on the MCLR pin differs from previous devices of this family. Voltages applied to the pin that exceed its specification can result in both Resets and current draws outside of device specification during the Reset event. For this reason, Microchip recommends that the MCLR pin no longer be tied directly to VDD. The use of an RC network, as shown in Figure 3-2, is suggested.

FIGURE 3-2: EXTERNAL POWER-ON RESET CIRCUIT (FOR SLOW VDD POWER-UP)



3.3 Power-up Timer (PWRT)

The Power-up Timer provides a fixed nominal time-out (parameter #33), only on power-up from the POR. The Power-up Timer operates on an internal RC oscillator. The chip is kept in Reset as long as the PWRT is active. The PWRT's time delay allows VDD to rise to an acceptable level. A configuration bit (PWRTEN in CONFIG2L register) is provided to enable/disable the PWRT.

The power-up time delay will vary from chip to chip due to VDD, temperature and process variation. See DC parameter #33 for details.

3.4 Oscillator Start-up Timer (OST)

The Oscillator Start-up Timer (OST) provides a 1024 oscillator cycle (from OSC1 input) delay after the PWRT delay is over (parameter #32). This additional delay ensures that the crystal oscillator or resonator has started and stabilized.

The OST time-out is invoked only for XT, LP, HS and HS4 modes and only on Power-on Reset or wake-up from Sleep.

3.5 PLL Lock Time-out

With the PLL enabled, the time-out sequence following a Power-on Reset is different from other oscillator modes. A portion of the Power-up Timer is used to provide a fixed time-out that is sufficient for the PLL to lock to the main oscillator frequency. This PLL lock time-out (TPLL) is typically 2 ms and follows the oscillator start-up time-out (OST).

3.6 Brown-out Reset (BOR)

A configuration bit, BOREN, can disable (if clear/ programmed), or enable (if set), the Brown-out Reset circuitry. If VDD falls below parameter D005 for greater than parameter #35, the brown-out situation resets the chip. A Reset may not occur if VDD falls below parameter D005 for less than parameter #35. The chip will remain in Brown-out Reset until VDD rises above BVDD. The Power-up Timer will then be invoked and will keep the chip in Reset an additional time delay (parameter #33). If VDD drops below BVDD while the Power-up Timer is running, the chip will go back into a Brown-out Reset and the Power-up Timer will be initialized. Once VDD rises above BVDD, the Power-up Timer will execute the additional time delay.

3.7 Time-out Sequence

On power-up, the time-out sequence is as follows: First, PWRT time-out is invoked after the POR time delay has expired, then OST is activated. The total time-out will vary based on oscillator configuration and the status of the PWRT. For example, in RC mode with the PWRT disabled, there will be no time-out at all. Figure 3-3, Figure 3-4, Figure 3-5, Figure 3-6 and Figure 3-7 depict time-out sequences on power-up. Since the time-outs occur from the POR pulse, if MCLR is kept low long enough, the time-outs will expire. Bringing MCLR high will begin execution immediately (Figure 3-5). This is useful for testing purposes or to synchronize more than one PIC18FXX8 device operating in parallel.

Table 3-2 shows the Reset conditions for some Special Function Registers, while Table 3-3 shows the Reset conditions for all registers.

TABLE 3-1: TIME-OUT IN VARIOUS SITUATIONS

Oscillator	Power-up	(2)	5 (2)	Wake-up from
Configuration	PWRTEN = 0	PWRTEN = 1	Brown-out ⁽²⁾	Sleep or Oscillator Switch
HS with PLL enabled ⁽¹⁾	72 ms + 1024 Tosc + 2 ms	1024 Tosc + 2 ms	72 ms + 1024 Tosc + 2 ms	1024 Tosc + 2 ms
HS, XT, LP	72 ms + 1024 Tosc	1024 Tosc	72 ms + 1024 Tosc	1024 Tosc
EC	72 ms	_	72 ms	—
External RC	72 ms		72 ms	_

Note 1: 2 ms = Nominal time required for the 4x PLL to lock.

2: 72 ms is the nominal Power-up Timer delay.

REGISTER 3-1: RCON REGISTER BITS AND POSITIONS

R/W-0	U-0	U-0	R/W-1	R/W-1	R/W-1	R/W-0	R/W-1
IPEN	—	—	RI	TO	PD	POR	BOR
bit 7							bit 0

TABLE 3-2:STATUS BITS, THEIR SIGNIFICANCE AND THE INITIALIZATION CONDITION FOR
RCON REGISTER

Condition	Program Counter	RCON Register	RI	то	PD	POR	BOR	STKFUL	STKUNF
Power-on Reset	0000h	01 110q	1	1	1	0	0	u	u
MCLR Reset during normal operation	0000h	00 011q	u	u	u	u	u	u	u
Software Reset during normal operation	0000h	00 011q	0	u	u	u	u	u	u
Stack Full Reset during normal operation	0000h	00 011q	u	u	u	1	1	u	1
Stack Underflow Reset during normal operation	0000h	00 011q	u	u	u	1	1	1	u
MCLR Reset during Sleep	0000h	00 011q	u	1	0	u	u	u	u
WDT Reset	0000h	00 011q	u	0	1	u	u	u	u
WDT Wake-up	PC + 2	01 101q	u	0	0	u	u	u	u
Brown-out Reset	0000h	01 110q	1	1	1	u	0	u	u
Interrupt wake-up from Sleep	PC + 2 ⁽¹⁾	01 101q	u	1	0	u	u	u	u

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0'

Note 1: When the wake-up is due to an interrupt and the GIEH or GIEL bits are set, the PC is loaded with the interrupt vector (000008h or 000018h).






FIGURE 3-4: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 1







FIGURE 3-5: TIME-OUT SEQUENCE ON POWER-UP (MCLR NOT TIED TO VDD): CASE 2









^{© 2006} Microchip Technology Inc.

TABLE 3-3:	INITIALIZATION CONDITIONS FOR ALL REGISTERS

Register Applicab		Register Applicable Devices		MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt	
TOSU	PIC18F2X8	PIC18F4X8	0 0000	0 0000	0 uuuu (3)	
TOSH	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu (3)	
TOSL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu ⁽³⁾	
STKPTR	PIC18F2X8	PIC18F4X8	00-0 0000	uu-0 0000	uu-u uuuu (3)	
PCLATU	PIC18F2X8	PIC18F4X8	0 0000	0 0000	u uuuu	
PCLATH	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu	
PCL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	PC + 2 ⁽²⁾	
TBLPTRU	PIC18F2X8	PIC18F4X8	00 0000	00 0000	uu uuuu	
TBLPTRH	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu	
TBLPTRL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu	
TABLAT	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu	
PRODH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PRODL	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
INTCON	PIC18F2X8	PIC18F4X8	0000 000x	0000 000u	uuuu uuuu (1)	
INTCON2	PIC18F2X8	PIC18F4X8	1111-1	1111-1	uuuu-u (1)	
INTCON3	PIC18F2X8	PIC18F4X8	11-0 0-00	11-0 0-00	uu-u u-uu (1)	
INDF0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
POSTINC0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
POSTDEC0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
PREINC0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
PLUSW0	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
FSR0H	PIC18F2X8	PIC18F4X8	xxxx	uuuu	uuuu	
FSR0L	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
WREG	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
INDF1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
POSTINC1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
POSTDEC1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
PREINC1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	
PLUSW1	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A	

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

- 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
- **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
- 4: See Table 3-2 for Reset value for specific condition.
- 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
- 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)							
Register	Applicabl	e Devices	Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt		
FSR1H	PIC18F2X8	PIC18F4X8	xxxx	uuuu	uuuu		
FSR1L	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
BSR	PIC18F2X8	PIC18F4X8	0000	0000	uuuu		
INDF2	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A		
POSTINC2	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A		
POSTDEC2	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A		
PREINC2	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A		
PLUSW2	PIC18F2X8	PIC18F4X8	N/A	N/A	N/A		
FSR2H	PIC18F2X8	PIC18F4X8	xxxx	uuuu	uuuu		
FSR2L	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
STATUS	PIC18F2X8	PIC18F4X8	x xxxx	u uuuu	u uuuu		
TMR0H	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
TMR0L	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TOCON	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu		
OSCCON	PIC18F2X8	PIC18F4X8	0	0	u		
LVDCON	PIC18F2X8	PIC18F4X8	00 0101	00 0101	uu uuuu		
WDTCON	PIC18F2X8	PIC18F4X8	0	0	u		
RCON ⁽⁴⁾	PIC18F2X8	PIC18F4X8	01 110q	00 011q	01 101q		
TMR1H	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TMR1L	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
T1CON	PIC18F2X8	PIC18F4X8	0-00 0000	u-uu uuuu	u-uu uuuu		
TMR2	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
PR2	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	1111 1111		
T2CON	PIC18F2X8	PIC18F4X8	-000 0000	-000 0000	-uuu uuuu		
SSPBUF	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
SSPADD	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
SSPSTAT	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
SSPCON1	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
SSPCON2	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
ADRESH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
ADRESL	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
ADCON0	PIC18F2X8	PIC18F4X8	0000 00-0	0000 00-0	uuuu uu-u		

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

4: See Table 3-2 for Reset value for specific condition.

5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.

6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3:	INITIALIZATIO	INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)						
Register	Applicabl	e Devices	Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt			
ADCON1	PIC18F2X8	PIC18F4X8	00 0000	00 0000	uu uuuu			
CCPR1H	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
CCPR1L	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
CCP1CON	PIC18F2X8	PIC18F4X8	00 0000	00 0000	uu uuuu			
ECCPR1H	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
ECCPR1L	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu			
ECCP1CON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	0000 0000			
ECCP1DEL	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	0000 0000			
ECCPAS	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	0000 0000			
CVRCON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			
CMCON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			
TMR3H	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
TMR3L	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
T3CON	PIC18F2X8	PIC18F4X8	0000 0000	uuuu uuuu	uuuu uuuu			
SPBRG	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			
RCREG	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			
TXREG	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			
TXSTA	PIC18F2X8	PIC18F4X8	0000 -010	0000 -010	uuuu -uuu			
RCSTA	PIC18F2X8	PIC18F4X8	0000 000x	0000 000u	uuuu uuuu			
EEADR	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
EEDATA	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
EECON2	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu			
EECON1	PIC18F2X8	PIC18F4X8	xx-0 x000	uu-0 u000	uu-0 u000			
IPR3	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu			
PIR3	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			
PIE3	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			
IPR2	PIC18F2X8	PIC18F4X8	-1-1 1111	-1-1 1111	-u-u uuuu			
PIR2	PIC18F2X8	PIC18F4X8	-0-0 0000	-0-0 0000	-u-u uuuu (1)			
PIE2	PIC18F2X8	PIC18F4X8	-0-0 0000	-0-0 0000	-u-u uuuu			
IPR1	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu			
PIR1	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu (1)			
PIE1	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu			

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

4: See Table 3-2 for Reset value for specific condition.

5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.

6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)							
Register	Applicable	e Devices	Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt		
TRISE	PIC18F2X8	PIC18F4X8	0000 -111	0000 -111	uuuu -uuu		
TRISD	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu		
TRISC	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu		
TRISB	PIC18F2X8	PIC18F4X8	1111 1111	1111 1111	uuuu uuuu		
TRISA ⁽⁵⁾	PIC18F2X8	PIC18F4X8	-111 1111 (5)	-111 1111 (5)	-uuu uuuu (5)		
LATE	PIC18F2X8	PIC18F4X8	xxx	uuu	uuu		
LATD	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
LATC	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
LATB	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
LATA ⁽⁵⁾	PIC18F2X8	PIC18F4X8	-xxx xxxx ⁽⁵⁾	-uuu uuuu ⁽⁵⁾	-uuu uuuu (5)		
PORTE	PIC18F2X8	PIC18F4X8	xxx	000	uuu		
PORTD	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
PORTC	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
PORTB	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
PORTA ⁽⁵⁾	PIC18F2X8	PIC18F4X8	-x0x 0000 (5)	-u0u 0000 (5)	-uuu uuuu (5)		
TXERRCNT	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
RXERRCNT	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
COMSTAT	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
CIOCON	PIC18F2X8	PIC18F4X8	00	00	uu		
BRGCON3	PIC18F2X8	PIC18F4X8	-0000	-0000	-uuuu		
BRGCON2	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
BRGCON1	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu		
CANCON	PIC18F2X8	PIC18F4X8	xxxx xxx-	uuuu uuu-	uuuu uuu-		
CANSTAT ⁽⁶⁾	PIC18F2X8	PIC18F4X8	xxx- xxx-	uuu- uuu-	uuu- uuu-		
RXB0D7	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0D6	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0D5	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0D4	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0D3	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0D2	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
RXB0D1	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
RXB0D0	PIC18F2X8	PIC18F4X8	XXXX XXXX	<u>uuuu</u> uuuu	uuuu uuuu		

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

4: See Table 3-2 for Reset value for specific condition.

5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.

6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)							
Register	Applicable Devices		Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt		
RXB0DLC	PIC18F2X8	PIC18F4X8	-xxx xxxx	-uuu uuuu	-uuu uuuu		
RXB0EIDL	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0EIDH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0SIDL	PIC18F2X8	PIC18F4X8	xxxx x-xx	uuuu u-uu	uuuu u-uu		
RXB0SIDH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB0CON	PIC18F2X8	PIC18F4X8	000- 0000	000- 0000	uuu- uuuu		
RXB1D7	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1D6	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1D5	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1D4	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1D3	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1D2	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1D1	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1D0	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1DLC	PIC18F2X8	PIC18F4X8	-xxx xxxx	-uuu uuuu	-uuu uuuu		
RXB1EIDL	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1EIDH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1SIDL	PIC18F2X8	PIC18F4X8	xxxx x-xx	uuuu u-uu	uuuu u-uu		
RXB1SIDH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
RXB1CON	PIC18F2X8	PIC18F4X8	000- 0000	000- 0000	uuu- uuuu		
TXB0D7	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0D6	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0D5	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0D4	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0D3	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
TXB0D2	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0D1	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0D0	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu		
TXB0DLC	PIC18F2X8	PIC18F4X8	-x xxxx	-u uuuu	-u uuuu		
TXB0EIDL	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0EIDH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu		
TXB0SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu		

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

- 2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).
- **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
- 4: See Table 3-2 for Reset value for specific condition.
- 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
- 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

TABLE 3-3:		JN CONDIT	IONS FOR ALL RE	GISTERS (CONTINUI	בט)
Register	Applicabl	e Devices	Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt
TXB0SIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB0CON	PIC18F2X8	PIC18F4X8	-000 0-00	-000 0-00	-uuu u-uu
TXB1D7	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D6	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D5	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D4	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1D3	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu
TXB1D2	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu
TXB1D1	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu
TXB1D0	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1DLC	PIC18F2X8	PIC18F4X8	-x xxxx	-u uuuu	-u uuuu
TXB1EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB1SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu
TXB1SIDH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu
TXB1CON	PIC18F2X8	PIC18F4X8	0000 0000	0000 0000	uuuu uuuu
TXB2D7	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D6	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D5	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D4	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D3	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D2	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D1	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2D0	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2DLC	PIC18F2X8	PIC18F4X8	-x xxxx	-u uuuu	-u uuuu
TXB2EIDL	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu
TXB2EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
TXB2SIDL	PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu
TXB2SIDH	PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu
TXB2CON	PIC18F2X8	PIC18F4X8	-000 0-00	-000 0-00	-uuu u-uu
RXM1EIDL	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu
RXM1EIDH	PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

3: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.

4: See Table 3-2 for Reset value for specific condition.

5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.

6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

© 2006 Microchip Technology Inc.

	JN CONDIT	IONS FOR ALL REG	IS I ERS (CONTINUE	Ξ U)	
Applicabl	e Devices	Power-on Reset, Brown-out Reset	MCLR Reset WDT Reset RESET Instruction Stack Resets	Wake-up via WDT or Interrupt	
PIC18F2X8	PIC18F4X8	xxxxx	uuuuu	uuuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxxxx	uuuuu	uuuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxxx xxxx	uuuu uuuu	uuuu uuuu	
PIC18F2X8	PIC18F4X8	xxx- x-xx	uuu- u-uu	uuu- u-uu	
PIC18F2X8	PIC18F4X8	XXXX XXXX	uuuu uuuu	uuuu uuuu	
	Applicabl PIC18F2X8 PIC18F2X8 <td< td=""><td>Applicable Devices PIC18F2X8 PIC18F4X8 <</td><td>Applicable Devices Power-on Reset, Brown-out Reset PIC18F2X8 PIC18F4X8 xxxxx PIC18F2X8 PIC18F4X8 xxxx xxxx PIC18F2X8</td><td>Applicable DevicesPower-on Reset, Brown-out ResetWDT Reset RESET Instruction Stack ResetsPIC18F2X8PIC18F4X8xxxxxuuuuuPIC18F2X8PIC18F4X8xxxx xxxxuuuu uuuuPIC18F2X8PIC18F4X8xxxx xxxxuuuu uuuuPIC18F2X8PIC18F4X8<</td></td<>	Applicable Devices PIC18F2X8 PIC18F4X8 <	Applicable Devices Power-on Reset, Brown-out Reset PIC18F2X8 PIC18F4X8 xxxxx PIC18F2X8 PIC18F4X8 xxxx xxxx PIC18F2X8	Applicable DevicesPower-on Reset, Brown-out ResetWDT Reset RESET Instruction Stack ResetsPIC18F2X8PIC18F4X8xxxxxuuuuuPIC18F2X8PIC18F4X8xxxx xxxxuuuu uuuuPIC18F2X8PIC18F4X8xxxx xxxxuuuu uuuuPIC18F2X8PIC18F4X8<	

TABLE 3-3: INITIALIZATION CONDITIONS FOR ALL REGISTERS (CONTINUED)

Legend: u = unchanged, x = unknown, - = unimplemented bit, read as '0', q = value depends on condition. Shaded cells indicate conditions do not apply for the designated device.

Note 1: One or more bits in the INTCONx or PIRx registers will be affected (to cause wake-up).

2: When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the PC is loaded with the interrupt vector (0008h or 0018h).

- **3:** When the wake-up is due to an interrupt and the GIEL or GIEH bit is set, the TOSU, TOSH and TOSL are updated with the current value of the PC. The STKPTR is modified to point to the next location in the hardware stack.
- 4: See Table 3-2 for Reset value for specific condition.
- 5: Bit 6 of PORTA, LATA and TRISA are enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, they are disabled and read '0'.
- 6: Values for CANSTAT also apply to its other instances (CANSTATRO1 through CANSTATRO4).

DS41159E-page 36

PROGRAM MEMORY MAP

4.0 MEMORY ORGANIZATION

There are three memory blocks in Enhanced MCU devices. These memory blocks are:

- Enhanced Flash Program Memory
- Data Memory
- EEPROM Data Memory

Data and program memory use separate busses, which allows concurrent access of these blocks. Additional detailed information on data EEPROM and Flash program memory is provided in Section 5.0 "Data EEPROM Memory" and Section 6.0 "Flash Program Memory", respectively.

4.1 Program Memory Organization

The PIC18F258/458 devices have a 21-bit program counter that is capable of addressing a 2-Mbyte program memory space.

The Reset vector address is at 0000h and the interrupt vector addresses are at 0008h and 0018h.

FIGURE 4-1: PROGRAM MEMORY MAP AND STACK FOR PIC18F248/448





Figure 4-1 shows the diagram for program memory map and stack for the PIC18F248 and PIC18F448. Figure 4-2 shows the diagram for the program memory map and stack for the PIC18F258 and PIC18F458.

4.1.1 INTERNAL PROGRAM MEMORY OPERATION

The PIC18F258 and the PIC18F458 have 32 Kbytes of internal Enhanced Flash program memory. This means that the PIC18F258 and the PIC18F458 can store up to 16K of single-word instructions. The PIC18F248 and PIC18F448 have 16 Kbytes of Enhanced Flash program memory. This translates into 8192 single-word instructions, which can be stored in the program memory. Accessing a location between the physically implemented memory and the 2-Mbyte address will cause a read of all '0's (a NOP instruction).

FIGURE 4-2:



© 2006 Microchip Technology Inc.

4.2 Return Address Stack

The return address stack allows any combination of up to 31 program calls and interrupts to occur. The PC (Program Counter) is pushed onto the stack when a PUSH, CALL or RCALL instruction is executed, or an interrupt is Acknowledged. The PC value is pulled off the stack on a RETURN, RETLW or a RETFIE instruction. PCLATU and PCLATH are not affected by any of the RETURN instructions.

The stack operates as a 31-word by 21-bit stack memory and a 5-bit Stack Pointer register, with the Stack Pointer initialized to 00000b after all Resets. There is no RAM associated with Stack Pointer 00000b. This is only a Reset value. During a CALL type instruction, causing a push onto the stack, the Stack Pointer is first incremented and the RAM location pointed to by the Stack Pointer is written with the contents of the PC. During a RETURN type instruction, causing a pop from the stack, the contents of the RAM location indicated by the STKPTR are transferred to the PC and then the Stack Pointer is decremented.

The stack space is not part of either program or data space. The Stack Pointer is readable and writable and the data on the top of the stack is readable and writable through SFR registers. Status bits indicate if the stack pointer is at or beyond the 31 levels provided.

4.2.1 TOP-OF-STACK ACCESS

The top of the stack is readable and writable. Three register locations, TOSU, TOSH and TOSL allow access to the contents of the stack location indicated by the STKPTR register. This allows users to implement a software stack, if necessary. After a CALL, RCALL or interrupt, the software can read the pushed value by reading the TOSU, TOSH and TOSL registers. These values can be placed on a user defined software stack. At return time, the software can replace the TOSU, TOSH and TOSL and do a return.

The user should disable the global interrupt enable bits during this time to prevent inadvertent stack operations.

4.2.2 RETURN STACK POINTER (STKPTR)

The STKPTR register contains the Stack Pointer value, the STKFUL (Stack Full) status bit and the STKUNF (Stack Underflow) status bits. Register 4-1 shows the STKPTR register. The value of the Stack Pointer can be 0 through 31. The Stack Pointer increments when values are pushed onto the stack and decrements when values are popped off the stack. At Reset, the Stack Pointer value will be '0'. The user may read and write the Stack Pointer value. This feature can be used by a Real-Time Operating System for return stack maintenance.

After the PC is pushed onto the stack 31 times (without popping any values off the stack), the STKFUL bit is set. The STKFUL bit can only be cleared in software or by a POR.

The action that takes place when the stack becomes full depends on the state of the STVREN (Stack Overflow Reset Enable) configuration bit. Refer to **Section 21.0 "Comparator Module**" for a description of the device configuration bits. If STVREN is set (default), the 31st push will push the (PC + 2) value onto the stack, set the STKFUL bit and reset the device. The STKFUL bit will remain set and the Stack Pointer will be set to '0'.

If STVREN is cleared, the STKFUL bit will be set on the 31st push and the Stack Pointer will increment to 31. The 32nd push will overwrite the 31st push (and so on), while STKPTR remains at 31.

When the stack has been popped enough times to unload the stack, the next pop will return a value of zero to the PC and sets the STKUNF bit, while the stack pointer remains at '0'. The STKUNF bit will remain set until cleared in software or a POR occurs.

Note: Returning a value of zero to the PC on an underflow has the effect of vectoring the program to the Reset vector, where the stack conditions can be verified and appropriate actions can be taken.

REGISTER 4-1: STKPTR: STACK POINTER REGISTER

R/C-0	R/C-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
STKFUL	STKUNF	—	SP4	SP3	SP2	SP1	SP0
bit 7							bit 0

bit 7 STKFUL: Stack Full Flag bit

1 = Stack became full or overflowed

0 = Stack has not become full or overflowed

bit 6 STKUNF: Stack Underflow Flag bit

1 = Stack underflow occurred

0 = Stack underflow did not occur


bit 5 Unimplemented: Read as '0'

bit 4-0 SP4:SP0: Stack Pointer Location bits

Note: Bit 7 and bit 6 need to be cleared following a stack underflow or a stack overflow.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	d bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	C = Clearable bit

FIGURE 4-3: RETURN ADDRESS STACK AND ASSOCIATED REGISTERS



^{© 2006} Microchip Technology Inc.

4.2.3 PUSH AND POP INSTRUCTIONS

Since the Top-of-Stack (TOS) is readable and writable, the ability to push values onto the stack and pull values off the stack, without disturbing normal program execution, is a desirable option. To push the current PC value onto the stack, a PUSH instruction can be executed. This will increment the Stack Pointer and load the current PC value onto the stack. TOSU, TOSH and TOSL can then be modified to place a return address on the stack.

The POP instruction discards the current TOS by decrementing the Stack Pointer. The previous value pushed onto the stack then becomes the TOS value.

4.2.4 STACK FULL/UNDERFLOW RESETS

These Resets are enabled by programming the STVREN configuration bit. When the STVREN bit is disabled, a full or underflow condition will set the appropriate STKFUL or STKUNF bit, but not cause a device Reset. When the STVREN bit is enabled, a full or underflow condition will set the appropriate STKFUL or STKUNF bit and then cause a device Reset. The STKFUL or STKUNF bits are only cleared by the user software or a POR.

4.3 Fast Register Stack

A "fast return" option is available for interrupts and calls. A fast register stack is provided for the Status, WREG and BSR registers and is only one layer in depth. The stack is not readable or writable and is loaded with the current value of the corresponding register when the processor vectors for an interrupt. The values in the fast register stack are then loaded back into the working registers if the FAST RETURN instruction is used to return from the interrupt.

A low or high priority interrupt source will push values into the stack registers. If both low and high priority interrupts are enabled, the stack registers cannot be used reliably for low priority interrupts. If a high priority interrupt occurs while servicing a low priority interrupt, the stack register values stored by the low priority interrupt will be overwritten.

If high priority interrupts are not disabled during low priority interrupts, users must save the key registers in software during a low priority interrupt.

If no interrupts are used, the fast register stack can be used to restore the Status, WREG and BSR registers at the end of a subroutine call. To use the fast register stack for a subroutine call, a FAST CALL instruction must be executed.

Example 4-1 shows a source code example that uses the fast register stack.

EXAMPLE 4-1: FAST REGISTER STACK CODE EXAMPLE CALL SUB1, FAST ;STATUS, WREG, BSR ;SAVED IN FAST REGISTER ;STACK

•	; STACK
•	
SUB1 •	
•	
RETURN FAST	;RESTORE VALUES SAVED ;IN FAST REGISTER STACK

4.4 PCL, PCLATH and PCLATU

The Program Counter (PC) specifies the address of the instruction to fetch for execution. The PC is 21 bits wide. The low byte is called the PCL register. This register is readable and writable. The high byte is called the PCH register. This register contains the PC<15:8> bits and is not directly readable or writable. Updates to the PCH register. The upper byte is called PCU. This register contains the PC<20:16> bits and is not directly readable or writable. Updates to the PCH register the PC<20:16> bits and is not directly readable or writable. Updates to the PCU register may be performed through the PCLATH register.

The PC addresses bytes in the program memory. To prevent the PC from becoming misaligned with word instructions, the LSb of PCL is fixed to a value of '0'. The PC increments by 2 to address sequential instructions in the program memory.

The CALL, RCALL, GOTO and program branch instructions write to the program counter directly. For these instructions, the contents of PCLATH and PCLATU are not transferred to the program counter.


The contents of PCLATH and PCLATU will be transferred to the program counter by an operation that writes PCL. Similarly, the upper two bytes of the program counter will be transferred to PCLATH and PCLATU by an operation that reads PCL. This is useful for computed offsets to the PC (see **Section 4.8.1** "**Computed GOTO**").

DS41159E-page 40

4.5 Clocking Scheme/Instruction Cycle

The clock input (from OSC1) is internally divided by four to generate four non-overlapping quadrature clocks, namely Q1, Q2, Q3 and Q4. Internally, the Program Counter (PC) is incremented every Q1, the instruction is fetched from the program memory and latched into the instruction register in Q4. The instruction is decoded and executed during the following Q1 through Q4. The clocks and instruction execution flow are shown in Figure 4-4.





4.6 Instruction Flow/Pipelining

An "Instruction Cycle" consists of four Q cycles (Q1, Q2, Q3 and Q4). The instruction fetch and execute are pipelined such that fetch takes one instruction cycle, while decode and execute take another instruction cycle. However, due to the pipelining, each instruction effectively executes in one cycle. If an instruction causes the program counter to change (e.g., GOTO), two cycles are required to complete the instruction (Example 4-2).

A fetch cycle begins with the Program Counter (PC) incrementing in Q1.

In the execution cycle, the fetched instruction is latched into the "Instruction Register" (IR) in cycle Q1. This instruction is then decoded and executed during the Q2, Q3 and Q4 cycles. Data memory is read during Q2 (operand read) and written during Q4 (destination write).

4.7 Instructions in Program Memory

The program memory is addressed in bytes. Instructions are stored as two bytes or four bytes in program memory. The Least Significant Byte of an instruction word is always stored in a program memory location with an even address (LSB = 0). Figure 4-3 shows an example of how instruction words are stored in the program memory. To maintain alignment with instruction boundaries, the PC increments in steps of 2 and the LSB will always read '0' (see Section 4.4 "PCL, PCLATH and PCLATU").

The CALL and GOTO instructions have an absolute program memory address embedded into the instruction. Since instructions are always stored on word boundaries, the data contained in the instruction is a word address. The word address is written to PC<20:1>, which accesses the desired byte address in program memory. Instruction #2 in Example 4-3 shows how the instruction "GOTO 00006h" is encoded in the program memory. Program branch instructions that encode a relative address offset operate in the same manner. The offset value stored in a branch instruction represents the number of single-word instructions by which the PC will be offset. Section 25.0 "Instruction Set Summary" provides further details of the instruction set.

^{© 2006} Microchip Technology Inc.

EXAMPLE 4-2: INSTRUCTION PIPELINE FLOW

	TCY0	Tcy1	TCY2	Тсү3	TCY4	TCY5
1. MOVLW 55h	Fetch 1	Execute 1		_		
2. MOVWF PORTB		Fetch 2	Execute 2		_	
3. BRA SUB_1			Fetch 3	Execute 3		
				Fetch 4	Flush	
4. BSF PORTA, BIT3 (Forced NOP)			1 CICIT 4	riuon	
4. BSF PORTA, BIT3 (5. Instruction @ addre				1 01011 4	Fetch SUB_1	Execute SUB_1

EXAMPLE 4-3: INSTRUCTIONS IN PROGRAM MEMORY

Instruction	Opcode	Memory	Address
			000007h
MOVLW 055h	0E55h	55h	000008h
		0Eh	000009h
GOTO 000006h	0EF03h, 0F000h	03h	00000Ah
		0EFh	00000Bh
		00h	00000Ch
		0F0h	00000Dh
MOVFF 123h, 456h	0C123h, 0F456h	23h	00000Eh
		0C1h	00000Fh
		56h	000010h
		0F4h	000011h
			000012h

DS41159E-page 42

4.7.1 TWO-WORD INSTRUCTIONS

The PIC18FXX8 devices have 4 two-word instructions: MOVFF, CALL, GOTO and LFSR. The 4 Most Significant bits of the second word are set to '1's and indicate a special NOP instruction. The lower 12 bits of the second word contain the data to be used by the instruction. If the first word of the instruction is executed, the data in the second word is accessed. If the second word of the instruction is executed by itself (first word was skipped), it will execute as a NOP. This action is necessary when the two-word instruction is preceded by a conditional instruction that changes the PC. A program example that demonstrates this concept is shown in Example 4-4. Refer to **Section 25.0 "Instruction Set Summary"** for further details of the instruction set.

4.8 Look-up Tables

Look-up tables are implemented two ways. These are:

- Computed GOTO
- Table Reads

4.8.1 COMPUTED GOTO

A computed GOTO is accomplished by adding an offset to the program counter (ADDWF PCL).

A look-up table can be formed with an ADDWF PCL instruction and a group of RETLW 0xnn instructions. WREG is loaded with an offset into the table before executing a call to that table. The first instruction of the called routine is the ADDWF PCL instruction. The next

instruction executed will be one of the RETLW 0xnn instructions that returns the value 0xnn to the calling function.

The offset value (value in WREG) specifies the number of bytes that the program counter should advance.

In this method, only one data byte may be stored in each instruction location and room on the return address stack is required.

- Note 1: The LSb of PCL is fixed to a value of '0'. Hence, computed GOTO to an odd address is not possible.
 - 2: The ADDWF PCL instruction does not update PCLATH/PCLATU. A read operation on PCL must be performed to update PCLATH and PCLATU.

4.8.2 TABLE READS/TABLE WRITES

A better method of storing data in program memory allows 2 bytes of data to be stored in each instruction location.

Look-up table data may be stored as 2 bytes per program word by using table reads and writes. The Table Pointer (TBLPTR) specifies the byte address and the Table Latch (TABLAT) contains the data that is read from, or written to, program memory. Data is transferred to/from program memory, one byte at a time.

A description of the table read/table write operation is shown in **Section 6.1** "Table Reads and Table Writes".

EXAMPLE 4-4: TWO-WORD INSTRUCTIONS

ASE							
	Object	Code				Source Code	
0110	0110	0000	0000	TSTFSZ	REG1	; is RAM location 0?	
1100	0001	0010	0011	MOVFF	REG1, REG2	; No, execute 2-word instruction	
1111	0100	0101	0110			; 2nd operand holds address of REG2	
0010	0100	0000	0000	ADDWF	F REG3 ; continue code		
	0100	0000				,	
CASE (
CASE						Source Code	
	2:	Code		TSTFSZ	REG1		
0110	2: Object	: Code	0000		REG1 REG1, REG2	Source Code	
0110	2: Object	Code	0000000011	TSTFSZ	-	Source Code ; is RAM location 0?	

^{© 2006} Microchip Technology Inc.

4.9 Data Memory Organization

The data memory is implemented as static RAM. Each register in the data memory has a 12-bit address, allowing up to 4096 bytes of data memory. Figure 4-6 shows the data memory organization for the PIC18FXX8 devices.

The data memory map is divided into as many as 16 banks that contain 256 bytes each. The lower 4 bits of the Bank Select Register (BSR<3:0>) select which bank will be accessed. The upper 4 bits for the BSR are not implemented.

The data memory contains Special Function Registers (SFRs) and General Purpose Registers (GPRs). The SFRs are used for control and status of the controller and peripheral functions, while GPRs are used for data storage and scratchpad operations in the user's application. The SFRs start at the last location of Bank 15 (FFFh) and grow downwards. GPRs start at the first location of Bank 0 and grow upwards. Any read of an unimplemented location will read as '0's.

The entire data memory may be accessed directly or indirectly. Direct addressing may require the use of the BSR register. Indirect addressing requires the use of the File Select Register (FSR). Each FSR holds a 12-bit address value that can be used to access any location in the data memory map without banking.

The instruction set and architecture allow operations across all banks. This may be accomplished by indirect addressing or by the use of the MOVFF instruction. The MOVFF instruction is a two-word/two-cycle instruction, that moves a value from one register to another.

To ensure that commonly used registers (SFRs and select GPRs) can be accessed in a single cycle, regardless of the current BSR values, an Access Bank is implemented. A segment of Bank 0 and a segment of Bank 15 comprise the Access RAM. Section 4.10 "Access Bank" provides a detailed description of the Access RAM.

4.9.1 GENERAL PURPOSE REGISTER FILE

The register file can be accessed either directly or indirectly. Indirect addressing operates through the File Select Registers (FSR). The operation of indirect addressing is shown in Section 4.12 "Indirect Addressing, INDF and FSR Registers".

Enhanced MCU devices may have banked memory in the GPR area. GPRs are not initialized by a Power-on Reset and are unchanged on all other Resets.

Data RAM is available for use as GPR registers by all instructions. Bank 15 (F00h to FFFh) contains SFRs. All other banks of data memory contain GPR registers, starting with Bank 0.

4.9.2 SPECIAL FUNCTION REGISTERS


The Special Function Registers (SFRs) are registers used by the CPU and peripheral modules for controlling the desired operation of the device. These registers are implemented as static RAM. A list of these registers is given in Table 4-1.

The SFRs can be classified into two sets: those associated with the "core" function and those related to the peripheral functions. Those registers related to the "core" are described in this section, while those related to the operation of the peripheral features are described in the section of that peripheral feature.

The SFRs are typically distributed among the peripherals whose functions they control.

The unused SFR locations will be unimplemented and read as '0's. See Table 4-1 for addresses for the SFRs.

DS41159E-page 44



DATA MEMORY MAP FOR PIC18F248/448 FIGURE 4-5:

© 2006 Microchip Technology Inc.




FIGURE 4-6: DATA MEMORY MAP FOR PIC18F258/458

DS41159E-page 46

TABLE 4-1:	SPECIAL FUNCTION REGISTER MAP
-------------------	-------------------------------

Address	Name	Address	Name	Address	Name	Address	Name
FFFh	TOSU	FDFh	INDF2 ⁽²⁾	FBFh	CCPR1H	F9Fh	IPR1
FFEh	TOSH	FDEh	POSTINC2 ⁽²⁾	FBEh	CCPR1L	F9Eh	PIR1
FFDh	TOSL	FDDh	POSTDEC2(2)	FBDh	CCP1CON	F9Dh	PIE1
FFCh	STKPTR	FDCh	PREINC2 ⁽²⁾	FBCh	ECCPR1H ⁽⁵⁾	F9Ch	_
FFBh	PCLATU	FDBh	PLUSW2 ⁽²⁾	FBBh	ECCPR1L ⁽⁵⁾	F9Bh	—
FFAh	PCLATH	FDAh	FSR2H	FBAh	ECCP1CON ⁽⁵⁾	F9Ah	—
FF9h	PCL	FD9h	FSR2L	FB9h	_	F99h	—
FF8h	TBLPTRU	FD8h	STATUS	FB8h	_	F98h	
FF7h	TBLPTRH	FD7h	TMR0H	FB7h		F97h	
FF6h	TBLPTRL	FD6h	TMR0L	FB6h	ECCPAS ⁽⁵⁾	F96h	TRISE ⁽⁵⁾
FF5h	TABLAT	FD5h	TOCON	FB5h	CVRCON ⁽⁵⁾	F95h	TRISD ⁽⁵⁾
FF4h	PRODH	FD4h		FB4h	CMCON ⁽⁵⁾	F94h	TRISC
FF3h	PRODL	FD3h	OSCCON	FB3h	TMR3H	F93h	TRISB
FF2h	INTCON	FD2h	LVDCON	FB2h	TMR3L	F92h	TRISA
FF1h	INTCON2	FD1h	WDTCON	FB1h	T3CON	F91h	—
	INTCON3	FD0h	RCON	FB0h		F90h	
	INDF0 ⁽²⁾	FCFh	TMR1H	FAFh	SPBRG	F8Fh	—
	POSTINC0 ⁽²⁾	FCEh	TMR1L	FAEh	RCREG	F8Eh	
	POSTDEC0 ⁽²⁾	FCDh	T1CON	FADh	TXREG	F8Dh	
	PREINC0 ⁽²⁾	FCCh	TMR2	FACh	TXSTA	F8Ch	LATD ⁽⁵⁾
FEBh	PLUSW0(2)	FCBh	PR2	FABh	RCSTA	F8Bh	LATC
FEAh	FSR0H	FCAh	T2CON	FAAh		F8Ah	LATB
FE9h	FSR0L	FC9h	SSPBUF	FA9h	EEADR	F89h	LATA
	WREG	FC8h	SSPADD	FA8h	EEDATA	F88h	—
	INDF1 ⁽²⁾	FC7h	SSPSTAT	FA7h	EECON2	F87h	
	POSTINC1 ⁽²⁾	FC6h	SSPCON1	FA6h	EECON1	F86h	
	POSTDEC1 ⁽²⁾	FC5h	SSPCON2	FA5h	IPR3	F85h	
	PREINC1 ⁽²⁾	FC4h	ADRESH	FA4h	PIR3	F84h	
	PLUSW1 ⁽²⁾	FC3h	ADRESL	FA3h	PIE3	F83h	PORTD ⁽⁵⁾
FE2h	FSR1H	FC2h	ADCON0	FA2h	IPR2	F82h	PORTC
FE1h	FSR1L	FC1h	ADCON1	FA1h	PIR2	F81h	PORTB
FE0h	BSR	FC0h	—	FA0h	PIE2	F80h	PORTA

Note 1: Unimplemented registers are read as '0'.

- 2: This is not a physical register.
- 3: Contents of register are dependent on WIN2:WIN0 bits in the CANCON register.
- 4: CANSTAT register is repeated in these locations to simplify application firmware. Unique names are given for each instance of the CANSTAT register due to the Microchip header file requirement.
- 5: These registers are not implemented on the PIC18F248 and PIC18F258.

^{© 2006} Microchip Technology Inc.

TABLE 4-1: SPECIAL FUNCTION REGISTER MAP (CONTINUED)

Address	Name	Address	Name	Address	Name	Address	Name
F7Fh		F5Fh	—	F3Fh		F1Fh	RXM1EIDL
F7Eh		F5Eh	CANSTATRO1 ⁽⁴⁾	F3Eh	CANSTATRO3 ⁽⁴⁾	F1Eh	RXM1EIDH
F7Dh		F5Dh	RXB1D7	F3Dh	TXB1D7	F1Dh	RXM1SIDL
F7Ch		F5Ch	RXB1D6	F3Ch	TXB1D6	F1Ch	RXM1SIDH
F7Bh		F5Bh	RXB1D5	F3Bh	TXB1D5	F1Bh	RXM0EIDL
F7Ah		F5Ah	RXB1D4	F3Ah	TXB1D4	F1Ah	RXM0EIDH
F79h	_	F59h	RXB1D3	F39h	TXB1D3	F19h	RXM0SIDL
F78h	—	F58h	RXB1D2	F38h	TXB1D2	F18h	RXM0SIDH
F77h	—	F57h	RXB1D1	F37h	TXB1D1	F17h	RXF5EIDL
F76h	TXERRCNT	F56h	RXB1D0	F36h	TXB1D0	F16h	RXF5EIDH
F75h	RXERRCNT	F55h	RXB1DLC	F35h	TXB1DLC	F15h	RXF5SIDL
F74h	COMSTAT	F54h	RXB1EIDL	F34h	TXB1EIDL	F14h	RXF5SIDH
F73h	CIOCON	F53h	RXB1EIDH	F33h	TXB1EIDH	F13h	RXF4EIDL
F72h	BRGCON3	F52h	RXB1SIDL	F32h	TXB1SIDL	F12h	RXF4EIDH
F71h	BRGCON2	F51h	RXB1SIDH	F31h	TXB1SIDH	F11h	RXF4SIDL
F70h	BRGCON1	F50h	RXB1CON	F30h	TXB1CON	F10h	RXF4SIDH
F6Fh	CANCON	F4Fh	—	F2Fh	_	F0Fh	RXF3EIDL
F6Eh	CANSTAT	F4Eh	CANSTATRO2 ⁽⁴⁾	F2Eh	CANSTATRO4 ⁽⁴⁾	F0Eh	RXF3EIDH
F6Dh		F4Dh	TXB0D7	F2Dh	TXB2D7	F0Dh	RXF3SIDL
F6Ch	RXB0D6 ⁽³⁾	F4Ch	TXB0D6	F2Ch	TXB2D6	F0Ch	RXF3SIDH
F6Bh		F4Bh	TXB0D5	F2Bh	TXB2D5	F0Bh	RXF2EIDL
F6Ah	RXB0D4 ⁽³⁾	F4Ah	TXB0D4	F2Ah	TXB2D4	F0Ah	RXF2EIDH
F69h	RXB0D3 ⁽³⁾	F49h	TXB0D3	F29h	TXB2D3	F09h	RXF2SIDL
F68h	RXB0D2 ⁽³⁾	F48h	TXB0D2	F28h	TXB2D2	F08h	RXF2SIDH
F67h	RXB0D1 ⁽³⁾	F47h	TXB0D1	F27h	TXB2D1	F07h	RXF1EIDL
F66h	RXB0D0 ⁽³⁾	F46h	TXB0D0	F26h	TXB2D0	F06h	RXF1EIDH
F65h	RXB0DLC ⁽³⁾	F45h	TXB0DLC	F25h	TXB2DLC	F05h	RXF1SIDL
F64h	RXB0EIDL ⁽³⁾	F44h	TXB0EIDL	F24h	TXB2EIDL	F04h	RXF1SIDH
F63h	RXB0EIDH ⁽³⁾	F43h	TXB0EIDH	F23h	TXB2EIDH	F03h	RXF0EIDL
F62h	RXB0SIDL ⁽³⁾	F42h	TXB0SIDL	F22h	TXB2SIDL	F02h	RXF0EIDH
F61h	RXB0SIDH ⁽³⁾	F41h	TXB0SIDH	F21h	TXB2SIDH	F01h	RXF0SIDL
F60h	RXB0CON ⁽³⁾	F40h	TXB0CON	F20h	TXB2CON	F00h	RXF0SIDH

Note: Shaded registers are available in Bank 15, while the rest are in Access Bank low.

Note 1: Unimplemented registers are read as '0'.

- 2: This is not a physical register.
- 3: Contents of register are dependent on WIN2:WIN0 bits in the CANCON register.
- 4: CANSTAT register is repeated in these locations to simplify application firmware. Unique names are given for each instance of the CANSTAT register due to the Microchip header file requirement.
- 5: These registers are not implemented on the PIC18F248 and PIC18F258.

DS41159E-page 48

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
TOSU	_	_	_	Top-of-Stack L	Ipper Byte (T	OS<20:16>)			0 0000	30, 38
TOSH	Top-of-Stack I	High Byte (TOS	<15:8>)						0000 0000	30, 38
TOSL	Top-of-Stack I	_ow Byte (TOS	<7:0>)						0000 0000	30, 38
STKPTR	STKFUL	STKUNF	—	Return Stack F	Pointer				00-0 0000	30, 39
PCLATU	—	—	bit 21 ⁽²⁾	Holding Regist	ter for PC<20	:16>			0 0000	30, 40
PCLATH	Holding Regis	ster for PC<15:8	3>						0000 0000	30, 40
PCL	PC Low Byte	(PC<7:0>)							0000 0000	30, 40
TBLPTRU	—	—	bit 21 ⁽²⁾	Program Mem	ory Table Poi	nter Upper Byt	e (TBLPTR<	20:16>)	00 0000	30, 68
TBLPTRH	Program Men	nory Table Poin	ter High Byte (TBLPTR<15:8>	>)				0000 0000	30, 68
TBLPTRL	Program Men	nory Table Poin	ter Low Byte (TBLPTR<7:0>)					0000 0000	30, 68
TABLAT	Program Men	nory Table Latcl	h						0000 0000	30, 68
PRODH	Product Regis	ster High Byte							xxxx xxxx	30, 75
PRODL	Product Regis	ster Low Byte							xxxx xxxx	30, 75
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	30, 79
INTCON2	RBPU	INTEDG0	INTEDG1	—	_	TMR0IP	-	RBIP	1111-1	30, 80
INTCON3	INT2IP	INT1IP	_	INT2IE	INT1IE	—	INT2IF	INT1IF	11-0 0-00	30, 81
INDF0	Uses contents	s of FSR0 to ad	dress data me	mory – value o	f FSR0 not ch	anged (not a p	hysical regis	ter)	N/A	30, 55
POSTINC0	Uses contents	s of FSR0 to ad	dress data me	mory – value of	f FSR0 post-ii	ncremented (n	ot a physical	register)	N/A	30, 55
POSTDEC0	Uses contents	s of FSR0 to ad	dress data me	mory – value of	f FSR0 post-ii	ncremented (n	ot a physical	register)	N/A	30, 55
PREINC0	Uses contents	s of FSR0 to ad	dress data me	mory – value of	f FSR0 pre-in	cremented (no	t a physical ı	egister)	N/A	30, 55
PLUSW0	Uses contents	s of FSR0 to ad	dress data me	mory – value of	f FSR0 offset	by W (not a pł	nysical regist	er)	N/A	30, 55
FSR0H	_	_	_	_	Indirect Data	a Memory Add	ress Pointer	0 High	xxxx	30, 55
FSR0L	Indirect Data	Memory Addres	ss Pointer 0 Lo	w Byte					XXXX XXXX	30, 55
WREG	Working Regi	ster							XXXX XXXX	30, 55
INDF1	Uses contents	s of FSR1 to ad	dress data me	mory – value of	f FSR1 not ch	anged (not a p	hysical regis	ter)	N/A	30, 55
POSTINC1	Uses contents	s of FSR1 to ad	dress data me	mory – value of	f FSR1 post-ii	ncremented (n	ot a physical	register)	N/A	30, 55
POSTDEC1	Uses contents	s of FSR1 to ad	dress data me	mory – value of	f FSR1 post-ii	ncremented (n	ot a physical	register)	N/A	30, 55
PREINC1	Uses contents	s of FSR1 to ad	dress data me	mory – value of	f FSR1 pre-in	cremented (no	t a physical ı	egister)	N/A	30, 55
PLUSW1	Uses contents	s of FSR1 to ad	dress data me	mory – value of	f FSR1 offset	by W (not a pł	nysical regist	er)	N/A	30, 55
FSR1H	—	—	—	—	Indirect Data	a Memory Add	ress Pointer	1 High	xxxx	31, 55
FSR1L	Indirect Data	Memory Addres	ss Pointer 1 Lo	w Byte					xxxx xxxx	31, 55
BSR	—	—	—	—	Bank Select	Register			0000	31, 54
INDF2	Uses contents	s of FSR2 to ad	dress data me	mory – value of	f FSR2 not ch	anged (not a p	physical regis	ster)	N/A	31, 55
POSTINC2	Uses contents	s of FSR2 to ad	dress data me	mory – value o	f FSR2 post-ii	ncremented (n	ot a physical	register)	N/A	31, 55
POSTDEC2	Uses contents	s of FSR2 to ad	dress data me	mory – value o	f FSR2 post-ii	ncremented (n	ot a physical	register)	N/A	31, 55
PREINC2	Uses contents	s of FSR2 to ad	dress data me	mory – value o	f FSR2 pre-in	cremented (no	t a physical ı	egister)	N/A	31, 55
PLUSW2	Uses contents	s of FSR2 to ad	dress data me	mory – value of	f FSR2 offset	by W (not a pł	nysical regist	er)	N/A	31, 55
FSR2H	—	—	_	—	Indirect Data	a Memory Add	ress Pointer	2 High	xxxx	31, 55
FSR2L	Indirect Data	Memory Addres	ss Pointer 2 Lo	w Byte		-			xxxx xxxx	31, 55
STATUS	—	—	—	Ν	OV	Z	DC	С	x xxxx	31, 57
TMR0H	Timer0 Regist	ter High Byte							0000 0000	31, 111
TMR0L	Timer0 Regist	ter Low Byte							xxxx xxxx	31, 111
TOCON	TMR0ON	T08BIT	TOCS	TOSE	PSA	T0PS2	T0PS1	T0PS0	1111 1111	31, 109
OSCCON	—	_	_	_	_	_	_	SCS	0	31, 20
LVDCON	_	_	IRVST	LVDEN	LVDL3	LVDL2	LVDL1	LVDL0	00 0101	31, 261
WDTCON	_	_	_	_	_	_	_	SWDTEN	0	31, 272
RCON	IPEN	_	_	RI	TO	PD	POR	BOR	01 110q	31, 58, 91

TABLE 4-2: REGISTER FILE SUMMARY

 $\label{eq:legend: Legend: Legend: u = unchanged, - = unimplemented, q = value depends on condition$

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

2: Bit 21 of the TBLPTRU allows access to the device configuration bits.

3: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

REGISTER FILE SUMMARY (CONTINUED) TABLE 4-2:

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
TMR1H	Timer1 Register High Byte								xxxx xxxx	31, 116
TMR1L	Timer1 Regist	ter Low Byte							xxxx xxxx	31, 116
T1CON	RD16	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	0-00 0000	31, 113
TMR2	Timer2 Regist	ter							0000 0000	31, 118
PR2	Timer2 Period	l Register							1111 1111	31, 118
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000 0000	31, 117
SSPBUF	SSP Receive	Buffer/Transmi	t Register						xxxx xxxx	31, 146
SSPADD	SSP Address	Register in I ² C	™ Slave mode	e. SSP Baud Ra	ate Reload Re	egister in I ² C N	laster mode.		0000 0000	31, 152
SSPSTAT	SMP	CKE	D/Ā	Р	S	R/W	UA	BF	0000 0000	31, 144, 153
SSPCON1	WCOL	SSPOV	SSPEN	СКР	SSPM3	SSPM2	SSPM1	SSPM0	0000 0000	31, 145, 145
SSPCON2	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN	0000 0000	31, 155
ADRESH	A/D Result Re	egister High By	te						xxxx xxxx	31, 243
ADRESL	A/D Result Re	egister Low Byt	e						xxxx xxxx	31, 243
ADCON0	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	—	ADON	0000 00-0	31, 241
ADCON1	ADFM	ADCS2	—	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	32, 242
CCPR1H	Capture/Com	pare/PWM Reg	ister 1 High By	/te					xxxx xxxx	32, 124
CCPR1L	Capture/Com	pare/PWM Reg	ister 1 Low By	te					xxxx xxxx	32, 124
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 0000	32, 123
ECCPR1H ⁽¹⁾	Enhanced Ca	pture/Compare	/PWM Registe	er 1 High Byte					xxxx xxxx	32, 133
ECCPR1L ⁽¹⁾	Enhanced Ca	pture/Compare	/PWM Registe	er 1 Low Byte					xxxx xxxx	32, 133
ECCP1CON ⁽¹⁾	EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0	0000 0000	32, 131
ECCP1DEL ⁽¹⁾	EPDC7	EPDC6	EPDC5	EPDC4	EPDC3	EPDC2	EPDC1	EPDC0	0000 0000	32, 140
ECCPAS ⁽¹⁾	ECCPASE	ECCPAS2	ECCPAS1	ECCPAS0	PSSAC1	PSSAC0	PSSBD1	PSSBD0	0000 0000	32, 142
CVRCON ⁽¹⁾	CVREN	CVROE	CVRR	CVRSS	CVR3	CVR2	CVR1	CVR0	0000 0000	32, 255
CMCON ⁽¹⁾	C2OUT	C1OUT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000 0000	32, 249
TMR3H	Timer3 Regist	ter High Byte							xxxx xxxx	32, 121
TMR3L	Timer3 Regist	ter Low Byte							xxxx xxxx	32, 121
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 0000	32, 119
SPBRG	USART Baud	Rate Generato	or						0000 0000	32, 185
RCREG	USART Recei	ive Register							0000 0000	32, 191
TXREG	USART Trans	mit Register							0000 0000	32, 189
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	32, 183
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	32, 184
EEADR	EEPROM Add	dress Register							xxxx xxxx	32, 59
EEDATA	EEPROM Dat	ta Register							xxxx xxxx	32, 59
EECON2	EEPROM Cor	ntrol Register 2	(not a physica	ıl register)					xxxx xxxx	32, 59
EECON1	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	xx-0 x000	32, 60, 67
IPR3	IRXIP	WAKIP	ERRIP	TXB2IP	TXB1IP	TXB0IP	RXB1IP	RXB0IP	1111 1111	32, 90
PIR3	IRXIF	WAKIF	ERRIF	TXB2IF	TXB1IF	TXB0IF	RXB1IF	RXB0IF	0000 0000	32, 84
PIE3	IRXIE	WAKIE	ERRIE	TXB2IE	TXB1IE	TXB0IE	RXB1IE	RXB0IE	0000 0000	32, 87
IPR2	—	CMIP	—	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP(1)	-1-1 1111	32, 89
PIR2	—	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF ⁽¹⁾	-0-0 0000	32, 83
PIE2		CMIE		EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE ⁽¹⁾	-0-0 0000	32, 86

 \mathbf{x} = unknown, \mathbf{u} = unchanged, - = unimplemented, \mathbf{q} = value depends on condition Legend: Note

1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

2: Bit 21 of the TBLPTRU allows access to the device configuration bits.

3: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	32, 88
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	32, 82
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	32, 85
TRISE ⁽¹⁾	IBF	OBF	IBOV	PSPMODE	_	Data Directio	n bits for POI	RTE ⁽¹⁾	0000 -111	33, 105
TRISD ⁽¹⁾	Data Direction	Control Regis	ter for PORTD	(1)					1111 1111	33, 102
TRISC		Control Regis							1111 1111	33, 100
TRISB	Data Direction	n Control Regis	ter for PORTB						1111 1111	33, 96
TRISA ⁽³⁾	_	Data Direction	Control Regis	ter for PORTA					-111 1111	33, 93
LATE ⁽¹⁾	_	—	—	—	_	Read PORTE PORTE Data		Write	xxx	33, 104
LATD ⁽¹⁾	Read PORTD	Data Latch, W	/rite PORTD Da	ata Latch ⁽¹⁾					xxxx xxxx	33, 102
LATC	Read PORTC	Data Latch, W	/rite PORTC Da	ata Latch					xxxx xxxx	33, 100
LATB	Read PORTB	Data Latch, W	rite PORTB Da	ata Latch					xxxx xxxx	33, 96
LATA ⁽³⁾	_	Read PORTA	Data Latch, W	rite PORTA Da	ta Latch				-xxx xxxx	33, 93
PORTE ⁽¹⁾	_	—	—	—	—	Read PORTE Latch ⁽¹⁾	Epins, Write F	PORTE Data	xxx	33, 104
PORTD ⁽¹⁾	Read PORTD	pins, Write PC	ORTD Data Late	ch ⁽¹⁾					xxxx xxxx	33, 102
PORTC	Read PORTC	pins, Write PC	ORTC Data Late	ch					xxxx xxxx	33, 100
PORTB	Read PORTB pins, Write PORTB Data Latch							xxxx xxxx	33, 96	
PORTA ⁽³⁾	_	Read PORTA	pins, Write PC	RTA Data Latc	h				-x0x 0000	33, 93
TXERRCNT	TEC7	TEC6	TEC5	TEC4	TEC3	TEC2	TEC1	TEC0	0000 0000	33, 209
RXERRCNT	REC7	REC6	REC5	REC4	REC3	REC2	REC1	REC0	0000 0000	33, 214
COMSTAT	RXB0OVFL	RXB10VFL	ТХВО	TXBP	RXBP	TXWARN	RXWARN	EWARN	0000 0000	33, 205
CIOCON	_	_	ENDRHI	CANCAP	_	_	_	_	00	33, 221
BRGCON3	_	WAKFIL	_	_	_	SEG2PH2	SEG2PH1	SEG2PH0	-0000	33, 220
BRGCON2	SEG2PHTS	SAM	SEG1PH2	SEG1PH1	SEG1PH0	PRSEG2	PRSEG1	PRSEG0	0000 0000	33, 219
BRGCON1	SJW1	SJW0	BRP5	BRP4	BRP3	BRP2	BRP1	BRP0	0000 0000	33, 218
CANCON	REQOP2	REQOP1	REQOP0	ABAT	WIN2	WIN1	WIN0	—	xxxx xxx-	33, 201
CANSTAT	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202
RXB0D7	RXB0D77	RXB0D76	RXB0D75	RXB0D74	RXB0D73	RXB0D72	RXB0D71	RXB0D70	XXXX XXXX	33, 214
RXB0D6	RXB0D67	RXB0D66	RXB0D65	RXB0D64	RXB0D63	RXB0D62	RXB0D61	RXB0D60	XXXX XXXX	33, 214
RXB0D5	RXB0D57	RXB0D56	RXB0D55	RXB0D54	RXB0D53	RXB0D52	RXB0D51	RXB0D50	XXXX XXXX	33, 214
RXB0D4	RXB0D47	RXB0D46	RXB0D45	RXB0D44	RXB0D43	RXB0D42	RXB0D41	RXB0D40	XXXX XXXX	33, 214
RXB0D3	RXB0D37	RXB0D36	RXB0D35	RXB0D34	RXB0D33	RXB0D32	RXB0D31	RXB0D30	xxxx xxxx	33, 214
RXB0D2	RXB0D27	RXB0D26	RXB0D25	RXB0D24	RXB0D23	RXB0D22	RXB0D21	RXB0D20	XXXX XXXX	33, 214
RXB0D1	RXB0D17	RXB0D16	RXB0D15	RXB0D14	RXB0D13	RXB0D12	RXB0D11	RXB0D10	XXXX XXXX	33, 214
RXB0D0	RXB0D07	RXB0D06	RXB0D05	RXB0D04	RXB0D03	RXB0D02	RXB0D01	RXB0D00	XXXX XXXX	33, 214
RXB0DLC	—	RXRTR	RB1	RB0	DLC3	DLC2	DLC1	DLC0	-xxx xxxx	34, 213
RXB0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	34, 213
RXB0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	34, 212
RXB0SIDL	SID2	SID1	SID0	SRR	EXID	—	EID17	EID16	xxxx x-xx	34, 212
RXB0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	34, 212
RXB0CON	RXFUL	RXM1	RXM0	—	RXRTRRO	RXB0DBEN	JTOFF	FILHIT0	000- 0000	34, 210

TABLE 4-2: REGISTER FILE SUMMARY (CC	ONTINUED)
--------------------------------------	-----------

Legend: Note

x = unknown, u = unchanged, - = unimplemented, q = value depends on condition These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's. 1:

2: Bit 21 of the TBLPTRU allows access to the device configuration bits.

RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes. 3:

^{© 2006} Microchip Technology Inc.

TABLE 4-2: REGISTER FILE SUMMARY (CONTINUED)										
File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
CANSTATRO1	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202
RXB1D7	RXB1D77	RXB1D76	RXB1D75	RXB1D74	RXB1D73	RXB1D72	RXB1D71	RXB1D70	xxxx xxxx	34, 214
RXB1D6	RXB1D67	RXB1D66	RXB1D65	RXB1D64	RXB1D63	RXB1D62	RXB1D61	RXB1D60	xxxx xxxx	34, 214
RXB1D5	RXB1D57	RXB1D56	RXB1D55	RXB1D54	RXB1D53	RXB1D52	RXB1D51	RXB1D50	xxxx xxxx	34, 214
RXB1D4	RXB1D47	RXB1D46	RXB1D45	RXB1D44	RXB1D43	RXB1D42	RXB1D41	RXB1D40	xxxx xxxx	34, 214
RXB1D3	RXB1D37	RXB1D36	RXB1D35	RXB1D34	RXB1D33	RXB1D32	RXB1D31	RXB1D30	xxxx xxxx	34, 214
RXB1D2	RXB1D27	RXB1D26	RXB1D25	RXB1D24	RXB1D23	RXB1D22	RXB1D21	RXB1D20	xxxx xxxx	34, 214
RXB1D1	RXB1D17	RXB1D16	RXB1D15	RXB1D14	RXB1D13	RXB1D12	RXB1D11	RXB1D10	xxxx xxxx	34, 214
RXB1D0	RXB1D07	RXB1D06	RXB1D05	RXB1D04	RXB1D03	RXB1D02	RXB1D01	RXB1D00	xxxx xxxx	34, 214
RXB1DLC	—	RXRTR	RB1	RB0	DLC3	DLC2	DLC1	DLC0	-xxx xxxx	34, 213
RXB1EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	34, 213
RXB1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	34, 212
RXB1SIDL	SID2	SID1	SID0	SRR	EXID	_	EID17	EID16	xxxx x-xx	34, 212
RXB1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	34, 212
RXB1CON	RXFUL	RXM1	RXM0	_	RXRTRRO	FILHIT2	FILHIT1	FILHITO	000- 0000	34, 211
CANSTATRO2	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202
TXB0D7	TXB0D77	TXB0D76	TXB0D75	TXB0D74	TXB0D73	TXB0D72	TXB0D71	TXB0D70	xxxx xxxx	34, 208
TXB0D6	TXB0D67	TXB0D66	TXB0D65	TXB0D64	TXB0D63	TXB0D62	TXB0D61	TXB0D60	xxxx xxxx	34, 208
TXB0D5	TXB0D57	TXB0D56	TXB0D55	TXB0D54	TXB0D53	TXB0D52	TXB0D51	TXB0D50	xxxx xxxx	34, 208
TXB0D4	TXB0D47	TXB0D46	TXB0D45	TXB0D44	TXB0D43	TXB0D42	TXB0D41	TXB0D40	xxxx xxxx	34, 208
TXB0D3	TXB0D37	TXB0D36	TXB0D35	TXB0D34	TXB0D33	TXB0D32	TXB0D31	TXB0D30	xxxx xxxx	34, 208
TXB0D2	TXB0D27	TXB0D26	TXB0D25	TXB0D24	TXB0D23	TXB0D22	TXB0D21	TXB0D20	xxxx xxxx	34, 208
TXB0D1	TXB0D17	TXB0D16	TXB0D15	TXB0D14	TXB0D13	TXB0D12	TXB0D11	TXB0D10	xxxx xxxx	34, 208
TXB0D0	TXB0D07	TXB0D06	TXB0D05	TXB0D04	TXB0D03	TXB0D02	TXB0D01	TXB0D00	xxxx xxxx	34, 208
TXB0DLC	_	TXRTR	_	_	DLC3	DLC2	DLC1	DLC0	-x xxxx	34, 209
TXB0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	34, 208
TXB0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	34, 207
TXB0SIDL	SID2	SID1	SID0	_	EXIDE	_	EID17	EID16	xxx- x-xx	34, 207
TXB0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	35, 207
TXB0CON	_	TXABT	TXLARB	TXERR	TXREQ	_	TXPRI1	TXPRI0	-000 0-00	35, 206
CANSTATRO3	OPMODE2	OPMODE1	OPMODE0	_	ICODE2	ICODE1	ICODE0	_	xxx- xxx-	33, 202
TXB1D7	TXB1D77	TXB1D76	TXB1D75	TXB1D74	TXB1D73	TXB1D72	TXB1D71	TXB1D70	xxxx xxxx	35, 208
TXB1D6	TXB1D67	TXB1D66	TXB1D65	TXB1D64	TXB1D63	TXB1D62	TXB1D61	TXB1D60	xxxx xxxx	35, 208
TXB1D5	TXB1D57	TXB1D56	TXB1D55	TXB1D54	TXB1D53	TXB1D52	TXB1D51	TXB1D50	xxxx xxxx	35, 208
TXB1D4	TXB1D47	TXB1D46	TXB1D45	TXB1D44	TXB1D43	TXB1D42	TXB1D41	TXB1D40	xxxx xxxx	35, 208
TXB1D3	TXB1D37	TXB1D36	TXB1D35	TXB1D34	TXB1D33	TXB1D32	TXB1D31	TXB1D30	xxxx xxxx	35, 208
TXB1D2	TXB1D27	TXB1D26	TXB1D25	TXB1D24	TXB1D23	TXB1D22	TXB1D21	TXB1D20	xxxx xxxx	35, 208
TXB1D1	TXB1D17	TXB1D16	TXB1D15	TXB1D14	TXB1D13	TXB1D12	TXB1D11	TXB1D10	xxxx xxxx	35, 208
TXB1D0	TXB1D07	TXB1D06	TXB1D05	TXB1D04	TXB1D03	TXB1D02	TXB1D01	TXB1D00	xxxx xxxx	35, 208
TXB1DLC	_	TXRTR	_	_	DLC3	DLC2	DLC1	DLC0	-x xxxx	35, 209
TXB1EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	XXXX XXXX	35, 208
TXB1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	XXXX XXXX	35, 207
TXB1SIDL	SID2	SID1	SID0		EXIDE		EID17	EID16	xxx- x-xx	35, 207
TXB1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	XXXX XXXX	35, 207
TXB1CON	_	TXABT	TXLARB	TXERR	TXREQ	_	TXPRI1	TXPRI0	0000 0000	35, 206
		170101					170 101	1751 110	2000 0000	00, 200

TABLE 4-2: REGISTER FILE SUMMARY (CONTINUED)

 $\label{eq:Legend: Legend: Legend: u = unknown, u = unknowed, - = unimplemented, q = value depends on condition$

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

2: Bit 21 of the TBLPTRU allows access to the device configuration bits.

3: RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes.

DS41159E-page 52

TABLE 4-2: REGISTER FILE SUMMARY (CONTINUED)										
File Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Details on Page:
CANSTATRO4	OPMODE2	OPMODE1	OPMODE0		ICODE2	ICODE1	ICODE0		xxx- xxx-	33, 202
TXB2D7	TXB2D77	TXB2D76	TXB2D75	TXB2D74	TXB2D73	TXB2D72	TXB2D71	TXB2D70	xxxx xxxx	35, 208
TXB2D6	TXB2D67	TXB2D66	TXB2D65	TXB2D64	TXB2D63	TXB2D62	TXB2D61	TXB2D60	XXXX XXXX	35, 208
TXB2D5	TXB2D57	TXB2D56	TXB2D55	TXB2D54	TXB2D53	TXB2D52	TXB2D51	TXB2D50	xxxx xxxx	35, 208
TXB2D4	TXB2D47	TXB2D46	TXB2D45	TXB2D44	TXB2D43	TXB2D42	TXB2D41	TXB2D40	XXXX XXXX	35, 208
TXB2D3	TXB2D37	TXB2D36	TXB2D35	TXB2D34	TXB2D33	TXB2D32	TXB2D31	TXB2D30	XXXX XXXX	35, 208
TXB2D2	TXB2D27	TXB2D26	TXB2D25	TXB2D24	TXB2D23	TXB2D22	TXB2D21	TXB2D20	xxxx xxxx	35, 208
TXB2D1	TXB2D17	TXB2D16	TXB2D15	TXB2D14	TXB2D13	TXB2D12	TXB2D11	TXB2D10	xxxx xxxx	35, 208
TXB2D0	TXB2D07	TXB2D06	TXB2D05	TXB2D04	TXB2D03	TXB2D02	TXB2D01	TXB2D00	xxxx xxxx	35, 208
TXB2DLC	—	TXRTR	—	—	DLC3	DLC2	DLC1	DLC0	-x xxxx	35, 209
TXB2EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	35, 208
TXB2EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	35, 207
TXB2SIDL	SID2	SID1	SID0	—	EXIDE	_	EID17	EID16	xxx- x-xx	35, 207
TXB2SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	35, 207
TXB2CON	-	TXABT	TXLARB	TXERR	TXREQ	_	TXPRI1	TXPRI0	-000 0-00	35, 206
RXM1EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	35, 217
RXM1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	35, 217
RXM1SIDL	SID2	SID1	SID0		_	-	EID17	EID16	xxxxx	36, 217
RXM1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 216
RXM0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 217
RXM0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	XXXX XXXX	36, 217
RXM0SIDL	SID2	SID1	SID0	_	_	_	EID17	EID16	xxxxx	36, 217
RXM0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 216
RXF5EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF5EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF5SIDL	SID2	SID1	SID0		EXIDEN	-	EID17	EID16	xxx- x-xx	36, 215
RXF5SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF4EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF4EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF4SIDL	SID2	SID1	SID0		EXIDEN	-	EID17	EID16	xxx- x-xx	36, 215
RXF4SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF3EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	XXXX XXXX	36, 216
RXF3EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	XXXX XXXX	36, 216
RXF3SIDL	SID2	SID1	SID0		EXIDEN	-	EID17	EID16	xxx- x-xx	36, 215
RXF3SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	XXXX XXXX	36, 215
RXF2EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	XXXX XXXX	36, 216
RXF2EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF2SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF2SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	XXXX XXXX	36, 215
RXF1EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF1EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF1SIDL	SID2	SID1	SID0		EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF1SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215
RXF0EIDL	EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0	xxxx xxxx	36, 216
RXF0EIDH	EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	xxxx xxxx	36, 216
RXF0SIDL	SID2	SID1	SID0	_	EXIDEN	_	EID17	EID16	xxx- x-xx	36, 215
RXF0SIDH	SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3	xxxx xxxx	36, 215

......

Legend: Note

 \mathbf{x} = unknown, \mathbf{u} = unchanged, - = unimplemented, \mathbf{q} = value depends on condition

1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

Bit 21 of the TBLPTRU allows access to the device configuration bits. 2:

RA6 and associated bits are configured as port pins in RCIO and ECIO Oscillator mode only and read '0' in all other oscillator modes. 3:

© 2006 Microchip Technology Inc.

4.10 Access Bank

The Access Bank is an architectural enhancement that is very useful for C compiler code optimization. The techniques used by the C compiler are also useful for programs written in assembly.

This data memory region can be used for:

- · Intermediate computational values
- · Local variables of subroutines
- · Faster context saving/switching of variables
- · Common variables
- Faster evaluation/control of SFRs (no banking)

The Access Bank is comprised of the upper 160 bytes in Bank 15 (SFRs) and the lower 96 bytes in Bank 0. These two sections will be referred to as Access Bank High and Access Bank Low, respectively. Figure 4-6 indicates the Access Bank areas.

A bit in the instruction word specifies if the operation is to occur in the bank specified by the BSR register or in the Access Bank.

When forced in the Access Bank (a = 0), the last address in Access Bank Low is followed by the first address in Access Bank High. Access Bank High maps most of the Special Function Registers so that these registers can be accessed without any software overhead.

4.11 Bank Select Register (BSR)

The need for a large general purpose memory space dictates a RAM banking scheme. The data memory is partitioned into sixteen banks. When using direct addressing, the BSR should be configured for the desired bank.

BSR<3:0> holds the upper 4 bits of the 12-bit RAM address. The BSR<7:4> bits will always read '0's and writes will have no effect.


A MOVLB instruction has been provided in the instruction set to assist in selecting banks.

If the currently selected bank is not implemented, any read will return all '0's and all writes are ignored. The Status register bits will be set/cleared as appropriate for the instruction performed.

Each Bank extends up to FFh (256 bytes). All data memory is implemented as static RAM.

A MOVFF instruction ignores the BSR since the 12-bit addresses are embedded into the instruction word.

Section 4.12 "Indirect Addressing, INDF and FSR Registers" provides a description of indirect addressing, which allows linear addressing of the entire RAM space.



DS41159E-page 54

© 2006 Microchip Technology Inc.

FIGURE 4-7: DIRECT ADDRESSING

4.12 Indirect Addressing, INDF and FSR Registers

Indirect addressing is a mode of addressing data memory where the data memory address in the instruction is not fixed. A SFR register is used as a pointer to the data memory location that is to be read or written. Since this pointer is in RAM, the contents can be modified by the program. This can be useful for data tables in the data memory and for software stacks. Figure 4-8 shows the operation of indirect addressing. This shows the moving of the value to the data memory address specified by the value of the FSR register.

Indirect addressing is possible by using one of the INDF registers. Any instruction using the INDF register actually accesses the register indicated by the File Select Register, FSR. Reading the INDF register itself, indirectly (FSR = 0), will read 00h. Writing to the INDF register indirectly, results in a no operation. The FSR register contains a 12-bit address which is shown in Figure 4-8.

The INDFn ($0 \le n \le 2$) register is not a physical register. Addressing INDFn actually addresses the register whose address is contained in the FSRn register (FSRn is a pointer). This is indirect addressing.

Example 4-5 shows a simple use of indirect addressing to clear the RAM in Bank 1 (locations 100h-1FFh) in a minimum number of instructions.

EXAMPLE 4-5: HOW TO CLEAR RAM (BANK 1) USING INDIRECT ADDRESSING

	LFSR	FSR0, 100h	;	
NEXT	CLRF	POSTINC0	;	Clear INDF
			;	register
			;	& inc pointer
	BTFSS	FSROH, 1	;	All done
			;	w/ Bank1?
	BRA	NEXT	;	NO, clear next
CONTINU	JE		;	
:			;	YES, continue

There are three indirect addressing registers. To address the entire data memory space (4096 bytes), these registers are 12 bits wide. To store the 12 bits of addressing information, two 8-bit registers are required. These indirect addressing registers are:

- 1. FSR0: composed of FSR0H:FSR0L
- 2. FSR1: composed of FSR1H:FSR1L
- 3. FSR2: composed of FSR2H:FSR2L

In addition, there are registers INDF0, INDF1 and INDF2, which are not physically implemented. Reading or writing to these registers activates indirect addressing, with the value in the corresponding FSR register being the address of the data.

If an instruction writes a value to INDF0, the value will be written to the address indicated by FSR0H:FSR0L. A read from INDF1 reads the data from the address indicated by FSR1H:FSR1L. INDFn can be used in code anywhere an operand can be used. If INDF0, INDF1 or INDF2 are read indirectly via an FSR, all '0's are read (zero bit is set). Similarly, if INDF0, INDF1 or INDF2 are written to indirectly, the operation will be equivalent to a NOP instruction and the Status bits are not affected.

4.12.1 INDIRECT ADDRESSING OPERATION

Each FSR register has an INDF register associated with it, plus four additional register addresses. Performing an operation on one of these five registers determines how the FSR will be modified during indirect addressing.

- When data access is done to one of the five INDFn locations, the address selected will configure the FSRn register to:
 - Do nothing to FSRn after an indirect access (no change) INDFn
 - Auto-decrement FSRn after an indirect access (post-decrement) – POSTDECn
 - Auto-increment FSRn after an indirect access (post-increment) – POSTINCn
 - Auto-increment FSRn before an indirect access (pre-increment) PREINCn
 - Use the value in the WREG register as an offset to FSRn. Do not modify the value of the WREG or the FSRn register after an indirect access (no change) – PLUSWn

When using the auto-increment or auto-decrement features, the effect on the FSR is not reflected in the Status register. For example, if the indirect address causes the FSR to equal '0', the Z bit will not be set.

Incrementing or decrementing an FSR affects all 12 bits. That is, when FSRnL overflows from an increment, FSRnH will be incremented automatically.

Adding these features allows the FSRn to be used as a software stack pointer in addition to its uses for table operations in data memory.


Each FSR has an address associated with it that performs an indexed indirect access. When a data access to this INDFn location (PLUSWn) occurs, the FSRn is configured to add the 2's complement value in the WREG register and the value in FSR to form the address before an indirect access. The FSR value is not changed.

If an FSR register contains a value that indicates one of the INDFn, an indirect read will read 00h (zero bit is set), while an indirect write will be equivalent to a NOP (Status bits are not affected).

If an indirect addressing operation is done where the target address is an FSRnH or FSRnL register, the write operation will dominate over the pre- or post-increment/decrement functions.

^{© 2006} Microchip Technology Inc.

FIGURE 4-8: INDIRECT ADDRESSING



DS41159E-page 56

4.13 Status Register

The Status register, shown in Register 4-2, contains the arithmetic status of the ALU. The Status register can be the destination for any instruction, as with any other register. If the Status register is the destination for an instruction that affects the Z, DC, C, OV or N bits, then the write to these five bits is disabled. These bits are set or cleared according to the device logic. Therefore, the result of an instruction with the Status register as destination may be different than intended.

For example, CLRF STATUS will clear the upper three bits and set the Z bit. This leaves the Status register as 000u uluu (where u = unchanged).

It is recommended, therefore, that only BCF, BSF, SWAPF, MOVFF and MOVWF instructions are used to alter the Status register, because these instructions do not affect the Z, C, DC, OV or N bits from the Status register. For other instructions which do not affect the status bits, see Table 25-2.

Note:	The C and DC bits operate as a Borrow	N
	and Digit Borrow bit respectively, in	n
	subtraction.	

REGISTER 4-2: STATUS REGISTER

U-0	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
—	—	—	Ν	OV	Z	DC	С
bit 7							bit 0

- bit 7-5 Unimplemented: Read as '0'
- bit 4 N: Negative bit

This bit is used for signed arithmetic (2's complement). It indicates whether the result of the ALU operation was negative (ALU MSb = 1).

- 1 = Result was negative
- 0 = Result was positive
- bit 3 OV: Overflow bit

This bit is used for signed arithmetic (2's complement). It indicates an overflow of the 7-bit magnitude which causes the sign bit (bit 7) to change state.

- 1 = Overflow occurred for signed arithmetic (in this arithmetic operation)
- 0 = No overflow occurred
- bit 2 Z: Zero bit
 - 1 = The result of an arithmetic or logic operation is zero
 - 0 = The result of an arithmetic or logic operation is not zero
- bit 1 DC: Digit Carry/Borrow bit
 - For ADDWF, ADDLW, SUBLW and SUBWF instructions:
 - 1 = A carry-out from the 4th low-order bit of the result occurred
 - 0 = No carry-out from the 4th low-order bit of the result
 - **Note:** For Borrow, the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRCF, RRNCF, RLCF and RLNCF) instructions, this bit is loaded with either bit 4 or bit 3 of the source register.

bit 0 C: Carry/Borrow bit

For ADDWF, ADDLW, SUBLW and SUBWF instructions:

- 1 = A carry-out from the Most Significant bit of the result occurred
- 0 = No carry-out from the Most Significant bit of the result occurred
- **Note:** For Borrow, the polarity is reversed. A subtraction is executed by adding the 2's complement of the second operand. For rotate (RRF, RLF) instructions, this bit is loaded with either the high or low-order bit of the source register.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

© 2006 Microchip Technology Inc.

4.14 RCON Register

The Reset Control (RCON) register contains flag bits that allow differentiation between the sources of a device Reset. These flags include the TO, PD, POR, BOR and RI bits. This register is readable and writable.

- Note 1: If the BOREN configuration bit is set, BOR is '1' on Power-on Reset. If the BOREN configuration bit is clear, BOR is unknown on Power-on Reset. The BOR status bit is a "don't care" and is not necessarily predictable if the brownout circuit is disabled (the BOREN configuration bit is clear). BOR must then be set by the user and checked on subsequent Resets to see if it is clear, indicating a brown-out has occurred.
 2: It is recommended that the POR bit be set after a Power-on Reset has been
 - after a Power-on Reset has been detected, so that subsequent Power-on Resets may be detected.

REGISTER 4-3:	RCON: RESET	CONTROL REGISTER

_	R/W-0	U-0	U-0	R/W-1	R/W	R/W	R/W-0	R/W-0	
	IPEN	_	_	RI	TO	PD	POR	BOR	
-	bit 7							bit 0	

bit 7	IPEN: Interrupt Priority Enable bit								
	1 = Enable priority levels or	n interrupts							
	0 = Disable priority levels o	n interrupts (PIC16C)	XX Compatibility mod	le)					
bit 6-5	Unimplemented: Read as	'0'							
bit 4	RI: RESET Instruction Flag	bit							
		= The RESET instruction was not executed							
		 The RESET instruction was executed causing a device Reset (must be set in software after a Brown-out Reset occurs) 							
bit 3	TO: Watchdog Time-out Flag bit								
	1 = After power-up, CLRWD		instruction						
	0 = A WDT time-out occurr	ed							
bit 2	PD: Power-down Detection	Flag bit							
	1 = After power-up or by the								
	0 = By execution of the SLE								
bit 1	POR: Power-on Reset Stat								
	1 = A Power-on Reset has		<i></i>	–					
	0 = A Power-on Reset occu	-	oftware after a Power	-on Reset occurs)					
bit 0	BOR: Brown-out Reset Sta								
	1 = A Brown-out Reset has		<i>"</i>						
	0 = A Brown-out Reset occ	urred (must be set in a	software after a Brown	1-OUT Reset occurs)					
	Legend:								
	R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'					
	-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown					

DS41159E-page 58

5.0 DATA EEPROM MEMORY

The data EEPROM is readable and writable during normal operation over the entire VDD range. The data memory is not directly mapped in the register file space. Instead, it is indirectly addressed through the Special Function Registers (SFR).

There are four SFRs used to read and write the program and data EEPROM memory. These registers are:

- EECON1
- EECON2
- EEDATA
- EEADR

The EEPROM data memory allows byte read and write. When interfacing to the data memory block, EEDATA holds the 8-bit data for read/write and EEADR holds the address of the EEPROM location being accessed. The PIC18FXX8 devices have 256 bytes of data EEPROM with an address range from 00h to FFh.

The EEPROM data memory is rated for high erase/ write cycles. A byte write automatically erases the location and writes the new data (erase-before-write). The write time is controlled by an on-chip timer. The write time will vary with voltage and temperature, as well as from chip-to-chip. Please refer to the specifications for exact limits.

5.1 EEADR Register

The address register can address up to a maximum of 256 bytes of data EEPROM.

5.2 EECON1 and EECON2 Registers

EECON1 is the control register for EEPROM memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the EEPROM write sequence.

Control bits, $\overline{\text{RD}}$ and $\overline{\text{WR}}$, initiate read and write operations, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at the completion of the read or write operation. The inability to clear the $\overline{\text{WR}}$ bit in software prevents the accidental or premature termination of a write operation.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a $\overline{\text{MCLR}}$ Reset, or a WDT Time-out Reset, during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR) due to the Reset condition forcing the contents of the registers to zero.

Note: Interrupt flag bit, EEIF in the PIR2 register, is set when write is complete. It must be cleared in software.

^{© 2006} Microchip Technology Inc.

TER 5-1:	EECON1:	EEPROM	CONTROL	. REGISTE	R 1			
	R/W-x	R/W-x	U-0	R/W-0	R/W-x	R/W-0	R/S-0	R/S-0
	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD
	bit 7							bit 0
bit 7	EEPGD: F	lash Prograr	n or Data E	EPROM Me	mory Select	bit		
		s program Fla s data EEPR						
bit 6	CFGS: Fla	sh Program/	Data EE or	Configuration	on Select bit			
		s Configurati s program Fla			nemory			
bit 5	Unimplem	ented: Read	d as '0'					
bit 4	FREE: Fla	sh Row Eras	se Enable bi	t				
	(reset l	the program by hardware m write only	-	w addressed	by TBLPTR	on the next	WR comm	and
bit 3		Nrite Error F	lag bit					
	 1 = A write operation is prematurely terminated (any MCLR or any WDT Reset during self-timed programming in normal operation) 0 = The write operation completed 							tion)
	Note: When a WRERR occurs, the EEPGD or FREE bits are not cleared. This allows tracing of the error condition.							
bit 2		rite Enable b write cycles	it					
	0 = Inhibits	s write to the	EEPROM o	or Flash mei	nory			
bit 1		Control bit						
	 1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cy (The operation is self-timed and the bit is cleared by hardware once write is complete. WR bit can only be set (not cleared) in software.) 							
	0 = Write c	ycle is comp	olete					
bit 0		Control bit						
	 1 = Initiates an EEPROM read (Read takes one cycle. RD is cleared in hardware. The RD bit can only be set (not clear in software. RD bit cannot be set when EEPGD = 1.) 							not cleared)
	0 = Does r	not initiate an	EEPROM	read				
	Legend:]
	B = Beada	hle hit W	– Writable k	bit $S = Se$	ttable bit	U = Unimp	lemented bit	t read as '0'

Legend:			
R = Readable bit	W = Writable bit	S = Settable bit	U = Unimplemented bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

REGISTER 5-1: EECON1: EEPROM CONTROL REGISTER 1

5.3 Reading the Data EEPROM Memory

To read a data memory location, the user must write the address to the EEADR register, clear the EEPGD and CFGS control bits (EECON1<7:6>) and then set control bit \overline{RD} (EECON1<0>). The data is available in the very next instruction cycle of the EEDATA register; therefore, it can be read by the next instruction. EEDATA will hold this value until another read operation or until it is written to by the user (during a write operation).

EXAMPLE 5-1:	DATA EEPROM READ
$\Box \land \exists \Box \cup \cup \Box$	

MOVLW MOVWF	DATA_EE EEADR	_ADDR	; ;Data Memory Address
			;to read
BCF	EECON1,	EEPGD	;Point to DATA memory
BCS	EECON1,	CFGS	;
BSF	EECON1,	RD	;EEPROM Read
MOVF	EEDATA,	W	;W = EEDATA

5.4 Writing to the Data EEPROM Memory

To write an EEPROM data location, the address must first be written to the EEADR register and the data written to the EEDATA register. Then, the sequence in Example 5-2 must be followed to initiate the write cycle.

The write will not initiate if the above sequence is not exactly followed (write 55h to EECON2, write 0AAh to EECON2, then set \overline{WR} bit) for each byte. It is strongly recommended that interrupts be disabled during this code segment.

Additionally, the WREN bit in EECON1 must be set to enable writes. This mechanism prevents accidental writes to data EEPROM due to unexpected code execution (i.e., runaway programs). The WREN bit should be kept clear at all times, except when updating the EEPROM. The WREN bit is not cleared by hardware.

After a write sequence has been initiated, clearing the WREN bit will not affect the current write cycle. The WR bit will be inhibited from being set unless the WREN bit is set. The WREN bit must be set on a previous instruction. Both WR and WREN cannot be set with the same instruction.

At the completion of the write cycle, the WR bit is cleared in hardware and the EEPROM Write Complete Interrupt Flag bit (EEIF) is set. The user may either enable this interrupt or roll this bit. EEIF must be cleared by software.

		DATA_EE_DATA EEDATA EECON1, EEPGD EECON1, CFGS EECON1, WREN	; Data Memory Value to write ; Point to DATA memory ; Access program FLASH or Data EEPROM memory ; Enable writes
Required Sequence	BCF MOVLW MOVWF MOVLW	INTCON, GIE 55h EECON2 0AAh	; Disable interrupts ; ; Write 55h ;
	MOVWF BSF BSF	EECON2 EECON1, WR	
			; user code execution
	• BCF	EECON1, WREN	; Disable writes on write complete (EEIF set)

EXAMPLE 5-2: DATA EEPROM WRITE

© 2006 Microchip Technology Inc.

5.5 Write Verify

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

Generally, a write failure will be a bit which was written as a '1', but reads back as a '0' (due to leakage off the cell).

5.6 Protection Against Spurious Write

There are conditions when the device may not want to write to the data EEPROM memory. To protect against spurious EEPROM writes, various mechanisms have been built-in. On power-up, the WREN bit is cleared. Also, the Power-up Timer (72 ms duration) prevents EEPROM write.

The write initiate sequence and the WREN bit together reduce the probability of an accidental write during brown-out, power glitch or software malfunction.

5.7 Operation During Code-Protect

Data EEPROM memory has its own code-protect mechanism. External read and write operations are disabled if either of these mechanisms are enabled.

The microcontroller itself can both read and write to the internal data EEPROM, regardless of the state of the code-protect configuration bit. Refer to **Section 24.0 "Special Features of the CPU"** for additional information.

5.8 Using the Data EEPROM

The data EEPROM is a high-endurance, byte addressable array that has been optimized for the storage of frequently changing information (e.g., program variables or other data that are updated often). Frequently changing values will typically be updated more often than specification D124 or D124A. If this is not the case, an array refresh must be performed. For this reason, variables that change infrequently (such as constants, IDs, calibration, etc.) should be stored in Flash program memory. A simple data EEPROM refresh routine is shown in Example 5-3.

Note: If data EEPROM is only used to store constants and/or data that changes rarely, an array refresh is likely not required. See specification D124 or D124A.

Loop	CLRF BCF BCF BSF BSF MOVLW	EEADR EECON1, CFGS EECON1, EEPGD INTCON, GIE EECON1, WREN EECON1, RD 55h	<pre>; Start at address 0 ; Set for memory ; Set for Data EEPROM ; Disable interrupts ; Enable writes ; Loop to refresh array ; Read current address ;</pre>
	MOVWF	EECON2	; Write 55h
	MOVLW	0AAh	i
	MOVWF	EECON2	; Write AAh
	BSF	EECON1, WR	; Set WR bit to begin write
	BTFSC	EECON1, WR	; Wait for write to complete
	BRA	\$-2	
	INCFSZ	EEADR, F	; Increment address
	BRA	Loop	; Not zero, do it again
	BCF	EECON1, WREN	; Disable writes
	BSF	INTCON, GIE	; Enable interrupts

EXAMPLE 5-3: DATA EEPROM REFRESH ROUTINE

DS41159E-page 62

TABLE 5-1: REGISTERS ASSOCIATED WITH DATA EEPROM MEMORY

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
EEADR	EEPROM Address Register								xxxx xxxx	uuuu uuuu
EEDATA	EEPROM Data Register								xxxx xxxx	uuuu uuuu
EECON2	EEPROM Control Register 2 (not a physical register) -								_	—
EECON1	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	xx-0 x000	uu-0 u000
IPR2	_	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP ⁽¹⁾	-1-1 1111	-1-1 1111
PIR2	—	CMIF	—	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF ⁽¹⁾	-0-0 0000	-0-0 0000
PIE2	_	CMIE	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE ⁽¹⁾	-0-0 0000	-0-0 0000

 $\label{eq:legend: Legend: Legend: u = unknown, u = unknown, r = reserved, - = unimplemented, read as `0'.$

Shaded cells are not used during Flash/EEPROM access.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 64

6.0 FLASH PROGRAM MEMORY

The Flash program memory is readable, writable and erasable during normal operation over the entire VDD range.

A read from program memory is executed on one byte at a time. A write to program memory is executed on blocks of 8 bytes at a time. Program memory is erased in blocks of 64 bytes at a time. A bulk erase operation may not be issued from user code.

Writing or erasing program memory will cease instruction fetches until the operation is complete. The program memory cannot be accessed during the write or erase, therefore, code cannot execute. An internal programming timer terminates program memory writes and erases.

A value written to program memory does not need to be a valid instruction. Executing a program memory location that forms an invalid instruction results in a NOP.

6.1 **Table Reads and Table Writes**

In order to read and write program memory, there are two operations that allow the processor to move bytes between the program memory space and the data RAM:

- Table Read (TBLRD)
- Table Write (TBLWT)

The program memory space is 16 bits wide, while the data RAM space is 8 bits wide. Table reads and table writes move data between these two memory spaces through an 8-bit register (TABLAT).

Table read operations retrieve data from program memory and place it into the data RAM space. Figure 6-1 shows the operation of a table read with program memory and data RAM.

Table write operations store data from the data memory space into holding registers in program memory. The procedure to write the contents of the holding registers into program memory is detailed in Section 6.5 "Writing to Flash Program Memory". Figure 6-2 shows the operation of a table write with program memory and data RAM.


Table operations work with byte entities. A table block containing data, rather than program instructions, is not required to be word aligned. Therefore, a table block can start and end at any byte address. If a table write is being used to write executable code into program memory, program instructions will need to be word aligned.

Instruction: TBLRD* Program Memory Table Pointer⁽¹⁾ Table Latch (8-bit) TBLPTRH TBLPTRU TBLPTRL TABLAT Program Memory (TBLPTR) Note 1: Table Pointer points to a byte in program memory.

FIGURE 6-1: TABLE READ OPERATION

^{© 2006} Microchip Technology Inc.





6.2 Control Registers

Several control registers are used in conjunction with the TBLRD and TBLWT instructions. These include the:

- EECON1 register
- EECON2 register
- TABLAT register
- TBLPTR registers

6.2.1 EECON1 AND EECON2 REGISTERS

EECON1 is the control register for memory accesses.

EECON2 is not a physical register. Reading EECON2 will read all '0's. The EECON2 register is used exclusively in the memory write and erase sequences.

Control bit EEPGD determines if the access will be a program or data EEPROM memory access. When clear, any subsequent operations will operate on the data EEPROM memory. When set, any subsequent operations will operate on the program memory.

Control bit CFGS determines if the access will be to the Configuration/Calibration registers or to program memory/data EEPROM memory. When set, subsequent operations will operate on Configuration registers regardless of EEPGD (see Section 24.0 "Special Features of the CPU"). When clear, memory selection access is determined by EEPGD. The FREE bit, when set, will allow a program memory erase operation. When the FREE bit is set, the erase operation is initiated on the next WR command. When FREE is clear, only writes are enabled.

The WREN bit, when set, will allow a write operation. On power-up, the WREN bit is clear. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, the user can check the WRERR bit and rewrite the location. It is necessary to reload the data and address registers (EEDATA and EEADR) due to Reset values of zero.

Control bits, $\overline{\text{RD}}$ and $\overline{\text{WR}}$, initiate read and write operations, respectively. These bits cannot be cleared, only set, in software. They are cleared in hardware at the completion of the read or write operation. The inability to clear the $\overline{\text{WR}}$ bit in software prevents the accidental or premature termination of a write operation. The $\overline{\text{RD}}$ bit cannot be set when accessing program memory (EEPGD = 1).

DS41159E-page 66

Note: Interrupt flag bit, EEIF in the PIR2 register, is set when write is complete. It must be cleared in software.

REGISTER 6-1:	EECON1: EEPROM CONTROL REGISTER 1								
	R/W-x	R/W-x	U-0	R/W-0	R/W-x	R/W-0	R/S-0	R/S-0	
	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	
	bit 7							bit 0	
bit 7				EPROM Me	mory Select	bit			
		program Fla data EEPR							
bit 6	CFGS: Flas	sh Program/	Data EE or	Configuratio	n Select bit				
		Configuration program Fla		EEPROM m	emory				
bit 5	Unimplem	ented: Read	d as '0'						
bit 4		sh Row Eras							
		d by comple		v addressed e operation)	by TBLPTR	l on the nex	t WR comm	and	
bit 3	WRERR: Write Error Flag bit								
	 1 = A write operation is prematurely terminated (any MCLR or any WDT Reset during self-timed programming in normal operation 0 = The write operation completed 					lion)			
	Note: When a WRERR occurs, the EEPGD and CFGS bits are not cleared. This allows tracing of the error condition.						his allows		
bit 2	WREN: Wr	ite Enable b	it						
	1 = Allows write cycles0 = Inhibits write to the EEPROM or Flash memory								
bit 1	WR: Write								
	 1 = Initiates a data EEPROM erase/write cycle or a program memory erase cycle or write cycle (The operation is self-timed and the bit is cleared by hardware once write is complete. The WR bit can only be set (not cleared) in software.) 0 = Write cycle to the EEPROM is complete 								
bit 0	RD: Read Control bit								
 1 = Initiates an EEPROM read (Read takes one cycle. RD is cleared in hardware. The RD bit can only be set (r in software. RD bit cannot be set when EEPGD = 1.) 0 = Does not initiate an EEPROM read 				not cleared)					
	Legend:								

Legend:			
R = Readable bit	W = Writable bit	S = Settable bit	U = Unimplemented bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

^{© 2006} Microchip Technology Inc.

6.2.2 TABLAT – TABLE LATCH REGISTER

The Table Latch (TABLAT) is an 8-bit register mapped into the SFR space. The Table Latch is used to hold 8-bit data during data transfers between program memory and data RAM.

6.2.3 TBLPTR – TABLE POINTER REGISTER

The Table Pointer (TBLPTR) addresses a byte within the program memory. The TBLPTR is comprised of three SFR registers: Table Pointer Upper Byte, Table Pointer High Byte and Table Pointer Low Byte (TBLPTRU:TBLPTRH:TBLPTRL). These three registers join to form a 22-bit wide pointer. The low-order 21 bits allow the device to address up to 2 Mbytes of program memory space. The 22nd bit allows access to the device ID, the user ID and the configuration bits.

The Table Pointer, TBLPTR, is used by the TBLRD and TBLWT instructions. These instructions can update the TBLPTR in one of four ways based on the table operation. These operations are shown in Table 6-1. These operations on the TBLPTR only affect the low-order 21 bits.

6.2.4 TABLE POINTER BOUNDARIES

TBLPTR is used in reads, writes and erases of the Flash program memory.

When a TBLRD is executed, all 22 bits of the Table Pointer determine which byte is read from program memory into TABLAT.

When a TBLWT is executed, the three LSbs of the Table Pointer (TBLPTR<2:0>) determine which of the eight program memory holding registers is written to. When the timed write to program memory (long write) begins, the 19 MSbs of the Table Pointer, TBLPTR (TBLPTR<21:3>), will determine which program memory block of 8 bytes is written to. For more detail, see **Section 6.5 "Writing to Flash Program Memory"**.


When an erase of program memory is executed, the 16 MSbs of the Table Pointer (TBLPTR<21:6>) point to the 64-byte block that will be erased. The Least Significant bits (TBLPTR<5:0>) are ignored.

Figure 6-3 describes the relevant boundaries of TBLPTR based on Flash program memory operations.

TABLE 6-1:	TABLE POINTER OPERATIONS WITH TBLRD AND TBLWT INSTRUCTIONS
IADLE V-I.	

Example	Operation on Table Pointer
TBLRD* TBLWT*	TBLPTR is not modified
TBLRD*+ TBLWT*+	TBLPTR is incremented after the read/write
TBLRD*- TBLWT*-	TBLPTR is decremented after the read/write
TBLRD+* TBLWT+*	TBLPTR is incremented before the read/write

FIGURE 6-3: TABLE POINTER BOUNDARIES BASED ON OPERATION



DS41159E-page 68


6.3 Reading the Flash Program Memory

The TBLRD instruction is used to retrieve data from program memory and places it into data RAM. Table reads from program memory are performed one byte at a time.

TBLPTR points to a byte address in program space. Executing TBLRD places the byte pointed to into TABLAT. In addition, TBLPTR can be modified automatically for the next table read operation.

The internal program memory is typically organized by words. The Least Significant bit of the address selects between the high and low bytes of the word. Figure 6-4 shows the interface between the internal program memory and the TABLAT.

FIGURE 6-4: READS FROM FLASH PROGRAM MEMORY



EXAMPLE 6-1: READING A FLASH PROGRAM MEMORY WORD

	MOVLW MOVWF MOVLW MOVLW MOVLW	CODE_ADDR_UPPER TBLPTRU CODE_ADDR_HIGH TBLPTRH CODE_ADDR_LOW TBLPTRL		Load TBLPTR with the base address of the word
READ_WORD				• • • • • • •
	TBLRD*	+	;	read into TABLAT and increment
	MOVF	TABLAT, W	;	get data
	MOVWF	WORD_LSB		
	TBLRD*	+	;	read into TABLAT and increment
	MOVF	TABLAT, W	;	get data
	MOVWF	WORD MSB		
		—		

^{© 2006} Microchip Technology Inc.

6.4 Erasing Flash Program Memory

The minimum erase block is 32 words or 64 bytes. Only through the use of an external programmer, or through ICSP control, can larger blocks of program memory be bulk erased. Word erase in the Flash array is not supported.

When initiating an erase sequence from the microcontroller itself, a block of 64 bytes of program memory is erased. The Most Significant 16 bits of the TBLPTR<21:6> point to the block being erased. TBLPTR<5:0> are ignored.

The EECON1 register commands the erase operation. The EEPGD bit must be set to point to the Flash program memory. The WREN bit must be set to enable write operations. The FREE bit is set to select an erase operation.

For protection, the write initiate sequence for EECON2 must be used.

A long write is necessary for erasing the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

6.4.1 FLASH PROGRAM MEMORY ERASE SEQUENCE

The sequence of events for erasing a block of internal program memory location is:

- 1. Load Table Pointer with address of row being erased.
- 2. Set the EECON1 register for the erase operation:
 - set the EEPGD bit to point to program memory;
 - clear the CFGS bit to access program memory;
 - set the WREN bit to enable writes;
 - set the FREE bit to enable the erase.
- 3. Disable interrupts.
- 4. Write 55h to EECON2.
- 5. Write 0AAh to EECON2.
- 6. Set the WR bit. This will begin the row erase cycle.
- 7. The CPU will stall for duration of the erase (about 2 ms using internal timer).
- 8. Re-enable interrupts.

ERASE_ROW	MOVLW MOVWF MOVLW MOVWF MOVLW MOVWF	upper (CODE_ADDR) TBLPTRU high (CODE_ADDR) TBLPTRH low (CODE_ADDR) TBLPTRL	; load TBLPTR with the base ; address of the memory block
	BSF BCF BSF BSF BCF	EECON1, EEPGD EECON1, CFGS EECON1, WREN EECON1, FREE INTCON, GIE	; point to FLASH program memory ; access FLASH program memory ; enable write to memory ; enable Row Erase operation ; disable interrupts
Required Sequence	MOVLW MOVWF MOVLW MOVWF BSF NOP	55h EECON2 0AAh EECON2 EECON1, WR	; write 55H ; write 0AAH ; start erase (CPU stall) ; NOP needed for proper code execution
	BSF	INTCON, GIE	; re-enable interrupts

EXAMPLE 6-2: ERASING A FLASH PROGRAM MEMORY ROW

6.5 Writing to Flash Program Memory

The minimum programming block is 4 words or 8 bytes. Word or byte programming is not supported.

Table writes are used internally to load the holding registers needed to program the Flash memory. There are 8 holding registers used by the table writes for programming.

Since the Table Latch (TABLAT) is only a single byte, the TBLWT instruction has to be executed 8 times for each programming operation. All of the table write operations will essentially be short writes, because only the holding registers are written. At the end of updating 8 registers, the EECON1 register must be written to, to start the programming operation with a long write.

The long write is necessary for programming the internal Flash. Instruction execution is halted while in a long write cycle. The long write will be terminated by the internal programming timer.

The EEPROM on-chip timer controls the write time. The write/erase voltages are generated by an on-chip charge pump rated to operate over the voltage range of the device for byte or word operations.

6.5.1 FLASH PROGRAM MEMORY WRITE SEQUENCE

The sequence of events for programming an internal program memory location should be:


- 1. Read 64 bytes into RAM.
- 2. Update data values in RAM as necessary.
- 3. Load Table Pointer with address being erased.
- 4. Do the row erase procedure.
- 5. Load Table Pointer with address of first byte being written.
- 6. Write the first 8 bytes into the holding registers using the TBLWT instruction, auto-increment may be used.
- 7. Set the EECON1 register for the write operation:
 - set the EEPGD bit to point to program memory;
 - · clear the CFGS bit to access program memory;
 - set the WREN to enable byte writes.
- 8. Disable interrupts.
- 9. Write 55h to EECON2.
- 10. Write AAh to EECON2.
- 11. Set the \overline{WR} bit. This will begin the write cycle.
- 12. The CPU will stall for duration of the write (about 2 ms using internal timer).
- 13. Re-enable interrupts.
- 14. Repeat steps 6-14 seven times to write 64 bytes.
- 15. Verify the memory (table read).

This procedure will require about 18 ms to update one row of 64 bytes of memory. An example of the required code is given in Example 6-3.

Note: Before setting the WR bit, the Table Pointer address needs to be within the intended address range of the 8 bytes in the holding registers.

FIGURE 6-5:

TABLE WRITES TO FLASH PROGRAM MEMORY



© 2006 Microchip Technology Inc.

EXAMPLE 6-3: WRITING TO FLASH PROGRAM MEMORY

EXAMPLE 6-3:	WRI	TING TO FLASH PROG	
	MOVLW	D'64	; number of bytes in erase block
	MOVWF	COUNTER	
	MOVLW	high (BUFFER_ADDR)	; point to buffer
	MOVWF	FSROH	
	MOVLW	low (BUFFER_ADDR)	
	MOVWF	FSROL	
	MOVLW	upper (CODE_ADDR)	; Load TBLPTR with the base
	MOVWF	TBLPTRU	; address of the memory block
	MOVLW MOVWF	high (CODE_ADDR) TBLPTRH	
	MOVLW	low (CODE ADDR)	
	MOVWF	TBLPTRL	
READ BLOCK			
	TBLRD*+		; read into TABLAT, and inc
	MOVF	TABLAT, W	; get data
	MOVWF		; store data
		COUNTER	; done?
MODIEV MODE	BRA	READ_BLOCK	; repeat
MODIFY_WORD	MOVLW	DATA ADDR HIGH	; point to buffer
	MOVUW	FSR0H	, point to builter
	MOVWP	DATA ADDR LOW	
	MOVWF	FSROL	
	MOVLW	NEW DATA LOW	; update buffer word
	MOVWF	POSTINCO	
	MOVLW	NEW_DATA_HIGH	
	MOVWF	INDFO	
ERASE_BLOCK			
	MOVLW MOVWF	upper (CODE_ADDR) TBLPTRU	; load TBLPTR with the base
	MOVWF MOVLW	high (CODE_ADDR)	; address of the memory block
	MOVWF	TBLPTRH	
	MOVLW	low (CODE ADDR)	
	MOVWF	 TBLPTRL	
	BSF	EECON1, EEPGD	; point to FLASH program memory
	BCF	EECON1, CFGS	; access FLASH program memory
	BSF	EECON1, WREN	; enable write to memory
	BSF	EECON1, FREE	; enable Row Erase operation
	BCF	INTCON, GIE	; disable interrupts
Required	MOVLW MOVWF	55h EECON2	; write 55H
Sequence	MOVLW	0AAh	, write son
bequence	MOVWF	EECON2	; write AAH
	BSF	EECON1, WR	; start erase (CPU stall)
	NOP		
	BSF	INTCON, GIE	; re-enable interrupts
	TBLRD*-		; dummy read decrement
WRITE_BUFFER_P		0	
	MOVLW	8 COUNTED III	; number of write buffer groups of 8 bytes
	MOVWF MOVLW	COUNTER_HI high (BUFFER ADDR)	; point to buffer
	MOVIN	FSROH	, point to barrer
	MOVLW	low (BUFFER ADDR)	
	MOVWF	FSROL	
PROGRAM_LOOP			
	MOVLW	8	; number of bytes in holding register
	MOVWF	COUNTER	
WRITE_WORD_TO	_		ach low hote of huffers late
	MOVFW	POSTINCO, W	; get low byte of buffer data
	MOVWF TBLWT+*	TABLAT	; present data to table latch ; write data, perform a short write
	* + 1 אחרפיד		; write data, perform a short write ; to internal TBLWT holding register.
	DECFSZ	COUNTER	; loop until buffers are full
	BRA	WRITE_WORD_TO_HREGS	-

WRITE_WORD_TO_	HREGS		
	MOVFW	POSTINCO, W	; get low byte of buffer data
	MOVWF	TABLAT	; present data to table latch
	TBLWT+*	•	; write data, perform a short write
			; to internal TBLWT holding register.
	DECFSZ	COUNTER	; loop until buffers are full
	BRA	WRITE_WORD_TO_HREGS	
PROGRAM_MEMORY			
	BSF	EECON1, EEPGD	; point to FLASH program memory
	BCF	EECON1, CFGS	; access FLASH program memory
	BSF	EECON1, WREN	; enable write to memory
	BCF	INTCON, GIE	; disable interrupts
	MOVLW	55h	; write 55h
Required	MOVWF	EECON2	
Sequence	MOVLW	0AAh	; write OAAh
	MOVWF	EECON2	; start program (CPU stall)
	BSF	EECON1, WR	
	NOP		
	BSF	INTCON, GIE	; re-enable interrupts
	DECFSZ	COUNTER_HI	; loop until done
	BRA	PROGRAM_LOOP	
	BCF	EECON1, WREN	; disable write to memory

EXAMPLE 6-3: WRITING TO FLASH PROGRAM MEMORY (CONTINUED)

6.5.2 WRITE VERIFY

Depending on the application, good programming practice may dictate that the value written to the memory should be verified against the original value. This should be used in applications where excessive writes can stress bits near the specification limit.

6.5.3 UNEXPECTED TERMINATION OF WRITE OPERATION

If a write is terminated by an unplanned event, such as loss of power or an unexpected Reset, the memory location just programmed should be verified and reprogrammed if needed. The WRERR bit is set when a write operation is interrupted by a MCLR Reset or a WDT Time-out Reset during normal operation. In these situations, users can check the WRERR bit and rewrite the location.

6.5.4 PROTECTION AGAINST SPURIOUS WRITES

To reduce the probability against spurious writes to Flash program memory, the write initiate sequence must also be followed. See **Section 24.0** "**Special Features of the CPU**" for more detail.

6.6 Flash Program Operation During Code Protection

See **Section 24.0 "Special Features of the CPU"** for details on code protection of Flash program memory.

^{© 2006} Microchip Technology Inc.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on: POR, BOR	Value on all other Resets
TBLPTRU	—	—	bit 21	Program M (TBLPTR<	lemory Tabl 20:16>)	00 0000	00 0000			
TBPLTRH	RH Program Memory Table Pointer High Byte (TBLPTR<15:8>)							0000 0000	0000 0000	
TBLPTRL	Program Memory Table Pointer Low Byte (TBLPTR<7:0>)								0000 0000	0000 0000
TABLAT	Program N	lemory Tab	le Latch						0000 0000	0000 0000
INTCON	GIE/GIEH	PEIE/ GIEL	TMR0IE	INTE	RBIE	TMR0IF	INTF	RBIF	0000 000x	0000 000u
EECON2	EEPROM	Control Reg	gister 2 (no	t a physical	register)				_	_
EECON1	EEPGD	CFGS	_	FREE	WRERR	WREN	WR	RD	xx-0 x000	uu-0 u000
IPR2	_	CMIP	-	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP ⁽¹⁾	-1-1 1111	-1-1 1111
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF ⁽¹⁾	-0-0 0000	-0-0 0000
PIE2	_	CMIE		EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE ⁽¹⁾	-0-0 0000	-0-0 0000

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'.

Shaded cells are not used during Flash/EEPROM access.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

DS41159E-page 74

7.0 8 x 8 HARDWARE MULTIPLIER

7.1 Introduction

An 8 x 8 hardware multiplier is included in the ALU of the PIC18FXX8 devices. By making the multiply a hardware operation, it completes in a single instruction cycle. This is an unsigned multiply that gives a 16-bit result. The result is stored in the 16-bit product register pair (PRODH:PRODL). The multiplier does not affect any flags in the ALUSTA register.

Making the 8 x 8 multiplier execute in a single cycle gives the following advantages:

- Higher computational throughput
- Reduces code size requirements for multiply algorithms

The performance increase allows the device to be used in applications previously reserved for Digital Signal Processors.

Table 7-1 shows a performance comparison between Enhanced devices using the single-cycle hardware multiply and performing the same function without the hardware multiply.

7.2 Operation

Example 7-1 shows the sequence to do an 8×8 unsigned multiply. Only one instruction is required when one argument of the multiply is already loaded in the WREG register.

Example 7-2 shows the sequence to do an 8 x 8 signed multiply. To account for the sign bits of the arguments, each argument's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

EXAMPLE 7-1: 8 x 8 UNSIGNED MULTIPLY ROUTINE

MOVF	ARG1,	W	;				
MULWF	ARG2		;	ARG1	*	ARG2	->
			;	PRO	DDI	H:PROI	DL

EXAMPLE 7-2: 8 x 8 SIGNED MULTIPLY ROUTINE

ſ	MOVF	ARG1,	W		
	MULWF	ARG2		;	ARG1 * ARG2 ->
				;	PRODH: PRODL
	BTFSC	ARG2,	SB	;	Test Sign Bit
	SUBWF	PRODH		;	PRODH = PRODH
				;	- ARG1
	MOVF	ARG2,	W		
	BTFSC	ARG1,	SB	;	Test Sign Bit
	SUBWF	PRODH		;	PRODH = PRODH
				;	- ARG2

		Program	Cycles	Time			
Routine	Multiply Method	Memory (Words)	(Max)	@ 40 MHz	@ 10 MHz	@ 4 MHz	
9 x 9 unsigned	Without hardware multiply	13	69	6.9 μs	27.6 μs	69 µs	
8 x 8 unsigned	Hardware multiply	1	1	100 ns	400 ns	1 μs	
	Without hardware multiply	33	91	9.1 μs	36.4 μs	91 μs	
8 x 8 signed	Hardware multiply	6	6	600 ns	36.4 μs 2.4 μs	6 µs	
16 v 16 unsigned	Without hardware multiply	21	242	24.2 μs	96.8 µs	242 μs	
16 x 16 unsigned	Hardware multiply	24	24	2.4 μs	9.6 µs	24 μs	
16 x 16 signed	Without hardware multiply	52	254	25.4 μs	102.6 μs	254 μs	
16 x 16 signed	Hardware multiply	36	36	3.6 μs	27.6 μs 400 ns 36.4 μs 2.4 μs 96.8 μs 9.6 μs	36 µs	

TABLE 7-1: PERFORMANCE COMPARISON

© 2006 Microchip Technology Inc.

Example 7-3 shows the sequence to do a 16 x 16 unsigned multiply. Equation 7-1 shows the algorithm that is used. The 32-bit result is stored in four registers, RES3:RES0.

EQUATION 7-1: 16 x 16 UNSIGNED MULTIPLICATION ALGORITHM

RES3:RES0	=	ARG1H:ARG1L • ARG2H:ARG2L (ARG1H • ARG2H • 2^{16}) + (ARG1H • ARG2L • 2^{8}) + (ARG1L • ARG2H • 2^{8}) +
		$(ARG1L \bullet ARG2L)$

EXAMPLE 7-3: 16 x 16 UNSIGNED MULTIPLY ROUTINE

	MOVF	ARG1L,	W	
	MULWF	ARG2L		; ARG1L * ARG2L ->
				; PRODH:PRODL
	MOVFF	PRODH,	RES1	i
	MOVFF	PRODL,	RES0	i
;				
	MOVF	ARG1H,	W	
	MULWF	ARG2H		; ARG1H * ARG2H ->
				; PRODH:PRODL
	MOVFF	PRODH,	RES3	;
	MOVFF	PRODL,	RES2	;
;				
	MOVF	ARG1L,	W	
	MULWF	ARG2H		; ARG1L * ARG2H ->
				; PRODH:PRODL
	MOVF	PRODL,	W	;
	ADDWF	RES1		; Add cross
	MOVF	PRODH,	W	; products
	ADDWFC			i
	CLRF	WREG		;
	ADDWFC	RES3		;
;				
	MOVF	ARG1H,	W	i
	MULWF	ARG2L		; ARG1H * ARG2L ->
				; PRODH:PRODL
	MOVF	PRODL,	W	
	ADDWF			; Add cross
		PRODH,	W	; products
	ADDWFC			;
	CLRF			i
	ADDWFC	RES3		;

Example 7-4 shows the sequence to do a 16 x 16 signed multiply. Equation 7-2 shows the algorithm used. The 32-bit result is stored in four registers, RES3:RES0. To account for the sign bits of the arguments, each argument pair's Most Significant bit (MSb) is tested and the appropriate subtractions are done.

EQUATION 7-2: 16 x 16 SIGNED MULTIPLICATION ALGORITHM

RES3:RES0

=	ARG1H:ARG1L • ARG2H:ARG2L	
	1.6	

 $= (ARG1H \bullet ARG2H \bullet 2^{16}) + (ARG1H \bullet ARG2L \bullet 2^{8}) + (ARG1L \bullet ARG2H \bullet 2^{8}) + (ARG1L \bullet ARG2H) + (-1 \bullet ARG2H < 7 > \bullet ARG1H: ARG1L \bullet 2^{16}) + (-1 \bullet ARG1H < 7 > \bullet ARG2H: ARG2L \bullet 2^{16})$

EXAMPLE 7-4: 16 x 16 SIGNED MULTIPLY ROUTINE

MOVF	ARG1L, W	
MULWF	ARG2L	; ARG1L * ARG2L ->
		; PRODH:PRODL
MOVFF	PRODH, RES	31 ;
MOVFF	PRODL, RES	
;	,	,
	ARG1H, W	
MULWF	ARG2H	; ARG1H * ARG2H ->
MOLWF	AKGZH	
MOUTE		; PRODH:PRODL
MOVFF	PRODH, RES	
MOVFF	PRODL, RES	32 ;
;		
	ARG1L, W	
MULWF	ARG2H	; ARG1L * ARG2H ->
		; PRODH:PRODL
MOVF	PRODL, W	;
ADDWF	RES1	; Add cross
MOVF		; products
ADDWFC		;
CLRF	WREG	;
ADDWFC	RES3	i
;		
	ARG1H, W	;
	ARG2L	, ; ARG1H * ARG2L ->
HOLWI	AROZE	; PRODH:PRODL
MOVF		
	PRODL, W	;
ADDWF	RES1	; Add cross
MOVF		
ADDWFC		;
CLRF		;
ADDWFC	RES3	;
;		
BTFSS		; ARG2H:ARG2L neg?
BRA	SIGN_ARG1	; no, check ARG1
MOVF	ARG1L, W	;
SUBWF	RES2	;
MOVF	ARG1H, W	;
SUBWFB	RES3	
;		
SIGN ARG1		
BTFSS	ARG1H, 7	; ARG1H:ARG1L neg?
BRA		; no, done
MOVF	ARG2L, W	;
SUBWF		
MOVF	ARG2H, W	;
SUBWFB		;
SORML.B	KE93	
CONT_CODE		
:		

8.0 INTERRUPTS

The PIC18FXX8 devices have multiple interrupt sources and an interrupt priority feature that allows each interrupt source to be assigned a high priority level or a low priority level. The high priority interrupt vector is at 000008h and the low priority interrupt vector is at 000018h. High priority interrupt events will override any low priority interrupts that may be in progress.

There are 13 registers that are used to control interrupt operation. These registers are:

- RCON
- INTCON
- INTCON2
- INTCON3
- PIR1, PIR2, PIR3
- PIE1, PIE2, PIE3
- IPR1, IPR2, IPR3

It is recommended that the Microchip header files, supplied with MPLAB[®] IDE, be used for the symbolic bit names in these registers. This allows the assembler/ compiler to automatically take care of the placement of these bits within the specified register.

Each interrupt source has three bits to control its operation. The functions of these bits are:

- Flag bit to indicate that an interrupt event occurred
- Enable bit that allows program execution to branch to the interrupt vector address when the flag bit is set
- Priority bit to select high priority or low priority

The interrupt priority feature is enabled by setting the IPEN bit (RCON register). When interrupt priority is enabled, there are two bits that enable interrupts globally. Setting the GIEH bit (INTCON<7>) enables all interrupts. Setting the GIEL bit (INTCON register) enables all interrupts that have the priority bit cleared. When the interrupt flag, enable bit and appropriate global interrupt enable bit are set, the interrupt will vector immediately to address 000008h or 000018h, depending on the priority level. Individual interrupts can be disabled through their corresponding enable bits.

When the IPEN bit is cleared (default state), the interrupt priority feature is disabled and interrupts are compatible with PICmicro[®] mid-range devices. In Compatibility mode, the interrupt priority bits for each source have no effect. The PEIE bit (INTCON register) enables/disables all peripheral interrupt sources. The GIE bit (INTCON register) enables/disables all interrupt sources. All interrupts branch to address 000008h in Compatibility mode.

When an interrupt is responded to, the global interrupt enable bit is cleared to disable further interrupts. If the IPEN bit is cleared, this is the GIE bit. If interrupt priority levels are used, this will be either the GIEH or GIEL bit. High priority interrupt sources can interrupt a low priority interrupt.


The return address is pushed onto the stack and the PC is loaded with the interrupt vector address (000008h or 000018h). Once in the Interrupt Service Routine, the source(s) of the interrupt can be determined by polling the interrupt flag bits. The interrupt flag bits must be cleared in software before re-enabling interrupts to avoid recursive interrupts.

The "return from interrupt" instruction, RETFIE, exits the interrupt routine and sets the GIE bit (GIEH or GIEL if priority levels are used), which re-enables interrupts.

For external interrupt events, such as the INT pins or the PORTB input change interrupt, the interrupt latency will be three to four instruction cycles. The exact latency is the same for one or two-cycle instructions. Individual interrupt flag bits are set regardless of the status of their corresponding enable bit or the GIE bit.

Note: Do not use the MOVFF instruction to modify any of the interrupt control registers while **any** interrupt is enabled. Doing so may cause erratic microcontroller behavior.





8.1 INTCON Registers

The INTCON registers are readable and writable registers which contain various enable, priority and flag bits. Because of the number of interrupts to be controlled, PIC18FXX8 devices have three INTCON registers. They are detailed in Register 8-1 through Register 8-3.

Note: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows software polling.

REGISTER 8-1: INTCON: INTERRUPT CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-x
GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INTOIF	RBIF
bit 7							bit C
	Clobal Interru	unt Enchla k	.:+				
	Global Interru N (RCON<7>)	-	DIC				
	s all unmaske						
	es all interrupt						
When IPEN	<u> (RCON<7>)</u>	= 1:					
	s all high prio		ts				
	es all priority i	-					
PEIE/GIEL	: Peripheral Ir	nterrupt Ena	able bit				
	<u>N (RCON<7>)</u>						
	s all unmaske es all peripher						
	• •	•)				
	<u>N (RCON<7>)</u> s all low priori		al interrunts				
	es all low prior						
TMROIE: T	MR0 Overflov	v Interrupt E	Enable bit				
	s the TMR0 o	-					
0 = Disable	es the TMR0 o	overflow inte	errupt				
INTOIE: IN	T0 External In	nterrupt Ena	ble bit				
	s the INT0 ex						
	es the INT0 ex						
	Port Change I	-					
	s the RB port	0	•				
	es the RB port MR0 Overflov	U	•				
	register has o	-	-	arad in softw	vara)		
	register did no				varcj		
	T0 External In		bit				
1 = The IN	T0 external in	terrupt occu	irred (must	be cleared i	n software b	by reading P	ORTB)
0 = The IN	T0 external in	terrupt did r	not occur				
RBIF: RB I	Port Change I	nterrupt Fla	g bit				
	t one of the R	-	-	-	be cleared i	n software)	
0 = None c	of the RB7:RB	4 pins have	changed st	ate			
Note:	A mismatch					ig PORTB v	vill end th
	mismatch co	ndition and	allow the hi	t to he clear	ed.		

Legena:			
R = Readable bit	W = Writable bit	U = Unimplemented	l bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

© 2006 Microchip Technology Inc.

REGISTER 8-2:	INTCON2	INTCON2: INTERRUPT CONTROL REGISTER 2										
	R/W-1	R/W-1	R/W-1	U-0	U-0	R/W-1	U-0	R/W-1				
	RBPU	INTEDG0	INTEDG1	_	_	TMR0IP		RBIP				
	bit 7							bit 0				
bit 7		RBPU: PORTB Pull-up Enable bit										
		 All PORTB pull-ups are disabled PORTB pull-ups are enabled by individual port latch values 										
bit 6	INTEDG0:	ITEDG0: External Interrupt 0 Edge Select bit										
		ot on rising e	•									
	-	 Interrupt on falling edge INTEDG1: External Interrupt 1 Edge Select bit 										
bit 5		External Inte ot on rising e		e Select bit								
		ot on falling e	•									
bit 4-3	Unimplem	ented: Read	d as '0'									
bit 2	TMR0IP: T	MR0 Overflo	ow Interrupt	Priority bit								
	1 = High pi	,										
	0 = Low pr	,										
bit 1	Unimplem	ented: Read	d as '0'									
bit 0	RBIP: RB	Port Change	Interrupt Pr	iority bit								
	1 = High p	,										
	0 = Low priority											
	Legend:											
	R = Reada	ble bit	W = W	/ritable bit	U = Unin	nplemented	bit_read as '	0'				
	-n = Value			it is set		s cleared	x = Bit is u					

Note: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an interrupt. This feature allows software polling.

R 8-3:	INTCON3: INTERRUPT CONTROL REGISTER 3											
	R/W-1	R/W-1	U-0	R/W-0	R/W-0	U-0	R/W-0	R/W-0				
	INT2IP	INT1IP	—	INT2IE	INT1IE	—	INT2IF	INT1IF				
	bit 7 bit											
bit 7	INT2IP: IN	T2 External	Interrupt Pri	ority bit								
	1 = High pr 0 = Low pri	iority		,								
bit 6	INT1IP: IN	T1 External	Interrupt Pri	ority bit								
	1 = High pr 0 = Low pri	•										
bit 5	Unimplem	ented: Read	d as '0'									
bit 4	INT2IE: IN	T2 External	Interrupt En	able bit								
	 1 = Enables the INT2 external interrupt 0 = Disables the INT2 external interrupt 											
bit 3	INT1IE: INT1 External Interrupt Enable bit											
		s the INT1 e s the INT1 e										
bit 2	Unimplem	ented: Read	d as '0'									
bit 1	INT2IF: IN	T2 External I	Interrupt Fla	g bit								
		T2 external i T2 external i			be cleared i	n software)						
bit 0	INT1IF: IN	T1 External I	Interrupt Fla	g bit								
		T1 external i T1 external i			be cleared i	n software)						
	Legend:											
	R = Reada	ble bit	W = W	/ritable bit	U = Unim	nplemented	bit, read as	'0'				
	-n = Value			it is set		s cleared	x = Bit is u					

interrupt. This feature allows software polling

Interrupt flag bits are set when an interrupt condition occurs regardless of the state

of its corresponding enable bit or the global interrupt enable bit. User software should ensure the appropriate interrupt flag bits are clear prior to enabling an

REGISTER 8-3: INTCON3: INTERRUPT CONTROL REGISTER 3

© 2006 Microchip Technology Inc.

Note:

8.2 **PIR Registers**

The Peripheral Interrupt Request (PIR) registers contain the individual flag bits for the peripheral interrupts (Register 8-4 through Register 8-6). Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Request (Flag) registers (PIR1, PIR2, PIR3).

- Note 1: Interrupt flag bits are set when an interrupt condition occurs regardless of the state of its corresponding enable bit or the Global Interrupt Enable bit, GIE (INTCON register).
 - 2: User software should ensure the appropriate interrupt flag bits are cleared prior to enabling an interrupt and after servicing that interrupt.

REGISTER

ER 8-4:	PIR1: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 1												
	R/W-0	R/W-0	R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0					
	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF					
	bit 7							bit 0					
bit 7	PSPIF: Parallel Slave Port Read/Write Interrupt Flag bit ⁽¹⁾												
	 1 = A read or a write operation has taken place (must be cleared in software) 0 = No read or write has occurred 												
bit 6		ADIF : A/D Converter Interrupt Flag bit 1 = An A/D conversion completed (must be cleared in software)											
	0 = The A/D					vare)							
bit 5	RCIF: USAF		•	•	,								
	1 = The US 0 = The US		ve buffer, RC ve buffer is e		(cleared wr	ien RCREG	is read)						
bit 4	TXIF: USAF												
	1 = The US 0 = The US		nit buffer, TX nit buffer is f		pty (cleared	when TXRE	G is written)					
bit 3	SSPIF: Mas	-											
	1 = The trar 0 = Waiting			complete (m	ust be clear	ed in softwa	re)						
bit 2	CCP1IF: CC	CP1 Interru	pt Flag bit										
		register ca	apture occur capture occu		e cleared in	software)							
	<u>Compare m</u> 1 = A TMR1		mpare mate	b occurred	(must be cl	oared in coff	waro)						
			compare ma				wale)						
	<u>PWM mode</u> Unused in tl	_											
bit 1	TMR2IF: TN		2 Match Inte	rrupt Flag bi	t								
	1 = TMR2 to	PR2 mate		(must be cle		ware)							
bit 0			ow Interrupt	0									
	1 = TMR1 re 0 = TMR1 re	•	rflowed (mus not overflow		d in software	e)							
			only availabl nented and			es. For PIC1	8F2X8 devi	ces, this bit					

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

	U-0	RIPHERAL R/W-0	U-0	R/W-0	、 R/W-0	, R/W-0	R/W-0	R/W-0			
	_	CMIF ⁽¹⁾	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF ⁽¹⁾			
	bit 7							bit 0			
bit 7	Unimplen	nented: Rea	d as '0'								
bit 6	CMIF: Comparator Interrupt Flag bit ⁽¹⁾										
	 1 = Comparator input has changed 0 = Comparator input has not changed 										
bit 5	Unimplen	Unimplemented: Read as '0'									
bit 4	EEIF: EEF	PROM Write	Operation	Interrupt Fla	ıg bit						
	 1 = Write operation is complete (must be cleared in software) 0 = Write operation is not complete 										
bit 3	BCLIF: Bus Collision Interrupt Flag bit										
	 1 = A bus collision occurred (must be cleared in software) 0 = No bus collision occurred 										
bit 2	LVDIF: Low-Voltage Detect Interrupt Flag bit										
		voltage conc evice voltage		· ·		,					
bit 1	TMR3IF:	TMR3 Overfl	ow Interrup	t Flag bit							
		register ove register did			ed in softwa	re)					
bit 0	ECCP1IF:	ECCP1 Inte	rrupt Flag	bit ⁽¹⁾							
	<u>Capture mode:</u> 1 = A TMR1 (TMR3) register capture occurred (must be cleared in software) 0 = No TMR1 (TMR3) register capture occurred <u>Compare mode:</u> 1 = A TMR1 register compare match occurred (must be cleared in software)										
	0 = No TMR1 register compare match occurred										
	<u>PWM moo</u> Unused in	<u>this mode.</u>									
		This bit is									

Note 1: This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bit,	read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared x =	= Bit is unknown

ER 8-6: PIR3: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 3											
R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0				
IRXIF	WAKIF	ERRIF	TXB2IF	TXB1IF	TXB0IF	RXB1IF	RXB0IF				
bit 7							bit 0				
IRXIF: Invalid Message Received Interrupt Flag bit											
	1 = An invalid message has occurred on the CAN bus										
0 = An invalid message has not occurred on the CAN bus											
WAKIF: Bu	is Activity W	ake-up Inte	rrupt Flag bi	t							
-											
0 = Activity	on the CAN	I bus has no	ot occurred								
ERRIF: CA	N bus Error	Interrupt Fl	ag bit								
				•	irces)						
0 = An erro	or has not oc	curred in the	e CAN modu	lle							
TXB2IF: Tr											
1 = Transmit Buffer 2 has completed transmission of a message and may be reloaded											
0 = Transm	hit Buffer 2 h	as not comp	pleted transr	nission of a	message						
TXB1IF: Tr	ansmit Buff	er 1 Interrup	t Flag bit								
						nay be reloa	ded				
0 = Transm	hit Buffer 1 h	as not comp	pleted transr	nission of a	message						
TXB0IF: Tr	ansmit Buff	er 0 Interrup	t Flag bit								
		•			•	nay be reloa	ded				
0 = Transmit Buffer 0 has not completed transmission of a message											
RXB1IF: R	eceive Buffe	er 1 Interrup	t Flag bit								
				0							
0 = Receiv	ve Buffer 1 h	as not recei	ved a new n	nessage							
RXB0IF: R	eceive Buffe	er 0 Interrup	t Flag bit								
0 = Receive	e Buffer 0 ha	as not receiv	/ed a new m	essage							
-											
Legend:											
	R/W-0 IRXIF bit 7 IRXIF: Inva 1 = An inva 0 = An inva WAKIF: Bu 1 = Activity 0 = Activity ERRIF: CA 1 = An error 0 = An error 0 = An error TXB2IF: Tr 1 = Transm 0 = Transm TXB1IF: Tr 1 = Transm 0 = Transm 0 = Transm 0 = Transm 1 = Transm 0 = Transm	R/W-0R/W-0IRXIFWAKIFbit 7IRXIF: Invalid Message1 = An invalid message0 = An invalid messageWAKIF: Bus Activity W1 = Activity on the CAN0 = An error has occurr0 = An error has not occurr1 = An error has not occurr0 = An error has not occurr1 = Transmit Buffer 2 h0 = Transmit Buffer 2 h0 = Transmit Buffer 2 h0 = Transmit Buffer 1 h0 = Transmit Buffer 1 h0 = Transmit Buffer 1 h0 = Transmit Buffer 0 h0 = Transmit Buffer 0 h0 = Transmit Buffer 1 h0 = Receive Buffer 0 ha1 = Receive Buffer 1 h0 = Receive Buffer 0 ha1 = Receive Buffer 0 ha	R/W-0R/W-0R/W-0IRXIFWAKIFERRIFbit 7IRXIF: Invalid Message Received I1 = An invalid message has occurr0 = An invalid message has not ocWAKIF: Bus Activity Wake-up Inter1 = Activity on the CAN bus has oc0 = Activity on the CAN bus has oc0 = Activity on the CAN bus has oc0 = Activity on the CAN bus has notERRIF: CAN bus Error Interrupt FI1 = An error has occurred in the CAN bus has not occurred in the CAN bus has not occurred in the CAN bus Error Interrupt I1 = Transmit Buffer 2 has complete0 = An error has not occurred in the CAN bus Error Interrupt1 = Transmit Buffer 2 has complete0 = Transmit Buffer 2 has not compTXB1IF: Transmit Buffer 1 Interrup1 = Transmit Buffer 1 has not compTXB0IF: Transmit Buffer 0 Interrup1 = Transmit Buffer 0 has not compTXB0IF: Receive Buffer 1 has not compRXB1IF: Receive Buffer 1 has not compRXB1IF: Receive Buffer 1 has not receive0 = Receive Buffer 1 has not receive1 = Receive Buffer 0 has not receive0 = Receive Buffer 0 has not receive1 = Receive Buffer 0 has not receive1 = Receive Buffer 0 has not receive0 = Receive Buffer 0 has not receive0 = Receive Buffer 0 has not receive	R/W-0R/W-0R/W-0R/W-0IRXIFWAKIFERRIFTXB2IFbit 7IRXIF: Invalid Message Received Interrupt Flag1 = An invalid message has occurred on the CA0 = An invalid message has not occurred on the WAKIF: Bus Activity Wake-up Interrupt Flag bit1 = Activity on the CAN bus has occurred0 = Activity on the CAN bus has not occurred0 = Activity on the CAN bus has not occurredERRIF: CAN bus Error Interrupt Flag bit1 = An error has occurred in the CAN module (0 = An error has not occurred in the CAN module (0 = An error has not occurred in the CAN module (0 = An error has not occurred in the CAN module (0 = Transmit Buffer 2 has completed transmiss0 = Transmit Buffer 1 Interrupt Flag bit1 = Transmit Buffer 1 has completed transmiss0 = Transmit Buffer 1 has not completed transmiss0 = Transmit Buffer 0 has not completed transmiss0 = Transmit Buffer 0 has not completed transmiss0 = Transmit Buffer 1 has not completed transmiss0 = Transmit Buffer 0 has not completed transmiss0 = Receive Buffer 1 has not received a new mess0 = Receive Buffer 1 has not received a new mess0 = Receive Buffer 0 has not received a new mess0 =	R/W-0R/W-0R/W-0R/W-0R/W-0IRXIFWAKIFERRIFTXB2IFTXB1IFbit 7IRXIF: Invalid Message Received Interrupt Flag bit1 = An invalid message has occurred on the CAN bus0 = An invalid message has not occurred on the CAN busWAKIF: Bus Activity Wake-up Interrupt Flag bit1 = Activity on the CAN bus has occurred0 = Activity on the CAN bus has occurred0 = Activity on the CAN bus has not occurredERRIF: CAN bus Error Interrupt Flag bit1 = An error has occurred in the CAN module (multiple souding the colspan="2">TAB21F: Transmit Buffer 2 Interrupt Flag bit1 = Transmit Buffer 2 has completed transmission of a mession of a messi	R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 R/W-0 IRXIF WAKIF ERRIF TXB2IF TXB1IF TXB0IF bit 7 IRXIF: Invalid Message Received Interrupt Flag bit 1 = An invalid message has occurred on the CAN bus 0 = An invalid message has not occurred on the CAN bus WAKIF: Bus Activity Wake-up Interrupt Flag bit 1 = Activity on the CAN bus has occurred 0 = Activity on the CAN bus has not occurred ERRIF: CAN bus Error Interrupt Flag bit 1 = An error has occurred in the CAN module (multiple sources) 0 = An error has not occurred in the CAN module TXB2IF: Transmit Buffer 2 Interrupt Flag bit 1 = Transmit Buffer 2 has completed transmission of a message and m 0 = Transmit Buffer 1 Interrupt Flag bit 1 = Transmit Buffer 1 Interrupt Flag bit 1 = Transmit Buffer 1 has completed transmission of a message and m 0 = Transmit Buffer 0 Interrupt Flag bit 1 = Transmit Buffer 0 Interrupt Flag bit 1 = Transmit Buffer 0 has completed transmission of a message TXB0IF: Transmit Buffer 0 Interrupt Flag bit 1 = Transmit Buffer 0 has not completed transmission of a message RXB1IF: Receive Buffer 1 Interrupt Flag bit <td< td=""><td>RW-0 RW-0 RW-0</td></td<>	RW-0 RW-0				

W = Writable bit

'1' = Bit is set

REGISTER 8-6: PIR3: PERIPHERAL INTERRUPT REQUEST (FLAG) REGISTER 3

U = Unimplemented bit, read as '0'

x = Bit is unknown

'0' = Bit is cleared

R = Readable bit

-n = Value at POR

8.3 PIE Registers

bit 7

bit 6

bit 5

bit 4

bit 3

bit 2

bit 1

bit 0

The Peripheral Interrupt Enable (PIE) registers contain the individual enable bits for the peripheral interrupts (Register 8-7 through Register 8-9). Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Enable registers (PIE1, PIE2, PIE3). When IPEN is clear, the PEIE bit must be set to enable any of these peripheral interrupts.

REGISTER 8-7:	NTERRUPT ENABLE REGISTER 1

R/W-0 PSPIE ⁽¹⁾	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0				
	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE				
bit 7							bit 0				
					(1)						
	rallel Slave I		•	ot Enable bit	(1)						
 1 = Enables the PSP read/write interrupt 0 = Disables the PSP read/write interrupt 											
ADIE: A/D	Converter Ir	nterrupt Ena	ble bit								
	s the A/D int										
0 = Disable	es the A/D in	terrupt									
	RT Receive	•									
	s the USAR		•								
	es the USAR		•								
	RT Transmi										
	s the USAR										
	es the USAR		•								
	ster Synchro s the MSSP		i Port Interru	ipt Enable b	IT						
	s the MSSP										
	CP1 Interru	•	t								
	s the CCP1		L								
	es the CCP1										
TMR2IE: T	MR2 to PR2	Match Inte	rrupt Enable	bit							
1 = Enable	s the TMR2	to PR2 mat	ch interrupt								
0 = Disable	es the TMR2	to PR2 mat	tch interrupt								
TMR1IE: T	MR1 Overflo	ow Interrupt	Enable bit								
	s the TMR1										
0 = Disable	es the TMR1	overflow in	terrupt								
Note 1:	This bit is o	•			es. For PIC1	8F2X8 devi	ces, this bit				
	is unimplen	nented and	reads as '0'.								

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

 $[\]ensuremath{\textcircled{}^{\odot}}$ 2006 Microchip Technology Inc.

REGISTER 8-8:	PIE2: PEF	RIPHERAL	INTERRU	PT ENABI	E REGIS	TER 2		
	U-0	R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	—	CMIE ⁽¹⁾	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE ⁽¹⁾
	bit 7							bit 0
bit 7	Unimplom	ented: Rea	d ac 'o'					
	•			L. I. (1)				
bit 6		nparator Inte	•					
		es the compa es the compa		-				
bit 5	Unimplem	ented: Rea	d as '0'					
bit 4	EEIE: EEP	ROM Write	Interrupt Er	able bit				
	1 = Enable 0 = Disable							
bit 3	BCLIE: Bu	s Collision I	nterrupt Ena	able bit				
	1 = Enable 0 = Disable							
bit 2		w-Voltage D	etect Interri	int Enable b	it			
SILE	1 = Enable	•			it.			
	0 = Disable	-						
bit 1	TMR3IE: T	MR3 Overfl	ow Interrupt	Enable bit				
	1 = Enable	s the TMR3	overflow in	terrupt				
	0 = Disable	es the TMR3	overflow ir	iterrupt				
bit 0	ECCP1IE:	ECCP1 Inte	rrupt Enabl	e bit ⁽¹⁾				
		s the ECCP						
	0 = Disable	es the ECCF	1 interrupt					

Note 1: This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented I	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

ER 8-9:	PIE3: PEF	RIPHERAL	INTERRU	PT ENABL	E REGIST	ER 3		
	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
	IRXIE	WAKIE	ERRIE	TXB2IE	TXB1IE	TXB0IE	RXB1IE	RXB0IE
	bit 7							bit 0
bit 7	IRXIE: Inva	alid CAN Me	ssage Rece	vived Interrup	ot Enable bit	t		
				age received age receive				
bit 6	WAKIE: B	us Activity W	lake-up Inte	rrupt Enable	bit			
		es the bus ac						
bit 5	ERRIE: CA	AN bus Erro	r Interrupt E	nable bit				
		es the CAN b es the CAN I						
bit 4	TXB2IE: ⊤	ransmit Buff	er 2 Interrup	ot Enable bit				
		es the Transr es the Trans						
bit 3	TXB1IE: ⊤	ransmit Buff	er 1 Interrup	t Enable bit				
		es the Transr es the Trans						
bit 2	TXB0IE: T	ransmit Buff	er 0 Interrup	t Enable bit				
		es the Transr es the Trans						
bit 1	RXB1IE: F	Receive Buff	er 1 Interrup	t Enable bit				
		es the Receives the Receives the Recei		•				
bit 0	RXB0IE: F	Receive Buff	er 0 Interrup	t Enable bit				
		es the Receives the Receives the Recei						
	Legend:]
	R = Reada	able bit	W = W	/ritable bit	U = Unim	plemented	bit, read as	ʻ0'

'1' = Bit is set

'0' = Bit is cleared

REGISTER 8-9: PIE3: PERIPHERAL INTERRUPT ENABLE REGISTER 3

-n = Value at POR

 $\ensuremath{\textcircled{}^{\odot}}$ 2006 Microchip Technology Inc.

x = Bit is unknown

8.4 IPR Registers

The Interrupt Priority (IPR) registers contain the individual priority bits for the peripheral interrupts. Due to the number of peripheral interrupt sources, there are three Peripheral Interrupt Priority registers (IPR1, IPR2 and IPR3). The operation of the priority bits requires that the Interrupt Priority Enable bit (IPEN) be set.

REGISTER 8-10: IPR1: PERIPHERAL INTERRUPT PRIORITY REGISTER 1

	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1		
	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP		
	bit 7			I	I	I	I	bit 0		
bit 7			Port Read/W	/rite Interrup	ot Priority bit	(1)				
	1 = High pri 0 = Low prie									
bit 6	ADIP: A/D (Converter I	nterrupt Prio	rity bit						
	1 = High pri 0 = Low prie									
bit 5	RCIP: USA	RT Receive	e Interrupt Pi	riority bit						
	1 = High pri 0 = Low prie	-								
bit 4	TXIP: USART Transmit Interrupt Priority bit									
	1 = High priority									
	0 = Low price	ority								
bit 3	SSPIP: Mas	ster Synchr	onous Seria	l Port Interru	ipt Priority b	it				
	1 = High pri	-								
	0 = Low price	•								
bit 2			pt Priority bi	t						
	1 = High pri 0 = Low prie	-								
bit 1	TMR2IP: T	MR2 to PR2	2 Match Inte	rrupt Priority	' bit					
	1 = High pri	1 = High priority								
	0 = Low price	ority								
bit 0			ow Interrupt	Priority bit						
	1 = High pri	-								
	0 = Low prie	ority								
			only availabl mented and			es. For PIC1	8F2X8 devi	ces, this bit		

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

DS41159E-page 88

	U-0	R/W-1	U-0	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1		
		CMIP ⁽¹⁾	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP ⁽¹⁾		
	bit 7	· · · · ·						bit 0		
bit 7	Unimplem	nented: Read	d as '0'							
bit 6	CMIP: Cor	mparator Inte	errupt Priori	ty bit ⁽¹⁾						
	1 = High p 0 = Low pr	•								
bit 5	Unimplem	nented: Read	d as '0'							
bit 4	EEIP: EEF	PROM Write	Interrupt Pr	iority bit						
	1 = High p 0 = Low pr	-								
bit 3	BCLIP: Bu	us Collision Ir	nterrupt Prie	ority bit						
	1 = High p 0 = Low pr	,								
bit 2	LVDIP: Low-Voltage Detect Interrupt Priority bit									
	1 = High p	•								
L.1. A	0 = Low pr	-								
bit 1	TMR3IP: TMR3 Overflow Interrupt Priority bit									
	1 = High p 0 = Low pr	•								
bit 0	ECCP1IP:	ECCP1 Inte	rrupt Priorit	y bit ⁽¹⁾						
	1 = High p									
	0 = Low pr	riority								

REGISTER 8-11: IPR2: PERIPHERAL INTERRUPT PRIORITY REGISTER 2

Note 1: This bit is only available on PIC18F4X8 devices. For PIC18F2X8 devices, this bit is unimplemented and reads as '0'.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

^{© 2006} Microchip Technology Inc.

IPR3: PERI	PHERAL	INTERRU	PT PRIORI	TY REGIS	TER 3		
R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
IRXIP	WAKIP	ERRIP	TXB2IP	TXB1IP	TXB0IP	RXB1IP	RXB0IP
bit 7							bit 0
	•	e Received I	nterrupt Pric	ority bit			
WAKIP: Bus	s Activity W	ake-up Inte	rrupt Priority	bit			
• •	-						
ERRIP: CAN	N bus Error	Interrupt Pr	iority bit				
5 1	,						
TXB2IP: Tra	ansmit Buff	er 2 Interrup	t Priority bit				
• •	-						
TXB1IP: Tra	ansmit Buff	er 1 Interrup	t Priority bit				
TXB0IP: Tra	ansmit Buff	er 0 Interrup	t Priority bit				
• .	•						
RXB1IP: Re	eceive Buffe	er 1 Interrup	t Priority bit				
• •	-						
RXB0IP: Re	eceive Buffe	er 0 Interrup	t Priority bit				
• •	-						
Legend:]
R = Readab	le bit	W = W	ritable bit	U = Unim	plemented	bit, read as '	0'
	R/W-1 IRXIP bit 7 IRXIP: Inval 1 = High price 0 = Low price WAKIP: Bus 1 = High price 0 = Low price ERRIP: CAN 1 = High price 0 = Low price TXB1P: Tra 1 = High price 0 = Low price TXB0IP: Tra 1 = High price 0 = Low price RXB0IP: Tra 1 = High price 0 = Low price RXB0IP: Ref 1 = High price 0 = Low price RXB0IP: Ref 1 = High price 0 = Low price RXB0IP: Ref 1 = High price 0 = Low price RXB0IP: Ref	R/W-1R/W-1IRXIPWAKIPbit 7IRXIP: Invalid Message1 = High priority0 = Low priorityWAKIP: Bus Activity W1 = High priority0 = Low priorityERRIP: CAN bus Error1 = High priority0 = Low priorityTXB2IP: Transmit Buff1 = High priority0 = Low priorityTXB2IP: Transmit Buff1 = High priority0 = Low priorityTXB1P: Transmit Buff1 = High priority0 = Low priorityTXB0IP: Transmit Buff1 = High priority0 = Low priorityRXB1IP: Receive Buff1 = High priority0 = Low priorityRXB1P: Receive Buff1 = High priority0 = Low priorityRXB0IP: Receive Buff1 = High priority0 = Low priorityRXB0IP: Receive Buff1 = High priority0 = Low priorityRXB0IP: Receive Buff1 = High priority0 = Low priority	R/W-1R/W-1R/W-1IRXIPWAKIPERRIPbit 7IRXIP: Invalid Message Received I1 = High priority0 = Low priorityWAKIP: Bus Activity Wake-up Inter1 = High priority0 = Low priorityERRIP: CAN bus Error Interrupt Pr1 = High priority0 = Low priorityTXB2IP: Transmit Buffer 2 Interrup1 = High priority0 = Low priorityTXB1P: Transmit Buffer 1 Interrup1 = High priority0 = Low priorityTXB0IP: Transmit Buffer 0 Interrup1 = High priority0 = Low priorityRXB0IP: Receive Buffer 1 Interrup1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrup1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrup1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrup1 = High priority0 = Low priorityExercise Buffer 0 Interrup1 = High priority0 = Low priority	R/W-1R/W-1R/W-1R/W-1IRXIPWAKIPERRIPTXB2IPbit 7IRXIP: Invalid Message Received Interrupt Prior1 = High priority0 = Low priorityWAKIP: Bus Activity Wake-up Interrupt Priority1 = High priority0 = Low priorityERRIP: CAN bus Error Interrupt Priority bit1 = High priority0 = Low priorityTXB2IP: Transmit Buffer 2 Interrupt Priority bit1 = High priority0 = Low priorityTXB1IP: Transmit Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityTXB0IP: Transmit Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: Transmit Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB1IP: Receive Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priority	R/W-1R/W-1R/W-1R/W-1R/W-1IRXIPWAKIPERRIPTXB2IPTXB1IPbit 7IRXIP: Invalid Message Received Interrupt Priority bit1 = High priority0 = Low priorityWAKIP: Bus Activity Wake-up Interrupt Priority bit1 = High priority0 = Low priorityERRIP: CAN bus Error Interrupt Priority bit1 = High priority0 = Low priorityTXB2IP: Transmit Buffer 2 Interrupt Priority bit1 = High priority0 = Low priorityTXB1IP: Transmit Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityTXB0IP: Transmit Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityTXB0IP: Transmit Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityExercise Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityLegend:	IRXIP WAKIP ERRIP TXB2IP TXB1IP TXB0IP bit 7 IRXIP: Invalid Message Received Interrupt Priority bit 1 = High priority 0 = Low priority WAKIP: Bus Activity Wake-up Interrupt Priority bit 1 = High priority 0 = Low priority WAKIP: Bus Activity Wake-up Interrupt Priority bit 1 = High priority 0 = Low priority ERRIP: CAN bus Error Interrupt Priority bit 1 = High priority 0 = Low priority TXB2IP: Transmit Buffer 2 Interrupt Priority bit 1 = High priority 0 = Low priority TXB1IP: Transmit Buffer 1 Interrupt Priority bit 1 = High priority 0 = Low priority TXB0IP: Transmit Buffer 0 Interrupt Priority bit 1 = High priority 0 = Low priority RXB1IP: Receive Buffer 1 Interrupt Priority bit 1 = High priority 0 = Low priority RXB0IP: Receive Buffer 0 Interrupt Priority bit 1 = High priority 0 = Low priority RXB0IP: Receive Buffer 0 Interrupt Priority bit 1 = High priority 0 = Low priority	R/W-1 R/W-1 R/W-1 R/W-1 R/W-1 R/W-1 R/W-1 IRXIP WAKIP ERRIP TXB2IP TXB1IP TXB0IP RXB1IP bit 7 IRXIP: Invalid Message Received Interrupt Priority bit 1 = High priority 0 = Low priority WAKIP: Bus Activity Wake-up Interrupt Priority bit 1 1 = High priority 0 = Low priority WAKIP: CAN bus Error Interrupt Priority bit 1 = High priority 0 = Low priority TXB2IP: Transmit Buffer 2 Interrupt Priority bit 1 = High priority 0 = Low priority TXB1IP: Transmit Buffer 1 Interrupt Priority bit 1 = High priority 0 = Low priority TXB0IP: Transmit Buffer 0 Interrupt Priority bit 1 = High priority 0 = Low priority TXB0IP: Transmit Buffer 1 Interrupt Priority bit 1 = High priority 0 = Low priority RXB1IP: Receive Buffer 1 Interrupt Priority bit 1 = High priority 0 = Low priority RXB0IP: Receive Buffer 0 Interrupt Priority bit 1 = High priority 0 = Low priority Image: Ima

REGISTER 8-12: IPR3: PERIPHERAL INTERRUPT PRIORITY REGISTER 3

Legend.			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

8.5 RCON Register

The Reset Control (RCON) register contains the IPEN bit which is used to enable prioritized interrupts. The functions of the other bits in this register are discussed in more detail in **Section 4.14** "**RCON Register**".

REGISTER 8-13: RCON: RESET CONTROL REGISTER

-n = Value at POR

0-10.								
	R/W-0	U-0	U-0	R/W-1	R-1	R-1	R/W-0	R/W-0
	IPEN	—		RI	TO	PD	POR	BOR
	bit 7							bit 0
bit 7	IPEN: Inter	rupt Priority	Enable bit					
		e priority leve						
	0 = Disable	e priority lev	els on interr	upts (PIC16	CXXX Comp	patibility mod	de)	
bit 6-5	Unimplem	ented: Read	d as '0'					
bit 4	RI: RESET	Instruction F	lag bit					
	For details	of bit operat	ion, see Re	gister 4-3.				
bit 3	TO: Watche	dog Time-ou	it Flag bit					
	For details	of bit operat	ion, see Re	gister 4-3.				
bit 2	PD: Power	-down Deteo	ction Flag bi	t				
	For details	of bit operat	ion, see Re	gister 4-3.				
bit 1	POR: Powe	er-on Reset	Status bit					
	For details	of bit operat	ion, see Re	gister 4-3.				
bit 0	BOR: Brow	n-out Reset	Status bit					
	For details of bit operation, see Register 4-3.							
	Legend:							
	R = Reada	ble bit	W = W	/ritable bit	U = Unin	plemented	bit, read as '	0'
	1							

'0' = Bit is cleared

'1' = Bit is set

x = Bit is unknown

^{© 2006} Microchip Technology Inc.

8.6 INT Interrupts

External interrupts on the RB0/INT0, RB1/INT1 and RB2/CANTX/INT2 pins are edge triggered: either rising if the corresponding INTEDGx bit is set in the INTCON2 register, or falling if the INTEDGx bit is clear. When a valid edge appears on the RBx/INTx pin, the corresponding flag bit INTxIF is set. This interrupt can be disabled by clearing the corresponding enable bit INTxIE. Flag bit INTxIF must be cleared in software in the Interrupt Service Routine before re-enabling the interrupt. All external interrupts (INT0, INT1 and INT2) can wake-up the processor from Sleep if bit INTxIE was set prior to going into Sleep. If the Global Interrupt Enable bit, GIE, is set, the processor will branch to the interrupt vector following wake-up.

Interrupt priority for INT1 and INT2 is determined by the value contained in the interrupt priority bits INT1IP (INTCON3<6>) and INT2IP (INTCON3<7>). There is no priority bit associated with INT0; it is always a high priority interrupt source.

8.7 TMR0 Interrupt

In 8-bit mode (which is the default), an overflow (FFh \rightarrow 00h) in the TMR0 register will set flag bit TMR0IF. In 16-bit mode, an overflow (FFFFh \rightarrow 0000h) in the TMR0H:TMR0L registers will set flag bit TMR0IF. The interrupt can be enabled/disabled by setting/clearing enable bit TMR0IE (INTCON register). Interrupt priority for Timer0 is determined by the value contained in the interrupt priority bit TMR0IP (INTCON2 register). See Section 11.0 "Timer0 Module" for further details.

8.8 **PORTB Interrupt-on-Change**

An input change on PORTB<7:4> sets flag bit RBIF (INTCON register). The interrupt can be enabled/ disabled by setting/clearing enable bit RBIE (INTCON register). Interrupt priority for PORTB interrupt-onchange is determined by the value contained in the interrupt priority bit RBIP (INTCON2 register).

8.9 Context Saving During Interrupts

During an interrupt, the return PC value is saved on the stack. Additionally, the WREG, Status and BSR registers are saved on the fast return stack. If a fast return from interrupt is not used (see Section 4.3 "Fast **Register Stack**"), the user may need to save the WREG, Status and BSR registers in software. Depending on the user's application, other registers may also need to be saved. Example 8-1 saves and restores the WREG, Status and BSR registers during an Interrupt Service Routine.

	on onthis of Aros	
MOVWF	W_TEMP	; W_TEMP is in Low Access bank
MOVFF	STATUS, STATUS_TEMP	; STATUS_TEMP located anywhere
MOVFF	BSR, BSR_TEMP	; BSR located anywhere
;		
; USER IS	R CODE	
;		
MOVFF	BSR_TEMP, BSR	; Restore BSR
MOVF	W_TEMP, W	; Restore WREG
MOVFF	STATUS_TEMP, STATUS	; Restore STATUS

EXAMPLE 8-1: SAVING STATUS, WREG AND BSR REGISTERS IN RAM

9.0 I/O PORTS

Depending on the device selected, there are up to five general purpose I/O ports available on PIC18FXX8 devices. Some pins of the I/O ports are multiplexed with an alternate function from the peripheral features on the device. In general, when a peripheral is enabled, that pin may not be used as a general purpose I/O pin.

Each port has three registers for its operation:

- TRIS register (Data Direction register)
- PORT register (reads the levels on the pins of the device)
- LAT register (output latch)

The data latch (LAT register) is useful for read-modify-write operations on the value that the I/O pins are driving.

9.1 PORTA, TRISA and LATA Registers

PORTA is a 7-bit wide, bidirectional port. The corresponding Data Direction register is TRISA. Setting a TRISA bit (= 1) will make the corresponding PORTA pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISA bit (= 0) will make the corresponding PORTA pin an output (i.e., put the contents of the output latch on the selected pin). On a Power-on Reset, these pins are configured as inputs and read as '0'.

Reading the PORTA register reads the status of the pins, whereas writing to it will write to the port latch.

Read-modify-write operations on the LATA register read and write the latched output value for PORTA.

The RA4 pin is multiplexed with the Timer0 module clock input to become the RA4/T0CKI pin. The RA4/T0CKI pin is a Schmitt Trigger input and an open-drain output. All other RA port pins have TTL input levels and full CMOS output drivers.

The other PORTA pins are multiplexed with analog inputs and the analog VREF+ and VREF- inputs. The operation of each pin is selected by clearing/setting the control bits in the ADCON1 register (A/D Control Register 1). On a Power-on Reset, these pins are configured as analog inputs and read as '0'.

Note:	On a Power-on Reset, RA5 and RA3:RA0
	are configured as analog inputs and read
	as '0'. RA6 and RA4 are configured as
	digital inputs.

The TRISA register controls the direction of the RA pins, even when they are being used as analog inputs. The user must ensure the bits in the TRISA register are maintained set, when using them as analog inputs.

EXAMPLE 9-1: INITIALIZING PORTA

CLRF	PORTA	;	Initialize PORTA by
		;	clearing output data latches
CLRF	LATA	;	Alternate method to clear
		;	output data latches
MOVLW	07h	;	Configure A/D
MOVWF	ADCON1	;	for digital inputs
MOVLW	0CFh	;	Value used to initialize
		;	data direction
MOVWF	TRISA	;	Set RA3:RA0 as inputs,
		;	RA5:RA4 as outputs
			Ŧ

^{© 2006} Microchip Technology Inc.





FIGURE 9-3: OSC2/CLKO/RA6 PIN BLOCK DIAGRAM



Name	Bit#	Buffer	Function
RA0/AN0/CVREF	bit 0	TTL	Input/output, analog input or analog comparator voltage reference output.
RA1/AN1	bit 1	TTL	Input/output or analog input.
RA2/AN2/VREF-	bit 2	TTL	Input/output, analog input or VREF
RA3/AN3/VREF+	bit 3	TTL	Input/output, analog input or VREF+.
RA4/T0CKI	bit 4	ST/OD	Input/output, external clock input for Timer0, output is open-drain type.
RA5/AN4/SS/LVDIN	bit 5	TTL	Input/output, analog input, slave select input for synchronous serial port or Low-Voltage Detect input.
OSC2/CLKO/RA6	bit 6	TTL	Oscillator clock output or input/output.

TABLE 9-1:PORTA FUNCTIONS

Legend: TTL = TTL input, ST = Schmitt Trigger input, OD = Open-Drain

TABLE 9-2: SUMMARY OF REGISTERS ASSOCIATED WITH PORTA

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTA		RA6	RA5	RA4	RA3	RA2	RA1	RA0	-00x 0000	-uuu uuuu
LATA		Latch A	Data Out	out Regist	er				-xxx xxxx	-uuu uuuu
TRISA		PORTA	PORTA Data Direction Register							-111 1111
ADCON1	ADFM	ADCS2	_		PCFG3	PCFG2	PCFG1	PCFG0	00 0000	uu uuuu

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by PORTA.

^{© 2006} Microchip Technology Inc.

9.2 PORTB, TRISB and LATB Registers

PORTB is an 8-bit wide, bidirectional port. The corresponding Data Direction register is TRISB. Setting a TRISB bit (= 1) will make the corresponding PORTB pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISB bit (= 0) will make the corresponding PORTB pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATB register, read and write the latched output value for PORTB.

EXAMPLE 9-2: INITIALIZING PORTB

CLRF	PORTB	; Initialize PORTB by
		; clearing output
		; data latches
CLRF	LATB	; Alternate method
		; to clear output
		; data latches
MOVLW	0CFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISB	; Set RB3:RB0 as inputs
		; RB5:RB4 as outputs
		; RB7:RB6 as inputs
1		

Each of the PORTB pins has a weak internal pull-up. A single control bit can turn on all the pull-ups. This is performed by clearing bit RBPU (INTCON2 register). The weak pull-up is automatically turned off when the port pin is configured as an output. The pull-ups are disabled on a Power-on Reset.

Four of the PORTB pins (RB7:RB4) have an interrupton-change feature. Only pins configured as inputs can cause this interrupt to occur (i.e., any RB7:RB4 pin configured as an output is excluded from the interrupton-change comparison). The input pins (of RB7:RB4) are compared with the old value latched on the last read of PORTB. The "mismatch" outputs of RB7:RB4 are ORed together to generate the RB Port Change Interrupt with Flag bit RBIF (INTCON register). This interrupt can wake the device from Sleep. The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of PORTB (except with the MOVFF instruction). This will end the mismatch condition.
- b) Clear flag bit RBIF.

A mismatch condition will continue to set flag bit RBIF. Reading PORTB will end the mismatch condition and allow flag bit RBIF to be cleared.

The interrupt-on-change feature is recommended for wake-up on key depression operation and operations where PORTB is only used for the interrupt-on-change feature. Polling of PORTB is not recommended while using the interrupt-on-change feature.

- Note 1: While in Low-Voltage ICSP mode, the RB5 pin can no longer be used as a general purpose I/O pin and should not be held low during normal operation to protect against inadvertent ICSP mode entry.
 - 2: When using Low-Voltage ICSP Programming (LVP), the pull-up on RB5 becomes disabled. If TRISB bit 5 is cleared, thereby setting RB5 as an output, LATB bit 5 must also be cleared for proper operation.

DS41159E-page 96




FIGURE 9-5:

RB1:RB0 PINS BLOCK DIAGRAM




FIGURE 9-6: RB2/CANTX/INT2 PIN BLOCK DIAGRAM





FIGURE 9-7: RB3/CANRX PIN BLOCK DIAGRAM



Name	Bit#	Buffer	Function			
RB0/INT0	bit 0	TTL/ST ⁽¹⁾	Input/output pin or external interrupt 0 input. Internal software programmable weak pull-up.			
RB1/INT1	bit 1	TTL/ST ⁽¹⁾	Input/output pin or external interrupt 1 input. Internal software programmable weak pull-up.			
RB2/CANTX/ INT2	bit 2	TTL/ST ⁽¹⁾	Input/output pin, CAN bus transmit pin or external interrupt 2 input. Internal software programmable weak pull-up.			
RB3/CANRX	bit 3	TTL	Input/output pin or CAN bus receive pin. Internal software programmable weak pull-up.			
RB4	bit 4	TTL	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up.			
RB5/PGM	bit 5	TTL	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Low-voltage serial programming enable.			
RB6/PGC	bit 6	TTL/ST ⁽²⁾	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming clock.			
RB7/PGD	bit 7	TTL/ST ⁽²⁾	Input/output pin (with interrupt-on-change). Internal software programmable weak pull-up. Serial programming data.			

TABLE 9-3: PORTB FUNCTIONS

Legend: TTL = TTL input, ST = Schmitt Trigger input

Note 1: This buffer is a Schmitt Trigger input when configured as the external interrupt.

2: This buffer is a Schmitt Trigger input when used in Serial Programming mode.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTB	RB7	RB6	RB5	RB4	RB3	RB2	RB1	RB0	xxxx xxxx	uuuu uuuu
LATB	LATB Data	_ATB Data Output Register								uuuu uuuu
TRISB	PORTB Da	ata Direction	Register						1111 1111	1111 1111
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
INTCON2	RBPU	INTEDG0	INTEDG1		_	TMR0IP	_	RBIP	1111-1	1111-1
INTCON3	INT2IP	INT1IP	_	INT2IE	INT1IE	—	INT2IF	INT1IF	11-0 0-00	11-1 0-00

Legend: x = unknown, u = unchanged. Shaded cells are not used by PORTB.

© 2006 Microchip Technology Inc.

9.3 PORTC, TRISC and LATC Registers

PORTC is an 8-bit wide, bidirectional port. The corresponding Data Direction register is TRISC. Setting a TRISC bit (= 1) will make the corresponding PORTC pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISC bit (= 0) will make the corresponding PORTC pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATC register, read and write the latched output value for PORTC.

PORTC is multiplexed with several peripheral functions (Table 9-5). PORTC pins have Schmitt Trigger input buffers.


When enabling peripheral functions, care should be taken in defining TRIS bits for each PORTC pin. Some peripherals override the TRIS bit to make a pin an output,

while other peripherals override the TRIS bit to make a pin an input. The user should refer to the corresponding peripheral section for the correct TRIS bit settings.

The pin override value is not loaded into the TRIS register. This allows read-modify-write of the TRIS register, without concern due to peripheral overrides.

E	EXAMP	LE 9-3:	INITIALIZING PORTC
	CLRF	PORTC	; Initialize PORTC by
			; clearing output
			; data latches
	CLRF	LATC	; Alternate method
			; to clear output
			; data latches
	MOVLW	0CFh	; Value used to
			; initialize data
			; direction
	MOVWF	TRISC	; Set RC3:RC0 as inputs
			; RC5:RC4 as outputs
			; RC7:RC6 as inputs

FIGURE 9-8: PORTC BLOCK DIAGRAM (PERIPHERAL OUTPUT OVERRIDE)



Name	Bit#	Buffer Type	Function
RC0/T1OSO/T1CKI	bit 0	ST	Input/output port pin, Timer1 oscillator output or Timer1/Timer3 clock input.
RC1/T1OSI	bit 1	ST	Input/output port pin or Timer1 oscillator input.
RC2/CCP1	bit 2	ST	Input/output port pin or Capture 1 input/Compare 1 output/ PWM1 output.
RC3/SCK/SCL	bit 3	ST	Input/output port pin or synchronous serial clock for SPI™/I ² C™.
RC4/SDI/SDA	bit 4	ST	Input/output port pin or SPI data in (SPI mode) or data I/O (I ² C mode).
RC5/SDO	bit 5	ST	Input/output port pin or synchronous serial port data output.
RC6/TX/CK	bit 6	ST	Input/output port pin, addressable USART asynchronous transmit or addressable USART synchronous clock.
RC7/RX/DT	bit 7	ST	Input/output port pin, addressable USART asynchronous receive or addressable USART synchronous data.

TABLE 9-5: PORTC FUNCTIONS

Legend: ST = Schmitt Trigger input

TABLE 9-6: SUMMARY OF REGISTERS ASSOCIATED WITH PORTC

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTC	RC7	RC6	RC5	RC4	RC3	RC2	RC1	RC0	xxxx xxxx	uuuu uuuu
LATC	LATC D	LATC Data Output Register xxxx xxxx								uuuu uuuu
TRISC	PORTC	ORTC Data Direction Register 1111 1111 1111								

Legend: x = unknown, u = unchanged

^{© 2006} Microchip Technology Inc.

9.4 PORTD, TRISD and LATD Registers

Note:	This	port	is	only	available	on	the
	PIC1	8F448	and	PIC1	8F458.		

PORTD is an 8-bit wide, bidirectional port. The corresponding Data Direction register for the port is TRISD. Setting a TRISD bit (= 1) will make the corresponding PORTD pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISD bit (= 0) will make the corresponding PORTD pin an output (i.e., put the contents of the output latch on the selected pin).

Read-modify-write operations on the LATD register read and write the latched output value for PORTD.

PORTD uses Schmitt Trigger input buffers. Each pin is individually configurable as an input or output.


PORTD can be configured as an 8-bit wide, microprocessor port (Parallel Slave Port or PSP) by setting the control bit PSPMODE (TRISE<4>). In this mode, the input buffers are TTL. See **Section 10.0 "Parallel Slave Port"** for additional information.

PORTD is also multiplexed with the analog comparator module and the ECCP module.

EXAMP	LE 9-4:	INITIALIZING PORTD
CLRF	PORTD	; Initialize PORTD by
		; clearing output
		; data latches
CLRF	LATD	; Alternate method
		; to clear output
		; data latches
MOVLW	07h	; comparator off
MOVWF	CMCON	
MOVLW	0CFh	; Value used to
		; initialize data
		; direction
MOVWF	TRISD	; Set RD3:RD0 as inputs
		; RD5:RD4 as outputs

; RD7:RD6 as inputs

FIGURE 9-9: PORTD BLOCK DIAGRAM IN I/O PORT MODE



Name	Bit#	Buffer Type	Function					
RD0/PSP0/C1IN+	bit 0	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 0 or C1IN+ comparator input.					
RD1/PSP1/C1IN-	bit 1	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 1 or C1IN- comparator input.					
RD2/PSP2/C2IN+	bit 2	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 2 or C2IN+ comparator input.					
RD3/PSP3/C2IN-	bit 3	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 3 or C2IN- comparator input.					
RD4/PSP4/ECCP1/P1A	bit 4	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 4 or ECCP1/P1A pin.					
RD5/PSP5/P1B	bit 5	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 5 or P1B pin.					
RD6/PSP6/P1C	bit 6	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 6 or P1C pin.					
RD7/PSP7/P1D	bit 7	ST/TTL ⁽¹⁾	Input/output port pin, Parallel Slave Port bit 7 or P1D pin.					

TABLE 9-7: PORTD FUNCTIONS

Legend: ST = Schmitt Trigger input, TTL = TTL input

Note 1: Input buffers are Schmitt Triggers when in I/O mode and TTL buffers when in Parallel Slave Port mode.

TABLE 9-8: SUMMARY OF REGISTERS ASSOCIATED WITH PORTD

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
PORTD	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0	xxxx xxxx	uuuu uuuu
LATD	LATD Data Output Register								xxxx xxxx	uuuu uuuu
TRISD	PORTD Data Direction Register								1111 1111	1111 1111
TRISE	IBF	OBF	IBOV	PSPMODE	_	TRISE2	TRISE1	TRISE0	0000 -111	0000 -111

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PORTD.

^{© 2006} Microchip Technology Inc.

9.5 PORTE, TRISE and LATE Registers

Note:	This	port	is	only	available	on	the		
	PIC18F448 and PIC18F458.								

PORTE is a 3-bit wide, bidirectional port. PORTE has three pins (RE0/AN5/RD, RE1/AN6/WR/C10UT and RE2/AN7/CS/C20UT) which are individually configurable as inputs or outputs. These pins have Schmitt Trigger input buffers.

Read-modify-write operations on the LATE register, read and write the latched output value for PORTE.

The corresponding Data Direction register for the port is TRISE. Setting a TRISE bit (= 1) will make the corresponding PORTE pin an input (i.e., put the corresponding output driver in a high-impedance mode). Clearing a TRISE bit (= 0) will make the corresponding PORTE pin an output (i.e., put the contents of the output latch on the selected pin).

The TRISE register also controls the operation of the Parallel Slave Port through the control bits in the upper half of the register. These are shown in Register 9-1.

When the Parallel Slave Port is active, the PORTE pins function as its control inputs. For additional details, refer to **Section 10.0 "Parallel Slave Port"**.

PORTE pins are also multiplexed with inputs for the A/D converter and outputs for the analog comparators. When selected as an analog input, these pins will read as '0's. Direction bits TRISE<2:0> control the direction of the RE pins, even when they are being used as analog inputs. The user must make sure to keep the pins configured as inputs when using them as analog inputs.

EXA	MPLE 9-5:	INITIALIZING PORTE					
CLRF	PORTE	; Initialize PORTE by					
		; clearing output					
		; data latches					
CLRF	LATE	; Alternate method					
		; to clear output					
		; data latches					
MOVL	W 03h	; Value used to					
		; initialize data					
		; direction					
MOVW	F TRISE	; Set RE1:RE0 as inputs					
		; RE2 as an output					
		; (RE4=0 - PSPMODE Off)					




FIGURE 9-10: PORTE BLOCK DIAGRAM

REGISTER 9-1:	TRISE REGISTER
---------------	----------------

ER 9-1:	I RISE RE	GISTER								
	R-0	R-0	R/W-0	R/W-0	U-0	R/W-1	R/W-1	R/W-1		
	IBF	OBF	IBOV	PSPMODE	—	TRISE2	TRISE1	TRISE0		
	bit 7							bit 0		
bit 7	IBF: Input Buffer Full Status bit									
		d has been i Ird has been		d waiting to be	read by the	e CPU				
bit 6	OBF : Output Buffer Full Status bit									
		utput buffer utput buffer		previously writ ad	ten word					
bit 5	IBOV: Inpu	ut Buffer Ov	erflow Dete	ct bit (in Micro	processor n	node)				
		e occurred v be cleared		viously input w	ord has not	been read				
	•	verflow occu)						
bit 4	PSPMOD	E: Parallel S	lave Port N	lode Select bit						
		el Slave Por								
	0 = Gener	al Purpose	I/O mode							
bit 3	Unimplem	nented: Rea	ad as '0'							
bit 2	TRISE2: F	RE2 Directio	n Control bi	t						
	1 = Input									
			<u> </u>							
bit 1		RE1 Directio	n Control bi	t						
	1 = Input 0 = Output	t								
bit 0	•	RE0 Directio	n Control bi	t						
	1 = Input									
	0 = Output	t								
	Legend:									
	R = Reada	able bit	W = 1	Writable bit	U = Unim	plemented	bit, read as	'0'		
	-n = Value	at POR	'1' =	Bit is set	'0' = Bit is	s cleared	x = Bit is u	nknown		

 $[\]ensuremath{\textcircled{}^{\circ}}$ 2006 Microchip Technology Inc.

Name Bit#		Buffer Type	Function
RE0/AN5/RD	bit 0	ST/TTL ⁽¹⁾	Input/output port pin, analog input or read control input in Parallel Slave Port mode.
RE1/AN6/WR/C1OUT	bit 1	ST/TTL ⁽¹⁾	Input/output port pin, analog input, write control input in Parallel Slave Port mode or Comparator 1 output.
RE2/AN7/CS/C2OUT	bit 2	ST/TTL ⁽¹⁾	Input/output port pin, analog input, chip select control input in Parallel Slave Port mode or Comparator 2 output.

TABLE 9-9:PORTE FUNCTIONS

Legend: ST = Schmitt Trigger input, TTL = TTL input

Note 1: Input buffers are Schmitt Triggers when in I/O mode and TTL buffers when in Parallel Slave Port mode.

TABLE 9-10: SUM	MMARY OF REGISTERS ASSOCIATED WITH PORTE
-----------------	--

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
TRISE	IBF	OBF	IBOV	PSPMODE	_	TRISE2	TRISE1	TRISE0	0000 -111	0000 -111
PORTE	_			_	Ι	Read POF Write POF	RTE pin/ RTE Data La	atch	xxx	uuu
LATE	—	_	_	—	_	Read POF Write POF	RTE Data L RTE Data L		xxx	uuu
ADCON1	ADFM	ADCS2		—	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	00 0000

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PORTE.

DS41159E-page 106

10.0 PARALLEL SLAVE PORT

Note:	The Parallel Slave Port is only available on
	PIC18F4X8 devices.

In addition to its function as a general I/O port, PORTD can also operate as an 8-bit wide Parallel Slave Port (PSP) or microprocessor port. PSP operation is controlled by the 4 upper bits of the TRISE register (Register 9-1). Setting control bit PSPMODE (TRISE<4>) enables PSP operation. In Slave mode, the port is asynchronously readable and writable by the external world.

The PSP can directly interface to an 8-bit microprocessor data bus. The external microprocessor can read or write the PORTD latch as an 8-bit latch. Setting the control bit PSPMODE enables the PORTE I/O pins to become control inputs for the microprocessor port. When set, port pin RE0 is the RD input, RE1 is the WR input and RE2 is the CS (chip select) input. For this functionality, the corresponding data direction bits of the TRISE register (TRISE<2:0>) must be configured as inputs (set).

A write to the PSP occurs when both the \overline{CS} and \overline{WR} lines are first detected low. A read from the PSP occurs when both the \overline{CS} and \overline{RD} lines are first detected low. The timing for the control signals in Write and Read modes is shown in Figure 10-2 and Figure 10-3, respectively.

FIGURE 10-1:

PORTD AND PORTE BLOCK DIAGRAM (PARALLEL SLAVE PORT)




FIGURE 10-2: PARALLEL SLAVE PORT WRITE WAVEFORMS

^{© 2006} Microchip Technology Inc.

PIC18FXX8




FIGURE 10-3: PARALLEL SLAVE PORT READ WAVEFORMS

TABLE 10-1: REGISTERS ASSOCIATED WITH PARALLEL SLAVE PORT

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		e on BOR	Valu all o Res	ther
PORTD	Port Data L	atch when w	vritten; Por	t pins when r	ead				xxxx	xxxx	uuuu	uuuu
LATD	LATD Data	LATD Data Output bits								xxxx	uuuu	uuuu
TRISD	PORTD Data Direction bits								1111	1111	1111	1111
PORTE	_	_	—	_	—	RE2	RE1	RE0		-xxx		-000
LATE	LATE Data Output bits									-xxx		-uuu
TRISE	IBF	OBF	IBOV	PSPMODE	_	PORTE Data Direction bits			0000	-111	0000	-111
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111	1111	1111	1111

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Parallel Slave Port.

11.0 TIMER0 MODULE

The Timer0 module has the following features:

- Software selectable as an 8-bit or 16-bit timer/counter
- Readable and writable
- Dedicated 8-bit software programmable prescaler
- · Clock source selectable to be external or internal
- Interrupt-on-overflow from FFh to 00h in 8-bit mode and FFFFh to 0000h in 16-bit mode
- · Edge select for external clock

Register 11-1 shows the Timer0 Control register (T0CON).

Figure 11-1 shows a simplified block diagram of the Timer0 module in 8-bit mode and Figure 11-2 shows a simplified block diagram of the Timer0 module in 16-bit mode.

The TOCON register is a readable and writable register that controls all the aspects of Timer0, including the prescale selection.

Note: Timer0 is enabled on POR.

REGISTER 11-1:	T0CON: TIMER0 CONTROL REGISTER

R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1
TMR0ON	T08BIT	TOCS	T0SE	PSA	T0PS2	T0PS1	T0PS0
bit 7							bit 0

	bit 7	TMR0ON:	Timer0 On/Off	Control bit
--	-------	---------	---------------	-------------

- 1 = Enables Timer0
- 0 = Stops Timer0
- bit 6 **T08BIT**: Timer0 8-bit/16-bit Control bit
 - 1 = Timer0 is configured as an 8-bit timer/counter
 - 0 = Timer0 is configured as a 16-bit timer/counter
- bit 5 TOCS: Timer0 Clock Source Select bit
 - 1 = Transition on TOCKI pin
 - 0 = Internal instruction cycle clock (CLKO)
- bit 4 TOSE: Timer0 Source Edge Select bit
 - 1 = Increment on high-to-low transition on T0CKI pin
 - 0 = Increment on low-to-high transition on T0CKI pin
- bit 3 PSA: Timer0 Prescaler Assignment bit
 - 1 = TImer0 prescaler is not assigned. Timer0 clock input bypasses prescaler.
 - 0 = Timer0 prescaler is assigned. Timer0 clock input comes from prescaler output.
- bit 2-0 TOPS2:TOPS0: Timer0 Prescaler Select bits
 - 111 = 1:256 Prescale value
 - 110 = 1:128 Prescale value
 - 101 = 1:64 Prescale value
 - 100 = 1:32 Prescale value
 - 011 = 1:16 Prescale value
 - 010 = 1:8 Prescale value
 - 001 = 1:4 Prescale value
 - 000 = 1:2 Prescale value


egend:	
--------	--

Legenu.					
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		


^{© 2006} Microchip Technology Inc.

PIC18FXX8

FIGURE 11-1: TIMER0 BLOCK DIAGRAM IN 8-BIT MODE







11.1 Timer0 Operation

Timer0 can operate as a timer or as a counter.

Timer mode is selected by clearing the T0CS bit. In Timer mode, the Timer0 module will increment every instruction cycle (without prescaler). If the TMR0L register is written, the increment is inhibited for the following two instruction cycles. The user can work around this by writing an adjusted value to the TMR0L register.

Counter mode is selected by setting the T0CS bit. In Counter mode, Timer0 will increment either on every rising or falling edge of pin RA4/T0CKI. The incrementing edge is determined by the Timer0 Source Edge Select bit (T0SE). Clearing the T0SE bit selects the rising edge. Restrictions on the external clock input are discussed below.

When an external clock input is used for Timer0, it must meet certain requirements. The requirements ensure the external clock can be synchronized with the internal phase clock (Tosc). Also, there is a delay in the actual incrementing of Timer0 after synchronization.

11.2 Prescaler

An 8-bit counter is available as a prescaler for the Timer0 module. The prescaler is not readable or writable.

The PSA and T0PS2:T0PS0 bits determine the prescaler assignment and prescale ratio.

Clearing bit PSA will assign the prescaler to the Timer0 module. When the prescaler is assigned to the Timer0 module, prescale values of 1:2, 1:4, ..., 1:256 are selectable.

When assigned to the Timer0 module, all instructions writing to the TMR0 register (e.g., CLRF TMR0, MOVWF TMR0, BSF TMR0, x.... etc.) will clear the prescaler count.

Note:	Writing to TMR0 when the prescaler is						
	assigned to Timer0 will clear the prescaler						
	count but will not change the prescaler						
	assignment.						

11.2.1 SWITCHING PRESCALER ASSIGNMENT

The prescaler assignment is fully under software control (i.e., it can be changed "on-the-fly" during program execution).

11.3 Timer0 Interrupt

The TMR0 interrupt is generated when the TMR0 register overflows from FFh to 00h in 8-bit mode or FFFFh to 000h in 16-bit mode. This overflow sets the TMR0IF bit. The interrupt can be masked by clearing the TMR0IE bit. The TMR0IF bit must be cleared in software by the Timer0 module Interrupt Service Routine before re-enabling this interrupt. The TMR0 interrupt cannot awaken the processor from Sleep since the timer is shut-off during Sleep.

11.4 16-Bit Mode Timer Reads and Writes

Timer0 can be set in 16-bit mode by clearing the T08BIT in T0CON. Registers TMR0H and TMR0L are used to access the 16-bit timer value.

TMR0H is not the high byte of the timer/counter in 16-bit mode, but is actually a buffered version of the high byte of Timer0 (refer to Figure 11-1). The high byte of the Timer0 timer/counter is not directly readable nor writable. TMR0H is updated with the contents of the high byte of Timer0 during a read of TMR0L. This provides the ability to read all 16 bits of Timer0 without having to verify that the read of the high and low byte were valid, due to a rollover between successive reads of the high and low byte.

A write to the high byte of Timer0 must also take place through the TMR0H Buffer register. Timer0 high byte is updated with the contents of the buffered value of TMR0H when a write occurs to TMR0L. This allows all 16 bits of Timer0 to be updated at once.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets	
TMR0L	Timer0 Module Low Byte Register								xxxx xxxx	uuuu uuuu	
TMR0H	Timer0 Modu	Timer0 Module High Byte Register							0000 0000	0000 0000	
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u	
T0CON	TMR0ON	T08BIT	TOCS	T0SE	PSA	T0PS2	T0PS1	T0PS0	1111 1111	1111 1111	
TRISA	— PORTA Data Direction Register ⁽¹⁾							-111 1111	-111 1111		

 TABLE 11-1:
 REGISTERS ASSOCIATED WITH TIMER0

Legend: x = unknown, u = unchanged, - = unimplemented locations read as '0'. Shaded cells are not used by Timer0.

Note 1: Bit 6 of PORTA, LATA and TRISA is enabled in ECIO and RCIO Oscillator modes only. In all other oscillator modes, it is disabled and reads as '0'.

^{© 2006} Microchip Technology Inc.

PIC18FXX8

NOTES:

DS41159E-page 112

12.0 TIMER1 MODULE

The Timer1 module timer/counter has the following features:

- 16-bit timer/counter (two 8-bit registers: TMR1H and TMR1L)
- Readable and writable (both registers)
- Internal or external clock select
- Interrupt-on-overflow from FFFFh to 0000h
- Reset from CCP module special event trigger

Register 12-1 shows the Timer1 Control register. This register controls the operating mode of the Timer1 module, as well as contains the Timer1 Oscillator Enable bit (T1OSCEN). Timer1 can be enabled/ disabled by setting/clearing control bit, TMR1ON (T1CON register).

Figure 12-1 is a simplified block diagram of the Timer1 module.

Note: Timer1 is disabled on POR.

REGISTER 12-1: T1CON: TIMER1 CONTROL REGISTER

R/W-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
RD16		T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR1ON
bit 7							bit 0

	RD16: 16-bit Read/Write Mode Enable bit
	 1 = Enables register read/write of Timer1 in one 16-bit operation 0 = Enables register read/write of Timer1 in two 8-bit operations
	Unimplemented: Read as '0'
-4	T1CKPS1:T1CKPS0: Timer1 Input Clock Prescale Select bits
	11 = 1:8 Prescale value
	10 = 1:4 Prescale value
	01 = 1:2 Prescale value
	00 = 1:1 Prescale value
	T1OSCEN: Timer1 Oscillator Enable bit
	1 = Timer1 oscillator is enabled
	0 = Timer1 oscillator is shut-off
	The oscillator inverter and feedback resistor are turned off to eliminate power drain.
	T1SYNC: Timer1 External Clock Input Synchronization Select bit
	When TMR1CS = 1:
	1 = Do not synchronize external clock input
	0 = Synchronize external clock input
	<u>When TMR1CS = 0</u> : This lift is immediate the interval shall be the TMR1CO \sim
	This bit is ignored. Timer1 uses the internal clock when $TMR1CS = 0$.
	TMR1CS: Timer1 Clock Source Select bit
	1 = External clock from pin RC0/T1OSO/T1CKI (on the rising edge)
	0 = Internal clock (Fosc/4)
	TMR1ON: Timer1 On bit
	1 = Enables Timer1
	0 = Stops Timer1

Legenu.					
R = Readable bit W = Writable bit		U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown		

^{© 2006} Microchip Technology Inc.

12.1 **Timer1 Operation**

Timer1 can operate in one of these modes:

· As a timer

FIGURE 12-1:


- · As a synchronous counter
- As an asynchronous counter

The operating mode is determined by the clock select bit, TMR1CS (T1CON register).

When TMR1CS is clear, Timer1 increments every instruction cycle. When TMR1CS is set, Timer1 increments on every rising edge of the external clock input or the Timer1 oscillator, if enabled.


When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T1CKI pins become inputs. That is, the TRISC<1:0> value is ignored.

Timer1 also has an internal "Reset input". This Reset can be generated by the CCP module (Section 15.1 "CCP1 Module").



TIMER1 BLOCK DIAGRAM





12.2 Timer1 Oscillator

A crystal oscillator circuit is built in between pins T1OSI (input) and T1OSO (amplifier output). It is enabled by setting control bit T1OSCEN (T1CON register). The oscillator is a low-power oscillator rated up to 50 kHz. It will continue to run during Sleep. It is primarily intended for a 32 kHz crystal. Table 12-1 shows the capacitor selection for the Timer1 oscillator.

The user must provide a software time delay to ensure proper start-up of the Timer1 oscillator.

TABLE 12-1: CAPACITOR SELECTION FOR THE ALTERNATE OSCILLATOR

OUDILLATON									
Osc Type	Freq	C1	C2						
LP	32 kHz	TBD ⁽¹⁾	TBD ⁽¹⁾						
	Crystal to be Tested:								
32.768 kHz Epson C-001R32.768K-A ±20 PPM									

- Note 1: Microchip suggests 33 pF as a starting point in validating the oscillator circuit.
 - Higher capacitance increases the stability of the oscillator, but also increases the start-up time.
 - Since each resonator/crystal has its own characteristics, the user should consult the resonator/crystal manufacturer for appropriate values of external components.
 - 4: Capacitor values are for design guidance only.

12.3 Timer1 Interrupt

The TMR1 register pair (TMR1H:TMR1L) increments from 0000h to FFFFh and rolls over to 0000h. The TMR1 Interrupt, if enabled, is generated on overflow which is latched in interrupt flag bit, TMR1IF (PIR registers). This interrupt can be enabled/disabled by setting/clearing TMR1 Interrupt Enable bit, TMR1IE (PIE registers).

12.4 Resetting Timer1 Using a CCP Trigger Output

If the CCP module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer1 and start an A/D conversion (if the A/D module is enabled).

Note:	The special event triggers f	from the CCP1
	module will not set inte	rrupt flag bit,
	TMR1IF (PIR registers).	-

Timer1 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer1 is running in Asynchronous Counter mode, this Reset operation may not work.

In the event that a write to Timer1 coincides with a special event trigger from CCP1, the write will take precedence.

In this mode of operation, the CCPR1H:CCPR1L register pair effectively becomes the period register for Timer1.

12.5 Timer1 16-Bit Read/Write Mode

Timer1 can be configured for 16-bit reads and writes (see Figure 12-2). When the RD16 control bit (T1CON register) is set, the address for TMR1H is mapped to a buffer register for the high byte of Timer1. A read from TMR1L will load the contents of the high byte of Timer1 into the Timer1 High Byte Buffer register. This provides the user with the ability to accurately read all 16 bits of Timer1 without having to determine whether a read of the high byte, followed by a read of the low byte, is valid due to a rollover between reads.

A write to the high byte of Timer1 must also take place through the TMR1H Buffer register. Timer1 high byte is updated with the contents of TMR1H when a write occurs to TMR1L. This allows a user to write all 16 bits to both the high and low bytes of Timer1 at once.

The high byte of Timer1 is not directly readable or writable in this mode. All reads and writes must take place through the Timer1 High Byte Buffer register. Writes to TMR1H do not clear the Timer1 prescaler. The prescaler is only cleared on writes to TMR1L.

^{© 2006} Microchip Technology Inc.

TABLE 12-2: REGISTERS ASSOCIATED WITH TIMER1 AS A TIMER/COUNTER

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value POR,		Valu all c Res	other
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111	1111	1111	1111
TMR1L	Holding Register for the Least Significant Byte of the 16-bit TMR1 Register									xxxx	uuuu	uuuu
TMR1H	Holding Register for the Most Significant Byte of the 16-bit TMR1 Register								xxxx	xxxx	uuuu	uuuu
T1CON	RD16	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR1ON	0-00	0000	u-uu	uuuu

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

DS41159E-page 116

13.0 TIMER2 MODULE

The Timer2 module timer has the following features:

- 8-bit timer (TMR2 register)
- 8-bit period register (PR2)
- Readable and writable (both registers)
- Software programmable prescaler (1:1, 1:4, 1:16)
- Software programmable postscaler (1:1 to 1:16)
- Interrupt on TMR2 match of PR2
- SSP module optional use of TMR2 output to generate clock shift

Register 13-1 shows the Timer2 Control register. Timer2 can be shut-off by clearing control bit TMR2ON (T2CON register) to minimize power consumption. Figure 13-1 is a simplified block diagram of the Timer2 module. The prescaler and postscaler selection of Timer2 are controlled by this register.

13.1 Timer2 Operation

Timer2 can be used as the PWM time base for the PWM mode of the CCP module. The TMR2 register is readable and writable and is cleared on any device Reset. The input clock (Fosc/4) has a prescale option of 1:1, 1:4 or 1:16, selected by control bits T2CKPS1:T2CKPS0 (T2CON register). The match output of TMR2 goes through a 4-bit postscaler (which gives a 1:1 to 1:16 scaling inclusive) to generate a TMR2 interrupt (latched in flag bit TMR2IF, PIR registers).

The prescaler and postscaler counters are cleared when any of the following occurs:

- A write to the TMR2 register
- A write to the T2CON register
- Any device Reset (Power-on Reset, MCLR Reset, Watchdog Timer Reset or Brown-out Reset)

TMR2 is not cleared when T2CON is written.

Note: Timer2 is disabled on POR.

REGISTER 13-1: T2CON: TIMER2 CONTROL REGISTER

U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
—	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0
bit 7							bit 0

bit 7 Unimplemented: Read as '0'

DIT 7	Unimplemented: Read a	S 0	
bit 6-3	TOUTPS3:TOUTPS0: Tin	ner2 Output Postscale	e Select bits
	0000 = 1:1 Postscale		
	0001 = 1:2 Postscale		
	•		
	•		
	•		
	1111 = 1:16 Postscale		
bit 2	TMR2ON: Timer2 On bit		
	1 = Timer2 is on		
	0 = Timer2 is off		
bit 1-0	T2CKPS1:T2CKPS0: Tim	ner2 Clock Prescale S	elect bits
	00 = Prescaler is 1		
	01 = Prescaler is 4		
	1x = Prescaler is 16		
	Legend:		
	R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'

-n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

^{© 2006} Microchip Technology Inc.

13.2 Timer2 Interrupt

The Timer2 module has an 8-bit period register, PR2. Timer2 increments from 00h until it matches PR2 and then resets to 00h on the next increment cycle. PR2 is a readable and writable register. The PR2 register is initialized to FFh upon Reset.

13.3 Output of TMR2

The output of TMR2 (before the postscaler) is a clock input to the Synchronous Serial Port module which optionally uses it to generate the shift clock.




FIGURE 13-1: TIMER2 BLOCK DIAGRAM

Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0			all c	ther
GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111	1111	1111	1111
Timer2 Module Register									0000	0000	0000
—	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000	0000	-000	0000
Timer2 Period Register								1111	1111	1111	1111
	GIE/GIEH PSPIF ⁽¹⁾ PSPIE ⁽¹⁾ PSPIP ⁽¹⁾ Timer2 Moo	GIE/GIEH PEIE/GIEL PSPIF ⁽¹⁾ ADIF PSPIE ⁽¹⁾ ADIE PSPIP ⁽¹⁾ ADIP Timer2 Module Register — TOUTPS3	GIE/GIEHPEIE/GIELTMR0IEPSPIF(1)ADIFRCIFPSPIE(1)ADIERCIEPSPIP(1)ADIPRCIPTimer2 Moule RegisterTOUTPS3TOUTPS2	GIE/GIEHPEIE/GIELTMR0IEINT0IEPSPIF(1)ADIFRCIFTXIFPSPIE(1)ADIERCIETXIEPSPIP(1)ADIPRCIPTXIPTimer2 Module RegisterTOUTPS3TOUTPS2TOUTPS1	GIE/GIEHPEIE/GIELTMROIEINTOIERBIEPSPIF(1)ADIFRCIFTXIFSSPIFPSPIE(1)ADIERCIETXIESSPIEPSPIP(1)ADIPRCIPTXIPSSPIPTimer2 MouteRegisterTOUTPS3TOUTPS2TOUTPS1	GIE/GIEHPEIE/GIELTMR0IEINT0IERBIETMR0IFPSPIF(1)ADIFRCIFTXIFSSPIFCCP1IFPSPIE(1)ADIERCIETXIESSPIECCP1IEPSPIP(1)ADIPRCIPTXIPSSPIPCCP1IPTimer2 MouterToUTPS3TOUTPS2TOUTPS1TOUTPS0TMR20N	GIE/GIEHPEIE/GIELTMROIEINTOIERBIETMROIFINTOIFPSPIF(1)ADIFRCIFTXIFSSPIFCCP1IFTMR2IFPSPIE(1)ADIERCIETXIESSPIECCP1IETMR2IEPSPIP(1)ADIPRCIPTXIPSSPIPCCP1IETMR2IETimer2 MoutresFegisterFOUTPS2TOUTPS1TOUTPS0TMR2ONT2CKPS1	GIE/GIEHPEIE/GIELTMROIEINTOIERBIETMROIFINTOIFRBIFPSPIF(1)ADIFRCIFTXIFSSPIFCCP1IFTMR2IFTMR1IFPSPIE(1)ADIERCIETXIESSPIECCP1IETMR2IETMR1IEPSPIP(1)ADIPRCIPTXIPSSPIPCCP1IETMR2IETMR1IETimer2 MoutresFegisterTXIPSSPIPTMR2ONT2CKPS1T2CKPS0	Bit 7Bit 6Bit 5Bit 4Bit 3Bit 3Bit 2Bit 1Bit 0PORGle/GleHPEIE/GIELTMR0IEINTOIERBIETMR0IFINTOIFRBIF0000PSPIF ⁽¹⁾ ADIFRCIFTXIFSSPIFCCP1IFTMR2IFTMR1IF0000PSPIP ⁽¹⁾ ADIERCIETXIESSPIECCP1IETMR2IETMR1IE0000PSPIP ⁽¹⁾ ADIPRCIPTXIPSSPIPCCP1IPTMR2IPTMR1IP1111Timer2 ModelRegisterTOUTPS1TOUTPS0TMR2ONT2CKPS1T2CKPS0-000	GIE/GIEH PEIE/GIEL TMR0IE INTOIE RBIE TMR0IF INTOIF RBIF 0000 0000x PSPIF ⁽¹⁾ ADIF RCIF TXIF SSPIF CCP1IF TMR2IF TMR1IF 0000 0000 PSPIF ⁽¹⁾ ADIF RCIF TXIF SSPIF CCP1IF TMR2IF TMR1IF 0000 0000 PSPIF ⁽¹⁾ ADIF RCIF TXIF SSPIF CCP1IF TMR2IF TMR1IF 0000 0000 PSPIP ⁽¹⁾ ADIP RCIP TXIP SSPIF CCP1IF TMR2IF TMR1IF 1111 1111 Timer2 Motule Registert TOUTPS3 TOUTPS1 TOUTPS0 TMR2ON T2CKPS1 72CKPS0 -000 0000	Bit 7 Bit 6 Bit 5 Bit 4 Bit 3 Bit 2 Bit 1 Bit 0 POR, BOR Bit 0 Gle/GleH PEIe/GleL TMR0IE INTOIE RBIE TMR0IF INTOIF RBIF 0000

TABLE 13-1: REGISTERS ASSOCIATED WITH TIMER2 AS A TIMER/COUNTER

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer2 module.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

14.0 TIMER3 MODULE

The Timer3 module timer/counter has the following features:

- 16-bit timer/counter (two 8-bit registers: TMR3H and TMR3L)
- Readable and writable (both registers)
- Internal or external clock select
- Interrupt-on-overflow from FFFFh to 0000h
- Reset from CCP1/ECCP1 module trigger

Figure 14-1 is a simplified block diagram of the Timer3 module.

Register 14-1 shows the Timer3 Control register. This register controls the operating mode of the Timer3 module and sets the CCP1 and ECCP1 clock source.

Register 12-1 shows the Timer1 Control register. This register controls the operating mode of the Timer1 module, as well as contains the Timer1 Oscillator Enable bit (T1OSCEN) which can be a clock source for Timer3.

Note: Timer3 is disabled on POR.

REGISTER 14-1: T3CON:TIMER3 CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON
bit 7							bit 0

bit 6,3	T3ECCP1:T3CCP1: Timer3 and Timer1 to CCP1/ECCP1 Enable bits $1x = $ Timer3 is the clock source for compare/capture CCP1 and ECCP1 modules
	01 = Timer3 is the clock source for compare/capture of ECCP1, Timer1 is the clock source for compare/capture of CCP1
	00 = Timer1 is the clock source for compare/capture CCP1 and ECCP1 modules
bit 5-4	T3CKPS1:T3CKPS0: Timer3 Input Clock Prescale Select bits
	11 = 1:8 Prescale value
	10 = 1:4 Prescale value
	01 = 1:2 Prescale value 00 = 1:1 Prescale value
bit 2	
DIL 2	T3SYNC: Timer3 External Clock Input Synchronization Control bit
	(Not usable if the system clock comes from Timer1/Timer3.) When TMR3CS = 1:
	1 = Do not synchronize external clock input
	0 = Synchronize external clock input
	When TMR3CS = <u>0</u> :
	This bit is ignored. Timer3 uses the internal clock when TMR3CS = 0 .
bit 1	TMR3CS: Timer3 Clock Source Select bit
	1 = External clock input from Timer1 oscillator or T1CKI (on the rising edge after the first falling edge)
	0 = Internal clock (Fosc/4)
bit 0	TMR3ON: Timer3 On bit
	1 = Enables Timer3
	0 = Stops Timer3
	Legend:
	R = Readable bit $W = Writable bit$ $U = Unimplemented bit, read as '0'$

'0' = Bit is cleared

'1' = Bit is set

-n = Value at POR

x = Bit is unknown

14.1 Timer3 Operation

Timer3 can operate in one of these modes:


- As a timer
- As a synchronous counter
- As an asynchronous counter

The operating mode is determined by the clock select bit, TMR3CS (T3CON register).


When TMR3CS = 0, Timer3 increments every instruction cycle. When TMR3CS = 1, Timer3 increments on every rising edge of the Timer1 external clock input or the Timer1 oscillator, if enabled.

When the Timer1 oscillator is enabled (T1OSCEN is set), the RC1/T1OSI and RC0/T1OSO/T1CKI pins become inputs. That is, the TRISC<1:0> value is ignored.

Timer3 also has an internal "Reset input". This Reset can be generated by the CCP module (Section 15.1 "CCP1 Module").







DS41159E-page 120

Downloaded from: http://www.datasheetcatalog.com/

14.2 Timer1 Oscillator

The Timer1 oscillator may be used as the clock source for Timer3. The Timer1 oscillator is enabled by setting the T1OSCEN bit (T1CON register). The oscillator is a low-power oscillator rated up to 50 kHz. Refer to **Section 12.0 "Timer1 Module**" for Timer1 oscillator details.

14.3 Timer3 Interrupt

The TMR3 register pair (TMR3H:TMR3L) increments from 0000h to 0FFFFh and rolls over to 0000h. The TMR3 interrupt, if enabled, is generated on overflow which is latched in interrupt flag bit TMR3IF (PIR registers). This interrupt can be enabled/disabled by setting/ clearing TMR3 Interrupt Enable bit, TMR3IE (PIE registers).

14.4 Resetting Timer3 Using a CCP Trigger Output

If the CCP module is configured in Compare mode to generate a "special event trigger" (CCP1M3:CCP1M0 = 1011), this signal will reset Timer3.

Note:	The special event triggers from the CC	Р
	module will not set interrupt flag b	it
	TMR3IF (PIR registers).	

Timer3 must be configured for either Timer or Synchronized Counter mode to take advantage of this feature. If Timer3 is running in Asynchronous Counter mode, this Reset operation may not work. In the event that a write to Timer3 coincides with a special event trigger from CCP1, the write will take precedence. In this mode of operation, the CCPR1H:CCPR1L register pair becomes the period register for Timer3. Refer to **Section 15.0** "**Capture/Compare/PWM (CCP) Modules**" for CCP details.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/ GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF	-0-0 0000	-0-0 0000
PIE2	_	CMIE	—	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE	-0-0 0000	-0-0 0000
IPR2	_	CMIP	—	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1 1111	-1-1 1111
TMR3L	Holding Reg	gister for the l	Least Signifi	icant Byte o	f the 16-bit T	MR3 Regis	ter		xxxx xxxx	uuuu uuuu
TMR3H	Holding Reg	gister for the I	Most Signific	cant Byte of	the 16-bit TM	VR3 Regist	ter		xxxx xxxx	uuuu uuuu
T1CON	RD16		T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR1ON	0-00 0000	u-uu uuuu
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 0000	uuuu uuuu

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the Timer1 module.

^{© 2006} Microchip Technology Inc.

PIC18FXX8

NOTES:

DS41159E-page 122

15.0 CAPTURE/COMPARE/PWM (CCP) MODULES

The CCP (Capture/Compare/PWM) module contains a 16-bit register that can operate as a 16-bit Capture register, as a 16-bit Compare register or as a PWM Duty Cycle register.

The operation of the CCP module is identical to that of the ECCP module (discussed in detail in Section 16.0 "Enhanced Capture/Compare/PWM (ECCP) Module") with two exceptions. The CCP module has a Capture special event trigger that can be used as a message received time-stamp for the CAN module (refer to **Section 19.0 "CAN Module**" for CAN operation) which the ECCP module does not. The ECCP module, on the other hand, has Enhanced PWM functionality and auto-shutdown capability. Aside from these, the operation of the module described in this section is the same as the ECCP.

The control register for the CCP module is shown in Register 15-1. Table 15-2 (following page) details the interactions of the CCP and ECCP modules.

REGISTER 15-1: CCP1CON: CCP1 CONTROL REGISTER

	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0
ł	oit 7							bit 0

- bit 7-6 **Unimplemented:** Read as '0'
- bit 5-4 DCxB1:DCxB0: PWM Duty Cycle bit 1 and bit 0

<u>Capture mode:</u>
Unused.
Compare mode:
Unused.

PWM mode:

These bits are the two LSbs (bit 1 and bit 0) of the 10-bit PWM duty cycle. The upper eight bits (DCx9:DCx2) of the duty cycle are found in CCPRxL.

bit 3-0 CCPxM3:CCPxM0: CCPx Mode Select bits

- 0000 = Capture/Compare/PWM off (resets CCPx module)
- 0001 = Reserved
- 0010 = Compare mode, toggle output on match (CCPxIF bit is set)
- 0011 = Capture mode, CAN message received (CCP1 only)
- 0100 = Capture mode, every falling edge
- 0101 = Capture mode, every rising edge
- 0110 = Capture mode, every 4th rising edge
- 0111 = Capture mode, every 16th rising edge
- 1000 = Compare mode, initialize CCP pin low, on compare match force CCP pin high (CCPIF bit is set)
- 1001 = Compare mode, initialize CCP pin high, on compare match force CCP pin low (CCPIF bit is set)
- 1010 = Compare mode, CCP pin is unaffected (CCPIF bit is set)
- 1011 = Compare mode, trigger special event (CCP1IF bit is set; CCP resets TMR1 or TMR3 and starts an A/D conversion if the A/D module is enabled)
- 11xx = PWM mode

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

^{© 2006} Microchip Technology Inc.

15.1 CCP1 Module

Capture/Compare/PWM Register1 (CCPR1) is comprised of two 8-bit registers: CCPR1L (low byte) and CCPR1H (high byte). The CCP1CON register controls the operation of CCP1. All are readable and writable.

Table 15-1 shows the timer resources of the CCP module modes.

TABLE 15-1: CCP1 MODE – TIMER RESOURCE

CCP1 Mode	Timer Resource
Capture	Timer1 or Timer3
Compare	Timer1 or Timer3
PWM	Timer2

15.2 Capture Mode

In Capture mode, CCPR1H:CCPR1L captures the 16bit value of the TMR1 or TMR3 register when an event occurs on pin RC2/CCP1. An event is defined as:

- · every falling edge
- · every rising edge
- every 4th rising edge
- every 16th rising edge

An event is selected by control bits CCP1M3:CCP1M0 (CCP1CON<3:0>). When a capture is made, the interrupt request flag bit, CCP1IF (PIR registers), is set. It must be cleared in software. If another capture occurs before the value in register CCPR1 is read, the old captured value will be lost.

15.2.1 CCP PIN CONFIGURATION

In Capture mode, the RC2/CCP1 pin should be configured as an input by setting the TRISC<2> bit.

Note:	If the RC2/CCP1 is configured as an out-
	put, a write to the port can cause a capture
	condition.

15.2.2 TIMER1/TIMER3 MODE SELECTION

The timers used with the capture feature (either Timer1 and/or Timer3) must be running in Timer mode or Synchronized Counter mode. In Asynchronous Counter mode, the capture operation may not work. The timer used with each CCP module is selected in the T3CON register.

CCP1 Mode	ECCP1 Mode	Interaction
Capture	Capture	TMR1 or TMR3 time base. Time base can be different for each CCP.
Capture	Compare	The compare could be configured for the special event trigger which clears either TMR1 or TMR3, depending upon which time base is used.
Compare	Compare	The compare(s) could be configured for the special event trigger which clears TMR1 or TMR3, depending upon which time base is used.
PWM	PWM	The PWMs will have the same frequency and update rate (TMR2 interrupt).
PWM	Capture	None.
PWM	Compare	None.

TABLE 15-2: INTERACTION OF CCP1 AND ECCP1 MODULES

15.2.3 SOFTWARE INTERRUPT

When the Capture mode is changed, a false capture interrupt may be generated. The user should keep bit CCP1IE (PIE registers) clear to avoid false interrupts and should clear the flag bit CCP1IF, following any such change in operating mode.

15.2.4 CCP1 PRESCALER

There are four prescaler settings specified by bits CCP1M3:CCP1M0. Whenever the CCP1 module is turned off, or the CCP1 module is not in Capture mode, the prescaler counter is cleared. This means that any Reset will clear the prescaler counter.

Switching from one capture prescaler to another may generate an interrupt. Also, the prescaler counter will not be cleared; therefore, the first capture may be from a non-zero prescaler. Example 15-1 shows the recommended method for switching between capture prescalers. This example also clears the prescaler counter and will not generate the "false" interrupt.

15.2.5 CAN MESSAGE TIME-STAMP


The CAN capture event occurs when a message is received in either of the receive buffers. The CAN module provides a rising edge to the CCP1 module to cause a capture event. This feature is provided to time-stamp the received CAN messages.

This feature is enabled by setting the CANCAP bit of the CAN I/O control register (CIOCON<4>). The message receive signal from the CAN module then takes the place of the events on RC2/CCP1.

EXAMPLE 15-1: CHANGING BETWEEN CAPTURE PRESCALERS

CLRF	CCP1CON, F	; Turn CCP module off
MOVLW	NEW_CAPT_PS	; Load WREG with the
		; new prescaler mode
		; value and CCP ON
MOVWF	CCP1CON	; Load CCP1CON with
		; this value

FIGURE 15-1: CAPTURE MODE OPERATION BLOCK DIAGRAM



15.3 Compare Mode

In Compare mode, the 16-bit CCPR1 and ECCPR1 register value is constantly compared against either the TMR1 register pair value or the TMR3 register pair value. When a match occurs, the CCP1 pin can have one of the following actions:

- Driven high
- Driven low
- Toggle output (high-to-low or low-to-high)
- Remains unchanged

The action on the pin is based on the value of control bits CCP1M3:CCP1M0. At the same time, interrupt flag bit CCP1IF is set.

15.3.1 CCP1 PIN CONFIGURATION

The user must configure the CCP1 pin as an output by clearing the appropriate TRISC bit.

Note:	Clearing the CCP1CON register will force					
	the CCP1 compare output latch to the					
	default low level. This is not the data latch.					

15.3.2 TIMER1/TIMER3 MODE SELECTION

Timer1 and/or Timer3 must be running in Timer mode, or Synchronized Counter mode, if the CCP module is using the compare feature. In Asynchronous Counter mode, the compare operation may not work.

15.3.3 SOFTWARE INTERRUPT MODE


When generate software interrupt is chosen, the CCP1 pin is not affected. Only a CCP interrupt is generated (if enabled).

15.3.4 SPECIAL EVENT TRIGGER

In this mode, an internal hardware trigger is generated, which may be used to initiate an action.

The special event trigger output of CCP1 resets either the TMR1 or TMR3 register pair. Additionally, the ECCP1 special event trigger will start an A/D conversion if the A/D module is enabled.

FIGURE 15-2: COMPARE MODE OPERATION BLOCK DIAGRAM



Note: The special event trigger from the ECCP1 module will not set the Timer1 or Timer3 interrupt flag bits.

-												
Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value o POR, B		all o	e on other sets
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INTOIF	RBIF	0000 00	00x	0000	000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 00	000	0000	0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 00	000	0000	0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1:	111	1111	1111
TRISD	PORTD Da	ata Direction	Register						1111 1:	111	1111	1111
TMR1L	Holding Re	egister for the	e Least Sigr	nificant Byte	of the 16-bi	t TMR1 Reg	jister		XXXX XX	xxx	uuuu	uuuu
TMR1H	Holding Re	egister for the	e Most Sign	ificant Byte	of the 16-bit	TMR1 Reg	ster		XXXX XX	xxx	uuuu	uuuu
T1CON	RD16	_	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	0-00 00	000	u-uu	uuuu
CCPR1L	Capture/Co	ompare/PWN	/ Register 1	(LSB)					XXXX XX	xxx	uuuu	uuuu
CCPR1H	Capture/Co	ompare/PWN	/ Register 1	(MSB)					XXXX XX	xxx	uuuu	uuuu
CCP1CON	_	_	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00 00	000	00	0000
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF	-0-0 00	000	- 0 - 0	0000
PIE2	_	CMIE	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE	-0-0 00	000	- 0 - 0	0000
IPR2	—	CMIP	—	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1 13	111	-1-1	1111
TMR3L	Holding Re	Holding Register for the Least Significant Byte of the 16-bit TMR3 Register							XXXX XX	xxx	uuuu	uuuu
TMR3H	Holding Re	Holding Register for the Most Significant Byte of the 16-bit TMR3 Register						XXXX XX	xxx	uuuu	uuuu	
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 00	000	uuuu	uuuu
Logondu												

TABLE 15-3: REGISTERS ASSOCIATED WITH CAPTURE, COMPARE, TIMER1 AND TIMER3

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

^{© 2006} Microchip Technology Inc.

15.4 PWM Mode


In Pulse-Width Modulation (PWM) mode, the CCP1 pin produces up to a 10-bit resolution PWM output. Since the CCP1 pin is multiplexed with the PORTC data latch, the TRISC<2> bit must be cleared to make the CCP1 pin an output.

Note:	Clearing the CCP1CON register will force
	the CCP1 PWM output latch to the default
	low level. This is not the PORTC I/O data
	latch.

Figure 15-3 shows a simplified block diagram of the CCP module in PWM mode.


For a step-by-step procedure on how to set up the CCP module for PWM operation, see **Section 15.4.3** "Setup for PWM Operation".

FIGURE 15-3: SIMPLIFIED PWM BLOCK DIAGRAM



A PWM output (Figure 15-4) has a time base (period) and a time that the output stays high (duty cycle). The frequency of the PWM is the inverse of the period (1/period).

FIGURE 15-4: PWM OUTPUT



15.4.1 PWM PERIOD

The PWM period is specified by writing to the PR2 register. The PWM period can be calculated using the following formula.


EQUATION 15-1:

 $PWM Period = [(PR2) + 1] \bullet 4 \bullet TOSC \bullet$ (TMR2 Prescale Value)

PWM frequency is defined as 1/[PWM period].

When TMR2 is equal to PR2, the following three events occur on the next increment cycle:

- TMR2 is cleared
- The CCP1 pin is set (exception: if PWM duty cycle = 0%, the CCP1 pin will not be set)
- The PWM duty cycle is latched from CCPR1L into CCPR1H



15.4.2 PWM DUTY CYCLE

The PWM duty cycle is specified by writing to the CCPR1L register and to the CCP1CON<5:4> bits. Up to 10-bit resolution is available. The CCPR1L contains the eight MSbs and the CCP1CON<5:4> contains the two LSbs. This 10-bit value is represented by CCPR1L:CCP1CON<5:4>. The following equation is used to calculate the PWM duty cycle in time.

EQUATION 15-2:

CCPR1L and CCP1CON<5:4> can be written to at any time, but the duty cycle value is not latched into CCPR1H until after a match between PR2 and TMR2 occurs (i.e., the period is complete). In PWM mode, CCPR1H is a read-only register.

The CCPR1H register and a 2-bit internal latch are used to double-buffer the PWM duty cycle. This double-buffering is essential for glitchless PWM operation.

When the CCPR1H and 2-bit latch match TMR2, concatenated with an internal 2-bit Q clock or 2 bits of the TMR2 prescaler, the CCP1 pin is cleared.

The maximum PWM resolution (bits) for a given PWM frequency is given by the following equation.

EQUATION 15-3:

PWM Resolution (max) =
$$\frac{\log\left(\frac{\text{Fosc}}{\text{FPWM}}\right)}{\log(2)}$$
 bits

Note: If the PWM duty cycle value is longer than the PWM period, the CCP1 pin will not be cleared.

15.4.3 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the CCP module for PWM operation:

- 1. Set the PWM period by writing to the PR2 register.
- 2. Set the PWM duty cycle by writing to the CCPR1L register and CCP1CON<5:4> bits.
- 3. Make the CCP1 pin an output by clearing the TRISC<2> bit.
- 4. Set the TMR2 prescale value and enable Timer2 by writing to T2CON.
- 5. Configure the CCP1 module for PWM operation.

TABLE 15-4: EXAMPLE PWM FREQUENCIES AND RESOLUTIONS AT 40 MHz

PWM Frequency	2.44 kHz	9.76 kHz	39.06 kHz	156.3 kHz	312.5 kHz	416.6 kHz
Timer Prescaler (1, 4, 16)	16	4	1	1	1	1
PR2 Value	0FFh	0FFh	0FFh	3Fh	1Fh	17h
Maximum Resolution (bits)	10	10	10	8	7	5.5

TABLE 15-5: REGISTERS ASSOCIATED WITH PWM AND TIMER2

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		ie on , BOR	all c	ue on other sets
INTCON	GIE/ GIEH	PEIE/ GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INTOIF	RBIF	0000	000x	0000	000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000	0000	0000	0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000	0000	0000	0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111	1111	1111	1111
TRISD	PORTD Da	ata Direction	Register						1111	1111	1111	1111
TMR2	Timer2 Mo	dule Registe	ər						0000	0000	0000	0000
PR2	Timer2 Mo	dule Period	Register						1111	1111	1111	1111
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000	0000	-000	0000
CCPR1L	Capture/Compare/PWM Register1 (LSB)							xxxx	xxxx	uuuu	uuuu	
CCPR1H	Capture/Compare/PWM Register1 (MSB)							xxxx	xxxx	uuuu	uuuu	
CCP1CON		—	DC1B1	DC1B0	CCP1M3	CCP1M2	CCP1M1	CCP1M0	00	0000	00	0000

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by PWM and Timer2.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

PIC18FXX8

NOTES:

DS41159E-page 130

16.0 ENHANCED CAPTURE/ COMPARE/PWM (ECCP) MODULE

Note:	The ECCP (Enhanced Capture/Compare/							
	PWM)	module	is	only	available	on		
	PIC18F	448 and F	PIC1	8F458	devices.			

This module contains a 16-bit register which can operate as a 16-bit Capture register, a 16-bit Compare register or a PWM Master/Slave Duty Cycle register. The operation of the ECCP module differs from the CCP (discussed in detail in **Section 15.0 "Capture/Compare/PWM (CCP) Modules**") with the addition of an Enhanced PWM module which allows for up to 4 output channels and user selectable polarity. These features are discussed in detail in **Section 16.5** "**Enhanced PWM Mode**". The module can also be programmed for automatic shutdown in response to various analog or digital events.

The control register for ECCP1 is shown in Register 16-1.

REGISTER 16-1: ECCP1CON: ECCP1 CONTROL REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0
bit 7			-		-		bit 0

bit 7-6 **EPWM1M<1:0>:** PWM Output Configuration bits

I<u>f ECCP1M<3:2> = 00, 01, 10:</u>

xx = P1A assigned as Capture/Compare input; P1B, P1C, P1D assigned as port pins If ECCP1M<3:2> = 11:

- 00 = Single output; P1A modulated; P1B, P1C, P1D assigned as port pins
- 01 = Full-bridge output forward; P1D modulated; P1A active; P1B, P1C inactive
- 10 = Half-bridge output; P1A, P1B modulated with deadband control; P1C, P1D assigned as port pins
- 11 = Full-bridge output reverse; P1B modulated; P1C active; P1A, P1D inactive
- bit 5-4 EDC1B<1:0>: PWM Duty Cycle Least Significant bits

Capture mode:

Unused. Compare mode:

Unused.

PWM mode:

These bits are the two LSbs of the PWM duty cycle. The eight MSbs are found in ECCPR1L.

bit 3-0 ECCP1M<3:0>: ECCP1 Mode Select bits

- 0000 = Capture/Compare/PWM off (resets ECCP module)
- 0001 = Unused (reserved)
- 0010 = Compare mode, toggle output on match (ECCP1IF bit is set)
- 0011 = Unused (reserved)
- 0100 = Capture mode, every falling edge
- 0101 = Capture mode, every rising edge
- 0110 = Capture mode, every 4th rising edge
- 0111 = Capture mode, every 16th rising edge
- 1000 = Compare mode, set output on match (ECCP1IF bit is set)
- 1001 = Compare mode, clear output on match (ECCP1IF bit is set)
- 1010 = Compare mode, ECCP1 pin is unaffected (ECCP1IF bit is set)
- 1011 = Compare mode, trigger special event (ECCP1IF bit is set; ECCP resets TMR1or TMR3 and starts an A/D conversion if the A/D module is enabled)
- 1100 = PWM mode; P1A, P1C active-high; P1B, P1D active-high
- 1101 = PWM mode; P1A, P1C active-high; P1B, P1D active-low
- 1110 = PWM mode; P1A, P1C active-low; P1B, P1D active-high
- 1111 = PWM mode; P1A, P1C active-low; P1B, P1D active-low

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

© 2006 Microchip Technology Inc.

16.1 ECCP1 Module

Enhanced Capture/Compare/PWM Register 1 (ECCPR1) is comprised of two 8-bit registers: ECCPR1L (low byte) and ECCPR1H (high byte). The ECCP1CON register controls the operation of ECCP1; the additional registers, ECCPAS and ECCP1DEL, control Enhanced PWM specific features. All registers are readable and writable.

Table 16-1 shows the timer resources for the ECCP module modes. Table 16-2 describes the interactions of the ECCP module with the standard CCP module.

In PWM mode, the ECCP module can have up to four available outputs, depending on which operating mode is selected. These outputs are multiplexed with PORTD and the Parallel Slave Port. Both the operating mode and the output pin assignments are configured by setting PWM output configuration bits, EPWM1M1:EPWM1M0 (ECCP1CON<7:6>). The specific pin assignments for the various output modes are shown in Table 16-3.

TABLE 16-1: ECCP1 MODE – TIMER RESOURCE

ECCP1 Mode	Timer Resource
Capture	Timer1 or Timer3
Compare	Timer1 or Timer3
PWM	Timer2

TABLE 16-2: INTERACTION OF CCP1 AND ECCP1 MODULES

ECCP1 Mode	CCP1 Mode	Interaction
Capture	Capture	TMR1 or TMR3 time base. Time base can be different for each CCP.
Capture	Compare	The compare could be configured for the special event trigger which clears either TMR1 or TMR3 depending upon which time base is used.
Compare	Compare	The compare(s) could be configured for the special event trigger which clears TMR1 or TMR3 depending upon which time base is used.
PWM	PWM	The PWMs will have the same frequency and update rate (TMR2 interrupt).
PWM	Capture	None
PWM	Compare	None

TABLE 16-3: PIN ASSIGNMENTS FOR VARIOUS ECCP MODES
--

ECCP Mode ⁽¹⁾	ECCP1CON Configuration	RD4	RD5	RD6	RD7
Conventional CCP Compatible	00xx11xx	ECCP1	RD<5>, PSP<5>	RD<6>, PSP<6>	RD<7>, PSP<7>
Dual Output PWM ⁽²⁾	10xx11xx	P1A	P1B	RD<6>, PSP<6>	RD<7>, PSP<7>
Quad Output PWM ⁽²⁾	x1xx11xx	P1A	P1B	P1C	P1D

Legend: x = Don't care. Shaded cells indicate pin assignments not used by ECCP in a given mode.

Note 1: In all cases, the appropriate TRISD bits must be cleared to make the corresponding pin an output.

2: In these modes, the PSP I/O control for PORTD is overridden by P1B, P1C and P1D.

16.2 Capture Mode

The Capture mode of the ECCP module is virtually identical in operation to that of the standard CCP module as discussed in **Section 15.1 "CCP1 Module"**. The differences are in the registers and port pins involved:

- The 16-bit Capture register is ECCPR1 (ECCPR1H and ECCPR1L);
- The capture event is selected by control bits ECCP1M3:ECCP1M0 (ECCP1CON<3:0>);
- The interrupt bits are ECCP1IE (PIE2<0>) and ECCP1IF (PIR2<0>); and
- The capture input pin is RD4 and its corresponding direction control bit is TRISD<4>.

Other operational details, including timer selection, output pin configuration and software interrupts, are exactly the same as the standard CCP module.

16.2.1 CAN MESSAGE TIME-STAMP

TABLE 16-4:

The special capture event for the reception of CAN messages (Section 15.2.5 "CAN Message Time-Stamp") is not available with the ECCP module.

16.3 Compare Mode

The Compare mode of the ECCP module is virtually identical in operation to that of the standard CCP module as discussed in **Section 15.2** "**Capture Mode**". The differences are in the registers and port pins as described in **Section 16.2** "**Capture Mode**". All other details are exactly the same.

16.3.1 SPECIAL EVENT TRIGGER

Except as noted below, the special event trigger output of ECCP1 functions identically to that of the standard CCP module. It may be used to start an A/D conversion if the A/D module is enabled.

Note: The special event trigger from the ECCP1 module will not set the Timer1 or Timer3 interrupt flag bits.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOI	all other
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INTOIF	RBIF	0000 000	x 0000 000u
PIR2	_	CMIF	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF	-0-0 000	0 -0-0 0000
PIE2	_	CMIE		EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE	-0-0 000	0 -0-0 0000
IPR2	_	CMIP		EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1 111	1 -1-1 1111
TMR1L	Holding Reg	jister for the I	Least Signi	ficant Byte	of the 16-bit	TMR1 Regi	ster		XXXX XXX	x uuuu uuuu
TMR1H	Holding Reg	jister for the I	Most Signif	icant Byte c	of the 16-bit	TMR1 Regis	ster		XXXX XXX	x uuuu uuuu
T1CON	RD16	—	T1CKPS1	T1CKPS0	T1OSCEN	T1SYNC	TMR1CS	TMR10N	0-00 000	0 u-uu uuuu
TMR3L	Holding Reg	jister for the I	Least Signi	ficant Byte	of the 16-bit	TMR3 Regi	ster		XXXX XXX	x uuuu uuuu
TMR3H	Holding Reg	jister for the I	Most Signif	icant Byte c	of the 16-bit	TMR3 Regis	ster		XXXX XXX	x uuuu uuuu
T3CON	RD16	T3ECCP1	T3CKPS1	T3CKPS0	T3CCP1	T3SYNC	TMR3CS	TMR3ON	0000 000	0 uuuu uuuu
TRISD	PORTD Dat	a Direction R	legister						1111 111	1 1111 1111
ECCPR1L	Capture/Cor	mpare/PWM	Register1 ((LSB)					XXXX XXX	x uuuu uuuu
ECCPR1H	Capture/Cor	mpare/PWM		XXXX XXX	x uuuu uuuu					
ECCP1CON	EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0	0000 000	0 0000 0000

REGISTERS ASSOCIATED WITH ENHANCED CAPTURE, COMPARE,

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the ECCP module and Timer1.

16.4 Standard PWM Mode

When configured in Single Output mode, the ECCP module functions identically to the standard CCP module in PWM mode as described in **Section 15.4** "**PWM Mode**". The differences in registers and ports are as described in **Section 16.2** "**Capture Mode**". In addition, the two Least Significant bits of the 10-bit PWM duty cycle value are represented by ECCP1CON<5:4>.

Note: When setting up single output PWM operations, users are free to use either of the processes described in Section 15.4.3 "Setup for PWM Operation" or Section 16.5.8 "Setup for PWM Operation". The latter is more generic, but will work for either single or multi-output PWM.

16.5 Enhanced PWM Mode

The Enhanced PWM mode provides additional PWM output options for a broader range of control applications. The module is an upwardly compatible version of the standard CCP module and is modified to provide up to four outputs, designated P1A through P1D. Users are also able to select the polarity of the signal (either active-high or active-low). The module's output mode and polarity are configured by setting the EPWM1M1:EPWM1M0 and ECCP1M3:ECCP1M0 bits of the ECCP1CON register (ECCP1CON<7:6> and ECCP1CON<3:0>, respectively). Figure 16-1 shows a simplified block diagram of PWM operation. All control registers are double-buffered and are loaded at the beginning of a new PWM cycle (the period boundary when the assigned timer resets) in order to prevent glitches on any of the outputs. The exception is the PWM Delay register, ECCP1DEL, which is loaded at either the duty cycle boundary or the boundary period (whichever comes first). Because of the buffering, the module waits until the assigned timer resets instead of starting immediately. This means that Enhanced PWM waveforms do not exactly match the standard PWM waveforms, but are instead offset by one full instruction cycle (4 TOSC).

As before, the user must manually configure the appropriate TRISD bits for output.

16.5.1 PWM OUTPUT CONFIGURATIONS

The EPWM1M<1:0> bits in the ECCP1CON register allow one of four configurations:

- Single Output
- · Half-Bridge Output
- Full-Bridge Output, Forward mode
- Full-Bridge Output, Reverse mode

The Single Output mode is the standard PWM mode discussed in **Section 15.4** "**PWM Mode**". The Half-Bridge and Full-Bridge Output modes are covered in detail in the sections that follow.

The general relationship of the outputs in all configurations is summarized in Figure 16-2.




FIGURE 16-1: SIMPLIFIED BLOCK DIAGRAM OF THE ENHANCED PWM MODULE

PIC18FXX8

FIGURE 16-2:	PWM OUTPUT REL	ΔΤΙΟΝΟΗΙΡΟ
		ALIONSHIPS

ECCP1CC	N SIGNAL	0	-	Duty Cycle>	1 -1	PR2 + 1
<7:6>			-		Period —	
	P1A Modulated, Active-High		; 		; 1	
00	P1A Modulated, Active-Low		1			
	P1A Modulated, Active-High		Ļ		1	1 1 1
1.0	P1A Modulated, Active-Low		: :		Delay	1 1 1
10	P1B Modulated, Active-High			Delay		i
	P1B Modulated, Active-Low		1 1 1		<u>.</u>	İ
	P1A Active, Active-High		1 1 1		- - - - -	
	P1A Active, Active-Low		1 1 1		1 1 1	- - - -
	P1B Inactive, Active-High				1 1 1	
	P1B Inactive, Active-Low		1 1 1		<u> </u> 	: i
01	P1C Inactive, Active-High		;		1 1 1	י י י
	P1C Inactive, Active-Low		1 1 1		1 1 1	! !
	P1D Modulated, Active-High		<u> </u>		į́	1 1
	P1D Modulated, Active-Low		1			
	P1A Inactive, Active-High		· · ·		1 1 1	· · ·
	P1A Inactive, Active-Low		<u>.</u>		- - - - -	
	P1B Modulated, Active-High		<u>.</u>		1	
	P1B Modulated, Active-Low		į			
11	P1C Active, Active-High		1 1 1		1 1 1	; ;
	P1C Active, Active-Low		1 1 1		1 1 1	, , ,
	P1D Inactive, Active-High		1		- - - -	
	P1D Inactive, Active-Low		1 1 1		1 1 1	
					1	:
Relations	hips:					

- Duty Cycle = Tosc * (CCPR1L<7:0>:CCP1CON<5:4>) * (TMR2 Prescale Value)
- Delay = 4 * Tosc * ECCP1DEL

© 2006 Microchip Technology Inc.

16.5.2 HALF-BRIDGE MODE

In the Half-Bridge Output mode, two pins are used as outputs to drive push-pull loads. The RD4/PSP4/ ECCP1/P1A pin has the PWM output signal, while the RD5/PSP5/P1B pin has the complementary PWM output signal (Figure 16-3). This mode can be used for half-bridge applications, as shown in Figure 16-4, or for full-bridge applications where four power switches are being modulated with two PWM signals.

In Half-Bridge Output mode, the programmable deadband delay can be used to prevent shoot-through current in bridge power devices. The value of register ECCP1DEL dictates the number of clock cycles before the output is driven active. If the value is greater than the duty cycle, the corresponding output remains inactive during the entire cycle. See **Section 16.5.4 "Programmable Dead-Band Delay"** for more details of the dead-band delay operations.

Since the P1A and P1B outputs are multiplexed with the PORTD<4> and PORTD<5> data latches, the TRISD<4> and TRISD<5> bits must be cleared to configure P1A and P1B as outputs.

FIGURE 16-3: HALF-BRIDGE PWM OUTPUT





FIGURE 16-4: EXAMPLES OF HALF-BRIDGE OUTPUT MODE APPLICATIONS




16.5.3 FULL-BRIDGE MODE

In Full-Bridge Output mode, four pins are used as outputs; however, only two outputs are active at a time. In the Forward mode, pin RD4/PSP4/ECCP1/P1A is continuously active and pin RD7/PSP7/P1D is modulated. In the Reverse mode, RD6/PSP6/P1C pin is continuously active and RD5/PSP5/P1B pin is modulated. These are illustrated in Figure 16-5.


FIGURE 16-5: FULL-BRIDGE PWM OUTPUT

P1A, P1B, P1C and P1D outputs are multiplexed with the PORTD<4:7> data latches. The TRISD<4:7> bits must be cleared to make the P1A, P1B, P1C and P1D pins output.



^{© 2006} Microchip Technology Inc.





16.5.3.1 Direction Change in Full-Bridge Mode

In the Full-Bridge Output mode, the EPWM1M1 bit in the ECCP1CON register allows the user to control the forward/reverse direction. When the application firmware changes this direction control bit, the ECCP1 module will assume the new direction on the next PWM cycle. The current PWM cycle still continues, however, the non-modulated outputs, P1A and P1C signals, will transition to the new direction Tosc, 4 Tosc or 16 Tosc earlier (for T2CKRS<1:0> = 00, 01 or 1x, respectively) before the end of the period. During this transition cycle, the modulated outputs, P1B and P1D, will go to the inactive state (Figure 16-7).

Note that in the Full-Bridge Output mode, the ECCP module does not provide any dead-band delay. In general, since only one output is modulated at all times, dead-band delay is not required. However, there is a situation where a dead-band delay might be required. This situation occurs when all of the following conditions are true:


- 1. The direction of the PWM output changes when the duty cycle of the output is at or near 100%.
- 2. The turn-off time of the power switch, including the power device and driver circuit, is greater than turn-on time.

Figure 16-8 shows an example where the PWM direction changes from forward to reverse at a near 100% duty cycle. At time t1, the outputs P1A and P1D become inactive, while output P1C becomes active. In this example, since the turn-off time of the power devices is longer than the turn-on time, a shoot-through current flows through power devices QB and QD (see Figure 16-6) for the duration of 't'. The same phenomenon will occur to power devices QA and QC for PWM direction change from reverse to forward.


If changing PWM direction at high duty cycle is required for an application, one of the following requirements must be met:

- 1. Avoid changing PWM output direction at or near 100% duty cycle.
- 2. Use switch drivers that compensate the slow turn off of the power devices. The total turn-off time (t_{off}) of the power device and the driver must be less than the turn-on time (t_{on}) .









^{© 2006} Microchip Technology Inc.

16.5.4 PROGRAMMABLE DEAD-BAND DELAY

In half-bridge or full-bridge applications, where all power switches are modulated at the PWM frequency at all times, the power switches normally require longer time to turn off than to turn on. If both the upper and lower power switches are switched at the same time (one turned on and the other turned off), both switches will be on for a short period of time until one switch completely turns off. During this time, a very high current (*shoot-through current*) flows through both power switches, shorting the bridge supply. To avoid this potentially destructive shoot-through current from flowing during switching, turning on the power switch is normally delayed to allow the other switch to completely turn off.

In the Half-Bridge Output mode, a digitally programmable dead-band delay is available to avoid shoot-through current from destroying the bridge power switches. The delay occurs at the signal transition from the non-active state to the active state. See Figure 16-3 for illustration. The ECCP1DEL register (Register 16-2) sets the amount of delay.

16.5.5 SYSTEM IMPLEMENTATION

When the ECCP module is used in the PWM mode, the application hardware must use the proper external pullup and/or pull-down resistors on the PWM output pins. When the microcontroller powers up, all of the I/O pins are in the high-impedance state. The external pull-up and pull-down resistors must keep the power switch devices in the off state until the microcontroller drives the I/O pins with the proper signal levels, or activates the PWM output(s).

16.5.6 START-UP CONSIDERATIONS

Prior to enabling the PWM outputs, the P1A, P1B, P1C and P1D latches may not be in the proper states. Enabling the TRISD bits for output at the same time with the ECCP1 module may cause damage to the power switch devices. The ECCP1 module must be enabled in the proper output mode with the TRISD bits enabled as inputs. Once the ECCP1 completes a full PWM cycle, the P1A, P1B, P1C and P1D output latches are properly initialized. At this time, the TRISD bits can be enabled for outputs to start driving the power switch devices. The completion of a full PWM cycle is indicated by the TMR2IF bit going from a '0' to a '1'.

16.5.7 OUTPUT POLARITY CONFIGURATION

The ECCP1M<1:0> bits in the ECCP1CON register allow user to choose the logic conventions (asserted high/low) for each of the outputs.

The PWM output polarities must be selected before the PWM outputs are enabled. Charging the polarity configuration while the PWM outputs are active is not recommended since it may result in unpredictable operation.

REGISTER 16-2: ECCP1DEL: PWM DELAY REGISTER

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
EPDC7	EPDC6	EPDC5	EPDC4	EPDC3	EPDC2	EPDC1	EPDC0		
bit 7									

bit 7-0 EPDC<7:0>: PWM Delay Count for Half-Bridge Output Mode bits

Number of FOSC/4 (TOSC * 4) cycles between the P1A transition and the P1B transition.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

16.5.8 SETUP FOR PWM OPERATION

The following steps should be taken when configuring the ECCP1 module for PWM operation:

- 1. Configure the PWM module:
 - a) Disable the ECCP1/P1A, P1B, P1C and/or P1D outputs by setting the respective TRISD bits.
 - b) Set the PWM period by loading the PR2 register.
 - c) Set the PWM duty cycle by loading the ECCPR1L register and ECCP1CON<5:4> bits.
 - d) Configure the ECCP1 module for the desired PWM operation by loading the ECCP1CON register with the appropriate value. With the ECCP1M<3:0> bits, select the active-high/low levels for each PWM output. With the EPWM1M<1:0> bits, select one of the available output modes.
 - e) For Half-Bridge Output mode, set the deadband delay by loading the ECCP1DEL register with the appropriate value.

- 2. Configure and start TMR2:
 - a) Clear the TMR2 interrupt flag bit by clearing the TMR2IF bit in the PIR1 register.
 - b) Set the TMR2 prescale value by loading the T2CKPS bits (T2CON<1:0>).
 - c) Enable Timer2 by setting the TMR2ON bit (T2CON<2>) register.
- 3. Enable PWM outputs after a new cycle has started:
 - a) Wait until TMR2 overflows (TMR2IF bit becomes a '1'). The new PWM cycle begins here.
 - b) Enable the ECCP1/P1A, P1B, P1C and/or P1D pin outputs by clearing the respective TRISD bits.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value POR, I		Value on all other Resets	
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000	000x	0000	000u
RCON	IPEN	_	—	RI	TO	PD	POR	BOR	01	110q	0 0	011q
IPR2	—	CMIP	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP	-1-1 3	1111	-1-1	1111
PIR2	—	CMIF — EEIF BCLIF LVDIF TMR3IF ECCP1IF						-0-0	0000	- 0 - 0	0000	
PIE2	_	- CMIE - EEIE BCLIE LVDIE TMR3IE ECCP1IE								0000	- 0 - 0	0000
TMR2	Timer2 Mod	ule Register							0000	0000	0000	0000
PR2	Timer2 Mod	ule Period Re	egister						1111 :	1111	1111	1111
T2CON	_	TOUTPS3	TOUTPS2	TOUTPS1	TOUTPS0	TMR2ON	T2CKPS1	T2CKPS0	-000	0000	-000	0000
TRISD	PORTD Dat	a Direction R	egister						1111 :	1111	1111	1111
ECCPR1H	Enhanced C	Capture/Comp	are/PWM R	egister 1 H	igh Byte				XXXX X	xxxx	uuuu	uuuu
ECCPR1L	Enhanced C	Capture/Comp	are/PWM R	egister 1 Lo	ow Byte				XXXX X	xxxx	uuuu	uuuu
ECCP1CON	EPWM1M1	EPWM1M0	EDC1B1	EDC1B0	ECCP1M3	ECCP1M2	ECCP1M1	ECCP1M0	0000	0000	0000	0000
ECCPAS	ECCPASE	ECCPAS2	ECCPAS1	ECCPAS0	PSSAC1	PSSAC0	PSSBD1	PSSBD0	0000	0000	0000	0000
ECCP1DEL	EPDC7	EPDC6	EPDC5	EPDC4	EPDC3	EPDC2	EPDC1	EPDC0	0000	0000	uuuu	uuuu

TABLE 16-5: REGISTERS ASSOCIATED WITH ENHANCED PWM AND TIMER2

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the ECCP module.

16.6 Enhanced CCP Auto-Shutdown

When the ECCP is programmed for any of the PWM modes, the output pins associated with its function may be configured for auto-shutdown.

Auto-shutdown allows the internal output of either of the two comparator modules, or the external interrupt 0, to asynchronously disable the ECCP output pins. Thus, an external analog or digital event can discontinue an ECCP sequence. The comparator output(s) to be used is selected by setting the proper mode bits in the ECCPAS register. To use external interrupt INT0 as a shutdown event, INT0IE must be set. To use either of the comparator module outputs as a shutdown event, corresponding comparators must be enabled. When a shutdown occurs, the selected output values (PSSACn, PSSBDn) are written to the ECCP port pins. The internal shutdown signal is gated with the outputs and will immediately and asynchronously disable the outputs. If the internal shutdown is still in effect at the time a new cycle begins, that entire cycle is suppressed, thus eliminating narrow, glitchy pulses.

The ECCPASE bit is set by hardware upon a comparator event and can only be cleared in software. The ECCP outputs can be re-enabled only by clearing the ECCPASE bit.

The Auto-Shutdown mode can be manually entered by writing a '1' to the ECCPASE bit.

REGISTER 16-3: ECCPAS: ENHANCED CAPTURE/COMPARE/PWM AUTO-SHUTDOWN CONTROL REGISTER

	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	ECCPASE	ECCPAS2	ECCPAS1	ECCPAS0	PSSAC1	PSSAC0	PSSBD1	PSSBD0
	bit 7							bit 0
bit 7	ECCPASE: ECCP Auto-Shutdown Event Status bit 0 = ECCP outputs enabled, no shutdown event 1 = A shutdown event has occurred, must be reset in software to re-enable ECCP							
bit 6-4	4 ECCPAS<2:0>: ECCP Auto-Shutdown bits							
	 000 = No auto-shutdown enabled, comparators have no effect on ECCP 001 = Comparator 1 output will cause shutdown 010 = Comparator 2 output will cause shutdown 011 = Either Comparator 1 or 2 can cause shutdown 100 = INT0 101 = INT0 or Comparator 1 output 110 = INT0 or Comparator 2 output 111 = INT0 or Comparator 1 or Comparator 2 output 							
bit 3-2	PSSACn: Pins A and C Shutdown State Control bits							
	00 = Drive Pins A and C to '0' 01 = Drive Pins A and C to '1' 1x = Pins A and C tri-state							
bit 1-0	 PSSBDn: Pins B and D Shutdown State Control bits 00 = Drive Pins B and D to '0' 01 = Drive Pins B and D to '1' 							
	1x = Pins B and D tri-state							
	Legend:							
	R = Readable bit W = Writable bit U = Unimplemented bit, read as '0'							
	The House bit W - Whale bit 0 - Ohimperioritod bit, feat as 0							

R = Readable bitW = Writable bitU = Unimplemented bit, read as '0'-n = Value at POR'1' = Bit is set'0' = Bit is clearedx = Bit is unknown

17.0 MASTER SYNCHRONOUS SERIAL PORT (MSSP) MODULE

17.1 Master SSP (MSSP) Module Overview

The Master Synchronous Serial Port (MSSP) module is a serial interface useful for communicating with other peripheral or microcontroller devices. These peripheral devices may be serial EEPROMs, shift registers, display drivers, A/D converters, etc. The MSSP module can operate in one of two modes:

- Serial Peripheral Interface (SPI)
- Inter-Integrated Circuit (I²C)
 - Full Master mode
 - Slave mode (with general address call)

The I²C interface supports the following modes in hardware:

- Master mode
- Multi-Master mode
- Slave mode

17.2 Control Registers

The MSSP module has three associated registers. These include a status register (SSPSTAT) and two control registers (SSPCON1 and SSPCON2). The use of these registers and their individual configuration bits differ significantly, depending on whether the MSSP module is operated in SPI or I^2C mode.

Additional details are provided under the individual sections.

17.3 SPI Mode

The SPI mode allows 8 bits of data to be synchronously transmitted and received simultaneously. All four modes of SPI are supported. To accomplish communication, typically three pins are used:


- Serial Data Out (SDO) RC5/SDO
- Serial Data In (SDI) RC4/SDI/SDA
- Serial Clock (SCK) RC3/SCK/SCL

Additionally, a fourth pin may be used when in a Slave mode of operation:

Slave Select (SS) – RA5/AN4/SS/LVDIN

Figure 17-1 shows the block diagram of the MSSP module when operating in SPI mode.

FIGURE 17-1: MSSP BLOCK DIAGRAM (SPI™ MODE)



^{© 2006} Microchip Technology Inc.

17.3.1 REGISTERS

The MSSP module has four registers for SPI mode operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible

SSPCON1 and SSPSTAT are the control and status registers in SPI mode operation. The SSPCON1 register is readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write. SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not doublebuffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

REGISTER 17-1: SSPSTAT: MSSP STATUS REGISTER (SPI MODE)

R/W-0	R/W-0	R-0	R-0	R-0	R-0	R-0	R-0
SMP	CKE	D/A	Р	S	R/W	UA	BF
bit 7							bit 0

bit 7	SMP: Sample bit								
	SPI Maste	r mode:							
			at end of data output tir						
	0 = Input data sampled at middle of data output time								
	SPI Slave								
			when SPI is used in Slaw	/e mode.					
bit 6		Clock Edge							
			transition from active to						
	0 = Iransr		transition from Idle to a						
	Note:	Polarity of c	clock state is set by the	CKP bit (SSPCON1<4>	·).				
bit 5	D/A: Data	Address bit							
	Used in I ²	C mode only.							
bit 4	P: Stop bit	1							
	Used in I ²	C mode only	y. This bit is cleared wl	hen the MSSP module	is disabled, SSPEN is				
	cleared.								
bit 3	S: Start bit	t							
	Used in I ²	C mode only.							
bit 2	R/W: Read	d/Write Inform	nation bit						
	Used in I ²	C mode only.							
bit 1	UA: Upda	te Address bi	it						
	Used in I ²	C mode only.							
bit 0	BF: Buffer	Full Status b	it (Receive mode only)						
			SSPBUF is full						
	0 = Receiv	ve not comple	ete, SSPBUF is empty						
	Legend:								
	R = Reada	able bit	W = Writable bit	U = Unimplemented b	it, read as '0'				
	-n = Value	at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown				

REGISTER 17-2: SSPCON1: MSSP CONTROL REGISTER 1 (SPI MODE)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0		
bit 7									

bit 7 WCOL: Write Collision Detect bit (Transmit mode only)

 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)

0 = No collision

bit 6 SSPOV: Receive Overflow Indicator bit

SPI Slave mode:

- 1 = A new byte is received while the SSPBUF register is still holding the previous data. In case of overflow, the data in SSPSR is lost. Overflow can only occur in Slave mode. The user must read the SSPBUF even if only transmitting data to avoid setting overflow (must be cleared in software).
- 0 = No overflow
 - **Note:** In Master mode, the overflow bit is not set since each new reception (and transmission) is initiated by writing to the SSPBUF register.

bit 5 SSPEN: Synchronous Serial Port Enable bit

- 1 = Enables serial port and configures SCK, SDO, SDI and \overline{SS} as serial port pins
- 0 = Disables serial port and configures these pins as I/O port pins

Note: When enabled, these pins must be properly configured as input or output.

- bit 4 CKP: Clock Polarity Select bit
 - 1 = Idle state for clock is a high level
 - 0 = Idle state for clock is a low level
- bit 3-0 SSPM3:SSPM0: Synchronous Serial Port Mode Select bits
 - 0101 = SPI Slave mode, clock = SCK pin, \overline{SS} pin control disabled, \overline{SS} can be used as I/O pin 0100 = SPI Slave mode, clock = SCK pin, \overline{SS} pin control enabled
 - 0011 = SPI Master mode, clock = TMR2 output/2
 - 0010 = SPI Master mode, clock = Fosc/64
 - 0001 = SPI Master mode, clock = Fosc/16
 - 0000 = SPI Master mode, clock = Fosc/4
 - **Note:** Bit combinations not specifically listed here are either reserved or implemented in I^2C mode only.

Legend:						
R = Readable bit	W = Writable bit	U = Unimplemented	J = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

17.3.2 OPERATION

When initializing the SPI, several options need to be specified. This is done by programming the appropriate control bits (SSPCON1<5:0> and SSPSTAT<7:6>). These control bits allow the following to be specified:

- Master mode (SCK is the clock output)
- Slave mode (SCK is the clock input)
- Clock Polarity (Idle state of SCK)
- Data Input Sample Phase (middle or end of data output time)
- Clock Edge (output data on rising/falling edge of SCK)
- Clock Rate (Master mode only)
- · Slave Select mode (Slave mode only)

The MSSP consists of a transmit/receive shift register (SSPSR) and a buffer register (SSPBUF). The SSPSR shifts the data in and out of the device, MSb first. The SSPBUF holds the data that was written to the SSPSR until the received data is ready. Once the 8 bits of data have been received, that byte is moved to the SSPBUF register. Then, the Buffer Full detect bit BF (SSPSTAT<0>) and the interrupt flag bit SSPIF are set. This double-buffering of the received data (SSPBUF) allows the next byte to start reception before reading the data that was just received. Any write to the

SSPBUF register during transmission/reception of data will be ignored and the Write Collision detect bit, WCOL (SSPCON1<7>), will be set. User software must clear the WCOL bit so that it can be determined if the following write(s) to the SSPBUF register completed successfully.

When the application software is expecting to receive valid data, the SSPBUF should be read before the next byte of data to transfer is written to the SSPBUF. Buffer Full bit, BF (SSPSTAT<0>), indicates when SSPBUF has been loaded with the received data (transmission is complete). When the SSPBUF is read, the BF bit is cleared. This data may be irrelevant if the SPI is only a transmitter. Generally, the MSSP interrupt is used to determine when the transmission/reception has completed. The SSPBUF must be read and/or written. If the interrupt method is not going to be used, then software polling can be done to ensure that a write collision does not occur. Example 17-1 shows the loading of the SSPBUF (SSPSR) for data transmission.

The SSPSR is not directly readable or writable and can only be accessed by addressing the SSPBUF register. Additionally, the MSSP Status register (SSPSTAT) indicates the various status conditions.

EXAMPLE 17-1: LOADING THE SSPBUF (SSPSR) REGISTER

В	BRA	SSPSTAT, BF LOOP SSPBUF, W	;Has data been received(transmit complete)? ;No ;WREG req = contents of SSPBUF
		RXDATA	;Save in user RAM, if data is meaningful
		TXDATA, W SSPBUF	;W reg = contents of TXDATA ;New data to xmit

17.3.3 ENABLING SPI I/O

To enable the serial port, SSP Enable bit, SSPEN (SSPCON1<5>), must be set. To reset or reconfigure SPI mode, clear the SSPEN bit, reinitialize the SSPCON registers and then, set the SSPEN bit. This configures the SDI, SDO, SCK and SS pins as serial port pins. For the pins to behave as the serial port function, some must have their data direction bits (in the TRIS register) appropriately programmed as follows:

- SDI is automatically controlled by the SPI module
- SDO must have TRISC<5> bit cleared
- SCK (Master mode) must have TRISC<3> bit cleared
- SCK (Slave mode) must have TRISC<3> bit set
- SS must have TRISA<5> bit set

Any serial port function that is not desired may be overridden by programming the corresponding data direction (TRIS) register to the opposite value.

17.3.4 TYPICAL CONNECTION

Figure 17-2 shows a typical connection between two microcontrollers. The master controller (Processor 1) initiates the data transfer by sending the SCK signal. Data is shifted out of both shift registers on their programmed clock edge and latched on the opposite edge of the clock. Both processors should be programmed to the same Clock Polarity (CKP), then both controllers would send and receive data at the same time. Whether the data is meaningful (or dummy data) depends on the application software. This leads to three scenarios for data transmission:

- Master sends data Slave sends dummy data
- Master sends data Slave sends data
- Master sends dummy data Slave sends data




FIGURE 17-2: SPI™ MASTER/SLAVE CONNECTION

^{© 2006} Microchip Technology Inc.

17.3.5 MASTER MODE

The master can initiate the data transfer at any time because it controls the SCK. The master determines when the slave (Processor 2, Figure 17-2) is to broadcast data by the software protocol.

In Master mode, the data is transmitted/received as soon as the SSPBUF register is written to. If the SPI is only going to receive, the SDO output could be disabled (programmed as an input). The SSPSR register will continue to shift in the signal present on the SDI pin at the programmed clock rate. As each byte is received, it will be loaded into the SSPBUF register as if a normal received byte (interrupts and status bits appropriately set). This could be useful in receiver applications as a "Line Activity Monitor" mode. The clock polarity is selected by appropriately programming the CKP bit (SSPCON1<4>). This then, would give waveforms for SPI communication as shown in Figure 17-3, Figure 17-5 and Figure 17-6, where the MSB is transmitted first. In Master mode, the SPI clock rate (bit rate) is user programmable to be one of the following:

- Fosc/4 (or Tcy)
- Fosc/16 (or 4 Tcy)
- Fosc/64 (or 16 Tcy)
- Timer2 output/2

This allows a maximum data rate (at 40 MHz) of 10.00 Mbps.

Figure 17-3 shows the waveforms for Master mode. When the CKE bit is set, the SDO data is valid before there is a clock edge on SCK. The change of the input sample is shown based on the state of the SMP bit. The time when the SSPBUF is loaded with the received data is shown.




FIGURE 17-3: SPI™ MODE WAVEFORM (MASTER MODE)

17.3.6 SLAVE MODE

In Slave mode, the data is transmitted and received as the external clock pulses appear on SCK. When the last bit is latched, the SSPIF interrupt flag bit is set.

While in Slave mode, the external clock is supplied by the external clock source on the SCK pin. This external clock must meet the minimum high and low times as specified in the electrical specifications.

While in Sleep mode, the slave can transmit/receive data. When a byte is received, the device will wake-up from Sleep. Before enabling the module in SPI Slave mode, the clock line must match the proper Idle state. The clock line can be observed by reading the SCK pin. The Idle state is determined by the CKP bit (SSPCON1<4>).

17.3.7 SLAVE SELECT SYNCHRONIZATION

The \overline{SS} pin allows a Synchronous Slave mode. The SPI must be in Slave mode with \overline{SS} pin control enabled (SSPCON1<3:0> = 04h). The pin must not be driven low for the \overline{SS} pin to function as an input. The data latch

must be high. When the \overline{SS} pin is low, transmission and reception are enabled and the SDO pin is driven. When the \overline{SS} pin goes high, the SDO pin is no longer driven, even if in the middle of a transmitted byte and becomes a floating output. External pull-up/pull-down resistors may be desirable depending on the application.


Note 1:	When the SPI is in Slave mode with \overline{SS} pin
	control enabled (SSPCON1<3:0> = 0100),
	the SPI module will reset if the \overline{SS} pin is set
	to VDD.

2: If the SPI is used in Slave mode with CKE set, then the SS pin control must be enabled.


When the SPI module resets, the bit counter is forced to '0'. This can be done by either forcing the SS pin to a high level or clearing the SSPEN bit.


To emulate two-wire communication, the SDO pin can be connected to the SDI pin. When the SPI needs to operate as a receiver, the SDO pin can be configured as an input. This disables transmissions from the SDO. The SDI can always be left as an input (SDI function) since it cannot create a bus conflict.

FIGURE 17-4: SLAVE SYNCHRONIZATION WAVEFORM




© 2006 Microchip Technology Inc.









17.3.8 SLEEP OPERATION

In Master mode, all module clocks are halted and the transmission/reception will remain in that state until the device wakes from Sleep. After the device returns to normal mode, the module will continue to transmit/ receive data.

In Slave mode, the SPI Transmit/Receive Shift register operates asynchronously to the device. This allows the device to be placed in Sleep mode and data to be shifted into the SPI Transmit/Receive Shift register. When all 8 bits have been received, the MSSP interrupt flag bit will be set and if enabled, will wake the device from Sleep.

17.3.9 EFFECTS OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

17.3.10 BUS MODE COMPATIBILITY

Table 17-1 shows the compatibility between the standard SPI modes and the states of the CKP and CKE control bits.

TABLE 17-1: SPI™ BUS MODES

Standard SPI Mode	Control Bits State				
Terminology	СКР	CKE			
0, 0	0	1			
0, 1	0	0			
1, 0	1	1			
1, 1	1	0			

There is also an SMP bit which controls when the data is sampled.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
TRISC	PORTC Dat	ta Direction F	Register						1111 1111	1111 1111
TRISA	—	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	-111 1111	-111 1111
SSPBUF	Synchronous Serial Port Receive Buffer/Transmit Register								xxxx xxxx	uuuu uuuu
SSPCON1	WCOL SSPOV SSPEN CKP SSPM3 SSPM2 SSPM1 SSPM0								0000 0000	0000 0000
SSPSTAT	SMP	CKE	D/A	Р	S	R/W	UA	BF	0000 0000	0000 0000

TABLE 17-2: REGISTERS ASSOCIATED WITH SPI™ OPERATION

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used by the MSSP in SPITM mode.**Note 1:**These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

17.4 I²C Mode


The MSSP module in I²C mode fully implements all master and slave functions (including general call support) and provides interrupts on Start and Stop bits in hardware to determine a free bus (multi-master function). The MSSP module implements the standard mode specifications, as well as 7-bit and 10-bit addressing.

Two pins are used for data transfer:

- Serial clock (SCL) RC3/SCK/SCL
- Serial data (SDA) RC4/SDI/SDA

The user must configure these pins as inputs or outputs through the TRISC<4:3> bits.

FIGURE 17-7: MSSP BLOCK DIAGRAM (I²C™ MODE)



17.4.1 REGISTERS

The MSSP module has six registers for $\mathsf{I}^2\mathsf{C}$ operation. These are:

- MSSP Control Register 1 (SSPCON1)
- MSSP Control Register 2 (SSPCON2)
- MSSP Status Register (SSPSTAT)
- Serial Receive/Transmit Buffer (SSPBUF)
- MSSP Shift Register (SSPSR) Not directly accessible
- MSSP Address Register (SSPADD)

SSPCON1, SSPCON2 and SSPSTAT are the control and status registers in I^2C mode operation. The SSPCON1 and SSPCON2 registers are readable and writable. The lower 6 bits of the SSPSTAT are read-only. The upper two bits of the SSPSTAT are read/write.

SSPSR is the shift register used for shifting data in or out. SSPBUF is the buffer register to which data bytes are written to or read from.

SSPADD register holds the slave device address when the SSP is configured in I^2C Slave mode. When the SSP is configured in Master mode, the lower seven bits of SSPADD act as the Baud Rate Generator reload value.

In receive operations, SSPSR and SSPBUF together create a double-buffered receiver. When SSPSR receives a complete byte, it is transferred to SSPBUF and the SSPIF interrupt is set.

During transmission, the SSPBUF is not doublebuffered. A write to SSPBUF will write to both SSPBUF and SSPSR.

DS41159E-page 152

SSPSTAT: MSSP STATUS REGISTER (I²C MODE) **REGISTER 17-3:** R/W-0 R/W-0 R-0 R-0 R-0 R-0 R-0 R-0 SMP CKE D/A Ρ S R/W UA ΒF bit 7 bit 0 bit 7 SMP: Slew Rate Control bit In Master or Slave mode: 1 = Slew rate control disabled for Standard Speed mode (100 kHz and 1 MHz) 0 = Slew rate control enabled for High-Speed mode (400 kHz) bit 6 CKE: SMBus Select bit In Master or Slave mode: 1 = Enable SMBus specific inputs 0 = Disable SMBus specific inputs D/A: Data/Address bit bit 5 In Master mode: Reserved. In Slave mode: 1 = Indicates that the last byte received or transmitted was data 0 = Indicates that the last byte received or transmitted was address bit 4 P: Stop bit 1 = Indicates that a Stop bit has been detected last 0 = Stop bit was not detected last This bit is cleared on Reset and when SSPEN is cleared. Note: bit 3 S: Start bit 1 = Indicates that a Start bit has been detected last 0 = Start bit was not detected last Note: This bit is cleared on Reset and when SSPEN is cleared. R/W: Read/Write Information bit (I²C mode only) bit 2 In Slave mode: 1 = Read0 = WriteThis bit holds the R/W bit information following the last address match. This bit is Note: only valid from the address match to the next Start bit, Stop bit or not ACK bit. In Master mode: 1 = Transmit is in progress 0 = Transmit is not in progress ORing this bit with SEN, RSEN, PEN, RCEN or ACKEN will indicate if the MSSP is Note: in Idle mode. bit 1 **UA:** Update Address bit (10-bit Slave mode only) 1 = Indicates that the user needs to update the address in the SSPADD register 0 = Address does not need to be updated bit 0 BF: Buffer Full Status bit In Transmit mode: 1 = Receive complete, SSPBUF is full 0 = Receive not complete, SSPBUF is empty In Receive mode: 1 = Data transmit in progress (does not include the ACK and Stop bits), SSPBUF is full 0 = Data transmit complete (does not include the ACK and Stop bits), SSPBUF is empty Legend: R = Readable bit W = Writable bit U = Unimplemented bit, read as '0' -n = Value at POR '1' = Bit is set '0' = Bit is cleared x = Bit is unknown

© 2006 Microchip Technology Inc.

PIC18FXX8

REGISTER 17-4: SSPCON1: MSSP CONTROL REGISTER 1 (I²C MODE)

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
WCOL	SSPOV	SSPEN	CKP	SSPM3	SSPM2	SSPM1	SSPM0
bit 7							bit 0

bit 7 WCOL: Write Collision Detect bit

In Master Transmit mode:

- 1 = A write to the SSPBUF register was attempted while the l²C conditions were not valid for a transmission to be started (must be cleared in software)
- $0 = No \ collision$
- In Slave Transmit mode:
- 1 = The SSPBUF register is written while it is still transmitting the previous word (must be cleared in software)
- 0 = No collision
- In Receive mode (Master or Slave modes):

This is a "don't care" bit.

bit 6 SSPOV: Receive Overflow Indicator bit

In Receive mode:

- 1 = A byte is received while the SSPBUF register is still holding the previous byte (must be cleared in software)
- 0 = No overflow
- In Transmit mode:

This is a "don't care" bit in Transmit mode.

- bit 5 SSPEN: Synchronous Serial Port Enable bit
 - 1 = Enables the serial port and configures the SDA and SCL pins as the serial port pins
 - 0 = Disables serial port and configures these pins as I/O port pins

Note: When enabled, the SDA and SCL pins must be properly configured as input or output.

- bit 4 **CKP:** SCK Release Control bit
 - In Slave mode:
 - 1 = Release clock
 - 0 = Holds clock low (clock stretch), used to ensure data setup time
 - In Master mode:

Unused in this mode.

bit 3-0 SSPM3:SSPM0: Synchronous Serial Port Mode Select bits

- $1111 = I^2C$ Slave mode, 10-bit address with Start and Stop bit interrupts enabled
- $1110 = I^2C$ Slave mode, 7-bit address with Start and Stop bit interrupts enabled
- $1011 = I^2C$ Firmware Controlled Master mode (Slave Idle)
- $1000 = I^2C$ Master mode, clock = Fosc/(4 * (SSPADD + 1))
- $0111 = I^2C$ Slave mode, 10-bit address
- $0110 = I^2C$ Slave mode, 7-bit address
 - **Note:** Bit combinations not specifically listed here are either reserved or implemented in SPI mode only.

Legend:

Logonal								
R = Readable bit	R = Readable bit W = Writable bit		U = Unimplemented bit, read as '0'					
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown					

DS41159E-page 154

REGISTER 17-5:	SSPCON	2: MSSP CC		EGISTER 2	(I ² C MOD	E)		
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	GCEN	ACKSTAT	ACKDT	ACKEN	RCEN	PEN	RSEN	SEN
	bit 7							bit 0
	0051							
bit 7		eneral Call Er e interrupt wh	-	-	-	received in	the SSDSI	כ
		al call addres	•	i call address	(000011) 15	received in	116 337 31	1
bit 6	ACKSTAT	: Acknowledg	e Status bit	(Master Trans	smit mode o	only)		
		wledge was r wledge was r						
bit 5	ACKDT: A	Acknowledge	Data bit (Ma	ster Receive	mode only)			
	1 = Not Ao 0 = Ackno	cknowledge wledge						
	Note:	Value that w the end of a		itted when th	e user initia	tes an Ackı	nowledge s	equence at
bit 4	ACKEN: A	Acknowledge	Sequence E	nable bit (Ma	ster Receiv	e mode on	ly)	
		e Acknowledg			SCL pins a	nd transmi	t ACKDT da	ata bit.
		natically clear owledge sequ		are.				
bit 3		eceive Enable		Mode only)				
		es Receive m	-					
bit 2	PEN: Stop	Condition Er	nable bit (Ma	ster mode or	ıly)			
		e Stop condition stress on the stop condition stress of the stop o	on on SDA a	nd SCL pins.	Automatica	ally cleared	by hardwa	re.
bit 1	RSEN: Re	epeated Start	Condition Er	nable bit (Mas	ster mode o	nly)		
		e Repeated Stated Stated Stated Start con		on SDA and S	SCL pins. Au	utomatically	cleared by	hardware.
bit 0	SEN: Star	t Condition Er	nable/Stretch	n Enable bit				
	In Master				.			
		e Start condition Idle	on on SDA a	nd SCL pins.	Automatica	ally cleared	by hardwa	re.
	In Slave mode:							
	 1 = Clock stretching is enabled for both slave transmit and slave receive (stretch enabled) 0 = Clock stretching is enabled for slave transmit only (Legacy mode) 							nableu)
	Legend:							
	R = Reada	able bit	W = W	ritable bit	U = Unim	plemented	bit, read as	'0'
	-n = Value	at POR	'1' = Bit	t is set	'0' = Bit is	cleared	x = Bit is ι	unknown
								_

Note: For bits ACKEN, RCEN, PEN, RSEN, SEN: If the I²C module is not in the Idle mode, this bit may not be set (no spooling) and the SSPBUF may not be written (or writes to the SSPBUF are disabled).

^{© 2006} Microchip Technology Inc.

17.4.2 OPERATION

The MSSP module functions are enabled by setting MSSP Enable bit, SSPEN (SSPCON1<5>).

The SSPCON1 register allows control of the I^2C operation. Four mode selection bits (SSPCON1<3:0>) allow one of the following I^2C modes to be selected:

- I²C Master mode, clock = OSC/4 (SSPADD +1)
- I²C Slave mode (7-bit address)
- I²C Slave mode (10-bit address)
- I²C Slave mode (7-bit address) with Start and Stop bit interrupts enabled
- I²C Slave mode (10-bit address) with Start and Stop bit interrupts enabled
- I²C Firmware Controlled Master mode, slave is Idle

Selection of any I²C mode with the SSPEN bit set forces the SCL and SDA pins to be open-drain, provided these pins are programmed to inputs by setting the appropriate TRISC bits. To ensure proper operation of the module, pull-up resistors must be provided externally to the SCL and SDA pins.

17.4.3 SLAVE MODE

In Slave mode, the SCL and SDA pins must be configured as inputs (TRISC<4:3> set). The MSSP module will override the input state with the output data when required (slave-transmitter).

The I²C Slave mode hardware will always generate an interrupt on an address match. Through the mode select bits, the user can also choose to interrupt on Start and Stop bits.

When an address is matched, or the data transfer after an address match is received, the hardware automatically will generate the Acknowledge (\overline{ACK}) pulse and load the SSPBUF register with the received value currently in the SSPSR register.

Any combination of the following conditions will cause the MSSP module not to give this ACK pulse:

- The Buffer Full bit, BF (SSPSTAT<0>), was set before the transfer was received.
- The overflow bit, SSPOV (SSPCON1<6>), was set before the transfer was received.

In this case, the SSPSR register value is not loaded into the SSPBUF, but bit SSPIF (PIR1<3>) is set. The BF bit is cleared by reading the SSPBUF register, while bit SSPOV is cleared through software.

The SCL clock input must have a minimum high and low for proper operation. The high and low times of the I^2C specification, as well as the requirement of the MSSP module, are shown in timing parameter #100 and parameter #101.

17.4.3.1 Addressing

Once the MSSP module has been enabled, it waits for a Start condition to occur. Following the Start condition, the 8 bits are shifted into the SSPSR register. All incoming bits are sampled with the rising edge of the clock (SCL) line. The value of register SSPSR<7:1> is compared to the value of the SSPADD register. The address is compared on the falling edge of the eighth clock (SCL) pulse. If the addresses match and the BF and SSPOV bits are clear, the following events occur:

- 1. The SSPSR register value is loaded into the SSPBUF register.
- 2. The Buffer Full bit BF is set.
- 3. An ACK pulse is generated.
- MSSP Interrupt Flag bit, SSPIF (PIR1<3>), is set (interrupt is generated if enabled) on the falling edge of the ninth SCL pulse.

In 10-bit Address mode, two address bytes need to be received by the slave. The five Most Significant bits (MSbs) of the first address byte specify if this is a 10-bit address. Bit R/\overline{W} (SSPSTAT<2>) must specify a write so the slave device will receive the second address byte. For a 10-bit address, the first byte would equal '11110 A9 A8 0', where 'A9' and 'A8' are the two MSbs of the address. The sequence of events for 10-bit address is as follows, with steps 7 through 9 for the slave-transmitter:

- 1. Receive first (high) byte of address (bits SSPIF, BF and bit UA (SSPSTAT<1>) are set).
- 2. Update the SSPADD register with second (low) byte of address (clears bit UA and releases the SCL line).
- 3. Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 4. Receive second (low) byte of address (bits SSPIF, BF and UA are set).
- 5. Update the SSPADD register with the first (high) byte of address. If match releases SCL line, this will clear bit UA.
- 6. Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.
- 7. Receive Repeated Start condition.
- 8. Receive first (high) byte of address (bits SSPIF and BF are set).
- 9. Read the SSPBUF register (clears bit BF) and clear flag bit SSPIF.

17.4.3.2 Reception

When the R/W bit of the address byte is clear and an address match occurs, the R/W bit of the SSPSTAT register is cleared. The received address is loaded into the SSPBUF register and the SDA line is held low (ACK).

When the address byte overflow condition exists, then the no Acknowledge (ACK) pulse is given. An overflow condition is defined as either bit BF (SSPSTAT<0>) is set or bit SSPOV (SSPCON1<6>) is set.

An MSSP interrupt is generated for each data transfer byte. Flag bit SSPIF (PIR1<3>) must be cleared in software. The SSPSTAT register is used to determine the status of the byte.

If SEN is enabled (SSPCON2<0> = 1), RC3/SCK/SCL will be held low (clock stretch) following each data transfer. The clock must be released by setting bit CKP (SSPCON1<4>). See **Section 17.4.4** "Clock **Stretching**" for more detail.

17.4.3.3 Transmission


When the R/W bit of the incoming address byte is set and an address match occurs, the R/W bit of the SSPSTAT register is set. The received address is loaded into the SSPBUF register. The ACK pulse will be sent on the ninth bit and pin RC3/SCK/SCL is held low regardless of SEN (see Section 17.4.4 "Clock Stretching" for more detail). By stretching the clock, the master will be unable to assert another clock pulse until the slave is done preparing the transmit data. The transmit data must be loaded into the SSPBUF register, which also loads the SSPSR register. Then, pin RC3/ SCK/SCL should be enabled by setting bit CKP (SSPCON1<4>). The eight data bits are shifted out on the falling edge of the SCL input. This ensures that the SDA signal is valid during the SCL high time (Figure 17-9).

The ACK pulse from the master-receiver is latched on the rising edge of the ninth SCL input pulse. If the SDA line is high (not ACK), then the data transfer is complete. In this case, when the ACK is latched by the slave, the slave logic is reset (resets SSPSTAT register) and the slave monitors for another occurrence of the Start bit. If the SDA line was low (ACK), the next transmit data must be loaded into the SSPBUF register. Again, pin RC3/SCK/SCL must be enabled by setting bit CKP.

An MSSP interrupt is generated for each data transfer byte. The SSPIF bit must be cleared in software and the SSPSTAT register is used to determine the status of the byte. The SSPIF bit is set on the falling edge of the ninth clock pulse.

^{© 2006} Microchip Technology Inc.






DS41159E-page 158

© 2006 Microchip Technology Inc.


Downloaded from: http://www.datasheetcatalog.com/





Downloaded from: http://www.datasheetcatalog.com/


© 2006 Microchip Technology Inc.



DS41159E-page 160

Downloaded from: http://www.datasheetcatalog.com/

© 2006 Microchip Technology Inc.



Downloaded from: http://www.datasheetcatalog.com/

17.4.4 CLOCK STRETCHING

Both 7 and 10-bit Slave modes implement automatic clock stretching during a transmit sequence.

The SEN bit (SSPCON2<0>) allows clock stretching to be enabled during receives. Setting SEN will cause the SCL pin to be held low at the end of each data receive sequence.

17.4.4.1 Clock Stretching for 7-bit Slave Receive Mode (SEN = 1)

In 7-bit Slave Receive mode, <u>on the falling edge of the</u> ninth clock at the end of the ACK sequence, if the BF bit is set, the CKP bit in the SSPCON1 register is automatically cleared, forcing the SCL output to be held low. The CKP being cleared to '0' will assert the SCL line low. The CKP bit must be set in the user's ISR before reception is allowed to continue. By holding the SCL line low, the user has time to service the ISR and read the contents of the SSPBUF before the master device can initiate another receive sequence. This will prevent buffer overruns from occurring.

- Note 1: If the user reads the contents of the SSPBUF before the falling edge of the ninth clock, thus clearing the BF bit, the CKP bit will not be cleared and clock stretching will not occur.
 - 2: The CKP bit can be set in software regardless of the state of the BF bit. The user should be careful to clear the BF bit in the ISR before the next receive sequence in order to prevent an overflow condition.

17.4.4.2 Clock Stretching for 10-bit Slave Receive Mode (SEN = 1)

In 10-bit Slave Receive mode, during the address sequence, clock stretching automatically takes place but CKP is not cleared. During this time, if the UA bit is set after the ninth clock, clock stretching is initiated. The UA bit is set after receiving the upper byte of the 10-bit address and following the receive of the second byte of the 10-bit address with the R/W bit cleared to '0'. The release of the clock line occurs upon updating SSPADD. Clock stretching will occur on each data receive sequence as described in 7-bit mode.

Note: If the user polls the UA bit and clears it by updating the SSPADD register before the falling edge of the ninth clock occurs and if the user hasn't cleared the BF bit by reading the SSPBUF register before that time, then the CKP bit will still NOT be asserted low. Clock stretching on the basis of the state of the BF bit only occurs during a data sequence, not an address sequence.

17.4.4.3 Clock Stretching for 7-bit Slave Transmit Mode

7-bit Slave Transmit mode implements clock stretching by clearing the CKP bit after the falling edge of the ninth clock if the BF bit is clear. This occurs regardless of the state of the SEN bit.

The user's ISR must set the CKP bit before transmission is allowed to continue. By holding the SCL line low, the user has time to service the ISR and load the contents of the SSPBUF before the master device can initiate another transmit sequence (see Figure 17-9).

Note 1:	If the user loads the contents of SSPBUF, setting the BF bit before the falling edge of the ninth clock, the CKP bit will not be cleared and clock stretching will not occur.
2:	The CKP bit can be set in software regardless of the state of the BF bit.


17.4.4.4 Clock Stretching for 10-bit Slave Transmit Mode

In 10-bit Slave Transmit mode, clock stretching is controlled during the first two address sequences by the state of the UA bit, just as it is in 10-bit Slave Receive mode. The first two addresses are followed by a third address sequence which contains the highorder bits of the 10-bit address and the R/W bit set to '1'. After the third address sequence is performed, the UA bit is not set, the module is now configured in Transmit mode and clock stretching is controlled by the BF flag as in 7-bit Slave Transmit mode (see Figure 17-11).

17.4.4.5 Clock Synchronization and the CKP bit


If a user clears the CKP bit, the SCL output is forced to '0'. Setting the CKP bit will not assert the SCL output low until the SCL output is already sampled low. If the user attempts to drive SCL low, the CKP bit will not assert the SCL line until an external I^2C master device has already asserted the SCL line. The SCL output will remain low until the CKP bit is set and all other devices on the I^2C bus have deasserted SCL. This ensures that a write to the CKP bit will not violate the minimum high time requirement for SCL (see Figure 17-12).






^{© 2006} Microchip Technology Inc.







© 2006 Microchip Technology Inc.

Downloaded from: http://www.datasheetcatalog.com/

DS41159E-page 165

PIC18FXX

17.4.5 GENERAL CALL ADDRESS SUPPORT

The addressing procedure for the I²C bus is such that the first byte after the Start condition usually determines which device will be the slave addressed by the master. The exception is the general call address which can address all devices. When this address is used, all devices should, in theory, respond with an Acknowledge.

The general call address is one of eight addresses reserved for specific purposes by the I²C protocol. It consists of all '0's with R/W = 0.


The general call address is recognized when the General Call Enable bit (GCEN) is enabled (SSPCON2<7> set). Following a Start bit detect, 8 bits are shifted into the SSPSR and the address is compared against the SSPADD. It is also compared to the general call address and fixed in hardware.

If the general call address matches, the SSPSR is transferred to the SSPBUF, the BF flag bit is set (eighth bit) and on the falling edge of the ninth bit (ACK bit), the SSPIF interrupt flag bit is set.

When the interrupt is serviced, the source for the interrupt can be checked by reading the contents of the SSPBUF. The value can be used to determine if the address was device specific or a general call address.

In 10-bit mode, the SSPADD is required to be updated for the second half of the address to match and the UA bit is set (SSPSTAT<1>). If the general call address is sampled when the GCEN bit is set, while the slave is configured in 10-bit Address mode, then the second half of the address is not necessary, the UA bit will not be set and the slave will begin receiving data after the Acknowledge (Figure 17-15).

FIGURE 17-15: SLAVE MODE GENERAL CALL ADDRESS SEQUENCE (7 OR 10-BIT ADDRESS MODE)



17.4.6 MASTER MODE

Master mode is enabled by setting and clearing the appropriate SSPM bits in SSPCON1 and by setting the SSPEN bit. In Master mode, the SCL and SDA lines are manipulated by the MSSP hardware.

Master mode of operation is supported by interrupt generation on the detection of the Start and Stop conditions. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I^2C bus may be taken when the P bit is set or the bus is Idle, with both the S and P bits clear.

In Firmware Controlled Master mode, user code conducts all I^2C bus operations based on Start and Stop bit conditions.


Once Master mode is enabled, the user has six options.

- 1. Assert a Start condition on SDA and SCL.
- 2. Assert a Repeated Start condition on SDA and SCL.
- 3. Write to the SSPBUF register initiating transmission of data/address.
- 4. Configure the I²C port to receive data.
- 5. Generate an Acknowledge condition at the end of a received byte of data.
- 6. Generate a Stop condition on SDA and SCL.

Note: The MSSP module, when configured in I²C Master mode, does not allow queueing of events. For instance, the user is not allowed to initiate a Start condition and immediately write the SSPBUF register to initiate transmission before the Start condition is complete. In this case, the SSPBUF will not be written to and the WCOL bit will be set, indicating that a write to the SSPBUF did not occur.

The following events will cause SSP Interrupt Flag bit, SSPIF, to be set (SSP interrupt if enabled):

- Start condition
- Stop condition
- Data transfer byte transmitted/received
- Acknowledge transmit
- Repeated Start



© 2006 Microchip Technology Inc.

17.4.6.1 I²C Master Mode Operation

The master device generates all of the serial clock pulses and the Start and Stop conditions. A transfer is ended with a Stop condition, or with a Repeated Start condition. Since the Repeated Start condition is also the beginning of the next serial transfer, the I²C bus will not be released.

In Master Transmitter mode, serial data is output through SDA while SCL outputs the serial clock. The first byte transmitted contains the slave address of the receiving device (7 bits) and the Read/Write (R/W) bit. In this case, the R/W bit will be logic '0'. Serial data is transmitted 8 bits at a time. After each byte is transmitted, an Acknowledge bit is received. Start and Stop conditions are output to indicate the beginning and the end of a serial transfer.

In Master Receive mode, the first byte transmitted contains the slave address of the transmitting device (7 bits) and the R/W bit. In this case, the R/W bit will be logic '1'. Thus, the first byte transmitted is a 7-bit slave address followed by a '1' to indicate receive bit. Serial data is received via SDA while SCL outputs the serial clock. Serial data is received 8 bits at a time. After each byte is received, an Acknowledge bit is transmitted. Start and Stop conditions indicate the beginning and end of transmission.

The Baud Rate Generator used for the SPI mode operation is used to set the SCL clock frequency for either 100 kHz, 400 kHz or 1 MHz I²C operation. See **Section 17.4.7** "**Baud Rate Generator**" for more details.

A typical transmit sequence would go as follows:

- 1. The user generates a Start condition by setting the Start Enable bit, SEN (SSPCON2<0>).
- 2. SSPIF is set. The MSSP module will wait the required start time before any other operation takes place.
- 3. The user loads the SSPBUF with the slave address to transmit.
- 4. Address is shifted out the SDA pin until all 8 bits are transmitted.
- 5. The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- 6. The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- 7. The user loads the SSPBUF with eight bits of data.
- 8. Data is shifted out the SDA pin until all 8 bits are transmitted.
- 9. The MSSP module shifts in the ACK bit from the slave device and writes its value into the SSPCON2 register (SSPCON2<6>).
- 10. The MSSP module generates an interrupt at the end of the ninth clock cycle by setting the SSPIF bit.
- 11. The user generates a Stop condition by setting the Stop Enable bit PEN (SSPCON2<2>).
- 12. Interrupt is generated once the Stop condition is complete.

DS41159E-page 168


17.4.7 BAUD RATE GENERATOR

In I²C Master mode, the Baud Rate Generator (BRG) reload value is placed in the lower 7 bits of the SSPADD register (Figure 17-17). When a write occurs to SSPBUF, the Baud Rate Generator will automatically begin counting. The BRG counts down to 0 and stops until another reload has taken place. The BRG count is decremented twice per instruction cycle (Tcr) on the Q2 and Q4 clocks. In I²C Master mode, the BRG is reloaded automatically.

Once the given operation is complete (i.e., transmission of the last data bit is followed by \overline{ACK}), the internal clock will automatically stop counting and the SCL pin will remain in its last state.

Table 17-3 demonstrates clock rates based on instruction cycles and the BRG value loaded into SSPADD.

FIGURE 17-17: BAUD RATE GENERATOR BLOCK DIAGRAM



Fosc	Fcy	Fcy * 2	BRG Value	FscL (2 Rollovers of BRG)
40 MHz	10 MHz	20 MHz	18h	400 kHz ⁽¹⁾
40 MHz	10 MHz	20 MHz	1Fh	312.5 kHz
40 MHz	10 MHz	20 MHz	63h	100 kHz
16 MHz	4 MHz	8 MHz	09h	400 kHz ⁽¹⁾
16 MHz	4 MHz	8 MHz	0Ch	308 kHz
16 MHz	4 MHz	8 MHz	27h	100 kHz
4 MHz	1 MHz	2 MHz	02h	333 kHz ⁽¹⁾
4 MHz	1 MHz	2 MHz	09h	100kHz
4 MHz	1 MHz	2 MHz	00h	1 MHz ⁽¹⁾


TABLE 17-3: I²C[™] CLOCK RATE w/BRG

Note 1: The I²C[™] interface does not conform to the 400 kHz I²C specification (which applies to rates greater than 100 kHz) in all details, but may be used with care where higher rates are required by the application.

17.4.7.1 Clock Arbitration

Clock arbitration occurs when the master, during any receive, transmit or Repeated Start/Stop condition, deasserts the SCL pin (SCL allowed to float high). When the SCL pin is allowed to float high, the Baud Rate Generator (BRG) is suspended from counting until the SCL pin is actually sampled high. When the SCL pin is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. This ensures that the SCL high time will always be at least one BRG rollover count in the event that the clock is held low by an external device (Figure 17-18).





DS41159E-page 170

17.4.8 I²C MASTER MODE START CONDITION TIMING

To initiate a Start condition, the user sets the Start condition enable bit, SEN (SSPCON2<0>). If the SDA and SCL pins are sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and starts its count. If SCL and SDA are both sampled high when the Baud Rate Generator times out (TBRG), the SDA pin is driven low. The action of the SDA being driven low, while SCL is high, is the Start condition and causes the S bit (SSPSTAT<3>) to be set. Following this, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and resumes its count. When the Baud Rate Generator times out (TBRG), the SEN bit (SSPCON2<0>) will be automatically cleared by hardware, the Baud Rate Generator is suspended, leaving the SDA line held low and the Start condition is complete.


Note: If, at the beginning of the Start condition, the SDA and SCL pins are already sampled low, or if during the Start condition, the SCL line is sampled low before the SDA line is driven low, a bus collision occurs; the Bus Collision Interrupt Flag, BCLIF, is set, the Start condition is aborted and the I²C module is reset into its Idle state.

17.4.8.1 WCOL Status Flag

If the user writes the SSPBUF when a Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

Note: Because queueing of events is not allowed, writing to the lower 5 bits of SSPCON2 is disabled until the Start condition is complete.

FIGURE 17-19: FIRST START BIT TIMING



^{© 2006} Microchip Technology Inc.

17.4.9 I²C MASTER MODE REPEATED START CONDITION TIMING

A Repeated Start condition occurs when the RSEN bit (SSPCON2 < 1 >) is programmed high and the I²C logic module is in the Idle state. When the RSEN bit is set, the SCL pin is asserted low. When the SCL pin is sampled low, the Baud Rate Generator is loaded with the contents of SSPADD<5:0> and begins counting. The SDA pin is released (brought high) for one Baud Rate Generator count (TBRG). When the Baud Rate Generator times out, if SDA is sampled high, the SCL pin will be deasserted (brought high). When SCL is sampled high, the Baud Rate Generator is reloaded with the contents of SSPADD<6:0> and begins counting. SDA and SCL must be sampled high for one TBRG. This action is then followed by assertion of the SDA pin (SDA = 0) for one TBRG while SCL is high. Following this, the RSEN bit (SSPCON2<1>) will be automatically cleared and the Baud Rate Generator will not be reloaded, leaving the SDA pin held low. As soon as a Start condition is detected on the SDA and SCL pins, the S bit (SSPSTAT<3>) will be set. The SSPIF bit will not be set until the Baud Rate Generator has timed out.

- Note 1: If RSEN is programmed while any other event is in progress, it will not take effect.
 - 2: A bus collision during the Repeated Start condition occurs if:
 - SDA is sampled low when SCL goes from low-to-high.
 - SCL goes low before SDA is asserted low. This may indicate that another master is attempting to transmit a data '1'.


Immediately following the SSPIF bit getting set, the user may write the SSPBUF with the 7-bit address in 7-bit mode, or the default first address in 10-bit mode. After the first eight bits are transmitted and an ACK is received, the user may then transmit an additional eight bits of address (10-bit mode) or eight bits of data (7-bit mode).

17.4.9.1 WCOL Status Flag

If the user writes the SSPBUF when a Repeated Start sequence is in progress, the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

Note: Because queueing of events is not allowed, writing of the lower 5 bits of SSPCON2 is disabled until the Repeated Start condition is complete.

FIGURE 17-20: REPEATED START CONDITION WAVEFORM



17.4.10 I²C MASTER MODE TRANSMISSION

Transmission of a data byte, a 7-bit address or the other half of a 10-bit address is accomplished by simply writing a value to the SSPBUF register. This action will set the Buffer Full flag bit BF and allow the Baud Rate Generator to begin counting and start the next transmission. Each bit of address/data will be shifted out onto the SDA pin after the falling edge of SCL is asserted (see data hold time specification parameter #106). SCL is held low for one Baud Rate Generator rollover count (TBRG). Data should be valid before SCL is released high (see data setup time specification parameter #107). When the SCL pin is released high, it is held that way for TBRG. The data on the SDA pin must remain stable for that duration and some hold time after the next falling edge of SCL. After the eighth bit is shifted out (the falling edge of the eighth clock), the BF flag is cleared and the master releases SDA. This allows the slave device being addressed to respond with an \overline{ACK} bit during the ninth bit time, if an address match occurred, or if data was received properly. The status of \overline{ACK} is written into the ACKDT bit on the falling edge of the ninth clock. If the master receives an Acknowledge, the Acknowledge Status bit, ACKSTAT, is cleared. If not, the bit is set. After the ninth clock, the SSPIF bit is set and the master clock (Baud Rate Generator) is suspended until the next data byte is loaded into the SSPBUF, leaving SCL low and SDA unchanged (Figure 17-21).

After the write to the SSPBUF, each bit of address will be shifted out on the falling edge of SCL until all seven address bits and the R/W bit are completed. On the falling edge of the eighth clock, the master will deassert the SDA pin, allowing the slave to respond with an Acknowledge. On the falling edge of the ninth clock, the master will sample the SDA pin to see if the address was recognized by a slave. The status of the ACK bit is loaded into the ACKSTAT status bit (SSPCON2<6>). Following the falling edge of the ninth clock transmission of the address, the SSPIF bit is set, the BF flag is cleared and the Baud Rate Generator is turned off until another write to the SSPBUF takes place, holding SCL low and allowing SDA to float.

17.4.10.1 BF Status Flag

In Transmit mode, the BF bit (SSPSTAT<0>) is set when the CPU writes to SSPBUF and is cleared when all 8 bits are shifted out.

17.4.10.2 WCOL Status Flag

If the user writes the SSPBUF when a transmit is already in progress (i.e., SSPSR is still shifting out a data byte), the WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).

WCOL must be cleared in software.

17.4.10.3 ACKSTAT Status Flag

In Transmit mode, the ACKSTAT bit (SSPCON2<6>) is cleared when the slave has sent an Acknowledge $(\overline{ACK} = 0)$ and is set when the slave does not Acknowledge ($\overline{ACK} = 1$). A slave sends an Acknowledge when it has recognized its address (including a general call) or when the slave has properly received its data.

17.4.11 I²C MASTER MODE RECEPTION

Master mode reception is enabled by programming the Receive Enable bit, RCEN (SSPCON2<3>).

Note:	The RCEN bit should be set after the \overline{ACK}	
	sequence is complete or the RCEN bit will	
	be disregarded.	

The Baud Rate Generator begins counting and on each rollover, the state of the SCL pin changes (high-to-low/ low-to-high) and data is shifted into the SSPSR. After the falling edge of the eighth clock, the receive enable flag is automatically cleared, the contents of the SSPSR are loaded into the SSPBUF, the BF flag bit is set, the SSPIF flag bit is set and the Baud Rate Generator is suspended from counting, holding SCL low. The MSSP is now in Idle state awaiting the next command. When the buffer is read by the CPU, the BF flag bit is automatically cleared. The user can then send an Acknowledge bit at the end of reception by setting the Sequence Enable bit, Acknowledge ACKEN (SSPCON2<4>).

17.4.11.1 BF Status Flag

In receive operation, the BF bit is set when an address or data byte is loaded into SSPBUF from SSPSR. It is cleared when the SSPBUF register is read.


17.4.11.2 SSPOV Status Flag

In receive operation, the SSPOV bit is set when 8 bits are received into the SSPSR and the BF flag bit is already set from a previous reception.

17.4.11.3 WCOL Status Flag


If the user writes the SSPBUF when a receive is already in progress (i.e., SSPSR is still shifting in a data byte), the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).

^{© 2006} Microchip Technology Inc.



Downloaded from: http://www.datasheetcatalog.com/

I8FXX8



© 2006 Microchip Technology Inc.

Downloaded from: http://www.datasheetcatalog.com/

DS41159E-page 175

PIC18FXX

17.4.12 ACKNOWLEDGE SEQUENCE TIMING

An Acknowledge sequence is enabled by setting the Acknowledge Sequence Enable bit. ACKEN (SSPCON2<4>). When this bit is set, the SCL pin is pulled low and the contents of the Acknowledge data bit are presented on the SDA pin. If the user wishes to generate an Acknowledge, then the ACKDT bit should be cleared. If not, the user should set the ACKDT bit before starting an Acknowledge sequence. The Baud Rate Generator then counts for one rollover period (TBRG) and the SCL pin is deasserted (pulled high). When the SCL pin is sampled high (clock arbitration), the Baud Rate Generator counts for TBRG. The SCL pin is then pulled low. Following this, the ACKEN bit is automatically cleared, the Baud Rate Generator is turned off and the MSSP module then goes into Idle mode (Figure 17-23).

17.4.12.1 WCOL Status Flag

If the user writes the SSPBUF when an Acknowledge sequence is in progress, then WCOL is set and the contents of the buffer are unchanged (the write doesn't occur).


17.4.13 STOP CONDITION TIMING

A Stop bit is asserted on the SDA pin at the end of a receive/transmit by setting the Stop Sequence Enable bit, PEN (SSPCON2<2>). At the end of a receive/ transmit, the SCL line is held low after the falling edge of the ninth clock. When the PEN bit is set, the master will assert the SDA line low. When the SDA line is sampled low, the Baud Rate Generator is reloaded and counts down to 0. When the Baud Rate Generator times out, the SCL pin will be brought high and one TBRG (Baud Rate Generator rollover count) later, the SDA pin will be deasserted. When the SDA pin is sampled high while SCL is high, the P bit (SSPSTAT<4>) is set. A TBRG later, the PEN bit is cleared and the SSPIF bit is set (Figure 17-24).


17.4.13.1 WCOL Status Flag

If the user writes the SSPBUF when a Stop sequence is in progress, then the WCOL bit is set and the contents of the buffer are unchanged (the write doesn't occur).

FIGURE 17-23: ACKNOWLEDGE SEQUENCE WAVEFORM







17.4.14 SLEEP OPERATION

While in Sleep mode, the I^2C module can receive addresses or data and when an address match or complete byte transfer occurs, wake the processor from Sleep (if the MSSP interrupt is enabled).

17.4.15 EFFECT OF A RESET

A Reset disables the MSSP module and terminates the current transfer.

17.4.16 MULTI-MASTER MODE

In Multi-Master mode, the interrupt generation on the detection of the Start and Stop conditions allows the determination of when the bus is free. The Stop (P) and Start (S) bits are cleared from a Reset or when the MSSP module is disabled. Control of the I^2C bus may be taken when the P bit (SSPSTAT<4>) is set, or the bus is Idle, with both the S and P bits clear. When the bus is busy, enabling the SSP interrupt will generate the interrupt when the Stop condition occurs.

In multi-master operation, the SDA line must be monitored for arbitration to see if the signal level is the expected output level. This check is performed in hardware with the result placed in the BCLIF bit.

The states where arbitration can be lost are:

- Address Transfer
- Data Transfer
- A Start Condition
- A Repeated Start Condition
- An Acknowledge Condition

17.4.17 MULTI -MASTER COMMUNICATION, BUS COLLISION AND BUS ARBITRATION

Multi-Master mode support is achieved by bus arbitration. When the master outputs address/data bits onto the SDA pin, arbitration takes place when the master outputs a '1' on SDA by letting SDA float high and another master asserts a '0'. When the SCL pin floats high, data should be stable. If the expected data on SDA is a '1' and the data sampled on the SDA pin = 0, then a bus collision has taken place. The master will set the Bus Collision Interrupt Flag BCLIF and reset the I^2C port to its Idle state (Figure 17-25).

If a transmit was in progress when the bus collision occurred, the transmission is halted, the BF flag is cleared, the SDA and SCL lines are deasserted and the SSPBUF can be written to. When the user services the bus collision Interrupt Service Routine and if the l^2C bus is free, the user can resume communication by asserting a Start condition.


If a Start, Repeated Start, Stop or Acknowledge condition was in progress when the bus collision occurred, the condition is aborted, the SDA and SCL lines are deasserted and the respective control bits in the SSPCON2 register are cleared. When the user services the bus collision Interrupt Service Routine and if the I^2C bus is free, the user can resume communication by asserting a Start condition.

The master will continue to monitor the SDA and SCL pins. If a Stop condition occurs, the SSPIF bit will be set.

A write to the SSPBUF will start the transmission of data at the first data bit regardless of where the transmitter left off when the bus collision occurred.

In Multi-Master mode, the interrupt generation on the detection of Start and Stop conditions allows the determination of when the bus is free. Control of the I^2C bus can be taken when the P bit is set in the SSPSTAT register or the bus is Idle and the S and P bits are cleared.

FIGURE 17-25: BUS COLLISION TIMING FOR TRANSMIT AND ACKNOWLEDGE



© 2006 Microchip Technology Inc.

PIC18FXX8

17.4.17.1 Bus Collision During a Start Condition

During a Start condition, a bus collision occurs if:

- a) SDA or SCL are sampled low at the beginning of the Start condition (Figure 17-26).
- b) SCL is sampled low before SDA is asserted low (Figure 17-27).

During a Start condition, both the SDA and the SCL pins are monitored.

If the SDA pin is already low, or the SCL pin is already low, then all of the following occur:

- the Start condition is aborted,
- the BCLIF flag is set and
- the MSSP module is reset to its Idle state (Figure 17-26).

The Start condition begins with the SDA and SCL pins deasserted. When the SDA pin is sampled high, the Baud Rate Generator is loaded from SSPADD<6:0> and counts down to 0. If the SCL pin is sampled low while SDA is high, a bus collision occurs because it is assumed that another master is attempting to drive a data '1' during the Start condition.

If the SDA pin is sampled low during this count, the BRG is reset and the SDA line is asserted early (Figure 17-28). If, however, a '1' is sampled on the SDA pin, the SDA pin is asserted low at the end of the BRG count. The Baud Rate Generator is then reloaded and counts down to 0 and during this time, if the SCL pins are sampled as '0', a bus collision does not occur. At the end of the BRG count, the SCL pin is asserted low.

Note: The reason that bus collision is not a factor during a Start condition is that no two bus masters can assert a Start condition at the exact same time. Therefore, one master will always assert SDA before the other. This condition does not cause a bus collision because the two masters must be allowed to arbitrate the first address following the Start condition. If the address is the same, arbitration must be allowed to continue into the data portion, Repeated Start or Stop conditions.






FIGURE 17-26: BUS COLLISION DURING START CONDITION (SDA ONLY)









^{© 2006} Microchip Technology Inc.

17.4.17.2 Bus Collision During a Repeated Start Condition

During a Repeated Start condition, a bus collision occurs if:

- a) A low level is sampled on SDA when SCL goes from low level to high level.
- b) SCL goes low before SDA is asserted low, indicating that another master is attempting to transmit a data '1'.

When the user deasserts SDA and the pin is allowed to float high, the BRG is loaded with SSPADD<6:0> and counts down to 0. The SCL pin is then deasserted and when sampled high, the SDA pin is sampled.

If SDA is low, a bus collision has occurred (i.e., another master is attempting to transmit a data '0', Figure 17-29). If SDA is sampled high, the BRG is reloaded and begins

counting. If SDA goes from high-to-low before the BRG times out, no bus collision occurs because no two masters can assert SDA at exactly the same time.


If SCL goes from high-to-low before the BRG times out and SDA has not already been asserted, a bus collision occurs. In this case, another master is attempting to transmit a data '1' during the Repeated Start condition (Figure 17-30).

If, at the end of the BRG time-out, both SCL and SDA are still high, the SDA pin is driven low and the BRG is reloaded and begins counting. At the end of the count, regardless of the status of the SCL pin, the SCL pin is driven low and the Repeated Start condition is complete.









DS41159E-page 180

17.4.17.3 Bus Collision During a Stop Condition

Bus collision occurs during a Stop condition if:

- a) After the SDA pin has been deasserted and allowed to float high, SDA is sampled low after the BRG has timed out.
- b) After the SCL pin is deasserted, SCL is sampled low before SDA goes high.

The Stop condition begins with SDA asserted low. When SDA is sampled low, the SCL pin is allowed to float. When the pin is sampled high (clock arbitration), the Baud Rate Generator is loaded with SSPADD<6:0> and counts down to 0. After the BRG times out, SDA is sampled. If SDA is sampled low, a bus collision has occurred. This is due to another master attempting to drive a data '0' (Figure 17-31). If the SCL pin is sampled low before SDA is allowed to float high, a bus collision occurs. This is another case of another master attempting to drive a data '0' (Figure 17-32).

FIGURE 17-31: BUS COLLISION DURING A STOP CONDITION (CASE 1)





FIGURE 17-32: BUS COLLISION DURING A STOP CONDITION (CASE 2)



^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 182

18.0 ADDRESSABLE UNIVERSAL SYNCHRONOUS ASYNCHRONOUS RECEIVER TRANSMITTER (USART)

The Universal Synchronous Asynchronous Receiver Transmitter (USART) module is one of the three serial I/O modules incorporated into PIC18FXX8 devices. (USART is also known as a Serial Communications Interface or SCI.) The USART can be configured as a full-duplex asynchronous system that can communicate with peripheral devices, such as CRT terminals and personal computers, or it can be configured as a half-duplex synchronous system that can communicate with peripheral devices, such as A/D or D/A integrated circuits, serial EEPROMs, etc. The USART can be configured in the following modes:

- Asynchronous (full-duplex)
- Synchronous Master (half-duplex)
- Synchronous Slave (half-duplex).

The SPEN (RCSTA register) and the TRISC<7> bits have to be set and the TRISC<6> bit must be cleared in order to configure pins RC6/TX/CK and RC7/RX/DT as the Universal Synchronous Asynchronous Receiver Transmitter.

Register 18-1 shows the Transmit Status and Control register (TXSTA) and Register 18-2 shows the Receive Status and Control register (RCSTA).

REGISTER 18-1: TXSTA: TRANSMIT STATUS AND CONTROL REGISTER

	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0	R-1	R/W-0						
	CSRC	TX9	TXEN	SYNC	—	BRGH	TRMT	TX9D						
	bit 7							bit 0						
L:1 7														
bit 7	Asynchrone	ck Source S	belect dit											
	Don't care.													
	<u>Synchrono</u>													
		mode (clock			om BRG)									
bit 6		node (clock Fransmit Ena		al source)										
		1 = Selects 9-bit transmission0 = Selects 8-bit transmission												
bit 5	TXEN: Trai	nsmit Enable	e bit											
	1 = Transm	nit enabled												
	0 = Transm													
	Note:	SREN/CRE	EN overrides	TXEN in Sy	/nc mode.									
bit 4		ART Mode S												
		onous mode Ironous mod												
bit 3	-	ented: Read												
bit 2	-	h Baud Rate												
	Asynchron													
	1 = High sp													
	0 = Low sp													
	<u>Synchrono</u> Unused in t													
bit 1		nsmit Shift F	legister Stat	us bit										
	1 = TSR er		0											
	0 = TSR fu													
bit 0		bit of Transr												
	Can be add	dress/data b	it or a parity	DIT.										
	Legend:													
	R = Reada	ble bit	W = W	/ritable bit	U = Unin	nplemented	bit, read as '	0'						
	-n = Value	at POR	'1' = B	it is set	'0' = Bit i	s cleared	x = Bit is u	nknown						

TER 18-2:	RCSTA: R	ECEIVE S	TATUS AN	ID CONTR		TER		
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R-0	R-0	R-x
	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D
	bit 7							bit 0
bit 7	SPEN: Seri	ial Port Ena	ble bit					
		ort enabled		RX/DT and	TX/CK pins	as serial po	ort pins)	
bit 6	RX9 : 9-bit F	Receive Ena	able bit					
		9-bit recept 8-bit recept						
bit 5	SREN: Sing	gle Receive	Enable bit					
	<u>Asynchrond</u> Don't care.	ous mode:						
	1 = Enables	<u>us mode – N</u> s single rece s single rec	eive	is cleared a	Ifter receptio	n is comple	te)	
	<u>Synchronou</u> Unused in t	<u>us mode – S</u> his mode.	<u>Slave:</u>					
bit 4	CREN: Cor	ntinuous Re	ceive Enable	e bit				
		<u>ous mode:</u> s continuous s continuou						
	<u>Synchronou</u> 1 = Enables		s receive unt	til enable bit	CREN is cle	ared (CRE	N overrides :	SREN)
		s continuou						
bit 3			ct Enable bi					
	-		<u>bit (RX9 = 1</u>	-				
	is set				ipt and load o			
bit 2		ning Error b		by too are r				parity bit
5112		g error (can		by reading	RCREG regi	ster and rec	eive next va	lid byte)
bit 1		errun Error b	hit					
Sit 1		n error (can	be cleared b	by clearing b	it CREN)			
bit 0		bit of Receiv	/ed Data					
			it or a parity	bit.				
	Legend:]
	R = Reada	ble bit	W = W	/ritable bit	U = Unim	plemented	bit, read as	'0'
						•	,	

'1' = Bit is set

'0' = Bit is cleared

REGISTER 18-2: RCSTA: RECEIVE STATUS AND CONTROL REGISTER

x = Bit is unknown

-n = Value at POR

18.1 USART Baud Rate Generator (BRG)

The BRG supports both the Asynchronous and Synchronous modes of the USART. It is a dedicated 8-bit Baud Rate Generator. The SPBRG register controls the period of a free running, 8-bit timer. In Asynchronous mode, bit BRGH (TXSTA register) also controls the baud rate. In Synchronous mode, bit BRGH is ignored. Table 18-1 shows the formula for computation of the baud rate for different USART modes which only apply in Master mode (internal clock).

Given the desired baud rate and FOSC, the nearest integer value for the SPBRG register can be calculated using the formula in Table 18-1. From this, the error in baud rate can be determined.

EXAMPLE 18-1. CALCULATING BALLD BATE ERBOR

Example 18-1 shows the calculation of the baud rate error for the following conditions:

```
Fosc = 16 MHz
Desired Baud Rate = 9600
BRGH = 0
SYNC = 0
```

It may be advantageous to use the high baud rate (BRGH = 1) even for slower baud clocks. This is because the FOSC/(16(X + 1)) equation can reduce the baud rate error in some cases.

Writing a new value to the SPBRG register causes the BRG timer to be reset (or cleared). This ensures the BRG does not wait for a timer overflow before outputting the new baud rate.

18.1.1 SAMPLING

The data on the RC7/RX/DT pin is sampled three times by a majority detect circuit to determine if a high or a low level is present at the RX pin.

EXAMIFLE 10-1.	CALCOLATING BADD HATE ERNOR
Desired Baud Rate	= Fosc/(64 (X + 1))
Solving for X:	
	X = ((Fosc/Desired Baud Rate)/64) - 1 X = ((16000000/9600)/64) - 1 X = [25.042] = 25
Calculated Baud Rate	$= \frac{16000000}{(64 (25 + 1))}$ = 9615
Error	 <u>(Calculated Baud Rate – Desired Baud Rate)</u> Desired Baud Rate (9615 – 9600)/9600 0.16%

TABLE 18-1: BAUD RATE FORMULA

SYNC	BRGH = 0 (Low Speed)	BRGH = 1 (High Speed)
0	(Asynchronous) Baud Rate = FOSC/(64 (X + 1))	Baud Rate = Fosc/(16 (X + 1))
1	(Synchronous) Baud Rate = FOSC/(4 (X + 1))	NA

Legend: X = value in SPBRG (0 to 255)

TABLE 18-2: REGISTERS ASSOCIATED WITH BAUD RATE GENERATOR

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
TXSTA	CSRC	TX9	TXEN	SYNC	—	BRGH	TRMT	TX9D	0000 -010	0000 -010
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
SPBRG	Baud Rat	e Genera	ator Regis		0000 0000	0000 0000				

Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used by the BRG.

^{© 2006} Microchip Technology Inc.

TABLE	: 18-3:	BAUD	RAIES	FUR 5	INCHR	ONOUS I	VIODE			1			
BAUD	Fosc =	40 MHz	SPBRG	33	MHz	SPBRG	25	MHz	SPBRG	20	MHz	SPBRG	
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
9.6	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
19.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
76.8	76.92	+0.16	129	77.10	+0.39	106	77.16	+0.47	80	76.92	+0.16	64	
96	96.15	+0.16	103	95.93	-0.07	85	96.15	+0.16	64	96.15	+0.16	51	
300	303.03	+1.01	32	294.64	-1.79	27	297.62	-0.79	20	294.12	-1.96	16	
500	500	0	19	485.30	-2.94	16	480.77	-3.85	12	500	0	9	
HIGH	10000	-	0	8250	-	0	6250	-	0	5000	-	0	
LOW	39.06	-	255	32.23	-	255	24.41	-	255	19.53	-	255	
BAUD	Fosc =	16 MHz	SPBRG	10	MHz	SPBRG	7.1590	9 MHz	SPBRG	5.0688 MHz		SPBRG	
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-	
9.6	NA	-	-	NA	-	-	9.62	+0.23	185	9.60	0	131	
19.2	19.23	+0.16	207	19.23	+0.16	129	19.24	+0.23	92	19.20	0	65	
76.8	76.92	+0.16	51	75.76	-1.36	32	77.82	+1.32	22	74.54	-2.94	16	
96	95.24	-0.79	41	96.15	+0.16	25	94.20	-1.88	18	97.48	+1.54	12	
300	307.70	+2.56	12	312.50	+4.17	7	298.35	-0.57	5	316.80	+5.60	3	
500	500	0	7	500	0	4	447.44	-10.51	3	422.40	-15.52	2	
HIGH	4000	-	0	2500	-	0	1789.80	-	0	1267.20	-	0	
LOW	15.63	-	255	9.77	-	255	6.99	-	255	4.95	-	255	
	_												
BAUD	Fosc =	4 MHz	SPBRG	3.5795	45 MHz	SPBRG	1 N	lHz	SPBRG	32.76	8 kHz	SPBRG	
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	
0.3	NA	-	-	NA	-	-	NA	-	-	0.30	+1.14	26	
1.2	NA	-	-	NA	-	-	1.20	+0.16	207	1.17	-2.48	6	
2.4	NA	-	-	NA	-	-	2.40	+0.16	103	2.73	+13.78	2	
9.6	9.62	+0.16	103	9.62	+0.23	92	9.62	+0.16	25	8.20	-14.67	0	
19.2	19.23	+0.16	51	19.04	-0.83	46	19.23	+0.16	12	NA	-	-	
76.8	76.92	+0.16	12	74.57	-2.90	11	83.33	+8.51	2	NA	-	-	
96	1000	+4.17	9	99.43	+3.57	8	83.33	-13.19	2	NA	-	-	
300	333.33	+11.11	2	298.30	-0.57	2	250	-16.67	0	NA	-	-	
500	500	0	1	447.44	-10.51	1	NA	-	-	NA	-	-	
HIGH	1000	-	0	894.89	-	0	250	-	0	8.20	-	0	
			-									-	

TABLE 18-3: BAUD RATES FOR SYNCHRONOUS MODE

TABLE	E 18-4:	BAUD) RATES	FOR A	SYNCH	RONOUS	MODE	(BRGH	= 0)			
BAUD	Fosc =	40 MHz	SPBRG	33	MHz	SPBRG	25	MHz	SPBRG	20	MHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	2.40	-0.07	214	2.40	-0.15	162	2.40	+0.16	129
9.6	9.62	+0.16	64	9.55	-0.54	53	9.53	-0.76	40	9.47	-1.36	32
19.2	18.94	-1.36	32	19.10	-0.54	26	19.53	+1.73	19	19.53	+1.73	15
76.8	78.13	+1.73	7	73.66	-4.09	6	78.13	+1.73	4	78.13	+1.73	3
96	89.29	-6.99	6	103.13	+7.42	4	97.66	+1.73	3	104.17	+8.51	2
300	312.50	+4.17	1	257.81	-14.06	1	NA	-	-	312.50	+4.17	0
500	625	+25.00	0	NA	-	-	NA	-	-	NA	-	-
HIGH	625	-	0	515.63	-	0	390.63	-	0	312.50	-	0
LOW	2.44	-	255	2.01	-	255	1.53	-	255	1.22	-	255
										1		
BAUD	Fosc =	16 MHz	SPBRG	10	MHz	SPBRG	7.15909 MHz		SPBRG	5.068	8 MHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	1.20	+0.16	207	1.20	+0.16	129	1.20	+0.23	92	1.20	0	65
2.4	2.40	+0.16	103	2.40	+0.16	64	2.38	-0.83	46	2.40	0	32
9.6	9.62	+0.16	25	9.77	+1.73	15	9.32	-2.90	11	9.90	+3.13	7
19.2	19.23	+0.16	12	19.53	+1.73	7	18.64	-2.90	5	19.80	+3.13	3
76.8	83.33	+8.51	2	78.13	+1.73	1	111.86	+45.65	0	79.20	+3.13	0
96	83.33	-13.19	2	78.13	-18.62	1	NA	-	-	NA	-	-
300	250	-16.67	0	156.25	-47.92	0	NA	-	-	NA	-	-
500	NA	-	-	NA	-	-	NA	-	-	NA	-	-
HIGH	250	-	0	156.25	-	0	111.86	-	0	79.20	-	0
LOW	0.98	-	255	0.61	-	255	0.44	-	255	0.31	-	255
BAUD	Fosc :	= 4 MHz	SPBRG	3.5795	545 MHz	SPBRG	11	MHz	SPBRG	32.76	68 kHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decima
0.3	0.30	-0.16	207	0.30	+0.23	185	0.30	+0.16	51	0.26	-14.67	1
1.2	1.20	+1.67	51	1.19	-0.83	46	1.20	+0.16	12	NA	-	-
2.4	2.40	+1.67	25	2.43	+1.32	22	2.23	-6.99	6	NA	-	-
9.6	8.93	-6.99	6	9.32	-2.90	5	7.81	-18.62	1	NA	-	-
19.2	20.83	+8.51	2	18.64	-2.90	2	15.63	-18.62	0	NA	-	-
76.8	62.50	-18.62	0	55.93	-27.17	0	NA	-	-	NA	-	-
96	NA	-	-	NA	-	-	NA	-	-	NA	-	-
300	NA	-	-	NA	-	-	NA	-	-	NA	-	-
500	NA	-	-	NA	-	-	NA	-	-	NA	-	-
HIGH	62.50	-	0	55.93	-	0	15.63	-	0	0.51	-	0
			č			~			č			÷

255

0.06

255

0.002

TABLE 18-4: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 0)

255

LOW

0.24

255

0.22

TABLE			RATES F			01003			1	[
BAUD RATE	Fosc =	40 MHz	SPBRG value	33	VHz	SPBRG value	25 I	VHz	SPBRG value	20	MHz	SPBRG value
(Kbps)	KBAUD	% ERROR	(decimal)	KBAUD	% ERROR	(decimal)	KBAUD	% ERROR	(decimal)	KBAUD	% ERROR	(decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	NA	-	-	NA	-	-
9.6	NA	-	-	9.60	-0.07	214	9.59	-0.15	162	9.62	+0.16	129
19.2	19.23	+0.16	129	19.28	+0.39	106	19.30	+0.47	80	19.23	+0.16	64
76.8	75.76	-1.36	32	76.39	-0.54	26	78.13	+1.73	19	78.13	+1.73	15
96	96.15	+0.16	25	98.21	+2.31	20	97.66	+1.73	15	96.15	+0.16	12
300	312.50	+4.17	7	294.64	-1.79	6	312.50	+4.17	4	312.50	+4.17	3
500	500	0	4	515.63	+3.13	3	520.83	+4.17	2	416.67	-16.67	2
HIGH	2500	-	0	2062.50	-	0	1562.50	-	0	1250	-	0
LOW	9.77	-	255	8,06	-	255	6.10	-	255	4.88	-	255
BAUD	Fosc =	16 MHz	SPBRG	10	MHz	SPBRG	7.1590	9 MHz	SPBRG	5.068	8 MHz	SPBRG
RATE		0/	value		%				value		0/	value
(Kbps)	KBAUD	% ERROR	(decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	(decimal)	KBAUD	% ERROR	(decimal)
0.3	NA	-	-	NA	-	-	NA	-	-	NA	-	-
1.2	NA	-	-	NA	-	-	NA	-	-	NA	-	-
2.4	NA	-	-	NA	-	-	2.41	+0.23	185	2.40	0	131
9.6	9.62	+0.16	103	9.62	+0.16	64	9.52	-0.83	46	9.60	0	32
19.2	19.23	+0.16	51	18.94	-1.36	32	19.45	+1.32	22	18.64	-2.94	16
76.8	76.92	+0.16	12	78.13	+1.73	7	74.57	-2.90	5	79.20	+3.13	3
96	100	+4.17	9	89.29	-6.99	6	89.49	-6.78	4	105.60	+10.00	2
300	333.33	+11.11	2	312.50	+4.17	1	447.44	+49.15	0	316.80	+5.60	0
500	500	0	1	625	+25.00	0	447.44	-10.51	0	NA	-	-
HIGH	1000	-	0	625	-	0	447.44	-	0	316.80	-	0
LOW	3.91	-	255	2.44	-	255	1.75	-	255	1.24	-	255
BAUD	Fosc =	4 MHz	SPBRG	3.5795	45 MHz	SPBRG	1 N	IHz	SPBRG	32.76	8 kHz	SPBRG
RATE (Kbps)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)	KBAUD	% ERROR	value (decimal)
0.3	NA	-	-	NA	-	-	0.30	+0.16	207	0.29	-2.48	6
1.2	1.20	+0.16	207	1.20	+0.23	185	1.20	+0.16	51	1.02	-14.67	1
2.4	2.40	+0.16	103	2.41	+0.23	92	2.40	+0.16	25	2.05	-14.67	0
9.6	9.62	+0.16	25	9.73	+1.32	22	8.93	-6.99	6	NA	-	-
19.2	19.23	+0.16	12	18.64	-2.90	11	20.83	+8.51	2	NA	-	-
76.8	NA	-	-	74.57	-2.90	2	62.50	-18.62	0	NA	-	-
96	NA	-	-	111.86	+16.52	1	NA	-	-	NA	-	-
300	NA	-	-	223.72	-25.43	0	NA	-	-	NA	-	-
						-						

-

0

255

NA

62.50

0.24

-

-

-

0

255

NA

2.05

0.008

-

-

-

0

255

TABLE 18-5: BAUD RATES FOR ASYNCHRONOUS MODE (BRGH = 1)

500

HIGH

LOW

NA

250

0.98

-

-

-

0

255

NA

55.93

0.22

-

-

18.2 USART Asynchronous Mode

In this mode, the USART uses standard Non-Returnto-Zero (NRZ) format (one Start bit, eight or nine data bits and one Stop bit). The most common data format is 8 bits. An on-chip dedicated 8-bit Baud Rate Generator can be used to derive standard baud rate frequencies from the oscillator. The USART transmits and receives the LSb first. The USART's transmitter and receiver are functionally independent but use the same data format and baud rate. The Baud Rate Generator produces a clock, either x16 or x64 of the bit shift rate, depending on the BRGH bit (TXSTA register). Parity is not supported by the hardware but can be implemented in software (and stored as the ninth data bit). Asynchronous mode is stopped during Sleep.

Asynchronous mode is selected by clearing the SYNC bit (TXSTA register).

The USART Asynchronous module consists of the following important elements:

- · Baud Rate Generator
- Sampling Circuit
- Asynchronous Transmitter
- Asynchronous Receiver.

18.2.1 USART ASYNCHRONOUS TRANSMITTER

The USART transmitter block diagram is shown in Figure 18-1. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The TSR register obtains its data from the Read/Write Transmit Buffer register (TXREG). The TXREG register is loaded with data in software. The TSR register is not loaded until the Stop bit has been transmitted from the previous load. As soon as the Stop bit is transmitted, the TSR is loaded with new data from the TXREG register (if available). Once the TXREG register transfers the data to the TSR register (occurs in one TcY), the TXREG register is set. This

interrupt can be enabled/disabled by setting/clearing enable bit TXIE (PIE1 register). Flag bit TXIF will be set regardless of the state of enable bit TXIE and cannot be cleared in software. It will reset only when new data is loaded into the TXREG register. While flag bit, TXIF, indicated the status of the TXREG register, another bit, TRMT (TXSTA register), shows the status of the TSR register. Status bit TRMT is a read-only bit which is set when the TSR register is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty.


- Note 1: The TSR register is not mapped in data memory, so it is not available to the user.
 - 2: Flag bit TXIF is set when enable bit TXEN is set.

Steps to follow when setting up an Asynchronous Transmission:

- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is desired, set bit BRGH (Section 18.1 "USART Baud Rate Generator (BRG)").
- 2. Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set transmit bit TX9. Can be used as address/data bit.
- 5. Enable the transmission by setting bit TXEN which will also set bit TXIF.
- 6. If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 7. Load data to the TXREG register (starts transmission).

Note: TXIF is not cleared immediately upon loading data into the transmit buffer TXREG. The flag bit becomes valid in the second instruction cycle following the load instruction.

FIGURE 18-1: USART TRANSMIT BLOCK DIAGRAM






FIGURE 18-3: ASYNCHRONOUS TRANSMISSION (BACK TO BACK)




TABLE 18-6: REGISTERS ASSOCIATED WITH ASYNCHRONOUS TRANSMISSION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
TXREG	USART Tra	ansmit Regis	ter						0000 0000	0000 0000
TXSTA	CSRC	TX9	TX9D	0000 -010	0000 -010					
SPBRG	Baud Rate	Generator F		0000 0000	0000 0000					
Lawrende										

 $\label{eq:logend: x = unknown, - = unimplemented locations read as `0'. Shaded cells are not used for asynchronous transmission.$

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

DS41159E-page 190

18.2.2 USART ASYNCHRONOUS RECEIVER

The receiver block diagram is shown in Figure 18-4. The data is received on the RC7/RX/DT pin and drives the data recovery block. The data recovery block is actually a high-speed shifter, operating at x16 times the baud rate, whereas the main receive serial shifter operates at the bit rate or at Fosc. This mode would typically be used in RS-232 systems.

Steps to follow when setting up an Asynchronous Reception:

- 1. Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is desired, set bit BRGH (Section 18.1 "USART Baud Rate Generator (BRG)").
- 2. Enable the asynchronous serial port by clearing bit SYNC and setting bit SPEN.
- З. If interrupts are desired, set enable bit RCIE.
- If 9-bit reception is desired, set bit RX9. 4
- Enable the reception by setting bit CREN. 5.
- 6. Flag bit RCIF will be set when reception is complete and an interrupt will be generated if enable bit RCIE was set.
- 7. Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- Read the 8-bit received data by reading the 8. RCREG register.
- 9. If any error occurred, clear the error by clearing enable bit CREN.

18.2.3 SETTING UP 9-BIT MODE WITH ADDRESS DETECT

This mode would typically be used in RS-485 systems. Steps to follow when setting up an Asynchronous Reception with Address Detect Enable:

- Initialize the SPBRG register for the appropriate baud rate. If a high-speed baud rate is required, set the BRGH bit.
- 2. Enable the asynchronous serial port by clearing the SYNC bit and setting the SPEN bit.
- 3. If interrupts are required, set the RCEN bit and select the desired priority level with the RCIP bit.
- Set the RX9 bit to enable 9-bit reception. 4
- Set the ADDEN bit to enable address detect. 5
- Enable reception by setting the CREN bit. 6.
- 7. The RCIF bit will be set when reception is complete. The interrupt will be Acknowledged if the RCIE and GIE bits are set.
- Read the RCSTA register to determine if any 8. error occurred during reception, as well as read bit 9 of data (if applicable).
- Read RCREG to determine if the device is being 9 addressed.
- 10. If any error occurred, clear the CREN bit.
- 11. If the device has been addressed, clear the ADDEN bit to allow all received data into the receive buffer and interrupt the CPU.




FIGURE 18-4: USART RECEIVE BLOCK DIAGRAM






TABLE 18-7: REGISTERS ASSOCIATED WITH ASYNCHRONOUS RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	x000 000x	0000 000u
RCREG	USART Rec	eive Register							0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate Generator Register								0000 0000	0000 0000
SPBRG	Baud Rate Generator Register								0000 0000	0000 000

Legend: x = unknown, - = unimplemented locations read as '0'. Shaded cells are not used for asynchronous reception.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

18.3 USART Synchronous Master Mode

In Synchronous Master mode, the data is transmitted in a half-duplex manner (i.e., transmission and reception do not occur at the same time). When transmitting data, the reception is inhibited and vice versa. Synchronous mode is entered by setting bit SYNC (TXSTA register). In addition, enable bit SPEN (RCSTA register) is set in order to configure the RC6/TX/CK and RC7/RX/DT I/O pins to CK (clock) and DT (data) lines, respectively. The Master mode indicates that the processor transmits the master clock on the CK line. The Master mode is entered by setting bit CSRC (TXSTA register).

18.3.1 USART SYNCHRONOUS MASTER TRANSMISSION

The USART transmitter block diagram is shown in Figure 18-1. The heart of the transmitter is the Transmit (Serial) Shift Register (TSR). The shift register obtains its data from the Read/Write Transmit Buffer register (TXREG). The TXREG register is loaded with data in software. The TSR register is not loaded until the last bit has been transmitted from the previous load. As soon as the last bit is transmitted, the TSR is loaded with new data from the TXREG (if available). Once the TXREG register transfers the data to the TSR register (occurs in one TCY), the TXREG is empty and interrupt bit TXIF (PIR1 register) is set. The interrupt can be enabled/disabled by setting/clearing enable bit TXIE (PIE1 register). Flag bit TXIF will be set regardless of the state of enable bit TXIE and cannot be cleared in

software. It will reset only when new data is loaded into the TXREG register. While flag bit, TXIF, indicates the status of the TXREG register, another bit, TRMT (TXSTA register), shows the status of the TSR register. TRMT is a read-only bit which is set when the TSR is empty. No interrupt logic is tied to this bit, so the user has to poll this bit in order to determine if the TSR register is empty. The TSR is not mapped in data memory, so it is not available to the user.

Steps to follow when setting up a Synchronous Master Transmission:

- 1. Initialize the SPBRG register for the appropriate baud rate (Section 18.1 "USART Baud Rate Generator (BRG)").
- 2. Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- 5. Enable the transmission by setting bit TXEN.
- 6. If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 7. Start transmission by loading data to the TXREG register.

Note: TXIF is not cleared immediately upon loading data into the transmit buffer TXREG. The flag bit becomes valid in the second instruction cycle following the load instruction.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INT0IF	RBIF	x000 0000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
TXREG	USART Trai	nsmit Registe	er						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	—	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate (Generator Re		0000 0000	0000 0000					

TABLE 18-8: REGISTERS ASSOCIATED WITH SYNCHRONOUS MASTER TRANSMISSION

Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous master transmission.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.





FIGURE 18-6: SYNCHRONOUS TRANSMISSION





18.3.2 USART SYNCHRONOUS MASTER RECEPTION

Once Synchronous Master mode is selected, reception is enabled by setting either enable bit SREN (RCSTA register) or enable bit CREN (RCSTA register). Data is sampled on the RC7/RX/DT pin on the falling edge of the clock. If enable bit SREN is set, only a single word is received. If enable bit CREN is set, the reception is continuous until CREN is cleared. If both bits are set, then CREN takes precedence. Steps to follow when setting up a Synchronous Master Reception:

- 1. Initialize the SPBRG register for the appropriate baud rate (Section 18.1 "USART Baud Rate Generator (BRG)").
- 2. Enable the synchronous master serial port by setting bits SYNC, SPEN and CSRC.
- 3. Ensure bits CREN and SREN are clear.
- 4. If interrupts are desired, set enable bit RCIE.
- 5. If 9-bit reception is desired, set bit RX9.
- 6. If a single reception is required, set bit SREN. For continuous reception, set bit CREN.
- 7. Interrupt flag bit RCIF will be set when reception is complete and an interrupt will be generated if the enable bit RCIE was set.
- 8. Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 9. Read the 8-bit received data by reading the RCREG register.
- 10. If any error occurred, clear the error by clearing bit CREN.


TABLE 18	-9: RE(GISTERS	ASSOCI	ATED W	ITH SYN	CHRON	OUS MA	STER RI	ECEPTION	

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
RCREG	USART Rec	ceive Registe	r						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC		BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate	0000 0000	0000 0000							

Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous master reception.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

FIGURE 18-8: SYNCHRONOUS RECEPTION (MASTER MODE, SREN)



18.4 USART Synchronous Slave Mode

Synchronous Slave mode differs from the Master mode in that the shift clock is supplied externally at the RC6/ TX/CK pin (instead of being supplied internally in Master mode). This allows the device to transfer or receive data while in Sleep mode. Slave mode is entered by clearing bit CSRC (TXSTA register).

18.4.1 USART SYNCHRONOUS SLAVE TRANSMIT

The operation of the Synchronous Master and Slave modes are identical, except in the case of the Sleep mode.

If two words are written to the TXREG and then the SLEEP instruction is executed, the following will occur:

- a) The first word will immediately transfer to the TSR register and transmit.
- b) The second word will remain in TXREG register.
- c) Flag bit TXIF will not be set.
- d) When the first word has been shifted out of TSR, the TXREG register will transfer the second word to the TSR and flag bit TXIF will be set.
- e) If enable bit TXIE is set, the interrupt will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector.

Steps to follow when setting up a Synchronous Slave Transmission:

- 1. Enable the synchronous slave serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. Clear bits CREN and SREN.
- 3. If interrupts are desired, set enable bit TXIE.
- 4. If 9-bit transmission is desired, set bit TX9.
- 5. Enable the transmission by setting enable bit TXEN.
- 6. If 9-bit transmission is selected, the ninth bit should be loaded in bit TX9D.
- 7. Start transmission by loading data to the TXREG register.

18.4.2 USART SYNCHRONOUS SLAVE RECEPTION

The operation of the Synchronous Master and Slave modes is identical, except in the case of the Sleep mode and bit SREN, which is a "don't care" in Slave mode.

If receive is enabled by setting bit CREN prior to the SLEEP instruction, then a word may be received during Sleep. On completely receiving the word, the RSR register will transfer the data to the RCREG register and if enable bit RCIE bit is set, the interrupt generated will wake the chip from Sleep. If the global interrupt is enabled, the program will branch to the interrupt vector.

Steps to follow when setting up a Synchronous Slave Reception:

- Enable the synchronous master serial port by setting bits SYNC and SPEN and clearing bit CSRC.
- 2. If interrupts are desired, set enable bit RCIE.
- 3. If 9-bit reception is desired, set bit RX9.
- 4. To enable reception, set enable bit CREN.
- Flag bit RCIF will be set when reception is complete. An interrupt will be generated if enable bit RCIE was set.
- Read the RCSTA register to get the ninth bit (if enabled) and determine if any error occurred during reception.
- 7. Read the 8-bit received data by reading the RCREG register.
- 8. If any error occurred, clear the error by clearing bit CREN.

DS41159E-page 196

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
TXREG	USART Trai	nsmit Registe	er						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate Generator Register									0000 0000

Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous slave transmission.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

TABLE 18-11: REGISTERS ASSOCIATED WITH SYNCHRONOUS SLAVE RECEPTION

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INTOIE	RBIE	TMR0IF	INTOIF	RBIF	0000 000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
RCSTA	SPEN	RX9	SREN	CREN	ADDEN	FERR	OERR	RX9D	0000 000x	0000 000u
RCREG	USART Red	ceive Registe	r						0000 0000	0000 0000
TXSTA	CSRC	TX9	TXEN	SYNC	_	BRGH	TRMT	TX9D	0000 -010	0000 -010
SPBRG	Baud Rate Generator Register									0000 0000

Legend: x = unknown, - = unimplemented, read as '0'. Shaded cells are not used for synchronous slave reception.

Note 1: These registers or register bits are not implemented on the PIC18F248 and PIC18F258 and read as '0's.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 198

19.0 CAN MODULE

19.1 Overview

The Controller Area Network (CAN) module is a serial interface, useful for communicating with other peripherals or microcontroller devices. This interface/protocol was designed to allow communications within noisy environments.

The CAN module is a communication controller, implementing the CAN 2.0 A/B protocol as defined in the BOSCH specification. The module will support CAN 1.2, CAN 2.0A, CAN 2.0B Passive and CAN 2.0B Active versions of the protocol. The module implementation is a full CAN system. The CAN specification is not covered within this data sheet. The reader may refer to the BOSCH CAN specification for further details.

The module features are as follows:

- Complies with ISO CAN Conformance Test
- Implementation of the CAN protocol CAN 1.2, CAN 2.0A and CAN 2.0B
- · Standard and extended data frames
- 0-8 bytes data length
- Programmable bit rate up to 1 Mbit/sec
- Support for remote frames
- Double-buffered receiver with two prioritized received message storage buffers
- 6 full (standard/extended identifier) acceptance filters, 2 associated with the high priority receive buffer and 4 associated with the low priority receive buffer
- 2 full acceptance filter masks, one each associated with the high and low priority receive buffers
- Three transmit buffers with application specified prioritization and abort capability
- Programmable wake-up functionality with integrated low-pass filter
- Programmable Loopback mode supports self-test operation
- Signaling via interrupt capabilities for all CAN receiver and transmitter error states
- Programmable clock source
- Programmable link to timer module for time-stamping and network synchronization
- Low-power Sleep mode

19.1.1 OVERVIEW OF THE MODULE

The CAN bus module consists of a protocol engine and message buffering and control. The CAN protocol engine handles all functions for receiving and transmitting messages on the CAN bus. Messages are transmitted by first loading the appropriate data registers. Status and errors can be checked by reading the appropriate registers. Any message detected on the CAN bus is checked for errors and then matched against filters to see if it should be received and stored in one of the 2 receive registers.

The CAN module supports the following frame types:

- Standard Data Frame
- Extended Data Frame
- Remote Frame
- Error Frame
- Overload Frame Reception
- Interframe Space


CAN module uses RB3/CANRX and RB2/CANTX/INT2 pins to interface with CAN bus. In order to configure CANRX and CANTX as CAN interface:

- bit TRISB<3> must be set;
- bit TRISB<2> must be cleared.

19.1.2 TRANSMIT/RECEIVE BUFFERS

The PIC18FXX8 has three transmit and two receive buffers, two acceptance masks (one for each receive buffer) and a total of six acceptance filters. Figure 19-1 is a block diagram of these buffers and their connection to the protocol engine.

^{© 2006} Microchip Technology Inc.



DS41159E-page 200

19.2 CAN Module Registers

Note:	Not all CAN registers are available in the
	Access Bank.

There are many control and data registers associated with the CAN module. For convenience, their descriptions have been grouped into the following sections:

- Control and Status Registers
- Transmit Buffer Registers (Data and Control)
- Receive Buffer Registers (Data and Control)
- Baud Rate Control Registers
- I/O Control Register
- · Interrupt Status and Control Registers

19.2.1 CAN CONTROL AND STATUS REGISTERS

The registers described in this section control the overall operation of the CAN module and show its operational status.

REGISTER 19-1:	CANCON:		NTROL REC	GISTER					
	R/W-1	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	
	REQOP2	REQOP1	REQOP0	ABAT	WIN2	WIN1	WIN0	_	
	bit 7		·					bit 0	
bit 7-5	REQOP2:REQOP0: Request CAN Operation Mode bits								
	1xx = Request Configuration mode								
	011 = Request Listen Only mode 010 = Request Loopback mode								
	001 = Request Disable mode								
	000 = Request Normal mode								
bit 4	bit 4 ABAT: Abort All Pending Transmissions bit								
	 1 = Abort all pending transmissions (in all transmit buffers) 0 = Transmissions proceeding as normal 								
bit 3-1	WIN2:WIN0: Window Address bits								
	This selects which of the CAN buffers to switch into the Access Bank area. This allows access to the buffer registers from any data memory bank. After a frame has caused an interrupt, the ICODE2:ICODE0 bits can be copied to the WIN2:WIN0 bits to select the correct buffer. See Example 19-1 for code example.								
		eive Buffer (eive Buffer (
		eive Buffer 1							
	100 = Transmit Buffer 0								
	011 = Transmit Buffer 1 010 = Transmit Buffer 2								
	010 = Fransmit Buffer 2 001 = Receive Buffer 0								
	000 = Receive Buffer 0								
bit 0	Unimplem	ented: Read	d as '0'						
	Legend:								
	R = Reada	ble bit	W = Writab	ole bit	U = Unim	plemented b	oit, read as ')'	
	1								

'1' = Bit is set

'0' = Bit is cleared

© 2006 Microchip Technology Inc.

-n = Value at POR

x = Bit is unknown

CANSTAT: CAN STATUS REGISTER REGISTER 19-2:

	R-1	R-0	R-0	U-0	R-0	R-0	R-0	U-0
	OPMODE2	OPMODE1	OPMODE0		ICODE2	ICODE1	ICODE0	_
-	bit 7							bit 0

bit 7-5

OPMODE2:OPMODE0: Operation Mode Status bits

- 111 = Reserved
- 110 = Reserved
- 101 = Reserved
- 100 = Configuration mode
- 011 = Listen Only mode
- 010 = Loopback mode
- 001 = Disable mode
- 000 = Normal mode

Before the device goes into Sleep mode, select Disable mode. Note:

bit 4 Unimplemented: Read as '0'

bit 3-1 ICODE2:ICODE0: Interrupt Code bits

When an interrupt occurs, a prioritized coded interrupt value will be present in the ICODE2:ICODE0 bits. These codes indicate the source of the interrupt. The ICODE2:ICODE0 bits can be copied to the WIN2:WIN0 bits to select the correct buffer to map into the Access Bank area. See Example 19-1 for code example.

- 111 = Wake-up on interrupt
- 110 = RXB0 interrupt
- 101 = RXB1 interrupt
- 100 = TXB0 interrupt
- 011 = TXB1 interrupt
- 010 = TXB2 interrupt
- 001 = Error interrupt
- 000 = No interrupt
- bit 0

Unimplemented: Read as '0'

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented I	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

EXAMPLE 19-1: WIN AND ICODE BITS USAGE IN INTERRUPT SERVICE ROUTINE TO ACCESS TX/RX BUFFERS

```
; Save application required context.
   ; Poll interrupt flags and determine source of interrupt
   ; This was found to be CAN interrupt
   ; TempCANCON and TempCANSTAT are variables defined in Access Bank low
   MOVFF CANCON, TempCANCON
                                       ; Save CANCON.WIN bits
                                        ; This is required to prevent CANCON
                                        ; from corrupting CAN buffer access
                                        ; in-progress while this interrupt
                                        ; occurred
   MOVFF CANSTAT, TempCANSTAT
                                        ; Save CANSTAT register
                                        ; This is required to make sure that
                                        ; we use same CANSTAT value rather
                                        ; than one changed by another CAN
                                        ; interrupt.
   MOVF
          TempCANSTAT, W
                                       ; Retrieve ICODE bits
   ANDLW b'00001110'
   ADDWF PCL, F
                                       ; Perform computed GOTO
                                       ; to corresponding interrupt cause
   BRA
          NoInterrupt
                                       ; 000 = No interrupt
   BRA
        ErrorInterrupt
                                       ; 001 = Error interrupt
                                       ; 010 = TXB2 interrupt
   BRA
          TXB2Interrupt
                                       ; 011 = TXB1 interrupt
   BRA
          TXB1Interrupt
   BRA
          TXB0Interrupt
                                       ; 100 = TXB0 interrupt
   BRA
          RXB1Interrupt
                                       ; 101 = RXB1 interrupt
   BRA
          RXB0Interrupt
                                       ; 110 = RXB0 interrupt
                                        ; 111 = Wake-up on interrupt
WakeupInterrupt
   BCF
          PIR3, WAKIF
                                       ; Clear the interrupt flag
   ; User code to handle wake-up procedure
   ; Continue checking for other interrupt source or return from here
NoInterrupt
                                        ; PC should never vector here. User may
                                        ; place a trap such as infinite loop or pin/port
                                        ; indication to catch this error.
ErrorInterrupt
   BCF PIR3, ERRIF
                                       ; Clear the interrupt flag
                                        ; Handle error.
   ....
   RETFIE
TXB2Interrupt
   BCF PIR3, TXB2IF
                                       ; Clear the interrupt flag
   GOTO AccessBuffer
TXB1Interrupt
   BCF PIR3, TXB1IF
                                       ; Clear the interrupt flag
   GOTO AccessBuffer
TXB0Interrupt
   BCF
          PIR3, TXBOIF
                                       ; Clear the interrupt flag
         AccessBuffer
   GOTO
RXB1Interrupt
   BCF PIR3, RXB1IF
                                       ; Clear the interrupt flag
   GOTO Accessbuffer
```

Г

EXAMPLE 19-1: WIN AND ICODE BITS USAGE IN INTERRUPT SERVICE ROUTINE TO ACCESS TX/RX BUFFERS (CONTINUED)

KB0Interru	ıpt	
BCF	PIR3, RXB0IF	; Clear the interrupt flag
GOTO	AccessBuffer	
ccessBuffe	er	; This is either TX or RX interrupt
; Copy	CANCON.ICODE bits to	CANSTAT.WIN bits
MOVF	CANCON, W	; Clear CANCON.WIN bits before copying
		; new ones.
ANDLW	b'11110001'	; Use previously saved CANCON value to
		; make sure same value.
MOVWF	CANCON	; Copy masked value back to TempCANCON
MOVF	TempCANSTAT, W	; Retrieve ICODE bits
ANDLW	b'00001110'	; Use previously saved CANSTAT value
		; to make sure same value.
IORWF	CANCON	; Copy ICODE bits to WIN bits.
		; Copy the result to actual CANCON
; Acces	s current buffer…	
; User	code	
: Resto	ore CANCON.WIN bits	
,	CANCON, W	; Preserve current non WIN bits
	b'11110001'	,
IORWF	TempCANCON, W	; Restore original WIN bits
MOVWF	CANCON	
; Do no	ot need to restore CAN	ISTAT - it is read-only register.
-		
; Retur	n from interrupt or o	check for another module interrupt source

ΓER 19-3:	COMSTAT:		CATION S	STATUS R	EGISTER					
	R/C-0	R/C-0	R-0	R-0	R-0	R-0	R-0	R-0		
	RXB00VFL	RXB10VFL	ТХВО	TXBP	RXBP	TXWARN	RXWARN	EWARN		
	bit 7							bit 0		
bit 7		Receive Buff		ow bit						
		Buffer 0 overf Buffer 0 has r		up d						
bit 6		Receive Buff								
DILO		Buffer 1 overf								
	0 = Receive Buffer 1 has not overflowed									
bit 5	bit 5 TXBO: Transmitter Bus-Off bit									
		Error Counte								
		Error Counte								
bit 4		mitter Bus Pa								
		sion Error Co sion Error Co								
bit 3	RXBP: Rece	iver Bus Pase	sive bit							
		Error Counter Error Counter								
bit 2	TXWARN: Tr	ransmitter Wa	rning bit							
		ansmit Error C Error Counte		5						
bit 1	RXWARN: R	leceiver Warn	ing bit							
		eceive Error C Error Counter		5						
bit 0	EWARN: Err	or Warning bi	t							
	This bit is a f	lag of the RX	WARN and	TXWARN b	its.					
		VARN or the 1								
	0 = Neither ti	he RXWARN	or the TXW	ARN bits ar	e set					
	Legend:									
	R = Readable	e bit W = V	Vritable bit	C = Cleara	able bit	U = Unimple	emented bit,	read as '0'		
	-n = Value at	POR '1' = E	Bit is set	'0' = Bit is	cleared	x = Bit is un	known			

REGISTER 19-3: COMSTAT: COMMUNICATION STATUS REGISTER

19.2.2 CAN TRANSMIT BUFFER REGISTERS

This section describes the CAN Transmit Buffer registers and their associated control registers.

REGISTER 19-4:	TXBnCON: TRANSMIT BUFFER n CONTROL REGISTERS									
	U-0	R-0	R-0	R-0	R/W-0	U-0	R/W-0	R/W-0		
		TXABT	TXLARB	TXERR	TXREQ	—	TXPRI1	TXPRI0		
	bit 7							bit 0		
L :+ 7										
bit 7	-	ented: Rea								
bit 6		TXABT: Transmission Aborted Status bit 1 = Message was aborted								
		ge was abol ge was not a								
bit 5		-	n Lost Arbitr	ation Status	bit					
	1 = Messa	1 = Message lost arbitration while being sent								
		 message did not lose arbitration while being sent 								
bit 4	TXERR: T	TXERR: Transmission Error Detected Status bit								
			ed while the	•	•					
bit 3			occur while		e was being	Sent				
DIL 3			uest Status I a message.			ABB and TY	(ERR hite			
			red when the							
	Note:	Clearing th	is bit in softw	vare while th	ne bit is set v	vill request a	a message a	abort.		
bit 2	Unimplem	ented: Rea	d as '0'							
bit 1-0	TXPRI1:T	KPRI0: Tran	smit Priority	bits						
	11 = Priori	ty Level 3 (h	nighest priori	ty)						
	10 = Priori									
	01 = Priori	•	owest priority	٥.						
	Note:	•			ha Transmit	Buffor will k	o transform	d They do		
	Note: These bits set the order in which the Transmit Buffer will be transferred. They do not alter the CAN message identifier.									
	Legend:									
	R = Reada	ble bit	W = Writa	ble bit	U = Unin	plemented	bit, read as	'0'		

'1' = Bit is set

'0' = Bit is cleared

-n = Value at POR

DS41159E-page 206

x = Bit is unknown

REGISTER 19-5: TXBnSIDH: TRANSMIT BUFFER n STANDARD IDENTIFIER, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3
bit 7							bit 0

bit 7-0 SID10:SID3: Standard Identifier bits if EXIDE = 0 (TXBnSID Register) or Extended Identifier bits EID28:EID21 if EXIDE = 1

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

REGISTER 19-6: TXBnSIDL: TRANSMIT BUFFER n STANDARD IDENTIFIER, LOW BYTE REGISTERS

R/W-	x R/W-	x R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
SID2	2 SID	1 SID0		EXIDE	—	EID17	EID16
bit 7				·			bit 0

- bit 7-5 SID2:SID0: Standard Identifier bits if EXIDE = 0 or Extended Identifier bits EID20:EID18 if EXIDE = 1
- bit 4 Unimplemented: Read as '0'
- bit 3 **EXIDE:** Extended Identifier enable bit
 - 1 = Message will transmit extended ID, SID10:SID0 becomes EID28:EID18
 - 0 = Message will transmit standard ID, EID17:EID0 are ignored
- bit 2 Unimplemented: Read as '0'
- bit 1-0 EID17:EID16: Extended Identifier bits

Legend:				
R = Readable bit	W = Writable bit	bit U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

REGISTER 19-7: TXBnEIDH: TRANSMIT BUFFER n EXTENDED IDENTIFIER, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8
bit 7							bit 0

bit 7-0 EID15:EID8: Extended Identifier bits

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

^{© 2006} Microchip Technology Inc.

REGISTER 19-8: TXBnEIDL: TRANSMIT BUFFER n EXTENDED IDENTIFIER, LOW BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0
bit 7							bit 0

bit 7-0

0 **EID7:EID0:** Extended Identifier bits

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

REGISTER 19-9: TXBnDm: TRANSMIT BUFFER n DATA FIELD BYTE m REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
TXBnDm7	TXBnDm6	TXBnDm5	TXBnDm4	TXBnDm3	TXBnDm2	TXBnDm1	TXBnDm0
bit 7							bit 0

bit 7-0 **TXBnDm7:TXBnDm0:** Transmit Buffer n Data Field Byte m bits (where $0 \le n < 3$ and 0 < m < 8) Each Transmit Buffer has an array of registers. For example, Transmit Buffer 0 has 7 registers: TXB0D0 to TXB0D7.

Legend:				
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

DS41159E-page 208

STER 19-10:	TXBnDLC	: TRANSM	IT BUFFE	R n DATA	LENGTH (CODE REC	AISTERS	
	U-0	R/W-x	U-0	U-0	R/W-x	R/W-x	R/W-x	R/W-x
	—	TXRTR	—	—	DLC3	DLC2	DLC1	DLC0
	bit 7							bit 0
bit 7	Unimplem	ented: Read	d as '0'					
bit 6	TXRTR: Tra	ansmission	Frame Rem	ote Transmi	ssion Reque	est bit		
	1 = Transm	itted messa	ge will have	TXRTR bit	set			
	0 = Transm	itted messa	ge will have	TXRTR bit	cleared			
bit 5-4	Unimplem	ented: Read	d as '0'					
bit 3-0	DLC3:DLC	0: Data Len	gth Code bi	ts				
	1111 = Res	served						
	1110 = Re s							
	1101 = Re s							
	1100 = Res 1011 = Res							
	1011 = Re							
	1001 = Res							
		ta Length =	8 bytes					
	0111 = Dat	ta Length =	7 bytes					
		ta Length =	•					
		ta Length =						
		ta Length =	•					
		ta Length = ta Length = 1						
		•	•					
	0001 = Data Length = 1 bytes 0000 = Data Length = 0 bytes							
	2000 Du		,					
	Legend:							
	Legend:							

REGISTER 19-10: TXBnDLC: TRANSMIT BUFFER n DATA LENGTH CODE REGISTER
--

Legend:				
R = Readable bit	dable bit $W = Writable bit$ $U = Unimplemented bit, read as '0'$			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

REGISTER 19-11: TXERRCNT: TRANSMIT ERROR COUNT REGISTER

R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
TEC7	TEC6	TEC5	TEC4	TEC3	TEC2	TEC1	TEC0
bit 7							bit 0

bit 7-0

TEC7:TEC0: Transmit Error Counter bits

This register contains a value which is derived from the rate at which errors occur. When the error count overflows, the bus-off state occurs. When the bus has 128 occurrences of 11 consecutive recessive bits, the counter value is cleared.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

CAN RECEIVE BUFFER 19.2.3 REGISTERS

This section shows the Receive Buffer registers with their associated control registers.

R = Readable bit

-n = Value at POR

ISTER 19-12:	RXB0CON: RECEIVE BUFFER 0 CONTROL REGISTER										
	R/C-0	R/W-0	R/W-0	U-0	R-0	R/W-0	R-0	R-0			
	RXFUL ⁽¹⁾	RXM1 ⁽¹⁾	RXM0 ⁽¹⁾	—	RXRTRRO	RXB0DBEN	JTOFF	FILHIT0			
	bit 7							bit 0			
bit 7	RXFUL: Receive Full Status bit ⁽¹⁾										
			ntains a rec open to rece		0						
	Note:	This bit is is read.	set by the C	CAN module	and must be	cleared by so	ftware afte	r the buffer			
bit 6-5	RXM1:RXM	MO: Receiv	e Buffer Mo	de bits ⁽¹⁾							
 11 = Receive all messages (including those with errors) 10 = Receive only valid messages with extended identifier 01 = Receive only valid messages with standard identifier 00 = Receive all valid messages 											
bit 4	Unimplem	Unimplemented: Read as '0'									
bit 3	RXRTRRO	: Receive I	Remote Tra	nsfer Reque	est Read-Only	/ bit					
		e transfer re note transfe	•								
bit 2	RXB0DBEN: Receive Buffer 0 Double-Buffer Enable bit										
	1 = Receive Buffer 0 overflow will write to Receive Buffer 10 = No Receive Buffer 0 overflow to Receive Buffer 1										
bit 1	JTOFF: Jump Table Offset bit (read-only copy of RXB0DBEN)										
	 1 = Allows jump table offset between 6 and 7 0 = Allows jump table offset between 1 and 0 										
	Note:	This bit all	ows same f	ilter jump ta	ble for both F	XB0CON and	RXB1CO	Ν.			
bit 0	FILHITO: F	ilter Hit bit									
	This bit ind	icates whic	h acceptanc	e filter enat	oled the mess	age reception	into Receiv	ve Buffer 0.			
	•	ance Filter	• •								
	0 = Accept	ance Filter	0 (HXF0)								
	Note 1:	Bits RXFL	IL, RXM1 ar	nd RXM0 of	RXB0CON a	re not mirrore	d in RXB10	CON.			
]			
	Legend:										

W = Writable bit C = Clearable bit

'0' = Bit is cleared

'1' = Bit is set

DS41159E-page 210

U = Unimplemented bit, read as '0'

x = Bit is unknown

STER 19-13:	RXB1CON: RECEIVE BUFFER 1 CONTROL REGISTER										
	R/C-0	R/W-0	R/W-0	U-0	R-0	R-0	R-0	R-0			
	RXFUL ⁽¹⁾	RXM1 ⁽¹⁾	RXM0 ⁽¹⁾		RXRTRRO	FILHIT2	FILHIT1	FILHIT0			
	bit 7							bit 0			
bit 7	RXFUL: Receive Full Status bit ⁽¹⁾										
	 1 = Receive buffer contains a received message 0 = Receive buffer is open to receive a new message 										
	Note:	is read.									
bit 6-5	RXM1:RXM0: Receive Buffer Mode bits ⁽¹⁾										
	 11 = Receive all messages (including those with errors) 10 = Receive only valid messages with extended identifier 01 = Receive only valid messages with standard identifier 00 = Receive all valid messages 										
bit 4	Unimplemented: Read as '0'										
bit 3	RXRTRRO: Receive Remote Transfer Request bit (read-only)										
	 1 = Remote transfer request 0 = No remote transfer request 										
bit 2-0	FILHIT2:FI	LHIT0: Filte	er Hit bits								
	These bits indicate which acceptance filter enabled the last message reception into Receive Buffer 1.										
	111 = Rese	erved									
	110 = Rese										
		eptance Filte	• • •								
		eptance Filte									
	010 = Acce	eptance Filte	er 2 (RXF2)								
					le when RXB le when RXB						
	Note 1:	Bits RXFU	_, RXM1 an	d RXM0 of I	RXB1CON are	e not mirror	ed in RXB00	CON.			

Legend:						
R = Readable bit	W = Writable bit	C = Clearable bit	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

REGISTER 19-13: RXB1CON: RECEIVE BUFFER 1 CONTROL REGISTER

 $[\]ensuremath{\textcircled{}^{\circ}}$ 2006 Microchip Technology Inc.

REGISTER 19-14: RXBnSIDH: RECEIVE BUFFER n STANDARD IDENTIFIER, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3
bit 7							bit 0

bit 7-0 SID10:SID3: Standard Identifier bits if EXID = 0 (RXBnSIDL Register) or Extended Identifier bits EID28:EID21 if EXID = 1

Legend:						
R = Readable bit	W = Writable bit	U = Unimplemented	U = Unimplemented bit, read as '0'			
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

REGISTER 19-15: RXBnSIDL: RECEIVE BUFFER n STANDARD IDENTIFIER, LOW BYTE REGISTERS

	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	<u>U-0</u>	R/W-x	R/W-x
	SID2	SID1	SID0	SRR	EXID	—	EID17	EID16
	bit 7							bit 0
bit 7-5	SID2:SID0:	Standard Id	dentifier bits	if $EXID = 0$	or			
	Extended lo	dentifier bits	EID20:EID1	18 if EXID =	1			
bit 4	SRR: Subs	titute Remo	te Request l	oit				
	This bit is a	lways 'o' wh	nen EXID =	1 or equal to	the value o	f RXRTRRC) (RXnBCO	N<3>)
	when EXID	= 0.						
bit 3	EXID: Exte	nded Identif	ier bit					
	1 = Receive	ed message	is an exten	ded data fra	me, SID10:8	SID0 are EI	028:EID18	
	0 = Receive	ed message	is a standa	rd data fram	е			
bit 2	Unimplem	ented: Read	d as '0'					
bit 1-0	EID17:EID	16: Extende	d Identifier b	oits				

Le	egend:				
R	= Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'		
-n	= Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown	

REGISTER 19-16: RXBnEIDH: RECEIVE BUFFER n EXTENDED IDENTIFIER, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8
bit 7							bit 0

bit 7-0 EID15:EID8: Extended Identifier bits

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

DS41159E-page 212

REGISTER 19-17: RXBnEIDL: RECEIVE BUFFER n EXTENDED IDENTIFIER, LOW BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0
bit 7							bit 0

bit 7-0 EID7:EID0: Extended Identifier bits

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

REGISTER 19-18: RXBnDLC: RECEIVE BUFFER n DATA LENGTH CODE REGISTERS

	U-0	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
	—	RXRTR	RB1	RB0	DLC3	DLC2	DLC1	DLC0
	bit 7							bit 0
bit 7	Unimplem	ented: Read	l as '0'					
bit 6	RXRTR: Re	eceiver Rem	ote Transm	ission Requ	est bit			
		e transfer rec						
		ote transfer	request					
bit 5	RB1: Rese							
		y CAN spec	and read a	s '0'.				
bit 4	RB0: Rese							
		y CAN spec						
bit 3-0		0: Data Len	gth Code bit	s				
	1111 = Inva							
	$1110 = \ln v_0$							
	1101 = Invalid 1100 = Invalid							
	$100 = \ln valid$ $1011 = \ln valid$							
	1010 = Invalid							
	1001 = Invalid 1000 = Data Length = 8 bytes							
		a Length = 1						
	0110 = Data Length = 6 bytes 0101 = Data Length = 5 bytes 0100 = Data Length = 4 bytes 0011 = Data Length = 3 bytes							
	0011 = Data Length = 2 bytes							
	0001 = Data Length = 1 bytes							
	0000 = Data Length = 0 bytes							
	Legend:							
	R = Readab	ole bit	W = Writak	ole bit	U = Unim	nplemented	bit, read as '	0'
	-n = Value a	at POR	'1' = Bit is	set	'0' = Bit i	s cleared	x = Bit is u	nknown

REGISTER 19-19: RXBnDm: RECEIVE BUFFER n DATA FIELD BYTE m REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
RXBnDm7	RXBnDm6	RXBnDm5	RXBnDm4	RXBnDm3	RXBnDm2	RXBnDm1	RXBnDm0
bit 7							bit 0

bit 7-0 **RXBnDm7:RXBnDm0:** Receive Buffer n Data Field Byte m bits (where $0 \le n < 1$ and 0 < m < 7) Each receive buffer has an array of registers. For example, Receive Buffer 0 has 8 registers: RXB0D0 to RXB0D7.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

REGISTER 19-20: RXERRCNT: RECEIVE ERROR COUNT REGISTER

R-0	R-0	R-0	R-0	R-0	R-0	R-0	R-0
REC7	REC6	REC5	REC4	REC3	REC2	REC1	REC0
bit 7							bit 0

bit 7-0 REC7:REC0: Receive Error Counter bits

This register contains the receive error value as defined by the CAN specifications. When RXERRCNT > 127, the module will go into an error passive state. RXERRCNT does not have the ability to put the module in "Bus-Off" state.

Legend:		
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'
-n = Value at POR	'1' = Bit is set	0' = Bit is cleared $x = Bit is unknown$

19.2.3.1 Message Acceptance Filters and Masks

This subsection describes the message acceptance filters and masks for the CAN receive buffers.

REGISTER 19-21: RXFnSIDH: RECEIVE ACCEPTANCE FILTER n STANDARD IDENTIFIER FILTER, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3
bit 7							bit 0

bit 7-0 SID10:SID3: Standard Identifier Filter bits if EXIDEN = 0 or Extended Identifier Filter bits EID28:EID21 if EXIDEN = 1

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

REGISTER 19-22: RXFnSIDL: RECEIVE ACCEPTANCE FILTER n STANDARD IDENTIFIER FILTER, LOW BYTE REGISTERS

	R/W-x	R/W-x	R/W-x	U-0	R/W-x	U-0	R/W-x	R/W-x		
	SID2	SID1	SID0	_	EXIDEN	—	EID17	EID16		
	bit 7							bit 0		
bit 7-5	sit 7-5 SID2:SID0: Standard Identifier Filter bits if EXIDEN = 0 or Extended Identifier Filter bits EID20:EID18 if EXIDEN = 1									
bit 4	Unimplemented: Read as '0'									
bit 3	EXIDEN: E	xtended Ide	ntifier Filter	Enable bit						
			•	ID message ID message						
bit 2	Unimplem	ented: Read	d as '0'							
bit 1-0	EID17:EID16: Extended Identifier Filter bits									
	Legend:									

Legend:								
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'					
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown					

REGISTER 19-23: RXFnEIDH: RECEIVE ACCEPTANCE FILTER n EXTENDED IDENTIFIER, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	
EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8	
bit 7							bit 0	

bit 7-0

EID15:EID8: Extended Identifier Filter bits

Legend:							
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown				

REGISTER 19-24: RXFnEIDL: RECEIVE ACCEPTANCE FILTER n EXTENDED IDENTIFIER, LOW BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0
bit 7							bit 0

bit 7-0 EID7:EID0: Extended Identifier Filter bits

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented bi	t, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	k = Bit is unknown

REGISTER 19-25: RXMnSIDH: RECEIVE ACCEPTANCE MASK n STANDARD IDENTIFIER MASK, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
SID10	SID9	SID8	SID7	SID6	SID5	SID4	SID3
bit 7							bit 0

bit 7-0 SID10:SID3: Standard Identifier Mask bits or Extended Identifier Mask bits EID28:EID21

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented b	oit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

REGISTER 19-26: RXMnSIDL: RECEIVE ACCEPTANCE MASK n STANDARD IDENTIFIER MASK, LOW BYTE REGISTERS

R/W-x	R/W-x	R/W-x	U-0	U-0	U-0	R/W-x	R/W-x
SID2	SID1	SID0	—	—	—	EID17	EID16
bit 7							bit 0

- bit 7-5 SID2:SID0: Standard Identifier Mask bits or Extended Identifier Mask bits EID20:EID18
- bit 4-2 Unimplemented: Read as '0'
- bit 1-0 EID17:EID16: Extended Identifier Mask bits

Legend:			
R = Readable bit W = Writable bit		U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

REGISTER 19-27: RXMnEIDH: RECEIVE ACCEPTANCE MASK n EXTENDED IDENTIFIER MASK, HIGH BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EID15	EID14	EID13	EID12	EID11	EID10	EID9	EID8
bit 7							bit 0

bit 7-0 EID15:EID8: Extended Identifier Mask bits

Legend:						
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

REGISTER 19-28: RXMnEIDL: RECEIVE ACCEPTANCE MASK n EXTENDED IDENTIFIER MASK, LOW BYTE REGISTERS

R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x	R/W-x
EID7	EID6	EID5	EID4	EID3	EID2	EID1	EID0
bit 7							bit 0

bit 7-0 EID7:EID0: Extended Identifier Mask bits

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

^{© 2006} Microchip Technology Inc.

19.2.4 CAN BAUD RATE REGISTERS

This subsection describes the CAN Baud Rate registers.

REGISTER 19-29: BRGCON1: BAUD RATE CONTROL REGISTER 1

	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
	SJW1	SJW0	BRP5	BRP4	BRP3	BRP2	BRP1	BRP0		
	bit 7							bit 0		
bit 7-6	SJW1:SJW	/0: Synchro	nized Jump	Width bits						
	11 = Synchronization Jump Width Time = 4 x TQ									
	$10 =$ Synchronization Jump Width Time = $3 \times TQ$									
	01 = Synchronization Jump Width Time = 2 x TQ									
	00 = Synchronization Jump Width Time = 1 x TQ									
bit 5-0	BRP5:BRP0: Baud Rate Prescaler bits									
		TQ = (2 x 64	,							
		TQ = (2 x 63)/Fosc							
	:									
	: 000001 — T	TQ = (2 x 2)/	Fosc							
		ΓQ = (2 x 1)/ ΓQ = (2 x 1)/								
		· · · · · · //								
	Legend:									
	R = Readal	ble bit	W = Writa	ble bit	U = Unin	nplemented	bit, read as	'0'		
	-n = Value a	at POR	'1' = Bit is	set		s cleared	x = Bit is u			

Note: This register is accessible in Configuration mode only.

DS41159E-page 218

STER 19-30:	BRGCON2:	BAUD R	ATE CONT	ROL REG	ISTER 2				
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
	SEG2PHTS	SAM	SEG1PH2	SEG1PH1	SEG1PH0	PRSEG2	PRSEG1	PRSEG0	
	bit 7							bit 0	
bit 7	SEG2PHTS:	Phase Seg	gment 2 Tim	e Select bit					
	1 = Freely pr 0 = Maximun	•		tion Process	sing Time (IF	T), whichev	ver is greate	r	
bit 6	SAM: Sampl	le of the CA	N bus Line	bit					
	 1 = Bus line is sampled three times prior to the sample point 0 = Bus line is sampled once at the sample point 								
bit 5-3	bit 5-3 SEG1PH2:SEG1PH0: Phase Segment 1 bits								
	111 = Phase Segment 1 Time = 8 x TQ 110 = Phase Segment 1 Time = 7 x TQ 101 = Phase Segment 1 Time = 6 x TQ 100 = Phase Segment 1 Time = 5 x TQ 011 = Phase Segment 1 Time = 4 x TQ 010 = Phase Segment 1 Time = 3 x TQ 001 = Phase Segment 1 Time = 2 x TQ 000 = Phase Segment 1 Time = 1 x TQ								
bit 2-0	PRSEG2:PRSEG0: Propagation Time Select bits $111 =$ Propagation Time = 8 x TQ $110 =$ Propagation Time = 7 x TQ $101 =$ Propagation Time = 6 x TQ $100 =$ Propagation Time = 5 x TQ $011 =$ Propagation Time = 4 x TQ $010 =$ Propagation Time = 3 x TQ $001 =$ Propagation Time = 2 x TQ $000 =$ Propagation Time = 1 x TQ								
	Legend:								
	R = Readable	e bit	W = Writab	le bit	U = Unim	plemented b	oit, read as '	0'	
	-n = Value at	POR	'1' = Bit is s	set	'0' = Bit is	cleared	x = Bit is u	nknown	
	L								

REGISTER 19-30: BRGCON2: BAUD RATE CONTROL REGISTER 2

Note: This register is accessible in Configuration mode only.

^{© 2006} Microchip Technology Inc.

bit 7 bit 6

bit 5-3 bit 2-0

REGISTER 19-31: BRGCON3: BAUD RATE CONTROL REGISTER 3

101 = Phase Segment 2 Time = 6 x Tq 100 = Phase Segment 2 Time = 5 x Tq 011 = Phase Segment 2 Time = 4 x Tq 010 = Phase Segment 2 Time = 3 x Tq 001 = Phase Segment 2 Time = 2 x Tq 000 = Phase Segment 2 Time = 1 x Tq

Legend:

R = Readable bit

-n = Value at POR

Note 1: Ignored if SEG2PHTS bit (BRGCON2<7>) is clear.

W = Writable bit

'1' = Bit is set

-31:	DRGCON	IS: DAUD	RAIECO		REGISIE	กง		
	U-0	R/W-0	U-0	U-0	U-0	R/W-0	R/W-0	R/W-0
		WAKFIL	—	—	_	SEG2PH2 ⁽¹⁾	SEG2PH1 ⁽¹⁾	SEG2PH0 ⁽¹⁾
	bit 7							bit 0
	Unimpler	nented: Re	ad as '0'					
	WAKFIL:	Selects CA	N bus Line	Filter for \	Nake-up b	it		
		CAN bus line bus line filte			e-up			
3	Unimpler	nented: Re	ad as '0'					
)	SEG2PH2	2:SEG2PH): Phase S	egment 2 ⁻	Time Selec	t bits ⁽¹⁾		
		ase Segme ase Segme						

DS41159E-page 220

U = Unimplemented bit, read as '0'

x = Bit is unknown

'0' = Bit is cleared

19.2.5 CAN MODULE I/O CONTROL REGISTER

bit bit

bit

bit

This register controls the operation of the CAN module's I/O pins in relation to the rest of the microcontroller.

REGISTER 19-32: CIOCON: CAN I/O CONTROL REGISTER

	U-0	U-0	R/W-0	R/W-0	U-0	U-0	U-0	U-0			
			ENDRHI	CANCAP	_		_	—			
	bit 7							bit 0			
t 7-6	Unimplem	ented: Read	las '∩'								
	•										
t 5		ENDRHI: Enable Drive High bit									
	1 = CANTX pin will drive VDD when recessive										
	0 = CANTX	(pin will tri-s	tate when re	ecessive							
t 4	CANCAP:	CAN Messa	ge Receive	Capture Ena	able bit						
	1 = Enable	CAN captur	e, CAN mes	ssage receiv	e signal repl	laces input o	on RC2/CCF	P1			
				P1 input to C	• .	•					
t 3-0	Unimplem	ented: Read	as '0'								
	Legend:										
	-										
	R = Readal	ble bit	W = Writa	ble bit	U = Unim	plemented	bit, read as	ʻ0'			
	-n = Value a	at POR	'1' = Bit is	set	'0' = Bit is	s cleared	x = Bit is u	nknown			

^{© 2006} Microchip Technology Inc.

19.2.6 CAN INTERRUPT REGISTERS

The registers in this section are the same as described in Section 8.0 "Interrupts". They are duplicated here for convenience.

-n = Value at POR

TER 19-33:	PIR3: PEF	RIPHERAL	INTERRU	PT REQUE	ST (FLAG	i) REGISTI	ER 3			
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0		
	IRXIF	WAKIF	ERRIF	TXB2IF	TXB1IF	TXB0IF	RXB1IF	RXB0IF		
	bit 7							bit 0		
bit 7	IRXIF: CAN Invalid Received Message Interrupt Flag bit									
	1 = An invalid message has occurred on the CAN bus									
		•	e on CAN bi							
bit 6				Interrupt Fl	ag bit					
 1 = Activity on CAN bus has occurred 0 = No activity on CAN bus 										
bit 5	ERRIF: CA	N bus Error	Interrupt Fla	ag bit						
	 1 = An error has occurred in the CAN module (multiple sources) 0 = No CAN module errors 									
bit 4	TXB2IF: C	AN Transmi	t Buffer 2 Int	terrupt Flag	bit					
			•	ed transmiss pleted transr		•	nay be reloa	ded		
bit 3				terrupt Flag		U				
				ed transmiss			nay be reloa	ded		
bit 2	TXB0IF: C	AN Transmi	t Buffer 0 Ini	terrupt Flag	bit					
				ed transmiss pleted transr			nay be reloa	ded		
bit 1	RXB1IF: C	AN Receive	Buffer 1 Int	errupt Flag I	oit					
	1 = Receiv	e Buffer 1 h	as received	a new mess	age					
	0 = Receiv	e Buffer 1 h	as not receiv	ved a new m	essage					
bit 0	RXB0IF: C	AN Receive	Buffer 0 Int	errupt Flag b	oit					
				a new mess ved a new m	0					
	Legend:]		
	R = Reada	hle hit	W = Writa	hle hit	LI = Unin	nlemented	bit, read as	'O'		
							5.1, 1000 05			

'1' = Bit is set

'0' = Bit is cleared

REGISTE

DS41159E-page 222

x = Bit is unknown

ER 19-34:	PIE3: PEF	RIPHERAL	INTERRU	PT ENABL	E REGIST	ER 3		
	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
	IRXIE	WAKIE	ERRIE	TXB2IE	TXB1IE	TXB0IE	RXB1IE	RXB0IE
	bit 7							bit 0
bit 7				sage Interrup	ot Enable bit			
 1 = Enable invalid message received interrupt 0 = Disable invalid message received interrupt 								
bit 6			0		aabla bit			
DILO			wake-up int	o Interrupt Ei				
			wake-up in					
bit 5	ERRIE: CA	N bus Erro	r Interrupt Er	nable bit				
			rror interrup					
	0 = Disable	e CAN bus e	error interrup	t				
bit 4				terrupt Enab	le bit			
			uffer 2 interr Suffer 2 inter	•				
bit 3				terrupt Enab	lo hit			
DIT 5			uffer 1 interr	•				
			Buffer 1 inter					
bit 2	TXB0IE: C	AN Transmi	it Buffer 0 In	terrupt Enab	le bit			
			uffer 0 interr					
			Suffer 0 inter	-				
bit 1				errupt Enab	le bit			
			uffer 1 interru uffer 1 interr					
bit 0				errupt Enab	le hit			
			uffer 0 interru	•				
			uffer 0 interr					
	Legend:							
	R = Reada	ble bit	W = Writa	ble bit	U = Unim	plemented	bit, read as '	0'
	-n = Value a	at POR	'1' = Bit is	set	'0' = Bit is	scleared	x = Bit is u	nknown

REGISTER 19-34: PIE3: PERIPHERAL INTERRUPT ENABLE REGISTER 3

IPR3: PERIPHERAL INTERRUPT PRIORITY REGISTER 3									
R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1	R/W-1		
IRXIP	WAKIP	ERRIP	TXB2IP	TXB1IP	TXB0IP	RXB1IP	RXB0IP		
bit 7							bit 0		
IRXIP: CA	N Invalid Re	ceived Mes	sage Interru	ot Priority bi	t				
• •	•								
0 = Low pr	iority								
WAKIP: C	AN bus Acti	vity Wake-u	o Interrupt P	riority bit					
• •	•								
0 = Low pr	iority								
ERRIP: CA	AN bus Erro	r Interrupt P	riority bit						
1 = High priority									
•	•								
TXB2IP: C	AN Transmi	it Buffer 2 In	terrupt Prior	ity bit					
• •	•								
	•								
		it Buffer 1 In	terrupt Prior	ity bit					
0 1									
•	,								
		it Buffer 0 In	terrupt Prior	ity bit					
• •	•								
-	-	Duffor 1 In	torrupt Driori	tu bit					
			terrupt Priori	ty Dit					
• •	•								
•	•	e Buffer 0 In	terrupt Priori	tv bit					
				.,					
• •	•								
ľ	,								
Legend:									
R = Reada	ble bit	W = Writa	ble bit	U = Unim	plemented	bit, read as	0'		
	R/W-1 IRXIP: CA 1 = High p 0 = Low pr WAKIP: C 1 = High p 0 = Low pr ERRIP: C/ 1 = High p 0 = Low pr TXB2IP: C 1 = High p 0 = Low pr TXB1IP: C 1 = High p 0 = Low pr TXB0IP: C 1 = High p 0 = Low pr RXB1IP: C 1 = High p 0 = Low pr RXB0IP: C 1 = High p 0 = Low pr RXB0IP: C 1 = High p 0 = Low pr RXB0IP: C	R/W-1R/W-1IRXIPWAKIPbit 7IRXIP: CAN Invalid Refine 1 = High priority0 = Low priorityWAKIP: CAN bus Activation1 = High priority0 = Low priorityERRIP: CAN bus Activation1 = High priority0 = Low priorityTXB2IP: CAN bus Error1 = High priority0 = Low priorityTXB2IP: CAN Transmit1 = High priority0 = Low priorityTXB1P: CAN Transmit1 = High priority0 = Low priorityTXB0IP: CAN Transmit1 = High priority0 = Low priorityRXB1IP: CAN Received1 = High priority0 = Low priorityRXB1IP: CAN Received1 = High priority0 = Low priorityRXB0IP: CAN Received1 = High priority0 = Low priorityRXB0IP: CAN Received1 = High priority0 = Low priorityRXB0IP: CAN Received1 = High priority0 = Low priority	R/W-1R/W-1R/W-1IRXIPWAKIPERRIPbit 7IRXIP: CAN Invalid Received Mess1 = High priority0 = Low priorityWAKIP: CAN bus Activity Wake-up1 = High priority0 = Low priorityERRIP: CAN bus Error Interrupt P1 = High priority0 = Low priorityTXB2IP: CAN Transmit Buffer 2 In1 = High priority0 = Low priorityTXB1IP: CAN Transmit Buffer 1 In1 = High priority0 = Low priorityTXB0IP: CAN Transmit Buffer 0 In1 = High priority0 = Low priorityRXB1IP: CAN Receive Buffer 1 In1 = High priority0 = Low priorityRXB1IP: CAN Receive Buffer 1 In1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 In1 = High priority0 = Low priorityRXBOIP: CAN Receive Buffer 0 In1 = High priority0 = Low priorityExercise Buffer 0 In1 = High priority0 = Low priorityExercise Buffer 0 In1 = High priority0 = Low priority	R/W-1R/W-1R/W-1R/W-1IRXIPWAKIPERRIPTXB2IPbit 7IRXIP: CAN Invalid Received Message Interrupt1 = High priority0 = Low priorityWAKIP: CAN bus Activity Wake-up Interrupt P1 = High priority0 = Low priorityERRIP: CAN bus Error Interrupt Priority bit1 = High priority0 = Low priorityTXB2IP: CAN Transmit Buffer 2 Interrupt Prior1 = High priority0 = Low priorityTXB1IP: CAN Transmit Buffer 1 Interrupt Prior1 = High priority0 = Low priorityTXB0IP: CAN Transmit Buffer 0 Interrupt Prior1 = High priority0 = Low priorityRXB0IP: CAN Transmit Buffer 0 Interrupt Prior1 = High priority0 = Low priorityRXB1IP: CAN Receive Buffer 1 Interrupt Prior1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priori1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priori1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priori1 = High priority0 = Low priorityImage: Can Receive Buffer 0 Interrupt Priori1 = High priority0 = Low priority	R/W-1R/W-1R/W-1R/W-1IRXIPWAKIPERRIPTXB2IPTXB1IPbit 7IRXIP: CAN Invalid Received Message Interrupt Priority bit1 = High priority0 = Low priorityWAKIP: CAN bus Activity Wake-up Interrupt Priority bit1 = High priority0 = Low priorityERRIP: CAN bus Activity Wake-up Interrupt Priority bit1 = High priority0 = Low priorityERRIP: CAN bus Error Interrupt Priority bit1 = High priority0 = Low priorityTXB2IP: CAN Transmit Buffer 2 Interrupt Priority bit1 = High priority0 = Low priorityTXB1IP: CAN Transmit Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityTXB0IP: CAN Transmit Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityEquation of the priority0 = Low priority	R/W-1R/W-1R/W-1R/W-1R/W-1IRXIPWAKIPERRIPTXB2IPTXB1IPTXB0IPbit 7IRXIP: CAN Invalid Received Message Interrupt Priority bit1 = High priority0 = Low priorityWAKIP: CAN bus Activity Wake-up Interrupt Priority bit1 = High priority0 = Low priorityWAKIP: CAN bus Activity Wake-up Interrupt Priority bit1 = High priority0 = Low priorityERRIP: CAN bus Error Interrupt Priority bit1 = High priority0 = Low priorityTXB2IP: CAN Transmit Buffer 2 Interrupt Priority bit1 = High priority0 = Low priorityTXB1IP: CAN Transmit Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityTXB0IP: CAN Transmit Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB1IP: CAN Receive Buffer 1 Interrupt Priority bit1 = High priority0 = Low priorityRXB1IP: CAN Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityRXB0IP: CAN Receive Buffer 0 Interrupt Priority bit1 = High priority0 = Low priorityEQuational Mathematical Statement Priority0 = Low priority	R/W-1 R/W-1 R/W-1 R/W-1 R/W-1 R/W-1 R/W-1 IRXIP WAKIP ERRIP TXB2IP TXB1IP TXB0IP RXB1IP bit 7 IRXIP: CAN Invalid Received Message Interrupt Priority bit 1 = High priority 0 = Low priority WAKIP: CAN bus Activity Wake-up Interrupt Priority bit 1 = High priority 0 = Low priority ERRIP: CAN bus Error Interrupt Priority bit 1 = High priority 0 = Low priority TXB2IP: CAN bus Error Interrupt Priority bit 1 = High priority 0 = Low priority TXB2IP: CAN Transmit Buffer 2 Interrupt Priority bit 1 = High priority 0 = Low priority TXB1IP: CAN Transmit Buffer 1 Interrupt Priority bit 1 = High priority 0 = Low priority TXB0IP: CAN Transmit Buffer 0 Interrupt Priority bit 1 = High priority 0 = Low priority RXB1IP: CAN Receive Buffer 1 Interrupt Priority bit 1 = High priority 0 = Low priority RXB0IP: CAN Receive Buffer 0 Interrupt Priority bit <td c<="" td=""></td>		

REGISTER 19-35: IPR3: PERIPHERAL INTERRUPT PRIORITY REGISTER 3

Legena:						
R = Readable bit	W = Writable bit	U = Unimplemented bit, read as '0'				
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown			

Address	Name	Address	Name Address Name		Address	Name	
F7Fh		F5Fh	_	F3Fh	_	F1Fh	RXM1EIDL
F7Eh	_	F5Eh	CANSTATRO1 ⁽²⁾	F3Eh	CANSTATRO3(2)	F1Eh	RXM1EIDH
F7Dh	_	F5Dh	RXB1D7	F3Dh	TXB1D7	F1Dh	RXM1SIDL
F7Ch	_	F5Ch	RXB1D6	F3Ch	TXB1D6	F1Ch	RXM1SIDH
F7Bh	_	F5Bh	RXB1D5	F3Bh	TXB1D5	F1Bh	RXM0EIDL
F7Ah	—	F5Ah	RXB1D4	F3Ah	TXB1D4	F1Ah	RXM0EIDH
F79h	_	F59h	RXB1D3	F39h	TXB1D3	F19h	RXM0SIDL
F78h	_	F58h	RXB1D2	F38h	TXB1D2	F18h	RXM0SIDH
F77h	_	F57h	RXB1D1	F37h	TXB1D1	F17h	RXF5EIDL
F76h	TXERRCNT	F56h	RXB1D0	F36h	TXB1D0	F16h	RXF5EIDH
F75h	RXERRCNT	F55h	RXB1DLC	F35h	TXB1DLC	F15h	RXF5SIDL
F74h	COMSTAT	F54h	RXB1EIDL	F34h	TXB1EIDL	F14h	RXF5SIDH
F73h	CIOCON	F53h	RXB1EIDH	F33h	TXB1EIDH	F13h	RXF4EIDL
F72h	BRGCON3	F52h	RXB1SIDL	F32h	TXB1SIDL	F12h	RXF4EIDH
F71h	BRGCON2	F51h	RXB1SIDH	F31h	TXB1SIDH	F11h	RXF4SIDL
F70h	BRGCON1	F50h	RXB1CON	F30h	TXB1CON	F10h	RXF4SIDH
F6Fh	CANCON	F4Fh	—	F2Fh	—	F0Fh	RXF3EIDL
F6Eh	CANSTAT	F4Eh	CANSTATRO2 ⁽²⁾	F2Eh	CANSTATRO4 ⁽²⁾	F0Eh	RXF3EIDH
F6Dh	RXB0D7	F4Dh	TXB0D7	F2Dh	TXB2D7	F0Dh	RXF3SIDL
F6Ch	RXB0D6	F4Ch	TXB0D6	F2Ch	TXB2D6	F0Ch	RXF3SIDH
F6Bh	RXB0D5	F4Bh	TXB0D5	F2Bh	TXB2D5	F0Bh	RXF2EIDL
F6Ah	RXB0D4	F4Ah	TXB0D4	F2Ah	TXB2D4	F0Ah	RXF2EIDH
F69h	RXB0D3	F49h	TXB0D3	F29h	TXB2D3	F09h	RXF2SIDL
F68h	RXB0D2	F48h	TXB0D2	F28h	TXB2D2	F08h	RXF2SIDH
F67h	RXB0D1	F47h	TXB0D1	F27h	TXB2D1	F07h	RXF1EIDL
F66h	RXB0D0	F46h	TXB0D0	F26h	TXB2D0	F06h	RXF1EIDH
F65h	RXB0DLC	F45h	TXB0DLC	F25h	TXB2DLC	F05h	RXF1SIDL
F64h	RXB0EIDL	F44h	TXB0EIDL	F24h	TXB2EIDL	F04h	RXF1SIDH
F63h	RXB0EIDH	F43h	TXB0EIDH	F23h	TXB2EIDH	F03h	RXF0EIDL
F62h	RXB0SIDL	F42h	TXB0SIDL	F22h	TXB2SIDL	F02h	RXF0EIDH
F61h	RXB0SIDH	F41h	TXB0SIDH	F21h	TXB2SIDH	F01h	RXF0SIDL
F60h	RXB0CON	F40h	TXB0CON	F20h	TXB2CON	F00h	RXF0SIDH

TADLE 13-1. CAN CONTROLLER REGISTER MAP	TABLE 19-1:	CAN CONTROLLER REGISTER MAP
---	-------------	-----------------------------

Note 1: Shaded registers are available in Access Bank low area while the rest are available in Bank 15.

2: CANSTAT register is repeated in these locations to simplify application firmware. Unique names are given for each instance of the CANSTAT register due to the Microchip Header file requirement.

^{© 2006} Microchip Technology Inc.

19.3 CAN Modes of Operation

The PIC18FXX8 has six main modes of operation:

- Configuration mode
- Disable mode
- Normal Operation mode
- · Listen Only mode
- · Loopback mode
- Error Recognition mode

All modes, except Error Recognition, are requested by setting the REQOP bits (CANCON<7:5>); Error Recognition is requested through the RXM bits of the Receive Buffer register(s). Entry into a mode is Acknowledged by monitoring the OPMODE bits.

When changing modes, the mode will not actually change until all pending message transmissions are complete. Because of this, the user must verify that the device has actually changed into the requested mode before fUrther Operations Are Executed.

19.3.1 CONFIGURATION MODE

The CAN module has to be initialized before the activation. This is only possible if the module is in the Configuration mode. The Configuration mode is requested by setting the REQOP2 bit. Only when the OPMODE2 status bit has a high level can the initialization be performed. Afterwards, the Configuration registers, the Acceptance Mask registers and the Acceptance Filter registers can be written. The module is activated by setting the REQOP control bits to zero.

The module will protect the user from accidentally violating the CAN protocol through programming errors. All registers which control the configuration of the module can not be modified while the module is online. The CAN module will not be allowed to enter the Configuration mode while a transmission is taking place. The CONFIG bit serves as a lock to protect the following registers.

- Configuration registers
- Bus Timing registers
- Identifier Acceptance Filter registers
- Identifier Acceptance Mask registers

In the Configuration mode, the module will not transmit or receive. The error counters are cleared and the interrupt flags remain unchanged. The programmer will have access to Configuration registers that are access restricted in other modes.

19.3.2 DISABLE MODE

In Disable mode, the module will not transmit or receive. The module has the ability to set the WAKIF bit due to bus activity, however, any pending interrupts will remain and the error counters will retain their value.

If REQOP<2:0> is set to '001', the module will enter the Module Disable mode. This mode is similar to disabling other peripheral modules by turning off the module enables. This causes the module internal clock to stop unless the module is active (i.e., receiving or transmitting a message). If the module is active, the module will wait for 11 recessive bits on the CAN bus, detect that condition as an IDLE bus, then accept the module disable command. OPMODE<2:0> = 001 indicates whether the module successfully went into Module Disable mode.

The WAKIF interrupt is the only module interrupt that is still active in the Module Disable mode. If the WAKIE is set, the processor will receive an interrupt whenever the CAN bus detects a dominant state, as occurs with a SOF. If the processor receives an interrupt while it is sleeping, more than one message may get lost. User firmware must anticipate this condition and request retransmission. If the processor is running while it receives an interrupt, only the first message may get lost.

The I/O pins will revert to normal I/O function when the module is in the Module Disable mode.

19.3.3 NORMAL MODE

This is the standard operating mode of the PIC18FXX8. In this mode, the device actively monitors all bus messages and generates Acknowledge bits, error frames, etc. This is also the only mode in which the PIC18FXX8 will transmit messages over the CAN bus.

19.3.4 LISTEN ONLY MODE

Listen Only mode provides a means for the PIC18FXX8 to receive all messages, including messages with errors. This mode can be used for bus monitor applications or for detecting the baud rate in 'hot plugging' situations. For auto-baud detection, it is necessary that there are at least two other nodes which are communicating with each other. The baud rate can be detected empirically by testing different values until valid messages are received. The Listen Only mode is a silent mode, meaning no messages will be transmitted while in this state, including error flags or Acknowledge signals. The filters and masks can be used to allow only particular messages to be loaded into the receive registers, or the filter masks can be set to all zeros to allow a message with any identifier to pass. The error counters are reset and deactivated in this state. The Listen Only mode is activated by setting the mode request bits in the CANCON register.

DS41159E-page 226

19.3.5 LOOPBACK MODE

This mode will allow internal transmission of messages from the transmit buffers to the receive buffers without actually transmitting messages on the CAN bus. This mode can be used in system development and testing. In this mode, the ACK bit is ignored and the device will allow incoming messages from itself, just as if they were coming from another node. The Loopback mode is a silent mode, meaning no messages will be transmitted while in this state, including error flags or Acknowledge signals. The TXCAN pin will revert to port I/O while the device is in this mode. The filters and masks can be used to allow only particular messages to be loaded into the receive registers. The masks can be set to all zeros to provide a mode that accepts all messages. The Loopback mode is activated by setting the mode request bits in the CANCON register.

19.3.6 ERROR RECOGNITION MODE

The module can be set to ignore all errors and receive all message. The Error Recognition mode is activated by setting the RXM<1:0> bits in the RXBnCON registers to '11'. In this mode, all messages, valid or invalid, are received and copied to the receive buffer.

19.4 CAN Message Transmission

19.4.1 TRANSMIT BUFFERS

The PIC18FXX8 implements three transmit buffers (Figure 19-2). Each of these buffers occupies 14 bytes of SRAM and are mapped into the device memory map.


For the MCU to have write access to the message buffer, the TXREQ bit must be clear, indicating that the message buffer is clear of any pending message to be transmitted. At a minimum, the TXBnSIDH, TXBnSIDL and TXBnDLC registers must be loaded. If data bytes are present in the message, the TXBnDm registers must also be loaded. If the message is to use extended identifiers, the TXBnEIDm registers must also be loaded and the EXIDE bit set.

Prior to sending the message, the MCU must initialize the TXInE bit to enable or disable the generation of an interrupt when the message is sent. The MCU must also initialize the TXP priority bits (see **Section 19.4.2 "Transmit Priority"**).

19.4.2 TRANSMIT PRIORITY

Transmit priority is a prioritization within the PIC18FXX8 of the pending transmittable messages. This is independent from and not related to any prioritization implicit in the message arbitration scheme built into the CAN protocol. Prior to sending the SOF, the priority of all buffers that are queued for transmission is compared. The transmit buffer with the highest priority will be sent first. If two buffers have the same priority setting, the buffer with the highest buffer number will be sent first. There are four levels of transmit priority. If TXP bits for a particular message buffer are set to '11', that buffer has the highest possible priority. If TXP bits for a particular message buffer are '00', that buffer has the lowest possible priority.

FIGURE 19-2: TRANSMIT BUFFER BLOCK DIAGRAM



^{© 2006} Microchip Technology Inc.

19.4.3 INITIATING TRANSMISSION

To initiate message transmission, the TXREQ bit must be set for each buffer to be transmitted. When TXREQ is set, the TXABT, TXLARB and TXERR bits will be cleared.

Setting the TXREQ bit does not initiate a message transmission; it merely flags a message buffer as ready for transmission. Transmission will start when the device detects that the bus is available. The device will then begin transmission of the highest priority message that is ready.


When the transmission has completed successfully, the TXREQ bit will be cleared, the TXBnIF bit will be set and an interrupt will be generated if the TXBnIE bit is set.

If the message transmission fails, the TXREQ will remain set, indicating that the message is still pending for transmission and one of the following condition flags will be set. If the message started to transmit but encountered an error condition, the TXERR and the IRXIF bits will be set and an interrupt will be generated. If the message lost arbitration, the TXLARB bit will be set.

19.4.4 ABORTING TRANSMISSION

The MCU can request to abort a message by clearing the TXREQ bit associated with the corresponding message buffer (TXBnCON<3>). Setting the ABAT bit (CANCON<4>) will request an abort of all pending messages. If the message has not yet started transmission, or if the message started but is interrupted by loss of arbitration or an error, the abort will be processed. The abort is indicated when the module sets the ABT bits for the corresponding buffer (TXBnCON<6>). If the message has started to transmit, it will attempt to transmit the current message fully. If the current message is transmitted fully and is not lost to arbitration or an error, the ABT bit will not be set because the message was transmitted successfully. Likewise, if a message is being transmitted during an abort request and the message is lost to arbitration or an error, the message will not be retransmitted and the ABT bit will be set, indicating that the message was successfully aborted.





^{© 2006} Microchip Technology Inc.

19.5 Message Reception

19.5.1 RECEIVE MESSAGE BUFFERING

The PIC18FXX8 includes two full receive buffers with multiple acceptance filters for each. There is also a separate Message Assembly Buffer (MAB) which acts as a third receive buffer (see Figure 19-4).

19.5.2 RECEIVE BUFFERS

Of the three receive buffers, the MAB is always committed to receiving the next message from the bus. The remaining two receive buffers are called RXB0 and RXB1 and can receive a complete message from the protocol engine. The MCU can access one buffer while the other buffer is available for message reception or holding a previously received message.

The MAB assembles all messages received. These messages will be transferred to the RXBn buffers only if the acceptance filter criteria are met.

Note: The entire contents of the MAB are moved into the receive buffer once a message is accepted. This means that regardless of the type of identifier (standard or extended) and the number of data bytes received, the entire receive buffer is overwritten with the MAB contents. Therefore, the contents of all registers in the buffer must be assumed to have been modified when any message is received.

When a message is moved into either of the receive buffers, the appropriate RXBnIF bit is set. This bit must be cleared by the MCU when it has completed processing the message in the buffer in order to allow a new message to be received into the buffer. This bit provides a positive lockout to ensure that the MCU has finished with the message before the PIC18FXX8 attempts to load a new message into the receive buffer. If the RXBnIE bit is set, an interrupt will be generated to indicate that a valid message has been received.

19.5.3 RECEIVE PRIORITY

RXB0 is the higher priority buffer and has two message acceptance filters associated with it. RXB1 is the lower priority buffer and has four acceptance filters associated with it. The lower number of acceptance filters makes the match on RXB0 more restrictive and implies a higher priority for that buffer. Additionally, the RXB0CON register can be configured such if RXB0 contains a valid message and another valid message is received, an overflow error will not occur and the new message will be moved into RXB1 regardless of the acceptance criteria of RXB1. There are also two programmable acceptance filter masks available, one for each receive buffer (see Section 19.6 "Message Acceptance Filters and Masks").

When a message is received, bits <3:0> of the RXBnCON register will indicate the acceptance filter number that enabled reception and whether the received message is a remote transfer request.

DS41159E-page 230

The RXM bits set special Receive modes. Normally, these bits are set to '00' to enable reception of all valid messages as determined by the appropriate acceptance filters. In this case, the determination of whether or not to receive standard or extended messages is determined by the EXIDE bit in the Acceptance Filter register. If the RXM bits are set to '01' or '10', the receiver will accept only messages with standard or extended identifiers, respectively. If an acceptance filter has the EXIDE bit set, such that it does not correspond with the RXM mode, that acceptance filter is rendered useless. These two modes of RXM bits can be used in systems where it is known that only standard or extended messages will be on the bus. If the RXM bits are set to '11', the buffer will receive all messages regardless of the values of the acceptance filters. Also, if a message has an error before the end of frame, that portion of the message assembled in the MAB before the error frame will be loaded into the buffer. This mode has some value in debugging a CAN system and would not be used in an actual system environment.


19.5.4 TIME-STAMPING

The CAN module can be programmed to generate a time-stamp for every message that is received. When enabled, the module generates a capture signal for CCP1 which in turns captures the value of either Timer1 or Timer3. This value can be used as the message time-stamp.


To use the time-stamp capability, the CANCAP bit (CIOCAN<4>) must be set. This replaces the capture input for CCP1 with the signal generated from the CAN module. In addition, CCP1CON<3:0> must be set to '0011' to enable the CCP special event trigger for CAN events.



RECEIVE BUFFER BLOCK DIAGRAM







© 2006 Microchip Technology Inc.

19.6 Message Acceptance Filters and Masks

The message acceptance filters and masks are used to determine if a message in the message assembly buffer should be loaded into either of the receive buffers. Once a valid message has been received into the MAB, the identifier fields of the message are compared to the filter values. If there is a match, that message will be loaded into the appropriate receive buffer. The filter masks are used to determine which bits in the identifier are examined with the filters. A truth table is shown below in Table 19-2 that indicates how each bit in the identifier is compared to the masks and filters to determine if a message should be loaded into a receive buffer. The mask essentially determines which bits to apply the acceptance filters to. If any mask bit is set to a zero, then that bit will automatically be accepted regardless of the filter bit.

Mask bit n	Filter bit n	Message Identifier bit n001	Accept or Reject bit n
0	х	x	Accept
1	0	0	Accept
1	0	1	Reject
1	1	0	Reject
1	1	1	Accept

TABLE 19-2: FILTER/MASK TRUTH TABLE

Legend: x = don't care

As shown in the receive buffer block diagram (Figure 19-4), acceptance filters RXF0 and RXF1 and filter mask RXM0 are associated with RXB0. Filters RXF2, RXF3, RXF4 and RXF5 and mask RXM1 are associated with RXB1. When a filter matches and a message is loaded into the receive buffer, the filter number that enabled the message reception is loaded into the FILHIT bit(s).

For RXB1, the RXB1CON register contains the FILHIT<2:0> bits. They are coded as follows:

- 101 = Acceptance Filter 5 (RXF5)
- 100 = Acceptance Filter 4 (RXF4)
- 011 = Acceptance Filter 3 (RXF3)
- 010 = Acceptance Filter 2 (RXF2)
- 001 = Acceptance Filter 1 (RXF1)
- 000 = Acceptance Filter 0 (RXF0)

Note: '000' and '001' can only occur if the RXB0DBEN bit is set in the RXB0CON register allowing RXB0 messages to rollover into RXB1.

The coding of the RXB0DBEN bit enables these three bits to be used similarly to the FILHIT bits and to distinguish a hit on filter RXF0 and RXF1, in either RXB0, or after a rollover into RXB1.


- 111 = Acceptance Filter 1 (RXF1)
- 110 = Acceptance Filter 0 (RXF0)
- 001 = Acceptance Filter 1 (RXF1)
- 000 = Acceptance Filter 0

If the RXB0DBEN bit is clear, there are six codes corresponding to the six filters. If the RXB0DBEN bit is set, there are six codes corresponding to the six filters plus two additional codes corresponding to RXF0 and RXF1 filters that rollover into RXB1.

If more than one acceptance filter matches, the FILHIT bits will encode the binary value of the lowest numbered filter that matched. In other words, if filter RXF2 and filter RXF4 match, FILHIT will be loaded with the value for RXF2. This essentially prioritizes the acceptance filters with a lower number filter having higher priority. Messages are compared to filters in ascending order of filter number.

The mask and filter registers can only be modified when the PIC18FXX8 is in Configuration mode. The mask and filter registers cannot be read outside of Configuration mode. When outside of Configuration mode, all mask and filter registers will be read as '0'.

FIGURE 19-6: MESSAGE ACCEPTANCE MASK AND FILTER OPERATION



DS41159E-page 232

19.7 Baud Rate Setting

All nodes on a given CAN bus must have the same nominal bit rate. The CAN protocol uses Non-Returnto-Zero (NRZ) coding which does not encode a clock within the data stream. Therefore, the receive clock must be recovered by the receiving nodes and synchronized to the transmitters clock.

As oscillators and transmission time may vary from node to node, the receiver must have some type of Phase Lock Loop (PLL) synchronized to data transmission edges to synchronize and maintain the receiver clock. Since the data is NRZ coded, it is necessary to include bit stuffing to ensure that an edge occurs at least every six bit times to maintain the Digital Phase Lock Loop (DPLL) synchronization.

The bit timing of the PIC18FXX8 is implemented using a DPLL that is configured to synchronize to the incoming data and provides the nominal timing for the transmitted data. The DPLL breaks each bit time into multiple segments made up of minimal periods of time called the *Time Quanta* (TQ).

Bus timing functions executed within the bit time frame, such as synchronization to the local oscillator, network transmission delay compensation and sample point positioning, are defined by the programmable bit timing logic of the DPLL.

All devices on the CAN bus must use the same bit rate. However, all devices are not required to have the same master oscillator clock frequency. For the different clock frequencies of the individual devices, the bit rate has to be adjusted by appropriately setting the baud rate prescaler and number of time quanta in each segment.

The *Nominal Bit Rate* is the number of bits transmitted per second, assuming an ideal transmitter with an ideal oscillator, in the absence of resynchronization. The nominal bit rate is defined to be a maximum of 1 Mb/s.



The Nominal Bit Time is defined as:

TBIT = 1/Nominal Bit Rate

The nominal bit time can be thought of as being divided into separate, non-overlapping time segments. These segments (Figure 19-7) include:

- Synchronization Segment (Sync_Seg)
- Propagation Time Segment (Prop_Seg)
- Phase Buffer Segment 1 (Phase_Seg1)
- Phase Buffer Segment 2 (Phase_Seg2)


The time segments (and thus, the nominal bit time) are, in turn, made up of integer units of time called time quanta or TQ (see Figure 19-7). By definition, the nominal bit time is programmable from a minimum of 8 TQ to a maximum of 25 TQ. Also, by definition, the minimum nominal bit time is 1 μ s corresponding to a maximum 1 Mb/s rate. The actual duration is given by the relationship:

Nominal Bit Time = TQ * (Sync_Seg + Prop_Seg + Phase_Seg1 + Phase_Seg2)

The time quantum is a fixed unit derived from the oscillator period. It is also defined by the programmable baud rate prescaler, with integer values from 1 to 64, in addition to a fixed divide-by-two for clock generation. Mathematically, this is

Tq (
$$\mu$$
s) = (2 * (BRP + 1))/Fosc (MHz)
or
Tq (μ s) = (2 * (BRP + 1)) * Tosc (μ s)

where FOSC is the clock frequency, TOSC is the corresponding oscillator period and BRP is an integer (0 through 63) represented by the binary values of BRGCON1<5:0>.



© 2006 Microchip Technology Inc.

19.7.1 TIME QUANTA

As already mentioned, the time quanta is a fixed unit derived from the oscillator period and baud rate prescaler. Its relationship to TBIT and the nominal bit rate is shown in Example 19-2.

EXAMPLE 19-2: CALCULATING TQ, NOMINAL BIT RATE AND NOMINAL BIT TIME

 $TQ (\mu s) = (2 * (BRP + 1))/FOSC (MHz)$

TBIT (μ s) = TQ (μ s) * number of TQ per bit interval Nominal Bit Rate (bits/s) = 1/TBIT

CASE 1:

For Fosc = 16 MHz, BRP<5:0> = 00h and Nominal Bit Time = 8 To:

 $TQ = (2 * 1)/16 = 0.125 \,\mu s \,(125 \,ns)$

TBIT = $8 * 0.125 = 1 \ \mu s \ (10^{-6} s)$

Nominal Bit Rate = $1/10^{-6} = 10^{6}$ bits/s (1 Mb/s)

CASE 2:

For Fosc = 20 MHz, BRP<5:0> = 01h and Nominal Bit Time = 8 Tq:

 $Tq = (2 * 2)/20 = 0.2 \ \mu s \ (200 \ ns)$

TBIT = $8 * 0.2 = 1.6 \,\mu s \,(1.6 * 10^{-6} s)$

Nominal Bit Rate = $1/1.6 * 10^{-6}$ s = 625,000 bits/s (625 Kb/s)

CASE 3:

For FOSC = 25 MHz, BRP<5:0> = 3Fh and Nominal Bit Time = 25 TQ: $TQ = (2 * 64)/25 = 5.12 \ \mu s$ TBIT = 25 * 5.12 = 128 \ \mu s (1.28 * 10⁻⁴s) Nominal Bit Rate = 1/1.28 * 10⁻⁴ = 7813 bits/s (7.8 Kb/s)

The frequencies of the oscillators in the different nodes must be coordinated in order to provide a system wide specified nominal bit time. This means that all oscillators must have a Tosc that is an integral divisor of TQ. It should also be noted that although the number of TQ is programmable from 4 to 25, the usable minimum is 8 TQ. A bit time of less than 8 TQ in length is not ensured to operate correctly.

19.7.2 SYNCHRONIZATION SEGMENT

This part of the bit time is used to synchronize the various CAN nodes on the bus. The edge of the input signal is expected to occur during the sync segment. The duration is 1 Tq.

19.7.3 PROPAGATION SEGMENT

This part of the bit time is used to compensate for physical delay times within the network. These delay times consist of the signal propagation time on the bus line and the internal delay time of the nodes. The length of the Propagation Segment can be programmed from 1 TQ to 8 TQ by setting the PRSEG2:PRSEG0 bits.

19.7.4 PHASE BUFFER SEGMENTS

The phase buffer segments are used to optimally locate the sampling point of the received bit within the nominal bit time. The sampling point occurs between Phase Segment 1 and Phase Segment 2. These segments can be lengthened or shortened by the resynchronization process. The end of Phase Segment 1 determines the sampling point within a bit time. Phase Segment 1 is programmable from 1 Tq to 8 Tq in duration. Phase Segment 2 provides delay before the next transmitted data transition and is also programmable from 1 Tq to 8 Tq in duration. However, due to IPT requirements, the actual minimum length of Phase Segment 2 is 2 Tq or it may be defined to be equal to the greater of Phase Segment 1 or the Information Processing Time (IPT).

19.7.5 SAMPLE POINT

The sample point is the point of time at which the bus level is read and the value of the received bit is determined. The sampling point occurs at the end of Phase Segment 1. If the bit timing is slow and contains many TQ, it is possible to specify multiple sampling of the bus line at the sample point. The value of the received bit is determined to be the value of the majority decision of three values. The three samples are taken at the sample point and twice before, with a time of TQ/2 between each sample.

19.7.6 INFORMATION PROCESSING TIME

The Information Processing Time (IPT) is the time segment, starting at the sample point, that is reserved for calculation of the subsequent bit level. The CAN specification defines this time to be less than or equal to 2 Tq. The PIC18FXX8 defines this time to be 2 Tq. Thus, Phase Segment 2 must be at least 2 Tq long.

DS41159E-page 234

19.8 Synchronization

To compensate for phase shifts between the oscillator frequencies of each of the nodes on the bus, each CAN controller must be able to synchronize to the relevant signal edge of the incoming signal. When an edge in the transmitted data is detected, the logic will compare the location of the edge to the expected time (Sync_Seg). The circuit will then adjust the values of Phase Segment 1 and Phase Segment 2, as necessary. There are two mechanisms used for synchronization.

19.8.1 HARD SYNCHRONIZATION

Hard synchronization is only done when there is a recessive to dominant edge during a bus Idle condition, indicating the start of a message. After hard synchronization, the bit time counters are restarted with Sync_Seg. Hard synchronization forces the edge which has occurred to lie within the synchronization segment of the restarted bit time. Due to the rules of synchronization, if a hard synchronization occurs, there will not be a resynchronization within that bit time.

19.8.2 RESYNCHRONIZATION

As a result of resynchronization, Phase Segment 1 may be lengthened or Phase Segment 2 may be shortened. The amount of lengthening or shortening of the phase buffer segments has an upper bound given by the Synchronization Jump Width (SJW). The value of the SJW will be added to Phase Segment 1 (see Figure 19-8) or subtracted from Phase Segment 2 (see Figure 19-9). The SJW is programmable between 1 Tq and 4 Tq.

Clocking information will only be derived from recessive to dominant transitions. The property, that only a fixed maximum number of successive bits have the same value, ensures resynchronization to the bit stream during a frame. The phase error of an edge is given by the position of the edge relative to Sync_Seg, measured in Tq. The phase error is defined in magnitude of Tq as follows:

- e = 0 if the edge lies within Sync_Seg.
- e > 0 if the edge lies before the sample point.
- e < 0 if the edge lies after the sample point of the previous bit.

If the magnitude of the phase error is less than or equal to the programmed value of the synchronization jump width, the effect of a resynchronization is the same as that of a hard synchronization.


If the magnitude of the phase error is larger than the synchronization jump width and if the phase error is positive, then Phase Segment 1 is lengthened by an amount equal to the synchronization jump width.

If the magnitude of the phase error is larger than the resynchronization jump width and if the phase error is negative, then Phase Segment 2 is shortened by an amount equal to the synchronization jump width.


19.8.3 SYNCHRONIZATION RULES


- Only one synchronization within one bit time is allowed.
- An edge will be used for synchronization only if the value detected at the previous sample point (previously read bus value) differs from the bus value immediately after the edge.
- All other recessive to dominant edges, fulfilling rules 1 and 2, will be used for resynchronization with the exception that a node transmitting a dominant bit will not perform a resynchronization as a result of a recessive to dominant edge with a positive phase error.





^{© 2006} Microchip Technology Inc.





19.9 Programming Time Segments

Some requirements for programming of the time segments:

- Prop Seg + Phase Seg 1 ≥ Phase Seg 2
- Phase Seg 2 ≥ Sync Jump Width

For example, assume that a 125 kHz CAN baud rate is desired using 20 MHz for Fosc. With a Tosc of 50 ns, a baud rate prescaler value of 04h gives a TQ of 500 ns. To obtain a nominal bit rate of 125 kHz, the nominal bit time must be 8 μ s or 16 TQ.

Using 1 TQ for the Sync Segment, 2 TQ for the Propagation Segment and 7 TQ for Phase Segment 1 would place the sample point at 10 TQ after the transition. This leaves 6 TQ for Phase Segment 2.

By the rules above, the Sync Jump Width could be the maximum of 4 Tq. However, normally a large SJW is only necessary when the clock generation of the different nodes is inaccurate or unstable, such as using ceramic resonators. Typically, an SJW of 1 is enough.

19.10 Oscillator Tolerance

As a rule of thumb, the bit timing requirements allow ceramic resonators to be used in applications with transmission rates of up to 125 Kbit/sec. For the full bus speed range of the CAN protocol, a quartz oscillator is required. A maximum node-to-node oscillator variation of 1.7% is allowed.

19.11 Bit Timing Configuration Registers

The Configuration registers (BRGCON1, BRGCON2, BRGCON3) control the bit timing for the CAN bus interface. These registers can only be modified when the PIC18FXX8 is in Configuration mode.

19.11.1 BRGCON1

The BRP bits control the baud rate prescaler. The SJW<1:0> bits select the synchronization jump width in terms of multiples of Tq.

19.11.2 BRGCON2

The PRSEG bits set the length of the Propagation Segment in terms of Tq. The SEG1PH bits set the length of Phase Segment 1 in TQ. The SAM bit controls how many times the RXCAN pin is sampled. Setting this bit to a '1' causes the bus to be sampled three times; twice at TQ/2 before the sample point and once at the normal sample point (which is at the end of Phase Segment 1). The value of the bus is determined to be the value read during at least two of the samples. If the SAM bit is set to a '0', then the RXCAN pin is sampled only once at the sample point. The SEG2PHTS bit controls how the length of Phase Segment 2 is determined. If this bit is set to a '1', then the length of Phase Segment 2 is determined by the SEG2PH bits of BRGCON3. If the SEG2PHTS bit is set to a '0', then the length of Phase Segment 2 is the greater of Phase Segment 1 and the information processing time (which is fixed at 2 TQ for the PIC18FXX8).

19.11.3 BRGCON3

The PHSEG2<2:0> bits set the length (in TQ) of Phase Segment 2 if the SEG2PHTS bit is set to a '1'. If the SEG2PHTS bit is set to a '0', then the PHSEG2<2:0> bits have no effect.

19.12 Error Detection

The CAN protocol provides sophisticated error detection mechanisms. The following errors can be detected.

19.12.1 CRC ERROR

With the Cyclic Redundancy Check (CRC), the transmitter calculates special check bits for the bit sequence, from the start of a frame until the end of the data field. This CRC sequence is transmitted in the CRC field. The receiving node also calculates the CRC sequence using the same formula and performs a comparison to the received sequence. If a mismatch is detected, a CRC error has occurred and an error frame is generated. The message is repeated.

19.12.2 ACKNOWLEDGE ERROR

In the Acknowledge field of a message, the transmitter checks if the Acknowledge slot (which was sent out as a recessive bit) contains a dominant bit. If not, no other node has received the frame correctly. An Acknowledge Error has occurred; an error frame is generated and the message will have to be repeated.

19.12.3 FORM ERROR

If a node detects a dominant bit in one of the four segments, including end of frame, interframe space, Acknowledge delimiter or CRC delimiter, then a Form Error has occurred and an error frame is generated. The message is repeated.

19.12.4 BIT ERROR

A Bit Error occurs if a transmitter sends a dominant bit and detects a recessive bit, or if it sends a recessive bit and detects a dominant bit, when monitoring the actual bus level and comparing it to the just transmitted bit. In the case where the transmitter sends a recessive bit and a dominant bit is detected during the arbitration field and the Acknowledge slot, no Bit Error is generated because normal arbitration is occurring.

19.12.5 STUFF BIT ERROR

If, between the start of frame and the CRC delimiter, six consecutive bits with the same polarity are detected, the bit stuffing rule has been violated. A Stuff Bit Error occurs and an error frame is generated. The message is repeated.

19.12.6 ERROR STATES

Detected errors are made public to all other nodes via error frames. The transmission of the erroneous message is aborted and the frame is repeated as soon as possible. Furthermore, each CAN node is in one of the three error states "error-active", "error-passive" or "bus-off" according to the value of the internal error counters. The error-active state is the usual state, where the bus node can transmit messages and activate error frames (made of dominant bits) without any restrictions. In the error-passive state, messages and passive error frames (made of recessive bits) may be transmitted. The bus-off state makes it temporarily impossible for the station to participate in the bus communication. During this state, messages can neither be received nor transmitted.

19.12.7 ERROR MODES AND ERROR COUNTERS


The PIC18FXX8 contains two error counters: the Receive Error Counter (RXERRCNT) and the Transmit Error Counter (TXERRCNT). The values of both counters can be read by the MCU. These counters are incremented or decremented in accordance with the CAN bus specification.

The PIC18FXX8 is error-active if both error counters are below the error-passive limit of 128. It is errorpassive if at least one of the error counters equals or exceeds 128. It goes to bus-off if the transmit error counter equals or exceeds the bus-off limit of 256. The device remains in this state until the bus-off recovery sequence is received. The bus-off recovery sequence consists of 128 occurrences of 11 consecutive recessive bits (see Figure 19-10). Note that the CAN module, after going bus-off, will recover back to erroractive without any intervention by the MCU if the bus remains Idle for 128 x 11 bit times. If this is not desired, the error Interrupt Service Routine should address this. The current error mode of the CAN module can be read by the MCU via the COMSTAT register.

Additionally, there is an Error State Warning flag bit, EWARN, which is set if at least one of the error counters equals or exceeds the error warning limit of 96. EWARN is reset if both error counters are less than the error warning limit.

^{© 2006} Microchip Technology Inc.





19.13 CAN Interrupts

The module has several sources of interrupts. Each of these interrupts can be individually enabled or disabled. The CANINTF register contains interrupt flags. The CANINTE register contains the enables for the 8 main interrupts. A special set of read-only bits in the CANSTAT register, the ICODE bits, can be used in combination with a jump table for efficient handling of interrupts.

All interrupts have one source, with the exception of the error interrupt. Any of the error interrupt sources can set the error interrupt flag. The source of the error interrupt can be determined by reading the Communication Status register, COMSTAT.

The interrupts can be broken up into two categories: receive and transmit interrupts.

The receive related interrupts are:

- Receive Interrupts
- Wake-up Interrupt
- Receiver Overrun Interrupt
- Receiver Warning Interrupt
- Receiver Error-Passive Interrupt
- The transmit related interrupts are:
- Transmit Interrupts
- Transmitter Warning Interrupt
- Transmitter Error-Passive Interrupt
- Bus-Off Interrupt

19.13.1 INTERRUPT CODE BITS

The source of a pending interrupt is indicated in the ICODE (Interrupt Code) bits of the CANSTAT register (ICODE<2:0>). Interrupts are internally prioritized such that the higher priority interrupts are assigned lower ICODE values. Once the highest priority interrupt condition has been cleared, the code for the next highest priority interrupt that is pending (if any) will be reflected by the ICODE bits (see Table 19-3, following page). Note that only those interrupt sources that have their associated CANINTE enable bit set will be reflected in the ICODE bits.

19.13.2 TRANSMIT INTERRUPT

When the transmit interrupt is enabled, an interrupt will be generated when the associated transmit buffer becomes empty and is ready to be loaded with a new message. The TXBnIF bit will be set to indicate the source of the interrupt. The interrupt is cleared by the MCU resetting the TXBnIF bit to a '0'.

19.13.3 RECEIVE INTERRUPT

When the receive interrupt is enabled, an interrupt will be generated when a message has been successfully received and loaded into the associated receive buffer. This interrupt is activated immediately after receiving the EOF field. The RXBnIF bit will be set to indicate the source of the interrupt. The interrupt is cleared by the MCU resetting the RXBnIF bit to a '0'.

ICOD <2:0>	Interrupt	Boolean Expression						
000	None	ERR•WAK•TX0•TX1•TX2•RX0• RX1						
001	Error	ERR						
010	TXB2	ERR•TX0•TX1•TX2						
011	TXB1	ERR•TX0•TX1						
100	TXB0	ERR•TX0						
101	RXB1	ERR•TX0•TX1•TX2•RX0•RX1						
110	RXB0	ERR•TX0•TX1•TX2•RX0						
111	Wake on Interrupt	ERR•TX0•TX1•TX2•RX0•RX1• WAK						
TX0 = T TX1 = T								

19.13.4 MESSAGE ERROR INTERRUPT

When an error occurs during transmission or reception of a message, the message error flag IRXIF will be set and if the IRXIE bit is set, an interrupt will be generated. This is intended to be used to facilitate baud rate determination when used in conjunction with Listen Only mode.

19.13.5 BUS ACTIVITY WAKE-UP INTERRUPT

When the PIC18FXX8 is in Sleep mode and the bus activity wake-up interrupt is enabled, an interrupt will be generated and the WAKIF bit will be set when activity is detected on the CAN bus. This interrupt causes the PIC18FXX8 to exit Sleep mode. The interrupt is reset by the MCU, clearing the WAKIF bit.

19.13.6 ERROR INTERRUPT

When the error interrupt is enabled, an interrupt is generated if an overflow condition occurs or if the error state of transmitter or receiver has changed. The error flags in COMSTAT will indicate one of the following conditions.

19.13.6.1 Receiver Overflow

An overflow condition occurs when the MAB has assembled a valid received message (the message meets the criteria of the acceptance filters) and the receive buffer associated with the filter is not available for loading of a new message. The associated COMSTAT.RXnOVFL bit will be set to indicate the overflow condition. This bit must be cleared by the MCU.

19.13.6.2 Receiver Warning

The receive error counter has reached the MCU warning limit of 96.

19.13.6.3 Transmitter Warning

The transmit error counter has reached the MCU warning limit of 96.

19.13.6.4 Receiver Bus Passive

The receive error counter has exceeded the errorpassive limit of 127 and the device has gone to error-passive state.

19.13.6.5 Transmitter Bus Passive

The transmit error counter has exceeded the errorpassive limit of 127 and the device has gone to error-passive state.

19.13.6.6 Bus-Off

The transmit error counter has exceeded 255 and the device has gone to bus-off state.

19.13.7 INTERRUPT ACKNOWLEDGE

Interrupts are directly associated with one or more status flags in the PIR register. Interrupts are pending as long as one of the flags is set. Once an interrupt flag is set by the device, the flag cannot be reset by the microcontroller until the interrupt condition is removed.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 240

20.0 COMPATIBLE 10-BIT ANALOG-TO-DIGITAL CONVERTER (A/D) MODULE

The Analog-to-Digital (A/D) Converter module has five inputs for the PIC18F2X8 devices and eight for the PIC18F4X8 devices. This module has the ADCON0 and ADCON1 register definitions that are compatible with the PICmicro[®] mid-range A/D module.

The A/D allows conversion of an analog input signal to a corresponding 10-bit digital number.

The A/D module has four registers. These registers are:

- A/D Result High Register (ADRESH)
- A/D Result Low Register (ADRESL)
- A/D Control Register 0 (ADCON0)
- A/D Control Register 1 (ADCON1)

The ADCON0 register, shown in Register 20-1, controls the operation of the A/D module. The ADCON1 register, shown in Register 20-2, configures the functions of the port pins.

REGISTER 20-1: ADCON0: A/D CONTROL REGISTER 0

R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	U-0	R/W-0
ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE		ADON
bit 7							bit 0

bit 7-6 ADCS1: ADCS0: A/D Conversion Clock Select bits (ADCON0 bits in bold)

ADCON1 <adcs2></adcs2>	ADCON0 <adcs1:adcs0></adcs1:adcs0>	Clock Conversion
0	00	Fosc/2
0	01	Fosc/8
0	10	Fosc/32
0	11	FRC (clock derived from the internal A/D RC oscillator)
1	00	Fosc/4
1	01	Fosc/16
1	10	Fosc/64
1	11	FRC (clock derived from the internal A/D RC oscillator)

bit 5-3 CHS2:CHS0: Analog Channel Select bits

- 000 = Channel 0 (AN0)
- 001 = Channel 1 (AN1)
- 010 = Channel 2 (AN2)
- 011 = Channel 3 (AN3)
- 100 = Channel 4 (AN4)
- 101 = Channel 5 (AN5)⁽¹⁾
- 110 = Channel 6 (AN6)⁽¹⁾
- 111 = Channel 7 (AN7)⁽¹⁾
 - Note 1: These channels are unimplemented on PIC18F2X8 (28-pin) devices. Do not select any unimplemented channel.
- bit 2 GO/DONE: A/D Conversion Status bit

When ADON = 1:

- 1 = A/D conversion in progress (setting this bit starts the A/D conversion which is automatically cleared by hardware when the A/D conversion is complete)
- 0 = A/D conversion not in progress
- bit 1 Unimplemented: Read as '0'
- bit 0 ADON: A/D On bit
 - 1 = A/D converter module is powered up
 - 0 = A/D converter module is shut-off and consumes no operating current

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

© 2006 Microchip Technology Inc.

REGISTER 20-2: ADCON1: A/D CONTROL REGISTER 1

R/W-0	R/W-0	U-0	U-0	R/W-0	R/W-0	R/W-0	R/W-0
ADFM	ADCS2	—	—	PCFG3	PCFG2	PCFG1	PCFG0
bit 7							bit 0

bit 7 ADFM: A/D Result Format Select bit

1 = Right justified. Six (6) Most Significant bits of ADRESH are read as '0'.
 0 = Left justified. Six (6) Least Significant bits of ADRESL are read as '0'.

bit 6 ADCS2: A/D Conversion Clock Select bit (ADCON1 bits in **bold**)

ADCON1 <adcs2></adcs2>	ADCON0 <adcs1:adcs0></adcs1:adcs0>	Clock Conversion
0	00	Fosc/2
0	01	Fosc/8
0	10	Fosc/32
0	11	FRC (clock derived from the internal A/D RC oscillator)
1	0 0	Fosc/4
1	01	Fosc/16
1	10	Fosc/64
1	11	FRC (clock derived from the internal A/D RC oscillator)

bit 5-4 Unimplemented: Read as '0'

bit 3-0 PCFG3:PCFG0: A/D Port Configuration Control bits

PCFG	AN7	AN6	AN5	AN4	AN3	AN2	AN1	AN0	VREF+	VREF-	C/R
0000	А	Α	Α	А	А	А	А	А	Vdd	Vss	8/0
0001	Α	Α	Α	А	VREF+	А	А	А	AN3	Vss	7/1
0010	D	D	D	А	А	А	А	А	Vdd	Vss	5/0
0011	D	D	D	А	VREF+	А	А	А	AN3	Vss	4/1
0100	D	D	D	D	А	D	А	А	Vdd	Vss	3/0
0101	D	D	D	D	VREF+	D	А	А	AN3	Vss	2/1
011x	D	D	D	D	D	D	D	D	_	—	0/0
1000	Α	Α	Α	Α	VREF+	VREF-	Α	Α	AN3	AN2	6/2
1001	D	D	Α	Α	А	Α	Α	Α	Vdd	Vss	6/0
1010	D	D	Α	Α	VREF+	Α	Α	Α	AN3	Vss	5/1
1011	D	D	Α	Α	VREF+	VREF-	Α	Α	AN3	AN2	4/2
1100	D	D	D	А	VREF+	VREF-	А	А	AN3	AN2	3/2
1101	D	D	D	D	VREF+	VREF-	А	А	AN3	AN2	2/2
1110	D	D	D	D	D	D	D	А	Vdd	Vss	1/0
1111	D	D	D	D	VREF+	VREF-	D	А	AN3	AN2	1/2

A = Analog input D = Digital I/O

C/R = # of analog input channels/# of A/D voltage references

Note: Shaded cells indicate channels available only on PIC18F4X8 devices.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

Note: On any device Reset, the port pins that are multiplexed with analog functions (ANx) are forced to be analog inputs.

DS41159E-page 242

The analog reference voltage is software selectable to either the device's positive and negative supply voltage (VDD and VSS) or the voltage level on the RA3/AN3/ VREF+ pin and RA2/AN2/VREF- pin.


The A/D converter has a unique feature of being able to operate while the device is in Sleep mode. To operate in Sleep, the A/D conversion clock must be derived from the A/D's internal RC oscillator.

The output of the sample and hold is the input into the converter which generates the result via successive approximation.

A device Reset forces all registers to their Reset state. This forces the A/D module to be turned off and any conversion is aborted.

Each port pin associated with the A/D converter can be configured as an analog input (RA3 can also be a voltage reference) or as a digital I/O.

The ADRESH and ADRESL registers contain the result of the A/D conversion. When the A/D conversion is complete, the result is loaded into the ADRESH/ADRESL registers, the GO/DONE bit (ADCON0<2>) is cleared and A/D Interrupt Flag bit, ADIF, is set. The block diagram of the A/D module is shown in Figure 20-1.





The value that is in the ADRESH/ADRESL registers is not modified for a Power-on Reset. The ADRESH/ ADRESL registers will contain unknown data after a Power-on Reset.

After the A/D module has been configured as desired, the selected channel must be acquired before the conversion is started. The analog input channels must have their corresponding TRIS bits selected as an input. To determine acquisition time, see **Section 20.1 "A/D Acquisition Requirements"**. After this acquisition time has elapsed, the A/D conversion can be started. The following steps should be followed for doing an A/D conversion:

- 1. Configure the A/D module:
 - Configure analog pins, voltage reference and digital I/O (ADCON1)
 - Select A/D input channel (ADCON0)
 - Select A/D conversion clock (ADCON0)
 - Turn on A/D module (ADCON0)
- 2. Configure A/D interrupt (if desired):
 - Clear ADIF bit
 - Set ADIE bit
 - Set GIE bit
- 3. Wait the required acquisition time.
- 4. Start conversion:
 - Set GO/DONE bit (ADCON0)
- 5. Wait for A/D conversion to complete, by either:
 - Polling for the GO/DONE bit to be cleared
 - OR
 - · Waiting for the A/D interrupt


Read A/D Result registers (ADRESH/ADRESL); clear bit ADIF if required.

7. For next conversion, go to step 1 or step 2 as required. The A/D conversion time per bit is defined as TAD. A minimum wait of 2 TAD is required before next acquisition starts.

20.1 A/D Acquisition Requirements

For the A/D converter to meet its specified accuracy, the charge holding capacitor (CHOLD) must be allowed to fully charge to the input channel voltage level. The analog input model is shown in Figure 20-2. The source impedance (Rs) and the internal sampling switch (Rss) impedance directly affect the time required to charge the capacitor CHOLD. The sampling switch (Rss) impedance varies over the device voltage (VDD). The source impedance affects the offset voltage at the analog input (due to pin leakage current). The maximum recommended impedance for analog sources is 2.5 k Ω . After the analog input channel is selected (changed), this acquisition must be done before the conversion can be started.

Note: When the conversion is started, the holding capacitor is disconnected from the input pin.



DS41159E-page 244

FIGURE 20-2: ANALOG INPUT MODEL

To calculate the minimum acquisition time, Equation 20-1 may be used. This equation assumes that 1/2 LSb error is used (1024 steps for the A/D). The 1/2 LSb error is the maximum error allowed for the A/D to meet its specified resolution.

Example 20-1 shows the calculation of the minimum required acquisition time TACQ. This calculation is based on the following application system assumptions:

•	CHOLD	=	120 pF

• Rs = $2.5 \text{ k}\Omega$

- Conversion Error \leq 1/2 LSb
- VDD = $5V \rightarrow Rss = 7 k\Omega$
- Temperature = 50° C (system max.)
- VHOLD = 0V @ time = 0

EQUATION 20-1: ACQUISITION TIME

TACQ	=	Amplifier Settling Time + Holding Capacitor Charging Time + Temperature Coefficient
	=	TAMP + TC + TCOFF

EQUATION 20-2: A/D MINIMUM CHARGING TIME

VHOLD	=	$(\text{VREF} - (\text{VREF}/2048)) \bullet (1 - e^{(-\text{Tc/CHOLD}(\text{Ric} + \text{Rss} + \text{Rs}))})$
or		
Тс	=	$-(120 \text{ pF})(1 \text{ k}\Omega + \text{Rss} + \text{Rs}) \ln(1/2047)$

EXAMPLE 20-1: CALCULATING THE MINIMUM REQUIRED ACQUISITION TIME

TACQ	=	TAMP + TC + TCOFF
Temper	ature	coefficient is only required for temperatures $> 25^{\circ}$ C.
TACQ	=	$2 \ \mu s + Tc + [(Temp - 25^{\circ}C)(0.05 \ \mu s/^{\circ}C)]$
ТС	=	-CHOLD (RIC + RSS + RS) $\ln(1/2047)$ -120 pF (1 k Ω + 7 k Ω + 2.5 k Ω) $\ln(0.0004885)$ -120 pF (10.5 k Ω) $\ln(0.0004885)$ -1.26 μ s (-7.6241) 9.61 μ s
TACQ	=	2 μs + 9.61 μs + [(50°C – 25°C)(0.05 μs/°C)] 11.61 μs + 1.25 μs 12.86 μs

Note: When using external voltage references with the A/D converter, the source impedance of the external voltage references must be less than 20Ω to obtain the specified A/D resolution. Higher reference source impedances will increase both offset and gain errors. Resistive voltage dividers will not provide a sufficiently low source impedance.

To maintain the best possible performance in A/D conversions, external VREF inputs should be buffered with an operational amplifier or other low output impedance circuit.

^{© 2006} Microchip Technology Inc.

20.2 Selecting the A/D Conversion Clock

The A/D conversion time per bit is defined as TAD. The A/D conversion requires 12 TAD per 10-bit conversion. The source of the A/D conversion clock is software selectable. The seven possible options for TAD are:

- 2 Tosc
- 4 Tosc
- 8 Tosc
- 16 Tosc
- 32 Tosc
- 64 Tosc
- Internal RC oscillator.

For correct A/D conversions, the A/D conversion clock (TAD) must be selected to ensure a minimum TAD time of 1.6 $\mu s.$

Table 20-1 shows the resultant TAD times derived from the device operating frequencies and the A/D clock source selected.

20.3 Configuring Analog Port Pins

The ADCON1, TRISA and TRISE registers control the operation of the A/D port pins. The port pins that are desired as analog inputs must have their corresponding TRIS bits set (input). If the TRIS bit is cleared (output), the digital output level (VOH or VOL) will be converted.

The A/D operation is independent of the state of the CHS2:CHS0 bits and the TRIS bits.

- Note 1: When reading the port register, all pins configured as analog input channels will read as cleared (a low level). Pins configured as digital inputs will convert an analog input. Analog levels on a digitally configured input will not affect the conversion accuracy.
 - 2: Analog levels on any pin that is defined as a digital input (including the AN4:AN0 pins) may cause the input buffer to consume current that is out of the device's specification.

TABLE 20-1: TAD VS. DEVICE OPERATING FREQUENCIES

AD Clock	Source (TAD)	Device Frequency						
Operation ADCS2:ADCS0		20 MHz	5 MHz	1.25 MHz	333.33 kHz			
2 Tosc	000	100 ns ⁽²⁾	400 ns ⁽²⁾	1.6 μs	6 µs			
4 Tosc	100	200 ns ⁽²⁾	800 ns ⁽²⁾	3.2 μs	12 μs			
8 Tosc	001	400 ns ⁽²⁾	1.6 μs	6.4 μs	24 μs ⁽³⁾			
16 Tosc	101	800 ns ⁽²⁾	3.2 μs	12.8 μs	48 μs ⁽³⁾			
32 Tosc	010	1.6 μs	6.4 μs	25.6 μs ⁽³⁾	96 μs ⁽³⁾			
64 Tosc	110	3.2 μs	12.8 μs	51.2 μs ⁽³⁾	192 μs ⁽³⁾			
RC	011	2-6 μs ⁽¹⁾	2-6 μs ⁽¹⁾	2-6 μs ⁽¹⁾	2-6 μs ⁽¹⁾			

Legend: Shaded cells are outside of recommended range.

2: These values violate the minimum required TAD time.

3: For faster conversion times, the selection of another clock source is recommended.

TABLE 20-2: TAD vs. DEVICE OPERATING FREQUENCIES (FOR EXTENDED, LF DEVICES)

AD Clock S	Source (TAD)	Device Frequency						
Operation ADCS2:ADCS0		4 MHz	2 MHz	1.25 MHz	333.33 kHz			
2 Tosc	000	500 ns ⁽²⁾	1.0 μs ⁽²⁾	1.6 μs ⁽²⁾	6 µs			
4 Tosc	100	1.0 μs ⁽²⁾	2.0 μs ⁽²⁾	3.2 μs ⁽²⁾	12 μs			
8 Tosc	001	2.0 μs ⁽²⁾	4.0 μs	6.4 μs	24 μs ⁽³⁾			
16 Tosc	101	4.0 μs ⁽²⁾	8.0 μs	12.8 μs	48 μs ⁽³⁾			
32 Tosc	010	8.0 μs	16.0 μs	25.6 μs ⁽³⁾	96 μs ⁽³⁾			
64 Tosc	110	16.0 μs	32.0 μs	51.2 μs ⁽³⁾	192 μs ⁽³⁾			
RC	011	3-9 μs ⁽¹⁾	3-9 μs ⁽¹⁾	3-9 μs ⁽¹⁾	3-9 μs ⁽¹⁾			

Legend: Shaded cells are outside of recommended range.

Note 1: The RC source has a typical TAD time of 6 μs.

- **2:** These values violate the minimum required TAD time.
- 3: For faster conversion times, the selection of another clock source is recommended.

DS41159E-page 246

Note 1: The RC source has a typical TAD time of 4 μ s.

20.4 A/D Conversions

Figure 20-4 shows the operation of the A/D converter after the GO bit has been set. Clearing the GO/DONE bit during a conversion will abort the current conversion. The A/D Result register pair will not be updated with the partially completed A/D conversion sample. That is, the ADRESH:ADRESL registers will continue to contain the value of the last completed conversion (or the last value written to the ADRESH:ADRESL registers). After the A/D conversion is aborted, a 2 TAD wait is required before the next acquisition is started. After this 2 TAD wait, acquisition on the selected channel is automatically started.

Note: The GO/DONE bit should NOT be set in the same instruction that turns on the A/D.

20.4.1 A/D RESULT REGISTERS

The ADRESH:ADRESL register pair is the location where the 10-bit A/D result is loaded at the completion of the A/D conversion. This register pair is 16 bits wide. The A/D module gives the flexibility to left or right justify the 10-bit result in the 16-bit result register. The A/D Format Select bit (ADFM) controls this justification. Figure 20-3 shows the operation of the A/D result justification. The extra bits are loaded with '0's. When an A/D result will not overwrite these locations (A/D disable), these registers may be used as two general purpose 8-bit registers.




FIGURE 20-3: A/D RESULT JUSTIFICATION

^{© 2006} Microchip Technology Inc.

20.5 Use of the ECCP Trigger

An A/D conversion can be started by the "special event trigger" of the ECCP module. This requires that the ECCP1M3:ECCP1M0 bits (ECCP1CON<3:0>) be programmed as '1011' and that the A/D module is enabled (ADON bit is set). When the trigger occurs, the GO/ DONE bit will be set, starting the A/D conversion and the Timer1 (or Timer3) counter will be reset to zero. Timer1 (or Timer3) is reset to automatically repeat the A/D acquisition period with minimal software overhead (moving ADRESH/ADRESL to the desired location). The appropriate analog input channel must be selected and the minimum acquisition done before the "special event trigger" sets the GO/DONE bit (starts a conversion).

If the A/D module is not enabled (ADON is cleared), the "special event trigger" will be ignored by the A/D module but will still reset the Timer1 (or Timer3) counter.




FIGURE 20-4: A/D CONVERSION TAD CYCLES

TABLE 20-3: SUMMARY OF A/D REGISTERS

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR, BOR	Value on all other Resets
INTCON	GIE/GIEH	PEIE/GIEL	TMR0IE	INT0IE	RBIE	TMR0IF	INT0IF	RBIF	0000 000x	0000 000u
PIR1	PSPIF ⁽¹⁾	ADIF	RCIF	TXIF	SSPIF	CCP1IF	TMR2IF	TMR1IF	0000 0000	0000 0000
PIE1	PSPIE ⁽¹⁾	ADIE	RCIE	TXIE	SSPIE	CCP1IE	TMR2IE	TMR1IE	0000 0000	0000 0000
IPR1	PSPIP ⁽¹⁾	ADIP	RCIP	TXIP	SSPIP	CCP1IP	TMR2IP	TMR1IP	1111 1111	1111 1111
PIR2	_	CMIF ⁽¹⁾	_	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF ⁽¹⁾	-0-0 0000	-0-0 0000
PIE2	_	CMIE ⁽¹⁾	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE ⁽¹⁾	-0-0 0000	-0-0 0000
IPR2	_	CMIP ⁽¹⁾	_	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP ⁽¹⁾	-1-1 1111	-1-1 1111
ADRESH	A/D Resul	t Register							xxxx xxxx	uuuu uuuu
ADRESL	A/D Resul	t Register							xxxx xxxx	uuuu uuuu
ADCON0	ADCS1	ADCS0	CHS2	CHS1	CHS0	GO/DONE	_	ADON	0000 00-0	0000 00-0
ADCON1	ADFM	ADCS2	_	_	PCFG3	PCFG2	PCFG1	PCFG0	00 0000	00 0000
PORTA	_	RA6	RA5	RA4	RA3	RA2	RA1	RA0	-x0x 0000	-u0u 0000
TRISA	—	PORTA Data	a Direction	Register					-111 1111	-111 1111
PORTE	_	—	_	—	_	RE2	RE1	RE0	xxx	000
LATE	_	—	_	—	_	LATE2	LATE1	LATE0	xxx	uuu
TRISE	IBF	OBF	IBOV	PSPMODE	_	TRISE2	TRISE1	TRISE0	0000 -111	0000 -111

 $\label{eq:Legend: Legend: x = unknown, u = unchanged, - = unimplemented, read as `0'. Shaded cells are not used for A/D conversion.$

Note 1: These bits are reserved on PIC18F2X8 devices; always maintain these bits clear.

21.0 COMPARATOR MODULE

Note:	The	ana	log	comp	arators	are	only
	availa	ble	on	the	PIC18	F448	and
	PIC18	3F45	8.				

The comparator module contains two analog comparators. The inputs to the comparators are multiplexed with the RD0 through RD3 pins. The on-chip voltage reference (Section 22.0 "Comparator Voltage **Reference Module**") can also be an input to the comparators. The CMCON register, shown in Register 21-1, controls the comparator input and output multiplexers. A block diagram of the comparator is shown in Figure 21-1.

REGISTER 21-1: CMCON: COMPARATOR CONTROL REGISTER

R-0	R-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0
C2OUT	C10UT	C2INV	C1INV	CIS	CM2	CM1	CM0
bit 7							bit 0

bit 7 C2OUT: Comparator 2 Output bit

 $\frac{\text{When C2INV} = 0:}{1 = C2 \text{ VIN+} > C2 \text{ VIN-}}$ 0 = C2 VIN+ < C2 VIN-

 $\frac{\text{When C2INV} = 1:}{1 = C2 \text{ VIN+} < C2 \text{ VIN-}} \\ 0 = C2 \text{ VIN+} > C2 \text{ VIN-}$

bit 6 **C1OUT**: Comparator 1 Output bit

 $\frac{\text{When C1INV} = 0:}{1 = C1 \text{ VIN} + > C1 \text{ VIN}}$ 0 = C1 VIN + < C1 VIN

- bit 5 C2INV: Comparator 2 Output Inversion bit
 - 1 = C2 output inverted
 - 0 = C2 output not inverted
- bit 4 C1INV: Comparator 1 Output Inversion bit
 - 1 = C1 output inverted
 - 0 = C1 output not inverted
- bit 3 **CIS**: Comparator Input Switch bit

When CM2:CM0 = 110:

- 1 = C1 VIN- connects to RD0/PSP0
 - C2 VIN- connects to RD2/PSP2
- 0 = C1 VIN- connects to RD1/PSP1
- C2 VIN- connects to RD3/PSP3
- bit 2-0 CM2:CM0: Comparator Mode bits

Figure 21-1 shows the Comparator modes and CM2:CM0 bit settings.


Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

© 2006 Microchip Technology Inc.

21.1 Comparator Configuration

There are eight modes of operation for the comparators. The CMCON register is used to select these modes. Figure 21-1 shows the eight possible modes. The TRISD register controls the data direction of the comparator pins for each mode. If the Comparator mode is changed, the comparator output level may not be valid for the specified mode change delay shown in Section 27.0 "Electrical Characteristics".

Note: Comparator interrupts should be disabled during a Comparator mode change; otherwise, a false interrupt may occur.




DS41159E-page 250

21.2 Comparator Operation

A single comparator is shown in Figure 21-2 along with the relationship between the analog input levels and the digital output. When the analog input at VIN+ is less than the analog input VIN-, the output of the comparator is a digital low level. When the analog input at VIN+ is greater than the analog input VIN-, the output of the comparator is a digital high level. The shaded areas of the output of the comparator in Figure 21-2 represent the uncertainty due to input offsets and response time.

21.3 Comparator Reference

An external or internal reference signal may be used depending on the comparator operating mode. The analog signal present at VIN- is compared to the signal at VIN+ and the digital output of the comparator is adjusted accordingly (Figure 21-2).



21.3.1 EXTERNAL REFERENCE SIGNAL

When external voltage references are used, the comparator module can be configured to have the comparators operate from the same or different reference sources. However, threshold detector applications may require the same reference. The reference signal must be between VSS and VDD and can be applied to either pin of the comparator(s).

21.3.2 INTERNAL REFERENCE SIGNAL

The comparator module also allows the selection of an internally generated voltage reference for the comparators. Section 22.0 "Comparator Voltage Reference Module" contains a detailed description of the module that provides this signal. The internal reference signal is used when comparators are in mode CM<2:0> = 110 (Figure 21-1). In this mode, the internal voltage reference is applied to the VIN+ pin of both comparators.

21.4 Comparator Response Time

Response time is the minimum time, after selecting a new reference voltage or input source, before the comparator output has a valid level. If the internal reference is changed, the maximum delay of the internal voltage reference must be considered when using the comparator outputs. Otherwise, the maximum delay of the comparators should be used (Section 27.0 "Electrical Characteristics").

21.5 Comparator Outputs

The comparator outputs are read through the CMCON register. These bits are read-only. The comparator outputs may also be directly output to the RE1 and RE2 I/O pins. When enabled, multiplexors in the output path of the RE1 and RE2 pins will switch and the output of each pin will be the unsynchronized output of the comparator. The uncertainty of each of the comparators is related to the input offset voltage and the response time given in the specifications. Figure 21-3 shows the comparator output block diagram.


The TRISE bits will still function as an output enable/ disable for the RE1 and RE2 pins while in this mode.

The polarity of the comparator outputs can be changed using the C2INV and C1INV bits (CMCON<4:5>).

- Note 1: When reading the Port register, all pins configured as analog inputs will read as a '0'. Pins configured as digital inputs will convert an analog input according to the Schmitt Trigger input specification.
 - 2: Analog levels on any pin defined as a digital input may cause the input buffer to consume more current than is specified.

^{© 2006} Microchip Technology Inc.

FIGURE 21-3: COMPARATOR OUTPUT BLOCK DIAGRAM



21.6 Comparator Interrupts

The comparator interrupt flag is set whenever there is a change in the output value of either comparator. Software will need to maintain information about the status of the output bits, as read from CMCON<7:6>, to determine the actual change that occurred. The CMIF bit (PIR2 register) is the Comparator Interrupt Flag. The CMIF bit must be reset by clearing '0'. Since it is also possible to write a '1' to this register, a simulated interrupt may be initiated.

The CMIE bit (PIE2 register) and the PEIE bit (INTCON register) must be set to enable the interrupt. In addition, the GIE bit must also be set. If any of these bits are clear, the interrupt is not enabled, though the CMIF bit will still be set if an interrupt condition occurs.

Note: If a change in the CMCON register (C1OUT or C2OUT) should occur when a read operation is being executed (start of the Q2 cycle), then the CMIF (PIR2 register) interrupt flag may not get set.

The user, in the Interrupt Service Routine, can clear the interrupt in the following manner:

- a) Any read or write of CMCON will end the mismatch condition.
- b) Clear flag bit CMIF.

A mismatch condition will continue to set flag bit CMIF. Reading CMCON will end the mismatch condition and allow flag bit CMIF to be cleared.

DS41159E-page 252

21.7 Comparator Operation During Sleep


When a comparator is active and the device is placed in Sleep mode, the comparator remains active and the interrupt is functional if enabled. This interrupt will wake-up the device from Sleep mode when enabled. While the comparator is powered up, higher Sleep currents than shown in the power-down current specification will occur. Each operational comparator will consume additional current, as shown in the comparator specifications. To minimize power consumption while in Sleep mode, turn off the comparators, CM<2:0> = 111, before entering Sleep. If the device wakes up from Sleep, the contents of the CMCON register are not affected.

21.8 Effects of a Reset

A device Reset forces the CMCON register to its Reset state, causing the comparator module to be in the Comparator Reset mode, CM<2:0> = 000. This ensures that all potential inputs are analog inputs. Device current is minimized when analog inputs are present at Reset time. The comparators will be powered down during the Reset interval.

21.9 Analog Input Connection Considerations

A simplified circuit for an analog input is shown in Figure 21-4. Since the analog pins are connected to a digital output, they have reverse biased diodes to VDD and Vss. The analog input, therefore, must be between Vss and VDD. If the input voltage deviates from this range by more than 0.6V in either direction, one of the diodes is forward biased and a latch-up condition may occur. A maximum source impedance of 10 k Ω is recommended for the analog sources. Any external component connected to an analog input pin, such as a capacitor or a Zener diode, should have very little leakage current.



^{© 2006} Microchip Technology Inc.

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0		e on DR	all o	e on ther sets
CMCON	C2OUT	C10UT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000	0000	0000	0000
CVRCON	CVREN	CVROE	CVRR	CVRSS	CVR3	CVR2	CVR1	CVR0	0000	0000	0000	0000
INTCON	GIE/ GIEH	PEIE/ GIEL	TMROIE	INTOIE	RBIE	TMR0IF	INTOIF	RBIF	0000	000x	0000	000u
PIR2	—	CMIF ⁽¹⁾	—	EEIF	BCLIF	LVDIF	TMR3IF	ECCP1IF ⁽¹⁾	- 0 - 0	0000	- 0 - 0	0000
PIE2	_	CMIE ⁽¹⁾	_	EEIE	BCLIE	LVDIE	TMR3IE	ECCP1IE ⁽¹⁾	- 0 - 0	0000	- 0 - 0	0000
IPR2	—	CMIP ⁽¹⁾	—	EEIP	BCLIP	LVDIP	TMR3IP	ECCP1IP ⁽¹⁾	-1-1	1111	-1-1	1111
PORTD	RD7	RD6	RD5	RD4	RD3	RD2	RD1	RD0	xxxx	xxxx	uuuu	uuuu
LATD	LATD7	LATD6	LATD5	LATD4	LATD3	LATD2	LATD1	LATD0	xxxx	xxxx	uuuu	uuuu
TRISD	PORTD	Data Dire	ction Reg	gister					1111	1111	1111	1111
PORTE	—	—	—	—	—	RE2	RE1	RE0		-xxx		-000
LATE	_	—	_			LATE2	LATE1	LATE0		-xxx		-uuu
TRISE	IBF ⁽¹⁾	OBF ⁽¹⁾	IBOV ⁽¹⁾	PSPMODE ⁽¹⁾	_	TRISE2	TRISE1	TRISE0	0000	-111	0000	-111
Lawand				ad unimale	in a start of the		a.1					

TABLE 21-1: REGISTERS ASSOCIATED WITH COMPARATOR MODULE

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'

Note 1: These bits are reserved on PIC18F2X8 devices; always maintain these bits clear.

DS41159E-page 254

22.0 COMPARATOR VOLTAGE REFERENCE MODULE

Note:	The comparator voltage reference is only							
	available	on	the	PIC18F448	and			
	PIC18F45	8.						

This module is a 16-tap resistor ladder network that provides a selectable voltage reference. The resistor ladder is segmented to provide two ranges of CVREF values and has a power-down function to conserve power when the reference is not being used. The CVRCON register controls the operation of the reference, as shown in Register 22-1. The block diagram is shown in Figure 22-1.

The comparator and reference supply voltage can come from either VDD and VSS, or the external VREF+ and VREF-, that are multiplexed with RA3 and RA2. The comparator reference supply voltage is controlled by the CVRSS bit.

22.1 Configuring the Comparator Voltage Reference

The comparator voltage reference can output 16 distinct voltage levels for each range. The equations used to calculate the output of the comparator voltage reference are as follows.

EQUATION 22-1:

If CVRR = 1: $CVREF = (CVR < 3:0 > /24) \times CVRSRC$ where: CVRSS = 1, CVRSRC = (VREF+) - (VREF-)CVRSS = 0, CVRSRC = AVDD - AVSS

EQUATION 22-2:

If CVRR = 0: $CVREF = (CVRSRC \times 1/4) + (CVR < 3:0 > /32) \times CVRSRC$ where: CVRSS = 1, CVRSRC = (VREF+) - (VREF-)CVRSS = 0, CVRSRC = AVDD - AVSS


The settling time of the Comparator Voltage Reference must be considered when changing the RA0/AN0/ CVREF output (see Table 27-4 in **Section 27.2 "DC Characteristics"**).

REGISTER 22-1: CVRCON: COMPARATOR VOLTAGE REFERENCE CONTROL REGISTER

	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	R/W-0	
	CVREN	CVROE	CVRR	CVRSS	CVR3	CVR2	CVR1	CVR0	
	bit 7							bit 0	
bit 7		omparator V	0	rence Enab	le bit				
		circuit powe							
		circuit powe							
bit 6		omparator V							
		voltage leve voltage is di							
6.4 C		0			AU/ANU/CVF	егріп			
bit 5		CVRR : Comparator VREF Range Selection bit 1 = 0.00 CVRSRC to 0.625 CVRSRC with CVRSRC/24 step size							
		VRSRC to 0.0			•				
bit 4		omparator V							
		rator referer				REF-)			
	0 = Compa	rator referer	nce source,	CVRSRC = V	′DD – ÝSS	,			
bit 3-0	CVR<3:0>	: Comparato	r VREF Valu	e Selection	$0 \le CVR3:C$	VR0 ≤ 15 b	its		
	When CVF								
	-	CVR3:CVR0/	′24) ● (CVR	SRC)					
	When CVF				(\mathbf{O}) $($				
	CVREF = 1/	4 • (CVRSRC	c) + (CVR3:	CVR0/32) •	(CVRSRC)				
]	
	Legend:								
	R = Reada			ritable bit			bit, read as '		
	-n = Value	at POR	'1' = Bi	t is set	'0' = Bit is	scleared	x = Bit is ur	nknown	

© 2006 Microchip Technology Inc.





22.2 Voltage Reference Accuracy/Error

The full range of voltage reference cannot be realized due to the construction of the module. The transistors on the top and bottom of the resistor ladder network (Figure 22-1) keep VREF from approaching the reference source rails. The voltage reference is derived from the reference source; therefore, the VREF output changes with fluctuations in that source. The absolute accuracy of the voltage reference can be found in **Section 27.0 "Electrical Characteristics"**.

22.3 Operation During Sleep

When the device wakes up from Sleep through an interrupt or a Watchdog Timer time-out, the contents of the CVRCON register are not affected. To minimize current consumption in Sleep mode, the voltage reference should be disabled.

22.4 Effects of a Reset

A device Reset disables the voltage reference by clearing bit CVREN (CVRCON register). This Reset also disconnects the reference from the RA2 pin by clearing bit CVROE (CVRCON register) and selects the high-voltage range by clearing bit CVRR (CVRCON register). The CVRSS value select bits, CVRCON<3:0>, are also cleared.

22.5 Connection Considerations

The voltage reference module operates independently of the comparator module. The output of the reference generator may be connected to the RA0/AN0 pin if the TRISA<0> bit is set and the CVROE bit (CVRCON<6>) is set. Enabling the voltage reference output onto the RA0/AN0 pin, with an input signal present, will increase current consumption. Connecting RA0/AN0 as a digital output, with CVRSS enabled, will also increase current consumption.

The RA0/AN0 pin can be used as a simple D/A output with limited drive capability. Due to the limited current drive capability, a buffer must be used on the voltage reference output for external connections to VREF. Figure 22-2 shows an example buffering technique.

FIGURE 22-2: VOLTAGE REFERENCE OUTPUT BUFFER EXAMPLE




TABLE 22-1: REGISTERS ASSOCIATED WITH COMPARATOR VOLTAGE REFERENCE

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Value on POR	Value all ot Rese	her
CVRCON	CVREN	CVROE	CVRR	CVRSS	CVR3	CVR2	CVR1	CVR0	0000 0000	0000	0000
CMCON	C2OUT	C1OUT	C2INV	C1INV	CIS	CM2	CM1	CM0	0000 0000	0000	0000
TRISA	_	TRISA6	TRISA5	TRISA4	TRISA3	TRISA2	TRISA1	TRISA0	-111 1111	-111 3	1111

Legend: x = unknown, u = unchanged, - = unimplemented, read as '0'. Shaded cells are not used with the comparator voltage reference.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 258

23.0 LOW-VOLTAGE DETECT


In many applications, the ability to determine if the device voltage (VDD) is below a specified voltage level is a desirable feature. A window of operation for the application can be created, where the application software can do "housekeeping tasks" before the device voltage exits the valid operating range. This can be done using the Low-Voltage Detect module.


This module is a software programmable circuitry, where a device voltage trip point can be specified. When the voltage of the device becomes lower than the specified point, an interrupt flag is set. If the interrupt is enabled, the program execution will branch to the interrupt vector address and the software can then respond to that interrupt source.

The Low-Voltage Detect circuitry is completely under software control. This allows the circuitry to be "turned off" by the software which minimizes the current consumption for the device. Figure 23-1 shows a possible application voltage curve (typically for batteries). Over time, the device voltage decreases. When the device voltage equals voltage VA, the LVD logic generates an interrupt. This occurs at time TA. The application software then has the time, until the device voltage is no longer in valid operating range, to shutdown the system. Voltage point VB is the minimum valid operating voltage specification. This occurs at time TB. The difference TB – TA is the total time for shutdown.

The block diagram for the LVD module is shown in Figure 23-2. A comparator uses an internally generated reference voltage as the set point. When the selected tap output of the device voltage crosses the set point (is lower than), the LVDIF bit is set.


Each node in the resistor divider represents a "trip point" voltage. The "trip point" voltage is the minimum supply voltage level at which the device can operate before the LVD module asserts an interrupt. When the supply voltage is equal to the trip point, the voltage tapped off of the resistor array is equal to the internal reference voltage generated by the voltage reference module. The comparator then generates an interrupt signal, setting the LVDIF bit. This voltage is software programmable to any one of 16 values (see Figure 23-2). The trip point is selected by programming the LVDL3:LVDL0 bits (LVDCON<3:0>).





^{© 2006} Microchip Technology Inc.

FIGURE 23-2: LOW-VOLTAGE DETECT (LVD) BLOCK DIAGRAM



The LVD module has an additional feature that allows the user to supply the trip voltage to the module from an external source. This mode is enabled when bits LVDL3:LVDL0 are set to '1111'. In this state, the comparator input is multiplexed from the external input pin LVDIN to one input of the comparator (Figure 23-3). The other input is connected to the internally generated voltage reference (parameter #D423 in **Section 27.2** "**DC Characteristics**"). This gives users flexibility, because it allows them to configure the Low-Voltage Detect interrupt to occur at any voltage in the valid operating range.




FIGURE 23-3: LOW-VOLTAGE DETECT (LVD) WITH EXTERNAL INPUT BLOCK DIAGRAM

DS41159E-page 260

Control Register 23.1

The Low-Voltage Detect Control register controls the operation of the Low Voltage Detect circuitry.

STER 23-1:	LVDCON:	LOW-VOL	TAGE DET	ECT CONT	FROL REG	ISTER		
	U-0	U-0	R-0	R/W-0	R/W-0	R/W-1	R/W-0	R/W-1
		—	IRVST	LVDEN	LVDL3	LVDL2	LVDL1	LVDL0
	bit 7							bit 0
bit 7-6	Unimplem	ented: Rea	d as '0'					
bit 5	IRVST: Inte	ernal Refere	nce Voltage	Stable Flag	bit			
	voltag 0 = Indica	e range tes that the	Low-Voltag	Detect logic e Detect log e LVD interru	jic will not g	enerate the	e interrupt	
bit 4	LVDEN: Lo	ow-Voltage D	Detect Powe	r Enable bit				
	1 = Enable	es LVD, powe es LVD, pow	ers up LVD o	circuit				
bit 3-0	1111 = Ex 1110 = 4.4 1100 = 3.9 1011 = 3.7 1010 = 3.5 1001 = 3.4 1000 = 3.2 0111 = 2.9 0110 = 2.7 0101 = 2.4 0100 = 2.4 0011 = 2.3	ternal analog 15V min4.8 16V min4.5 26V min4.2 26V min4.0 57V min3.8 17V min3.7 27V min3.5 27V min3.0 57V min2.8 18V min2.6 37V min2.5	g input is use 3V max. V max. V max. 8V max. 7V max. 5V max. 5V max. 2V max. 9V max. 8V max. 7V max.	tion Limit bit		LVDIN pin)		
	0010 = 2.1	18V min2.3	6V max.					

REGIS

0001 = 1.98V min.-2.14V max.

0000 = Reserved

Note: LVDL3:LVDL0 modes, which result in a trip point below the valid operating voltage of the device, are not tested.

Legend:			
R = Readable bit	W = Writable bit	U = Unimplemented	bit, read as '0'
-n = Value at POR	'1' = Bit is set	'0' = Bit is cleared	x = Bit is unknown

^{© 2006} Microchip Technology Inc.

23.2 Operation

Depending on the power source for the device voltage, the voltage normally decreases relatively slowly. This means that the LVD module does not need to be constantly operating. To decrease the current requirements, the LVD circuitry only needs to be enabled for short periods where the voltage is checked. After doing the check, the LVD module may be disabled.

Each time that the LVD module is enabled, the circuitry requires some time to stabilize. After the circuitry has stabilized, all status flags may be cleared. The module will then indicate the proper state of the system.

The following steps are needed to set up the LVD module:

- Write the value to the LVDL3:LVDL0 bits (LVDCON register) which selects the desired LVD trip point.
- 2. Ensure that LVD interrupts are disabled (the LVDIE bit is cleared or the GIE bit is cleared).
- 3. Enable the LVD module (set the LVDEN bit in the LVDCON register).
- 4. Wait for the LVD module to stabilize (the IRVST bit to become set).
- 5. Clear the LVD interrupt flag, which may have falsely become set, until the LVD module has stabilized (clear the LVDIF bit).
- 6. Enable the LVD interrupt (set the LVDIE and the GIE bits).

Figure 23-4 shows typical waveforms that the LVD module may be used to detect.




FIGURE 23-4: LOW-VOLTAGE DETECT WAVEFORMS

DS41159E-page 262

23.2.1 REFERENCE VOLTAGE SET POINT

The internal reference voltage of the LVD module may be used by other internal circuitry (the Programmable Brown-out Reset). If these circuits are disabled (lower current consumption), the reference voltage circuit requires a time to become stable before a low-voltage condition can be reliably detected. This time is invariant of system clock speed. This start-up time is specified in electrical specification parameter #36. The low-voltage interrupt flag will not be enabled until a stable reference voltage is reached. Refer to the waveform in Figure 23-4.

23.2.2 CURRENT CONSUMPTION

When the module is enabled, the LVD comparator and voltage divider are enabled and will consume static current. The voltage divider can be tapped from multiple places in the resistor array. Total current consumption, when enabled, is specified in electrical specification parameter #D022B.

23.3 Operation During Sleep

When enabled, the LVD circuitry continues to operate during Sleep. If the device voltage crosses the trip point, the LVDIF bit will be set and the device will wakeup from Sleep. Device execution will continue from the interrupt vector address if interrupts have been globally enabled.

23.4 Effects of a Reset

A device Reset forces all registers to their Reset state. This forces the LVD module to be turned off.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 264

24.0 SPECIAL FEATURES OF THE CPU

There are several features intended to maximize system reliability, minimize cost through elimination of external components, provide power-saving operating modes and offer code protection. These are:

- Oscillator Selection
- Reset
 - Power-on Reset (POR)
 - Power-up Timer (PWRT)
 - Oscillator Start-up Timer (OST)
 - Brown-out Reset (BOR)
- Interrupts
- Watchdog Timer (WDT)
- Sleep
- Code Protection
- ID Locations
- In-Circuit Serial Programming

All PIC18FXX8 devices have a Watchdog Timer which is permanently enabled via the configuration bits or software controlled. It runs off its own RC oscillator for added reliability. There are two timers that offer necessary delays on power-up. One is the Oscillator Start-up Timer (OST), intended to keep the chip in Reset until the crystal oscillator is stable. The other is the Power-up Timer (PWRT) which provides a fixed delay on power-up only, designed to keep the part in Reset while the power supply stabilizes. With these two timers on-chip, most applications need no external Reset circuitry. Sleep mode is designed to offer a very Low-Current Power-Down mode. The user can wake-up from Sleep through external Reset, Watchdog Timer wake-up or through an interrupt. Several oscillator options are also made available to allow the part to fit the application. The RC oscillator option saves system cost while the LP crystal option saves power. A set of configuration bits is used to select various options.

24.1 Configuration Bits

The configuration bits can be programmed (read as '0') or left unprogrammed (read as '1'), to select various device configurations. These bits are mapped starting at program memory location 300000h.

The user will note that address 300000h is beyond the user program memory space. In fact, it belongs to the configuration memory space (300000h-3FFFFh) which can only be accessed using table reads and table writes.

Programming the Configuration registers is done in a manner similar to programming the Flash memory. The EECON1 register WR bit starts a self-timed write to the Configuration register. In normal operation mode, a TBLWT instruction, with the TBLPTR pointed to the Configuration register, sets up the address and the data for the Configuration register write. Setting the WR bit starts a long write to the Configuration register. The Configuration registers are written a byte at a time. To write or erase a configuration cell, a TBLWT instruction can write a '1' or a '0' into the cell.

File	Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0	Default/ Unprogrammed Value
300001h	CONFIG1H			OSCSEN			FOSC2	FOSC1	FOSC0	1111
300002h	CONFIG2L	_	_	_	_	BORV1	BORV0	BOREN	PWRTEN	1111
300003h	CONFIG2H					WDTPS2	WDTPS1	WDTPS0	WDTEN	1111
300006h	CONFIG4L	DEBUG	_	_	_	_	LVP	_	STVREN	11-1
300008h	CONFIG5L		_	_	_	CP3	CP2	CP1	CP0	1111
300009h	CONFIG5H	CPD	CPB	-	-	—	—	-	—	11
30000Ah	CONFIG6L	_	_	-	-	WRT3	WRT2	WRT1	WRT0	1111
30000Bh	CONFIG6H	WRTD	WRTB	WRTC	-	—	—	-	—	111
30000Ch	CONFIG7L	_	_	_	_	EBTR3	EBTR2	EBTR1	EBTR0	1111
30000Dh	CONFIG7H	_	EBTRB	_	_	—	—	_	—	-1
3FFFFEh	DEVID1	DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0	(1)
3FFFFFh	DEVID2	DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3	0000 1000

 TABLE 24-1:
 CONFIGURATION BITS AND DEVICE IDS

Legend: x = unknown, u = unchanged, - = unimplemented, q = value depends on condition. Shaded cells are unimplemented, read as '0'.

Note 1: See Register 24-11 for DEVID1 values.

© 2006 Microchip Technology Inc.

							-000000	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
	U-0	U-0	R/P-1	U-0	U-0	R/P-1	R/P-1	R/P-1
	—	—	OSCSEN	—	—	FOSC2	FOSC1	FOSC0
	bit 7							bit 0
bit 7-6	Unimplem	ented: Read	as '0'					
bit 5	OSCSEN:	Oscillator Sy	stem Clock S	witch Enable	bit			
			ock switch op					
	0 = Oscillat	or system cl	ock switch op	tion is enable	ed (oscillator	switching	is enabled)	
bit 4-3	Unimplem	ented: Read	as '0'					
bit 2-0	FOSC2:FO	SCO: Oscilla	tor Selection	bits				
			SC2 configu					
			PLL enabled	-	ency = (4 x F	OSC)		
			SC2 configui		-by-1 clock o	utout		
	011 = RC c				-by-4 Clock O	uipui		
	010 = HS c	oscillator						
	001 = XT c	scillator						
	000 = LP o	scillator						
	Legend:							
	R = Readal	ble bit	P = Program	nmable bit	U = Unimple	emented bi	t, read as '	0'
	-n = Value	when device	is unprogram	med	u = Unchang	ged from p	rogramme	d state

REGISTER 24-1: CONFIG1H: CONFIGURATION REGISTER 1 HIGH (BYTE ADDRESS 300001h)

REGISTER 24-2: CONFIG2L: CONFIGURATION REGISTER 2 LOW (BYTE ADDRESS 300002h)

	U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
	—				BORV1	BORV0	BOREN	PWRTEN
	bit 7							bit 0
bit 7-4 bit 3-2	•			oltage bits				
	01 = VBOR 00 = VBOR	set to 4.2V						
bit 1	BOREN: B	rown-out Res	set Enable bi	t				
		out Reset en out Reset dis						
bit 0	PWRTEN :	Power-up Tir	ner Enable b	oit				
	1 = PWRT							
	0 = PWRT	enabled						
	Legend:							
	R = Readal -n = Value	ble bit when device	P = Prograr is unprogran				bit, read as programm	

REGISTER 24-3: CONFIG2H: CONFIGURATION REGISTER 2 HIGH (BYTE ADDRESS 300003h)

U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
	—	—	—	WDTPS2	WDTPS1	WDTPS0	WDTEN
bit 7							bit 0

bit 7-4 Unimplemented: Read as '0'

bit 3-1 WDTPS2:WDTPS0: Watchdog Timer Postscale Select bits

- 111 **= 1:128**
- 110 **= 1:64**
- 101 **= 1:32**
- 100 = 1:16
- 011 **= 1:8**
- 010 = **1**:4
- 001 = 1:2
- 000 = 1:1
 - **Note:** The Watchdog Timer postscale select bits configuration used in the PIC18FXXX devices has changed from the configuration used in the PIC18CXXX devices.

bit 0 WDTEN: Watchdog Timer Enable bit

- 1 = WDT enabled
- 0 = WDT disabled (control is placed on the SWDTEN bit)

Legend:		
R = Readable bit	P = Programmable bit	U = Unimplemented bit, read as '0'
-n = Value when device	ce is unprogrammed	u = Unchanged from programmed state

REGISTER 24-4: CONFIG4L: CONFIGURATION REGISTER 4 LOW (BYTE ADDRESS 300006h)

,								
R/P-1								
STVREN								
bit 0								
se I/O pins.								
ebug.								
Jnimplemented: Read as '0'								
LVP: Low-Voltage ICSP Enable bit								
as '0'								
as '(

-n = Value when device is unprogrammed

u = Unchanged from programmed state

REGISTER 24-5:	5: CONFIG5L: CONFIGURATION REGISTER 5 LOW (BYTE ADDRESS 300)							08h)		
	U-0	U-0	U-0	U-0	R/C-1	R/C-1	R/C-1	R/C-1		
			—		CP3 ⁽¹⁾	CP2 ⁽¹⁾	CP1	CP0		
	bit 7	bit 7 bit 0								
bit 7-4	Unimpleme	ented: Read	as '0'							
bit 3	CP3: Code	Protection b	it ⁽¹⁾							
		 1 = Block 3 (006000-007FFFh) not code-protected 0 = Block 3 (006000-007FFFh) code-protected 								
bit 2	CP2: Code Protection bit ⁽¹⁾									
		(004000-00 (004000-00	-	code-protecte	ed					
bit 1	CP1: Code	Protection b	it							
		(002000-003 (002000-003		code-protecte	ed					
bit 0	CP0: Code	CP0: Code Protection bit								
	1 = Block 0 (000200-001FFFh) not code-protected0 = Block 0 (000200-001FFFh) code-protected									
	Note 1:	Unimplemer	nted in PIC18	3FX48 device	es; maintair	Note 1: Unimplemented in PIC18FX48 devices; maintain this bit set.				

Legend:		
R = Readable bit	C = Clearable bit	U = Unimplemented bit, read as '0'
-n = Value when devi	ice is unprogrammed	u = Unchanged from programmed state

REGISTER 24-6: CONFIG5H: CONFIGURATION REGISTER 5 HIGH (BYTE ADDRESS 300009h)

	R/C-1	R/C-1	U-0	U-0	Ú-0	U-0	U-0	Ú-0
	CPD	CPB	_				—	
	bit 7							bit 0
h:+ 7			Dada Duata a	41 a. a. b. 14				
bit 7		EEPROM (
	 1 = Data EEPROM not code-protected 0 = Data EEPROM code-protected 							
bit 6	CPB: Boot	Block Code	Protection	bit				
		``	,	not code-pr				
	0 = Boot B	lock (00000	0-0001FFh)	code-protec	cted			
bit 5-0	Unimplem	ented: Rea	d as '0'					
	Legend:							
	R = Reada	ble bit	C = Clear	able bit	U = Unin	nplemented	bit, read as '	0'

R = Readable bit	C = Clearable bit	U = Unimplemented bit, read as '0'
-n = Value when device	ce is unprogrammed	u = Unchanged from programmed state

DS41159E-page 268

REGISTER 24-7: CONFIG6L: CONFIGURATION REGISTER 6 LOW (BYTE ADDRESS 30000Ah)

11 27-7.					01011			
	U-0	U-0	U-0	U-0	R/P-1	R/P-1	R/P-1	R/P-1
	—	—	—	_	WRT3 ⁽¹⁾	WRT2 ⁽¹⁾	WRT1	WRT0
	bit 7							bit 0
bit 7-4	Unimplem	ented: Read	as '0'					
bit 3	WRT3: Wri	ite Protection	bit ⁽¹⁾					
		8 (006000-00 8 (006000-00	,		ed			
h 11 O	 Block 3 (006000-007FFFh) write-protected WRT2: Write Protection bit⁽¹⁾ 							
bit 2								
		2 (004000-00	,	•	ed			
	0 = Block 2	2 (004000-00	5FFFh) write	e-protected				
bit 1	WRT1: Wri	ite Protection	bit					
	1 = Block 1	(002000-00	3FFFh) not v	write-protect	ed			
	0 = Block 1	(002000-00	3FFFh) write	e-protected				
bit 0	WRT0: Wri	ite Protection	bit					
	1 = Block 0 (000200-001FFFh) not write-protected							
	0 = Block 0) (000200-00	1FFFh) write	e-protected				
	Note 1:	Unimpleme	nted in PIC1	8FX48 devic	es; maintair	n this bit set		

Legend:		
R = Readable bit	P = Programmable bit	U = Unimplemented bit, read as '0'
-n = Value when devic	e is unprogrammed	u = Unchanged from programmed state

REGISTER 24-8: CONFIG6H: CONFIGURATION REGISTER 6 HIGH (BYTE ADDRESS 30000Bh)

240.								
	R/P-1	R/P-1	R-1	U-0	U-0	U-0	U-0	U-0
	WRTD	WRTB	WRTC	—	—	—	—	—
	bit 7							bit 0
bit 7	WRID: Da	ata EEPRON	I write Prot	ection bit				
	1 = Data E	EPROM no	t write-prote	cted				
	0 = Data E	EPROM wr	te-protected	k				
bit 6	WRTB: Bo	ot Block Wr	ite Protectio	on bit				
	1 = Boot B	lock (00000	0-0001FFh)	not write-pr	otected			
		•	,	write-protec				
bit 5	WRTC: Co	onfiguration	Register Wr	ite Protectio	n bit			
	1 = Config	uration regis	ters (30000	0-3000FFh)	not write-pr	otected		
	•	•	•	0-3000FFh)				
	Note:	This bit is r	ead-only ar	nd cannot be	changed in	user mode.		
bit 4-0	Unimplem	ented: Rea	d as '0'					

Legend:		
R = Readable bit	P = Programmable bit	U = Unimplemented bit, read as '0'
-n = Value when device	e is unprogrammed	u = Unchanged from programmed state

^{© 2006} Microchip Technology Inc.

					R/P-1	R/P-1	R/P-1	R/P-1
		—	—	—	EBTR3 ⁽¹⁾	EBTR2 ⁽¹⁾	EBTR1	EBTR0
	bit 7							bit 0
oit 7-4	Unimplem	ented: Rea	ad as '0'					
oit 3	-		Protection bit	(1)				
							d in other blo other blocks	
oit 2	EBTR2: Ta	able Read F	Protection bit	(1)				
		•	,	•			d in other blo other blocks	cks
oit 1	EBTR1: Ta	able Read F	Protection bit					
				-			d in other blo other blocks	cks
oit O	EBTR0: Ta	able Read F	Protection bit					
		•	,	•			d in other blo other blocks	

REGISTER 24-9: CONFIG7L: CONFIGURATION REGISTER 7 LOW (BYTE ADDRESS 30000Ch)

Legend:		
R = Readable bit	P = Programmable bit	U = Unimplemented bit, read as '0'
-n = Value when device	e is unprogrammed	u = Unchanged from programmed state

REGISTER 24-10: CONFIG7H: CONFIGURATION REGISTER 7 HIGH (BYTE ADDRESS 30000Dh)

U-0	R/P-1	U-0	U-0	U-0	U-0	U-0	U-0
—	EBTRB	—	_	—	—	_	—
bit 7							bit 0

bit 7 Unimplemented: Read as '0'

bit 6 **EBTRB:** Boot Block Table Read Protection bit

1 = Boot Block (000000-0001FFh) not protected from table reads executed in other blocks

0 = Boot Block (000000-0001FFh) protected from table reads executed in other blocks

bit 5-0 Unimplemented: Read as '0'

Legend:		
R = Readable bit	P = Programmable bit	U = Unimplemented bit, read as '0'
-n = Value when device	e is unprogrammed	u = Unchanged from programmed state

DS41159E-page 270

REGISTER 24-11: DEVID1: DEVICE ID REGISTER 1 FOR PIC18FXX8 DEVICES (BYTE ADDRESS 3FFFFEh)

R	R	R	R	R	R	R	R
DEV2	DEV1	DEV0	REV4	REV3	REV2	REV1	REV0
bit 7							bit 0

bit 7-5 **DEV2:DEV0:** Device ID bits These bits are used with the DEV<10:3> bits in the Device ID Register 2 to identify the part number.

000 = PIC18F248

001 = PIC18F448

010 = PIC18F258

011 = PIC18F458

bit 4-0 REV4:REV0: Revision ID bits

These bits are used to indicate the device revision.

Legend:		
R = Readable bit	P = Programmable bit	U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed		u = Unchanged from programmed state

REGISTER 24-12: DEVID2: DEVICE ID REGISTER 2 FOR PIC18FXX8 DEVICES (BYTE ADDRESS 3FFFFFh)

R	R	R	R	R	R	R	R
DEV10	DEV9	DEV8	DEV7	DEV6	DEV5	DEV4	DEV3
bit 7							bit 0

bit 7-0 DEV10:DEV3: Device ID bits

These bits are used with the DEV<2:0> bits in the Device ID Register 1 to identify the part number.

00001000 = PIC18FXX8

Legend:		
R = Readable bit	P = Programmable bit	U = Unimplemented bit, read as '0'
-n = Value when device is unprogrammed		u = Unchanged from programmed state

24.2 Watchdog Timer (WDT)

The Watchdog Timer is a free running, on-chip RC oscillator which does not require any external components. This RC oscillator is separate from the RC oscillator of the OSC1/CLKI pin. That means that the WDT will run, even if the clock on the OSC1/CLKI and OSC2/CLKO/RA6 pins of the device has been stopped, for example, by execution of a SLEEP instruction.

During normal operation, a WDT time-out generates a device Reset (Watchdog Timer Reset). If the device is in Sleep mode, a WDT time-out causes the device to wake-up and continue with <u>normal</u> operation (Watchdog Timer wake-up). The TO bit in the RCON register will be cleared upon a WDT time-out.

The Watchdog Timer is enabled/disabled by a device configuration bit. If the WDT is enabled, software execution may not disable this function. When the WDTEN configuration bit is cleared, the SWDTEN bit enables/disables the operation of the WDT. The WDT time-out period values may be found in **Section 27.0** "**Electrical Characteristics**" under parameter #31. Values for the WDT postscaler may be assigned using the configuration bits.

Note: The CLRWDT and SLEEP instructions clear the WDT and the postscaler if assigned to the WDT and prevent it from timing out and generating a device Reset condition.

Note: When a CLRWDT instruction is executed and the postscaler is assigned to the WDT, the postscaler count will be cleared but the postscaler assignment is not changed.

24.2.1 CONTROL REGISTER

Register 24-13 shows the WDTCON register. This is a readable and writable register which contains a control bit that allows software to override the WDT enable configuration bit only when the configuration bit has disabled the WDT.

REGISTER 24-13: WDTCON: WATCHDOG TIMER CONTROL REGISTER

U-0	U-0	U-0	U-0	U-0	U-0	U-0	R/W-0
	—	—	—	—	—	—	SWDTEN
bit 7							bit 0

bit 7-1 Unimplemented: Read as '0'

1 = Watchdog Timer is on

0 = Watchdog Timer is turned off if the WDTEN configuration bit in the Configuration register = 0

Legend:

Legena.	
R = Readable bit	W = Writable bit
U = Unimplemented bit, read as '0'	-n = Value at POR

bit 0 SWDTEN: Software Controlled Watchdog Timer Enable bit

24.2.2 WDT POSTSCALER

The WDT has a postscaler that can extend the WDT Reset period. The postscaler is selected at the time of device programming by the value written to the CONFIG2H Configuration register.




FIGURE 24-1: WATCHDOG TIMER BLOCK DIAGRAM

TABLE 24-2: SUMMARY OF WATCHDOG TIMER REGISTERS

Name	Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
CONFIG2H					WDTPS2	WDTPS1	WDTPS0	WDTEN
RCON	IPEN	_	_	RI	TO	PD	POR	BOR
WDTCON	_				_	_		SWDTEN

Legend: Shaded cells are not used by the Watchdog Timer.

^{© 2006} Microchip Technology Inc.

24.3 Power-Down Mode (Sleep)

Power-down mode is entered by executing a SLEEP instruction.

If enabled, the Watchdog Timer will be cleared but keeps running, the PD bit (RCON<2>) is cleared, the TO bit (RCON<3>) is set and the oscillator driver is turned off. The I/O ports maintain the status they had before the SLEEP instruction was executed (driving high, low or high-impedance).

For lowest current consumption in this mode, place all I/O pins at either VDD or VSS, ensure no external circuitry is drawing current from the I/O pin, power-down the A/D and disable external clocks. Pull all I/O pins that are high-impedance inputs, high or low externally, to avoid switching currents caused by floating inputs. The TOCKI input should also be at VDD or VSS for lowest current consumption. The contribution from on-chip pull-ups on PORTB should be considered.

The MCLR pin must be at a logic high level (VIHMC).

24.3.1 WAKE-UP FROM SLEEP

The device can wake-up from Sleep through one of the following events:

- 1. External Reset input on MCLR pin.
- 2. Watchdog Timer wake-up (if WDT was enabled).
- 3. Interrupt from INT pin, RB port change or a peripheral interrupt.

The following peripheral interrupts can wake the device from Sleep:

- 1. PSP read or write.
- 2. TMR1 interrupt. Timer1 must be operating as an asynchronous counter.
- 3. TMR3 interrupt. Timer3 must be operating as an asynchronous counter.
- 4. CCP Capture mode interrupt.
- 5. Special event trigger (Timer1 in Asynchronous mode using an external clock).
- 6. MSSP (Start/Stop) bit detect interrupt.
- 7. MSSP transmit or receive in Slave mode (SPI/I^2C) .
- 8. USART RX or TX (Synchronous Slave mode).
- 9. A/D conversion (when A/D clock source is RC).
- 10. EEPROM write operation complete.
- 11. LVD interrupt.

Other peripherals cannot generate interrupts, since during Sleep, no on-chip clocks are present.

External MCLR Reset will cause a device Reset. All other events are considered a continuation of program execution and will cause a "wake-up". The TO and PD bits in the RCON register can be used to determine the cause of the device Reset. The PD bit, which is set on power-up, is cleared when Sleep is invoked. The TO bit is cleared if a WDT time-out occurred (and caused wake-up).

When the SLEEP instruction is being executed, the next instruction (PC + 2) is prefetched. For the device to wake-up through an interrupt event, the corresponding interrupt enable bit must be set (enabled). Wake-up is regardless of the state of the GIE bit. If the GIE bit is clear (disabled), the device continues execution at the instruction after the SLEEP instruction. If the GIE bit is set (enabled), the device executes the instruction after the SLEEP instruction and then branches to the interrupt address. In cases where the execution of the instruction following SLEEP is not desirable, the user should have a NOP after the SLEEP instruction.

24.3.2 WAKE-UP USING INTERRUPTS


When global interrupts are disabled (GIE cleared) and any interrupt source has both its interrupt enable bit and interrupt flag bit set, one of the following will occur:

- If an interrupt condition (interrupt flag bit and interrupt enable bits are set) occurs **before** the execution of a SLEEP instruction, the SLEEP instruction will complete as a NOP. Therefore, the WDT and WDT postscaler will not be cleared, the TO bit will not be set and the PD bit will not be cleared.
- If the interrupt condition occurs during or after the execution of a SLEEP instruction, the device will immediately wake-up from Sleep. The SLEEP instruction will be completely executed before the wake-up. Therefore, the WDT and WDT postscaler will be cleared, the TO bit will be set and the PD bit will be cleared.

Even if the flag bits were checked before executing a $\$ SLEEP instruction, it may be possible for flag bits to become set before the SLEEP instruction completes. To determine whether a SLEEP instruction executed, test the \overline{PD} bit. If the \overline{PD} bit is set, the SLEEP instruction was executed as a NOP.

To ensure that the WDT is cleared, a CLRWDT instruction should be executed before a SLEEP instruction.

DS41159E-page 274



WAKE-UP FROM SLEEP THROUGH INTERRUPT^(1,2) **FIGURE 24-2:**

AI, in S of LP Oscillator mode assumed. GIE = 1 assumed. In this case, after wake-up, the processor jumps to the interrupt routine. If GIE = 0, execution will continue in-line. Tost = 1024 Tosc (drawing not to scale). This delay will not occur for RC and EC Oscillator modes. CLKO is not available in these oscillator modes but shown here for timing reference. 2:

3: 4:

^{© 2006} Microchip Technology Inc.

24.4 Program Verification and Code Protection

The overall structure of the code protection on the PIC18 Flash devices differs significantly from other PICmicro devices.

The user program memory is divided into five blocks. One of these is a boot block of 512 bytes. The remainder of the memory is divided into four blocks on binary boundaries. Each of the five blocks has three code protection bits associated with them. They are:

- Code-Protect bit (CPn)
- Write-Protect bit (WRTn)
- External Block Table Read bit (EBTRn)

Figure 24-3 shows the program memory organization for 16 and 32-Kbyte devices and the specific code protection bit associated with each block. The actual locations of the bits are summarized in Table 24-3.

FIGURE 24-3: CODE-PROTECTED PROGRAM MEMORY FOR PIC18FXX8

	MEMORY S	ZE/DEVICE		Block Code Protection
	16 Kbytes 32 Kbyt (PIC18FX48) (PIC18FX		Address Range	Controlled By:
Boot	Block	Boot Block	000000h 0001FFh	CPB, WRTB, EBTRB
Blo	ock 0	Block 0	000200h 001FFFh	CP0, WRT0, EBTR0
Blo	ock 1	Block 1	002000h 003FFFh	CP1, WRT1, EBTR1
	emented ad '0's	Block 2	004000h 005FFFh	CP2, WRT2, EBTR2
	emented ad '0's	Block 3	006000h 007FFFh	CP3, WRT3, EBTR3
	emented ad '0's	Unimplemented Read '0's	008000h	(Unimplemented Memory Space)
			1FFFFFh	

TABLE 24-3: SUMMARY OF CODE PROTECTION REGISTERS

File Name		Bit 7	Bit 6	Bit 5	Bit 4	Bit 3	Bit 2	Bit 1	Bit 0
300008h	CONFIG5L		—	_		CP3	CP2	CP1	CP0
300009h	CONFIG5H	CPD	CPB	—	—	—	—	—	—
30000Ah	CONFIG6L	_	—	_	_	WRT3	WRT2	WRT1	WRT0
30000Bh	CONFIG6H	WRTD	WRTB	WRTC	_	—	—	—	_
30000Ch	CONFIG7L	—	—	—	—	EBTR3	EBTR2	EBTR1	EBTR0
30000Dh	CONFIG7H	_	EBTRB	_	_	—	—	—	_

Legend: Shaded cells are unimplemented.

DS41159E-page 276


24.4.1 PROGRAM MEMORY CODE PROTECTION

The user memory may be read to or written from any location using the table read and table write instructions. The device ID may be read with table reads. The Configuration registers may be read and written with the table read and table write instructions.

In user mode, the CPn bits have no direct effect. CPn bits inhibit external reads and writes. A block of user memory may be protected from table writes if the WRTn configuration bit is '0'. The EBTRn bits control table reads. For a block of user memory with the EBTRn bit set to '0', a table read instruction that executes from within that block is allowed to read. A table read instruction that executes from a location outside of that block is not allowed to read and will result in reading '0's. Figures 24-4 through 24-6 illustrate table write and table read protection.

Note:	Code protection bits may only be written to
	a '0' from a '1' state. It is not possible to
	write a '1' to a bit in the '0' state. Code
	protection bits are only set to '1' by a full
	chip erase or block erase function. The full
	chip erase and block erase functions can
	only be initiated via ICSP or an external
	programmer.

FIGURE 24-4:	TABLE WRITE	WRTn	DISALLOWED
			DIOMEEOILED



^{© 2006} Microchip Technology Inc.







FIGURE 24-6: EXTERNAL BLOCK TABLE READ (EBTRn) ALLOWED



DS41159E-page 278

24.4.2 DATA EEPROM CODE PROTECTION

The entire data EEPROM is protected from external reads and writes by two bits: CPD and WRTD. CPD inhibits external reads and writes of data EEPROM. WRTD inhibits external writes to data EEPROM. The CPU can continue to read and write data EEPROM regardless of the protection bit settings.

24.4.3 CONFIGURATION REGISTER PROTECTION

The Configuration registers can be write-protected. The WRTC bit controls protection of the Configuration registers. In user mode, the WRTC bit is readable only. WRTC can only be written via ICSP or an external programmer.

24.5 ID Locations

Eight memory locations (20000h-200007h) are designated as ID locations where the user can store checksum or other code identification numbers. These locations are accessible during normal execution through the TBLRD and TBLWT instructions or during program/verify. The ID locations can be read when the device is code-protected.

24.6 In-Circuit Serial Programming

PIC18FXXX microcontrollers can be serially programmed while in the end application circuit. This is simply done with two lines for clock and data and three other lines for power, ground and the programming voltage. This allows customers to manufacture boards with unprogrammed devices and then program the microcontroller just before shipping the product. This also allows the most recent firmware or a custom firmware to be programmed.

24.7 In-Circuit Debugger

When the DEBUG bit in Configuration register, CONFIG4L, is programmed to a '0', the In-Circuit Debugger functionality is enabled. This function allows simple debugging functions when used with MPLAB[®] IDE. When the microcontroller has this feature enabled, some of the resources are not available for general use. Resources used include 2 I/O pins, stack locations, program memory and data memory. For more information on the resources required, see the User's Guide for the In-Circuit Debugger you are using. To use the In-Circuit Debugger function of the microcontroller, the design must implement In-Circuit Serial Programming connections to MCLR/VPP, VDD, GND, RB7 and RB6. This will interface to the In-Circuit Debugger module available from Microchip or one of the third party development tool companies. The Microchip In-Circuit Debugger (ICD) used with the PIC18FXXX microcontrollers is the MPLAB[®] ICD 2.

24.8 Low-Voltage ICSP Programming

The LVP bit in Configuration register, CONFIG4L, enables Low-Voltage ICSP Programming. This mode allows the microcontroller to be programmed via ICSP using a VDD source in the operating voltage range. This only means that VPP does not have to be brought to VIHH but can instead be left at the normal operating voltage. In this mode, the RB5/PGM pin is dedicated to the programming function and ceases to be a general purpose I/O pin. During programming, VDD is applied to the MCLR/VPP pin. To enter Programming mode, VDD must be applied to the RB5/PGM pin, provided the LVP bit is set. The LVP bit defaults to a ('1') from the factory.

- Note 1: The High-Voltage Programming mode is always available, regardless of the state of the LVP bit, by applying VIHH to the MCLR pin.
 - 2: While in Low-Voltage ICSP mode, the RB5 pin can no longer be used as a general purpose I/O pin.
 - **3:** When using Low-Voltage ICSP Programming (LVP) and the pull-ups on PORTB are enabled, bit 5 in the TRISB register must be cleared to disable the pull-up on RB5 and ensure the proper operation of the device.

If Low-Voltage Programming mode is not used, the LVP bit can be programmed to a '0' and RB5/PGM becomes a digital I/O pin. However, the LVP bit may only be programmed when programming is entered with VIHH on MCLR/VPP. The LVP bit can only be charged when using high voltage on MCLR.

It should be noted that once the LVP bit is programmed to '0', only the High-Voltage Programming mode is available and only High-Voltage Programming mode can be used to program the device.

When using Low-Voltage ICSP Programming, the part must be supplied 4.5V to 5.5V if a bulk erase will be executed. This includes reprogramming of the codeprotect bits from an ON state to an OFF state. For all other cases of Low-Voltage ICSP Programming, the part may be programmed at the normal operating voltage. This means unique user IDs or user code can be reprogrammed or added.

^{© 2006} Microchip Technology Inc.

NOTES:

DS41159E-page 280

25.0 INSTRUCTION SET SUMMARY

The PIC18 instruction set adds many enhancements to the previous PICmicro instruction sets, while maintaining an easy migration from these PICmicro instruction sets.

Most instructions are a single program memory word (16 bits) but there are three instructions that require two program memory locations.

Each single-word instruction is a 16-bit word divided into an opcode, which specifies the instruction type and one or more operands, which further specify the operation of the instruction.

The instruction set is highly orthogonal and is grouped into four basic categories:

- Byte-oriented operations
- Bit-oriented operations
- Literal operations
- Control operations

The PIC18 instruction set summary in Table 25-2 lists **byte-oriented**, **bit-oriented**, **literal** and **control** operations. Table 25-1 shows the opcode field descriptions.

Most **byte-oriented** instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The destination of the result (specified by 'd')
- 3. The accessed memory (specified by 'a')

The file register designator 'f' specifies which file register is to be used by the instruction.

The destination designator 'd' specifies where the result of the operation is to be placed. If 'd' is zero, the result is placed in the WREG register. If 'd' is one, the result is placed in the file register specified in the instruction.

All **bit-oriented** instructions have three operands:

- 1. The file register (specified by 'f')
- 2. The bit in the file register (specified by 'b')
- 3. The accessed memory (specified by 'a')

The bit field designator 'b' selects the number of the bit affected by the operation, while the file register designator 'f' represents the number of the file in which the bit is located.

The **literal** instructions may use some of the following operands:

- A literal value to be loaded into a file register (specified by 'k')
- The desired FSR register to load the literal value into (specified by 'f')
- No operand required (specified by '—')

The **control** instructions may use some of the following operands:

- A program memory address (specified by 'n')
- The mode of the CALL or RETURN instructions (specified by 's')
- The mode of the table read and table write instructions (specified by 'm')
- No operand required (specified by '—')

All instructions are a single word, except for three double-word instructions. These three instructions were made double-word instructions so that all the required information is available in these 32 bits. In the second word, the 4 MSbs are '1's. If this second word is executed as an instruction (by itself), it will execute as a NOP.

All single-word instructions are executed in a single instruction cycle, unless a conditional test is true or the program counter is changed as a result of the instruction. In these cases, the execution takes two instruction cycles, with the additional instruction cycle(s) executed as a NOP.

The double-word instructions execute in two instruction cycles.

One instruction cycle consists of four oscillator periods. Thus, for an oscillator frequency of 4 MHz, the normal instruction execution time is 1 μ s. If a conditional test is true, or the program counter is changed as a result of an instruction, the instruction execution time is 2 μ s. Two-word branch instructions (if true) would take 3 μ s.

Figure 25-1 shows the general formats that the instructions can have.

All examples use the format 'nnh' to represent a hexadecimal number, where 'h' signifies a hexadecimal digit.

The Instruction Set Summary, shown in Table 25-2, lists the instructions recognized by the Microchip MPASM[™] Assembler.

Section 25.2 "Instruction Set" provides a description of each instruction.

25.1 Read-Modify-Write Operations

Any instruction that specifies a file register as part of the instruction performs a Read-Modify-Write (R-M-W) operation. The register is read, the data is modified and the result is stored according to either the instruction or the destination designator 'd'. A read operation is performed on a register even if the instruction writes to that register.


For example, a "CLRF PORTB" instruction will read PORTB, clear all the data bits, then write the result back to PORTB. This example would have the unintended result that the condition that sets the RBIF flag would be cleared.

^{© 2006} Microchip Technology Inc.

TABLE 25-1: OPCODE FIELD DESCRIPTIONS

Field	Description						
a	RAM access bit:						
	a = 0: RAM location in Access RAM (BSR register is ignored)						
	a = 1: RAM bank is specified by BSR register						
bbb	Bit address within an 8-bit file register (0 to 7).						
BSR	Bank Select Register. Used to select the current RAM bank.						
d	Destination select bit:						
	d = 0: store result in WREG d = 1: store result in file register f						
dest	Destination either the WREG register or the specified register file location.						
f	8-bit register file address (0x00 to 0xFF).						
fs	12-bit register file address (0x000 to 0xFFF). This is the source address.						
fd	12-bit register file address (0x000 to 0xFFF). This is the destination address.						
k	Literal field, constant data or label (may be either an 8-bit, 12-bit or a 20-bit value).						
label	Label name.						
	The mode of the TBLPTR register for the table read and table write instructions.						
mm	Only used with table read and table write instructions:						
*	No change to register (such as TBLPTR with table reads and writes)						
*+	Post-Increment register (such as TBLPTR with table reads and writes)						
*-	Post-Decrement register (such as TBLPTR with table reads and writes)						
+*	Pre-Increment register (such as TBLPTR with table reads and writes)						
	The relative address (2's complement number) for relative branch instructions or the direct address for						
n	Call/Branch and Return instructions.						
PRODH	Product of Multiply High Byte.						
PRODL	Product of Multiply Low Byte.						
s	Fast Call/Return mode select bit:						
5	s = 0: do not update into/from shadow registers						
	s = 1: certain registers loaded into/from shadow registers (Fast mode)						
u	Unused or unchanged.						
WREG	Working register (accumulator).						
х	Don't care (0 or 1).						
	The assembler will generate code with $x = 0$. It is the recommended form of use for compatibility with all						
	Microchip software tools.						
TBLPTR	21-bit Table Pointer (points to a program memory location).						
TABLAT	8-bit Table Latch.						
TOS	Top-of-Stack.						
PC	Program Counter						
PCL	Program Counter Low Byte.						
PCH	Program Counter High Byte.						
PCLATH	Program Counter High Byte Latch.						
PCLATU	Program Counter Upper Byte Latch.						
GIE	Global Interrupt Enable bit.						
WDT	Watchdog Timer.						
TO	Time-out bit.						
PD	Power-Down bit.						
C, DC, Z, OV, N	ALU status bits: Carry, Digit Carry, Zero, Overflow, Negative.						
[]	Optional.						
()	Contents.						
\rightarrow	Assigned to.						
< >	Register bit field.						
E	In the set of.						
italics	User defined term (font is courier).						

DS41159E-page 282



© 2006 Microchip Technology Inc.

TABLE 25-2: PIC18FXXX INSTRUCTION SET

Mnemonic, Operands		Description	Cycles	16-Bit Instruction Word				Status	Nata -
				MSb			LSb	Affected	Notes
BYTE-ORIENTED FILE REGISTER OPERATIONS									
ADDWF	, - ,	Add WREG and f	1	0010	01da	ffff	ffff	C, DC, Z, OV, N	
ADDWFC	f, d, a	Add WREG and Carry bit to f	1	0010	00da	ffff	ffff	C, DC, Z, OV, N	1, 2
ANDWF	f, d, a	AND WREG with f	1	0001	01da	ffff	ffff	Z, N	1,2
CLRF	f, a	Clear f	1	0110	101a	ffff	ffff	Z	2
COMF	f, d, a	Complement f	1	0001	11da	ffff	ffff	Z, N	1, 2
CPFSEQ	f, a	Compare f with WREG, skip =	1 (2 or 3)	0110	001a	ffff	ffff	None	4
CPFSGT	f, a	Compare f with WREG, skip >	1 (2 or 3)	0110	010a	ffff	ffff	None	4
CPFSLT	f, a	Compare f with WREG, skip <	1 (2 or 3)	0110	000a	ffff	ffff	None	1, 2
DECF	f, d, a	Decrement f	1	0000	01da	ffff	ffff	C, DC, Z, OV, N	1, 2, 3, 4
DECFSZ	f, d, a	Decrement f, Skip if 0	1 (2 or 3)	0010	11da	ffff	ffff	None	1, 2, 3, 4
DCFSNZ	f, d, a	Decrement f, Skip if Not 0	1 (2 or 3)	0100	11da	ffff	ffff	None	1, 2
INCF	f, d, a	Increment f	1 ΄	0010	10da	ffff	ffff	C, DC, Z, OV, N	1, 2, 3, 4
INCFSZ	f, d, a	Increment f, Skip if 0	1 (2 or 3)	0011	11da	ffff	ffff	None	4
INFSNZ	f, d, a	Increment f, Skip if Not 0	1 (2 or 3)		10da	ffff	ffff	None	1, 2
IORWF	f, d, a	Inclusive OR WREG with f	1		00da	ffff	ffff		1, 2
MOVF	f, d, a	Move f	1		00da	ffff	ffff	Z. N	1
MOVFF	f _s , f _d		2		ffff	ffff		None	•
morri	's' 'd	f _d (destination) 2nd word			ffff	ffff	ffff		
MOVWF	f, a	Move WREG to f	1	0110	111a	ffff	ffff	None	
MULWF	f, a	Multiply WREG with f	1	0000	001a	ffff	ffff	None	
NEGF	f, a	Negate f	1	0110	110a	ffff	ffff	C, DC, Z, OV, N	12
RLCF	,	Rotate Left f through Carry	1	0011	01da	ffff	ffff	C, Z, N	•, –
RLNCF		Rotate Left f (No Carry)	1	0100	01da 01da	ffff		Z, N	1, 2
RRCF			1	0011	00da	ffff	ffff	C, Z, N	1, 2
RRNCF	f, d, a	Rotate Right f (No Carry)	1	0100	00da 00da	ffff	ffff		
SETF	f, a	Set f	1	0110	100a	ffff	ffff	None	
SUBFWB	f, d, a	Subtract f from WREG with	1		100a 01da	ffff	ffff	C, DC, Z, OV, N	1 2
	1, u, a	borrow	'	0101	UIUA	LLLL		0, 00, 2, 00, 1	1, 2
SUBWF	f, d, a	Subtract WREG from f	1	0101	11da	ffff	ffff	C, DC, Z, OV, N	
SUBWFB	f, d, a	Subtract WREG from f with	1		10da	ffff	ffff	C, DC, Z, OV, N	1.2
0001110	i, a, a	borrow		0101	rouu			0, 20, 2, 01, 11	•, –
SWAPF	f, d, a	Swap nibbles in f	1	0011	10da	ffff	ffff	None	4
TSTFSZ	f. a	Test f, skip if 0	1 (2 or 3)	0110	100a 011a	ffff	ffff	None	4 1, 2
XORWF	f, d, a	Exclusive OR WREG with f	1	0001		ffff	ffff	Z, N	·, <u>~</u>
-	BIT-ORIENTED FILE REGISTER OPERATIONS								
BCF		1	1	1001	h h l	<i><i>EEEE</i></i>		None	1.0
		Bit Clear f	-		bbba	ffff	ffff		1,2
BSF		Bit Set f	1		bbba	ffff	ffff	None	1,2
BTFSC		Bit Test f, Skip if Clear	1 (2 or 3)		bbba	ffff	ffff	None	3, 4
BTFSS			1 (2 or 3)		bbba	ffff	ffff	None	3, 4
BTG		Bit Toggle f	1		bbba	ffff		None	1, 2

Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

2: If this instruction is executed on the TMR0 register (and where applicable, d = 1), the prescaler will be cleared if assigned.

3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

- 4: Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.
- 5: If the table write starts the write cycle to internal memory, the write will continue until terminated.

DS41159E-page 284

Mnemonic, Operands		Description	Cycles	16-Bit Instruction Word				Status	Notes
				MSb			LSb	Affected	Notes
CONTROL	OPER	ATIONS							
BC	n	Branch if Carry	1 (2)	1110	0010	nnnn	nnnn	None	
BN	n	Branch if Negative	1 (2)	1110	0110	nnnn	nnnn	None	
BNC	n	Branch if Not Carry	1 (2)	1110	0011	nnnn	nnnn	None	
BNN	n	Branch if Not Negative	1 (2)	1110	0111	nnnn	nnnn	None	
BNOV	n	Branch if Not Overflow	1 (2)	1110	0101	nnnn	nnnn	None	
BNZ	n	Branch if Not Zero	2	1110	0001	nnnn	nnnn	None	
BOV	n	Branch if Overflow	1 (2)	1110	0100	nnnn	nnnn	None	
BRA	n	Branch Unconditionally	1 (2)	1101	0nnn	nnnn	nnnn	None	
BZ	n	Branch if Zero	1 (2)	1110	0000	nnnn	nnnn	None	
CALL	n, s	Call subroutine1st word	2	1110	110s	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
CLRWDT	—	Clear Watchdog Timer	1	0000	0000	0000	0100	TO, PD	
DAW	—	Decimal Adjust WREG	1	0000	0000	0000	0111	С	
GOTO	n	Go to address 1st word	2	1110	1111	kkkk	kkkk	None	
		2nd word		1111	kkkk	kkkk	kkkk		
NOP	—	No Operation	1	0000	0000	0000	0000	None	
NOP	—	No Operation	1	1111	xxxx	xxxx	xxxx	None	4
POP	—	Pop top of return stack (TOS)	1	0000	0000	0000	0110	None	
PUSH	—	Push top of return stack (TOS)	1	0000	0000	0000	0101	None	
RCALL	n	Relative Call	2	1101	1nnn	nnnn	nnnn	None	
RESET		Software device Reset	1	0000	0000	1111	1111	All	
RETFIE	S	Return from interrupt enable	2	0000	0000	0001	000s	GIE/GIEH,	
								PEIE/GIEL	
RETLW	k	Return with literal in WREG	2	0000	1100	kkkk	kkkk	None	
RETURN	S	Return from Subroutine	2	0000	0000	0001	001s	None	
SLEEP	—	Go into Standby mode	1	0000	0000	0000	0011	TO, PD	

TABLE 25-2: PIC18FXXX INSTRUCTION SET (CONTINUED)

Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

2: If this instruction is executed on the TMR0 register (and where applicable, d = 1), the prescaler will be cleared if assigned.

3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

4: Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

5: If the table write starts the write cycle to internal memory, the write will continue until terminated.

^{© 2006} Microchip Technology Inc.

TABLE 25-2: PIC18FXXX INSTRUCTION SET (CONTINUED)

Mnemonic, Operands		Description	Cycles	16-Bit Instruction Word				Status	Natas
				MSb			LSb	Affected	Notes
LITERAL OPERATIONS									
ADDLW	k	Add literal and WREG	1	0000	1111	kkkk	kkkk	C, DC, Z, OV, N	
ANDLW	k	AND literal with WREG	1	0000	1011	kkkk	kkkk	Z, N	
IORLW	k	Inclusive OR literal with WREG	1	0000	1001	kkkk	kkkk	Z, N	
LFSR	f, k	Move literal (12-bit)2nd word	2	1110	1110	00ff	kkkk	None	
		to FSRx 1st word		1111	0000	kkkk	kkkk		
MOVLB	k	Move literal to BSR<3:0>	1	0000	0001	0000	kkkk	None	
MOVLW	k	Move literal to WREG	1	0000	1110	kkkk	kkkk	None	
MULLW	k	Multiply literal with WREG	1	0000	1101	kkkk	kkkk	None	
RETLW	k	Return with literal in WREG	2	0000	1100	kkkk	kkkk	None	
SUBLW	k	Subtract WREG from literal	1	0000	1000	kkkk	kkkk	C, DC, Z, OV, N	
XORLW	k	Exclusive OR literal with WREG	1	0000	1010	kkkk	kkkk	Z, N	
DATA ME	DATA MEMORY								
TBLRD*		Table Read	2	0000	0000	0000	1000	None	
TBLRD*+		Table Read with post-increment		0000	0000	0000	1001	None	
TBLRD*-		Table Read with post-decrement		0000	0000	0000	1010	None	
TBLRD+*		Table Read with pre-increment		0000	0000	0000	1011	None	
TBLWT*		Table Write	2 (5)	0000	0000	0000	1100	None	
TBLWT*+		Table Write with post-increment		0000	0000	0000	1101	None	
TBLWT*-		Table Write with post-decrement		0000	0000	0000	1110	None	
TBLWT+*		Table Write with pre-increment		0000	0000	0000	1111	None	

Note 1: When a Port register is modified as a function of itself (e.g., MOVF PORTB, 1, 0), the value used will be that value present on the pins themselves. For example, if the data latch is '1' for a pin configured as input and is driven low by an external device, the data will be written back with a '0'.

2: If this instruction is executed on the TMR0 register (and where applicable, d = 1), the prescaler will be cleared if assigned.

3: If Program Counter (PC) is modified or a conditional test is true, the instruction requires two cycles. The second cycle is executed as a NOP.

4: Some instructions are 2-word instructions. The second word of these instructions will be executed as a NOP unless the first word of the instruction retrieves the information embedded in these 16 bits. This ensures that all program memory locations have a valid instruction.

5: If the table write starts the write cycle to internal memory, the write will continue until terminated.

25.2 Instruction Set

ADDLW	ADD Literal	to W		
Syntax:	[label] ADD	DLW k		
Operands:	$0 \leq k \leq 255$			
Operation:	$(W) + k \to W$	1		
Status Affected:	N, OV, C, DC	C, Z		
Encoding:	0000	1111	kkkk	kkkk
Description:	The contents literal 'k' and			
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q	3	Q4
Decode	Read literal 'k'	Proc Da		rite to W
Example: Before Instru W =	0x10	0x15		
After Instruct W =	ion 0x25			

ADDWF	ADD W to f	1			
Syntax:	[label] ADI	DWF	f [,d [,a	a]]	
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$				
Operation:	$(W) + (f) \rightarrow$	dest			
Status Affected:	N, OV, C, D	C, Z			
Encoding:	0010	01da	fff	f	ffff
Description:	Add W to re result is stor (default). If will be select used.	red in W red back fa' is '0',	. If 'd' i in reg the Ac	s '1 iste ces	', the r 'f' s Bank
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q	3		Q4
Decode	Read register 'f'	Proce Dat		-	/rite to stination
Example:	ADDWF	REG,	W		
Before Instruct W REG After Instructio	= 0x17 = 0xC2				
W REG	= 0xD9 = 0xC2				

Downloaded from: http://www.datasheetcatalog.com/

 $\ensuremath{\textcircled{}^\circ}$ 2006 Microchip Technology Inc.

ADDWFC	ADD W and Carry bit to f
Syntax:	[<i>label</i>] ADDWFC f [,d [,a]]
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$
Operation:	$(W) + (f) + (C) \to dest$
Status Affected:	N, OV, C, DC, Z
Encoding:	0010 00da ffff ffff
Description:	Add W, the Carry flag and data memory location 'f'. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in data memory location 'f'. If 'a' is '0', the Access Bank will be selected. If 'a' is '1', the BSR will not be overridden.
Words:	1
Cycles:	1
Q Cycle Activity:	
Q1	Q2 Q3 Q4
Decode	ReadProcessWrite toregister 'f'Datadestination
<u>Example:</u> Before Instrue Carry bi	
REG W	= 0x02 = 0x4D
After Instructi Carry bi REG W	

ANDLW	AND Litera	l with W	,	
Syntax:	[<i>label</i>] AN	IDLW I	<	
Operands:	$0 \le k \le 255$			
Operation:	(W) .AND. I	$k \to W$		
Status Affected:	N, Z			
Encoding:	0000	1011	kkkk	kkkk
Description:	The conten 8-bit literal			
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q3	;	Q4
Decode	Read literal 'k'	Proce Data		rite to W
Fuemales		05 8		
<u>Example:</u>	ANDLW	0x5F		
Before Instru	uction			

Before Instru	uction	
W	=	0xA3
After Instruct	tion	
W	=	0x03

	AND W wit	nt	
Syntax:	[<i>label</i>] AN	IDWF f [,d [,a]]
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$		
Operation:	(W) .AND. ((f) \rightarrow dest	
Status Affected:	N, Z		
Encoding:	0001	01da ffi	ff ffff
Description:	register 'f'. I in W. If 'd' is in register 'f Access Bar	ts of W are AN f 'd' is '0', the r s '1', the result i' (default). If 'a k will be selec Il not be overrie	esult is stored is stored back a' is '0', the ted. If 'a' is '1'
Words:	1		
Cycles:	1		
Q Cycle Activity:			
Q1	Q2	Q3	Q4
Decode	Read register 'f'	Process Data	Write to destination
Example:	ANDWF	REG, W	
Before Instruc	tion		
W REG	= 0x17 = 0xC2		
After Instruction	on = 0x02		

BC		Branch if C	arry		
Synta	ax:	[label] BC	n		
Oper	ands:	-128 ≤ n ≤ 1	27		
Oper	ation:	if Carry bit is (PC) + 2 +		С	
Statu	is Affected:	None			
Enco	oding:	1110	0010	nnnn	nnnn
Desc	ription:	If the Carry bit is '1', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will hav incremented to fetch the next instruc- tion, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.			
Word	ds:	1			
Cycle	es:	1(2)			
QC	ycle Activity: Imp:				
	Q1	Q2	Q3		Q4
	Decode	Read literal 'n'	Proces Data		te to PC
	No operation	No operation	No operati	on op	No eration
lf No	o Jump:				
	Q1	Q2	Q3		Q4
	Decode	Read literal 'n'	Proces Data		No eration
<u>Exar</u>	nple:	HERE	BC C	JUMP	
	Before Instruct PC After Instructi	= ad	dress (H	IERE)	
	If Carry	= 1;			

BCF		Bit Clear f				
Syntax		[label] B	CF f,b[,	,a]		
Opera	nds:	$\begin{array}{l} 0 \leq f \leq 255 \\ 0 \leq b \leq 7 \\ a \in [0,1] \end{array}$				
Operat	tion:	$0 \rightarrow f < b >$				
Status	Affected:	None				
Encod	ing:	1001	bbba	fff	f	ffff
Descri	ption:	ion: Bit 'b' in register 'f' is cleared. If 'a' is '0', the Access Bank will be selected, over- riding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).				
Words	:	1				
Cycles	:	1				
Q Cyc	cle Activity:					
_	Q1	Q2	Q	3		Q4
	Decode	Read register 'f'	Proce Dat			Write gister 'f'
Examp	ole:	BCF	FLAG_RI	EG, 7		
Before Instruction FLAG_REG = 0xC7 After Instruction FLAG_REG = 0x47						

BN		Branch if I	Vegative	•	
Synta	ax:	[label] BN	l n		
Opera	ands:	-128 ≤ n ≤	127		
Opera	ation:	if Negative (PC) + 2 +		;	
Statu	s Affected:	None			
Enco	ding:	1110	0110	nnnn	n nnnn
Desc	ription:	If the Nega program wi The 2's cor added to th incremente tion, the ne PC + 2 + 2 two-cycle ir	II branch nplemen e PC. Sir d to fetcl w addres n. This ir	t numbe nce the n the ne ss will b nstructio	er '2n' is PC will have xt instruc- e
Word	s:	1			
Cycle	es:	1(2)			
Q Cy If Ju	ycle Activity: mp:				
	Q1	Q2	Q	3	Q4
	Decode	Read literal 'n'	Proce Dat		Write to PC
	No operation	No operation	No opera		No operation
lf No	Jump:	operation	opera	uon	operation
	Q1	Q2	Q	3	Q4
	Decode	Read literal 'n'	Proce		No operation
Exam	nple:	HERE	BN	Jump	

Before Instruction PC	=	address (HERE)
After Instruction		
If Negative	=	1;
PC	=	address (Jump)
If Negative	=	0; address (HERE + 2)
FC	-	audiess (HERE + 2)

BNC		Branch if N	lot Carry		BNN		Branch if I	Not Negative	
Synta	ax:	[label] BN	C n		Synt	ax:	[label] BN	NN n	
Opera	ands:	-128 ≤ n ≤ 1	27		Oper	ands:	-128 ≤ n ≤	127	
Opera	ation:	if Carry bit is (PC) + 2 + 2			Oper	ration:	if Negative (PC) + 2 +		
Statu	s Affected:	None			Statu	is Affected:	None		
Enco	ding:	1110	0011 nn	nn nnnn	Enco	oding:	1110	0111 nr	inn nnnn
Desc	ription:	will branch. The 2's com added to the incremented tion, the new	plement num PC. Since th to fetch the w address wil . This instruc	ne PC will have next instruc-	Desc	ription:	program wi The 2's cor added to th incremente tion, the ne	nplement nun e PC. Since the d to fetch the w address wi n. This instruc	nber '2n' is ne PC will hav next instruc-
Word	s:	1			Word	ds:	1		
Cycle	es:	1(2)			Cycle	es:	1(2)		
Q Cy If Ju	ycle Activity: mp:					ycle Activity: Imp:			
	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	Decode	Read literal 'n'	Process Data	Write to PC		Decode	Read literal 'n'	Process Data	Write to PC
	No operation	No operation	No operation	No operation		No operation	No operation	No operation	No operation
If No	o Jump:				If N	o Jump:			
-	Q1	Q2	Q3	Q4		Q1	Q2	Q3	Q4
	Decode	Read literal 'n'	Process Data	No operation		Decode	Read literal 'n'	Process Data	No operation
<u>Exam</u>	<u>nple:</u>	HERE	BNC Jum	p	Exar	nple:	HERE	BNN Jum	þ
I	Before Instruc	ction				Before Instru	ction		
	PC	= ad	dress (HERI	Ξ)		PC	= ac	ddress (HER	E)
L	After Instructi If Carry PC If Carry	= 0;	dress (Jump)		After Instruct If Negat PC	ive = 0; = ac	ddress (Jum	<u>o</u>)
	PC		dress (HERI	E + 2)		If Negat PC		ddress (HER	E + 2)

BNO	v	Branch if Not Overflow					
Synta	ax:	[<i>label</i>] BN	OV n				
Oper	ands:	-128 ≤ n ≤ 1	27				
Oper	ation:	if Overflow I (PC) + 2 + 2					
Statu	s Affected:	None					
Enco	ding:	1110	0101 nnr	ın nnnn			
Desc	ription:	program wil The 2's com added to the incremented tion, the new PC + 2 + 2r	If the Overflow bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will have incremented to fetch the next instruc- tion, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.				
Word	ls:	1	1				
Cycle	es:	1(2)					
Q Cycle Activity: If Jump:							
	Q1	Q2	Q3	Q4			
	Decode	Read literal 'n'	Process Data	Write to PC			
	No operation	No operation	No operation	No operation			
lf No	o Jump:						
	Q1	Q2	Q3	Q4			
	Decode	Read literal 'n'	Process Data	No operation			
<u>Exan</u>	nple:	HERE	BNOV Jump				
Before Instruction PC = address (HERE) After Instruction If Overflow = 0; PC = address (Jump)							
	If Overflow = 1; PC = address (HERE + 2)						

			7			
Synta		[<i>label</i>] BN				
Oper	ands:	-128 ≤ n ≤ 127				
Oper	ation:	if Zero bit is '0' (PC) + 2 + 2n \rightarrow PC				
Statu	is Affected:	None				
Enco	oding:	1110	0001	nnnn	nnnn	
Desc	rription:	If the Zero bit is '0', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will ha incremented to fetch the next instruc- tion, the new address will be PC + 2 + 2n. This instruction is then two-cycle instruction.				
Word	ds:	1				
Cycle	es:	1(2)				
QC	ycle Activity: Imp:	()				
	Q1	Q2	Q3		Q4	
	Decode	Read literal 'n'	Proce Data		/rite to PC	
	No operation	No operation	No operat	ion d	No operation	
If No	o Jump:					
			~~~			
	Q1	Q2	Q3	1	Q4	
	Q1 Decode	Read literal	Proce	SS	No	
				SS		
Exan	Decode	Read literal	Proce Data	SS	No	
	Decode	Read literal 'n' HERE ction = ad on = 0;	Proce Data	ss a d Jump IERE)	No	

BRA	,	Unconditional Branch			BSF	
Synta	ax:	[ <i>label</i> ] BF	RA n		Synta	
Oper	rands:	-1024 ≤ n ≤	-1024 ≤ n ≤ 1023			
Oper	ration:	(PC) + 2 +	$(PC) + 2 + 2n \rightarrow PC$			
Statu	is Affected:	None	None			
Enco	oding:	1101	0nnn n	nnn nnnn	Opera 	
Desc	cription:	the PC. Sin incremente instruction, PC + 2 + 2	Add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is a two-cycle instruction.			
Word	ds:	1				
Cycle	es:	2			Words	
QC	ycle Activity:				Cycle	
	Q1	Q2	Q3	Q4	Q Cy	
	Decode	Read literal 'n'	Process Data	Write to PC	ſ	
	No	No	No	No	] [	
	operation	operation	operation	operation	J	
					Exam	
<u>Exan</u>	nple:	HERE	BRA Jur	np	E	
	Before Instruc PC	= ac	ddress (HEF	RE)	ļ	
	After Instruction	on				

address (Jump)

=

BSF	Bit Set f				
Syntax:	[label] BS	F f,b[,a	a]		
Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ 0 \leq b \leq 7 \\ a \in [0,1] \end{array}$				
Operation:	$1 \rightarrow f < b >$				
Status Affected:	None				
Encoding:	1000	bbba	fff	f	ffff
Description:	Bit 'b' in reg Access Ban overriding th the bank wil BSR value.	nk will be he BSR v	select /alue. I	ed, f 'a'	= 1, then
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q	3		Q4
Decode	Read register 'f'	Proce Dat			Write gister 'f'
Example:	BSF I	FLAG_RI	EG, 7		
Before Instruc FLAG_R After Instructic FLAG_R	EG = 0x on	:0A :8A			

PC

BTFSC		Bit Test F	ile,	Skip if (	Clear		
Syntax:		[ <i>label</i> ] B	TFS	SC f,b[,	a]		
Operands:		$0 \le f \le 255$ $0 \le b \le 7$ $a \in [0,1]$					
Operation:		skip if (f <b>) = 0</b>					
Status Affecte	d:	None					
Encoding:		1011 bbba ffff fff					ffff
Description:		If bit 'b' in register 'f' is '0', then the next instruction is skipped. If bit 'b' is '0', then the next instruction fetched during the current instruction execution is discarded and a NOP is executed instead, making this a two-cyc instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default)				uction ction P is two-cycle s Bank 3SR ill be	
Words:		1					
Cycles:				les if sk 2-word i			
Q Cycle Activ	vity:	00		0			0.1
Q1 Deco	40	Q2 Read		Q3 Proce			Q4 No
Deco	1e	register '	f'	Dat		op	peration
lf skip:							
Q1		Q2		Q	3		Q4
No		No		No			No
operat		operation		opera		ор	eration
If skip and fo	llowed		d in				
Q1		Q2		Q			Q4
No		No	•	No			No
operat No	ion	operation No	1	operat No		ομ	eration No
operat	ion	operation	า	operat		on	eration
Example:		HERE FALSE TRUE		TFSC	FLAG		
Before Ir PC	nstruc	tion =	ad	dress (I	HERE)		
	tructio LAG< PC LAG< PC	1> = =	1;		TRUE) FALSI		

ffff ffff '1', then the next next instruction rent instruction and a NOP is ing this a two-cycl the Access Bank
1', then the next next instruction rent instruction and a NOP is ing this a two-cycl
1', then the next next instruction rent instruction and a NOP is ing this a two-cycl
1', then the next next instruction rent instruction and a NOP is ing this a two-cycl
1', then the next next instruction rent instruction and a NOP is ing this a two-cycl
1', then the next next instruction rent instruction and a NOP is ing this a two-cycl
1', then the next next instruction rent instruction and a NOP is ing this a two-cycl
next instruction rent instruction and a NOP is ing this a two-cycl
ding the BSR ne bank will be SR value (default).
ip and followed instruction.
Q4
ss No
a operation
Q4
No
ion operation
_
ion operation
No
ion operation
ic :

BTG	Bit Toggle f			
Syntax:	[label] BTG	f,b[,a]		
Operands:	0 ≤ f ≤ 255 0 ≤ b ≤ 7			
	a ∈ [0,1]			
Operation:	$(\overline{f}\!<\!b\!\!>) \to f\!<\!b\!\!>$	>		
Status Affected:	None			
Encoding:	0111	bbba	ffff	ffff
Description:	Bit 'b' in data inverted. If 'a be selected, 'a' = 1, then t per the BSR	' is '0', th overridin he bank	e Access g the BSF will be sel	Bank will Value. If
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q	3	Q4
Decode	Read register 'f'	Proce Data		Write gister 'f'
Example:	BTG	PORTC,	4	
Before Instru PORTC		0101 <b>[0</b> :	x75]	
After Instruct		0101 <b>[0</b> :		

Synta	ax:	[ <i>label</i> ] BOV n				
	ands:		-128 < n < 127			
•	ration:	if Overflow bit is '1' (PC) + 2 + 2n $\rightarrow$ PC				
Statu	is Affected:	None				
Enco	oding:	1110	0100	nnnn	nnnn	
Desc	ription:	If the Overflow bit is '1', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will ha incremented to fetch the next instruc- tion, the new address will be PC + 2 + 2n. This instruction is then two-cycle instruction.				
Word	ds:	1				
Cycle	es:	1(2)				
Q C If Ju	ycle Activity: Imp:					
	•					
	Q1	Q2	Q		Q4	
	Q1 Decode	Q2 Read literal 'n'	Q3 Proce Dat	ess	Q4 Write to PC	
		Read literal	Proce	ass	Write to	
lf No	Decode	Read literal 'n' No	Proce Dat	ass	Write to PC No	
lf No	Decode No operation	Read literal 'n' No	Proce Dat	a tion c	Write to PC No	
lf No	Decode No operation o Jump:	Read literal 'n' No operation	Proce Dat No operat	tion c	Write to PC No operation	
	Decode No operation o Jump: Q1 Decode	Read literal 'n' No operation Q2 Read literal	Proce Dat No operation	tion c	Write to PC No operation Q4 No	
<u>Exan</u>	Decode No operation o Jump: Q1 Decode	Read literal 'n' No operation Q2 Read literal 'n' HERE ction = ac	Proce Dat No operal Q3 Proce Dat BOV	ess a tion c 3 ess a c	Write to PC No operation Q4 No	

^{© 2006} Microchip Technology Inc.

ΒZ		Branch if Zero					
Synta	ax:	[label] BZ	[ <i>label</i> ] BZ n				
Oper	ands:	-128 ≤ n ≤ 127					
Oper	ation:	if Zero bit is '1' (PC) + 2 + 2n $\rightarrow$ PC					
Statu	s Affected:	None	None				
Enco	ding:	1110	1110 0000 nnnn nnn				
Desc	ription:	If the Zero bit is '1', then the program will branch. The 2's complement number '2n' is added to the PC. Since the PC will hav incremented to fetch the next instruc- tion, the new address will be PC + 2 + 2n. This instruction is then a two-cycle instruction.					
Word	ls:	1					
Cycle	es:	1(2)					
Q C If Ju	ycle Activity: mp:						
	Q1	Q2	Q	3	Q4		
	Decode	Read literal 'n'	Proce Dat		Write to PC		
	No	No	No		No		
	operation	operation	opera	tion	operation		
It No	o Jump: Q1	Q2	Q	3	Q4		
	Decode	Read literal	Proce	-	No		
	Debbuc	'n'	Dat		operation		
<u>Exan</u>	n <u>ple:</u> Before Instruc PC		BZ	Jump	)		
	After Instruction If Zero PC If Zero PC	= 1; = ac = 0;	ddress	(Jump) (HERE			

CALL			-1		
Syntax:	[ <i>label</i> ] CALL k[,s]				
Operands:	0 ≤ k ≤ 1048575 s ∈ [0,1]				
Operation:	$(PC) + 4 \rightarrow TOS,$				
operation	$(PC) + 4 \rightarrow TOS,$ k $\rightarrow$ PC<20:1>,				
	if s = 1				
	$(W) \rightarrow WS,$ (Status) $\rightarrow$	STATUS	S.		
	$(BSR) \rightarrow BS$		-,		
Status Affected:	None				
Encoding:					
1st word (k<7:0>)	1110	110s	k ₇ kk		kkkk
2nd word(k<19:8>) Description:	Subroutine	k ₁₉ kkk	kkk		kkkk
	51A1055 a	and BSR	S. If 's	'= 0	, no
	update occu 20-bit value CALL is a tv	urs (defa 'k' is loa	ult). Th ded in	hen, to P	the C<20:1
Words:	update occu 20-bit value	urs (defa 'k' is loa	ult). Th ded in	hen, to P	the C<20:1
Words: Cycles:	update occu 20-bit value CALL is a tv	urs (defa 'k' is loa	ult). Th ded in	hen, to P	the C<20:1
	update occu 20-bit value CALL is a tv 2	urs (defa 'k' is loa	ult). Th ded in	hen, to P	the C<20:1
Cycles: Q Cycle Activity: Q1	update occu 20-bit value CALL is a tw 2 2 Q2	urs (defa 'k' is loa vo-cycle Q3	ult). Th ded in instruc	hen, to P ction	the C<20:1 1.
Cycles: Q Cycle Activity:	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal	urs (defa 'k' is loa vo-cycle Q3 Push P	ult). The ded in the d	hen, to P ction	the C<20:1 n. Q4 ad litera
Cycles: Q Cycle Activity: Q1	update occu 20-bit value CALL is a tw 2 2 Q2	urs (defa 'k' is loa vo-cycle Q3	ult). The ded in the d	hen, to P ction Rea 'k'	the C<20:1 h. Q4 ad litera <19:8>,
Cycles: Q Cycle Activity: Q1 Decode No	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal 'k'<7:0>,	urs (defa 'k' is loa vo-cycle Q3 Push P stac No	ult). Th ded in instruct C to k	hen, to Po ction 'k'- Wri	the C<20:1 n. Q4 ad litera <19:8>, te to PC No
Cycles: Q Cycle Activity: Q1 Decode	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal 'k'<7:0>,	urs (defa 'k' is loa vo-cycle Q3 Push P stac	ult). Th ded in instruct C to k	hen, to Po ction 'k'- Wri	the C<20:1 n. Q4 ad litera <19:8>, te to PC No
Cycles: Q Cycle Activity: Q1 Decode No	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal 'k'<7:0>,	urs (defa 'k' is loa vo-cycle Q3 Push P stac No	ult). Th ded in instruct C to k tion	hen, to P ction 'k'- Wri op	the C<20:1 n. Q4 ad litera <19:8>, te to PC No
Cycles: Q Cycle Activity: Q1 Decode No operation Example: Before Instruct	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal 'k'<7:0>, No operation HERE tion	urs (defa 'k' is loa vo-cycle Q3 Push P stac No opera	ult). Th ded in instruct C to k tion	hen, to P ction 'k'- Wri op	the C<20:1 ad litera <19:8>, te to PC No peration
Cycles: Q Cycle Activity: Q1 Decode No operation Example: Before Instruct PC	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal 'k'<7:0>, No operation HERE tion = address	urs (defa 'k' is loa vo-cycle Q3 Push P stac No opera	ult). Th ded in instruct C to k tion	hen, to P ction 'k'- Wri op	the C<20:1 ad litera <19:8>, te to PC No peration
Cycles: Q Cycle Activity: Q1 Decode No operation Example: Before Instruct	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal 'k'<7:0>, No operation HERE tion = address	urs (defa 'k' is loa vo-cycle Q3 Push P stac No opera CALL S (HERF	ult). The ded in instruct PC to k tion THE 3	hen, to P ction 'k'- Wri op	the C<20:1 ad litera <19:8>, te to PC No peration
Cycles: Q Cycle Activity: Q1 Decode No operation Example: Before Instruct PC After Instructio	update occu 20-bit value CALL is a tw 2 2 Q2 Read literal 'k'<7:0>, No operation HERE tion = address	urs (defa 'k' is loa vo-cycle Push P stac No opera CALL s (HERF s (THEF	ult). The ded in instruct PC to k tion THE 3	Rea 'k'- Wri RE, 1	the C<20:1 ad litera <19:8>, te to PC No veration

CLRF	Clear f					
Syntax:	[ label ] CLF	[ <i>label</i> ]CLRF f[,a]				
Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ a \in [0,1] \end{array}$					
Operation:	$\begin{array}{l} 000h \rightarrow f \\ 1 \rightarrow Z \end{array}$					
Status Affected:	Z					
Encoding:	0110	101a	fff	f fff	f	
Description: Words: Cycles:	Clears the c register. If 'a be selected If 'a' = 1, the as per the E 1	a' is '0', t , overrid en the ba	he Acc ing the ank will	ess Bank BSR valu I be select	ie.	
Q Cycle Activity:	00	0		0.4		
Q1 Decode	Q2 Read	Q3 Proce		Q4 Write		
Decode	register 'f'	Data		register '	f'	
Example: Before Instruc FLAG R			G_REG			

	Clear Wate	hdog Ti	mer	
Syntax:	[label] Cl	RWDT		
Operands:	None			
Operation:	$\begin{array}{l} 000h \rightarrow WDT, \\ 000h \rightarrow WDT \text{ postscaler,} \\ 1 \rightarrow \overline{TO}, \\ 1 \rightarrow \overline{PD} \end{array}$			
Status Affected:	TO, PD			
Encoding:	0000	0000	0000	0100
Description:	Watchdog postscaler of and PD are	of the WI		
Words:	1			
Words: Cycles:	1 1			
	•			
Cycles:	•	Q	3	Q4
Cycles: Q Cycle Activity:	1 Q2 No	Proce	ess	No
Cycles: Q Cycle Activity: Q1 Decode	1 Q2 No operation	1	ess	
Cycles: Q Cycle Activity: Q1 Decode Example:	1 Q2 No operation	Proce	ess	No
Cycles: Q Cycle Activity: Q1 Decode	1 Q2 No operation CLRWDT tion unter =	Proce	ess	No

COMF	Complement f	CPFSEQ	Compare f with W, Skip if f = W
Syntax:	[ <i>label</i> ] COMF f [,d [,a]]	Syntax:	[label] CPFSEQ f[,a]
Operands:	$0 \le f \le 255$	Operands:	$0 \le f \le 255$
	d ∈ [0,1]		a ∈ [0,1]
	a ∈ [0,1]	Operation:	(f) - (W),
Operation: Status Affected:	$(\overline{f}) \rightarrow dest$ N, Z	·	skip if (f) = (W) (unsigned comparison)
Encoding:	0001 11da ffff ffff	Status Affected:	None
0		Encoding:	0110 001a ffff ffff
Description:	The contents of register 'f' are complemented. If 'd' is '0', the result is	Description:	Compares the contents of data memory
	stored in W. If 'd' is '1', the result is	Description.	location 'f' to the contents of W by
	stored back in register 'f' (default). If 'a'		performing an unsigned subtraction.
	is '0', the Access Bank will be selected,		If 'f' = W, then the fetched instruction is
	overriding the BSR value. If 'a' = 1, then		discarded and a NOP is executed
	the bank will be selected as per the		instead, making this a two-cycle
	BSR value (default).		instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR
Words:	1		value. If 'a' = 1, then the bank will be
Cycles:	1		selected as per the BSR value (default).
Q Cycle Activity:		Words:	1
Q1	Q2 Q3 Q4	Cycles:	1(2)
Decode	Read Process Write to		Note: 3 cycles if skip and followed
	register 'f' Data destination		by a 2-word instruction.
Example:	COME DEC N	Q Cycle Activity:	
Example:	COMF REG, W	Q1	Q2 Q3 Q4
Before Instruc REG		Decode	Read Process No
After Instructio			register 'f' Data operation
REG	= 0x13	lf skip:	
W	= 0xEC	Q1	Q2 Q3 Q4
		No	No No No
		operation	operation operation operation
		•	d by 2-word instruction:
		Q1	Q2 Q3 Q4
		No operation	No No No operation operation
		No	No No No
		operation	operation operation operation
		oporation	
		Example:	HERE CPFSEQ REG
		<u>example.</u>	NEQUAL :
			EQUAL :
		Before Instruc	ction
		PC Addr	ess = HERE
		W REG	= ? = ?
		After Instruction	•
			UTT

If REG PC If REG PC

= = ≠ W; Address (EQUAL) W; Address (NEQUAL)

CPF	SGT	Compare f	with W, Skip	if f > W			
Synta	ax:	[label] CF	PFSGT f[,a]				
Oper	ands:	$\begin{array}{l} 0 \leq f \leq 255 \\ a \in \ [0,1] \end{array}$					
Oper	ation:	• • • •	(f) – (W), skip if (f) > (W) (unsigned comparison)				
Statu	s Affected:	None					
Enco	ding:	0110	010a fff	f ffff			
Description: Compares the contents of data mem location 'f' to the contents of the W b performing an unsigned subtraction. If the contents of 'f' are greater than contents of WREG, then the fetched instruction is discarded and a NOP is executed instead, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, th the bank will be selected as per the BSR value (default).							
Word	ls:	1					
Cycle	es:		ycles if skip ar a 2-word instru				
QC	ycle Activity:	·					
	Q1	Q2	Q3	Q4			
	Decode	Read register 'f'	Process Data	No operation			
lf sk	ip:						
	Q1	Q2	Q3	Q4			
	No operation	No operation	No operation	No operation			
lf sk	ip and followe	•					
	Q1	Q2	Q3	Q4			
	No operation	No operation	No operation	No operation			
	No	No	No	No			
	operation	operation	operation	operation			
<u>Exan</u>	nple:	HERE NGREATER GREATER	NGREATER :				
	Before Instruc PC W	= Ad	ldress (HERE	)			
	vv After Instructio	•					
	If REG PC If REG	> W = Ac ≤ W	<b>ldress</b> (GREA				
	PC	= Ac	ldress (NGRE	ATER)			

CPFS	SLT	Compare f	with W, Skip	if f < W			
Synta	ax:	[label] CI	PFSLT f[,a]				
Oper	ands:	$\begin{array}{l} 0 \leq f \leq 255 \\ a \in \ [0,1] \end{array}$					
Oper	ation:		(f) - (W), skip if $(f) < (W)$ (unsigned comparison)				
Statu	s Affected:	None					
Enco	ding:	0110	000a fff	f ffff			
Desc	ription:	location 'f' t performing If the conten- contents of instruction i executed in two-cycle in Access Ban	he contents of o the contents an unsigned s nts of 'f' are les W, then the fe s discarded ar stead, making astruction. If 'a' ik will be select I not be overrid	of W by ubtraction. ss than the tched id a NOP is this a is '0', the ted. If 'a' is '1',			
Word	ls:	1					
Cycle	es:		ycles if skip ar a 2-word instr				
QC	ycle Activity:						
1	Q1	Q2	Q3	Q4			
	Decode	Read register 'f'	Process Data	No operation			
lf sk	in [.]	register i	Data	operation			
ii on	Q1	Q2	Q3	Q4			
1	No	No	No	No			
	operation	operation	operation	operation			
lf sk	ip and followe	d by 2-word in	struction:				
i	Q1	Q2	Q3	Q4			
	No	No	No	No			
	operation	operation	operation	operation			
	No operation	No operation	No operation	No operation			
Exan	<u> </u>		CPFSLT REG	oporation			
<u></u>	<u></u>		:				
	Before Instruc PC W		Idress (HERE	)			
	After Instructio If REG PC	< W	; <b>ldress</b> (less	)			

© 2006 Microchip Technology Inc.

DAW	Decimal Ac	djust W Regis	ter	DECF	Decrement	f			
Syntax:	[label] DA	AW .		Syntax:	[label] DI	ECF f[,d[,a]	]		
Operands: Operation:	None Operands: If $[W<3:0>> 9]$ or $[DC = 1]$ then $(W<3:0>) + 6 \rightarrow W<3:0>;$		Operands:	0 ≤ f ≤ 255 d ∈ [0,1] a ∈ [0,1]					
	else	0 -> W<0.0>,		Operation:	(f) – 1 $\rightarrow$ de	est			
	$(W{<}3{:}0{>})\toW{<}3{:}0{>}$			Status Affected:	C, DC, N, C	DV, Z			
	If $[W<7:4>>9]$ or $[C = 1]$ then $(W<7:4>) + 6 \rightarrow W<7:4>;$ else $(W<7:4>) \rightarrow W<7:4>$		$\rightarrow$ W<7:4>; Description:		0000				
					result is sto result is sto				
Status Affected:	С					'a' is '0', the A			
Encoding:	0000 0000 0000 0111					cted, overridir = 1, then the	0		
Description:		the eight-bit v				,	value (default).		
	resulting from the earlier addition of two		Words:	1					
	•	riables (each in packed BCD format) Id produces a correct packed BCD		Cycles:	1				
	result.			Q Cycle Activity:					
Words:	1			Q1	Q2	Q3	Q4		
Cycles:	1			Decode	Read	Process	Write to		
Q Cycle Activity:					register 'f'	Data	destination		
Q1	Q2	Q3	Q4	Example:	DECF	CNT,			
Decode	Read	Process	Write	Before Instr		CINI,			
Example 1:	DAW	Data	W	CNT	= 0x01				
Before Instruc				Z	= 0				
W	= 0xA5			After Instruc CNT	= 0x00				
C DC	= 0 = 0			Z	= 1				
After Instructio W C	on = 0x05 = 1								
DC Example 2:	= 0								
Before Instruc W C DC	= 0xCE = 0 = 0								
After Instructio W C DC	on = 0x34 = 1 = 0								

Synta	FSZ	Decrement	f, Skip if 0				
- ,	ax:	[label] DE	ECFSZ f[,d[	,a]]			
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	d ∈ [0,1]				
Oper	ation:	(f) – 1 $\rightarrow$ de skip if result					
Statu	s Affected:	None					
Enco	ding:	0010	11da ffi	ff ffff			
Description: The contents of register 'f' are decremented. If 'd' is '0', the result placed in W. If 'd' is '1', the result placed back in register 'f' (default If the result is '0', the next instruct which is already fetched is discar and a NOP is executed instead, m it a two-cycle instruction. If 'a' is 'n Access Bank will be selected, overriding the BSR value. If 'a' = then the bank will be selected as the BSR value (default).				the result is ne result is (default). t instruction s discarded stead, making If 'a' is '0', the cted, . If 'a' = 1,			
Word	ls:	1	· · · ·				
Cycle			vcles if skip ar a 2-word instru				
QC	ycle Activity:	0.0	•••	<u>.</u>			
	Q1 Decode	Q2 Read	Q3 Process	Q4 Write to			
	Decoue	register 'f'	Data	destination			
lf sk	kip:	•					
	01						
	Q1	Q2	Q3	Q4			
	No	No	No	No			
16 - 1	No operation	No operation	No operation	1			
lf sk	No operation ip and followe	No operation d by 2-word in:	No operation struction:	No operation			
lf sk	No operation ip and followe Q1	No operation d by 2-word in: Q2	No operation struction: Q3	No operation Q4			
lf sk	No operation ip and followe Q1 No	No operation d by 2-word in: Q2 No	No operation struction: Q3 No	No operation Q4 No			
lf sk	No operation ip and followe Q1	No operation d by 2-word in: Q2	No operation struction: Q3	No operation Q4			
lf sk	No operation ip and followe Q1 No operation	No operation d by 2-word in: Q2 No operation	No operation struction: Q3 No operation	No operation Q4 No operation			
lf sk Exan	No operation ip and followe Q1 No operation No operation	No operation d by 2-word in: Q2 No operation No	No operation struction: Q3 No operation No	No operation Q4 No operation No			
Exan	No operation ip and followe Q1 No operation No operation	No operation d by 2-word in: Q2 No operation No operation HERE CONTINUE	No operation G3 No operation No operation DECFSZ GOTO	No operation Q4 No operation No operation			
Exan	No operation ip and followe Q1 No operation No operation mple: Before Instruct PC	No operation d by 2-word in: Q2 No operation No operation HERE CONTINUE continue con = Address on = CNT	No operation G3 No operation No operation DECFSZ GOTO	No operation Q4 No operation No operation			

DCFSNZ	Decremen	t f, Skip if n	ot 0				
Syntax:	[label] D	CFSNZ f[,	d [,a]]				
Operands:	0 ≤ f ≤ 255 d ∈ [0,1] a ∈ [0,1]	d ∈ [0,1]					
Operation:	(f) – 1 $\rightarrow$ de skip if resu						
Status Affected:	None						
Encoding:	0100	11da f	fff	ffff			
Description:	decrement placed in V placed bac If the result instruction discarded a instead, ma instruction. will be sele value. If 'a'	tts of registe ed. If 'd' is '0 J. If 'd' is '1', k in register t is not '0', th which is alre and a NOP is aking it a two If 'a' is '0', th cted, overric = 1, then th s per the BSI	', the r the re 'f' (def e next ady fe execu o-cycle ne Acc ling the e bank	result is sult is ault). tched is tted ress Bank e BSR s will be			
Words:	1						
Cycles:		ycles if skip a 2-word ins					
Q Cycle Activity:							
Q1	Q2	Q3		Q4			
Decode	Read	Process		Vrite to			
lf skip:	register 'f'	Data	des	stination			
Q1	Q2	Q3		Q4			
No	No	No		No			
operation	operation	operation	ор	eration			
If skip and followe	d by 2-word in	struction:					
Q1	Q2	Q3		Q4			
No operation	No operation	No operation	op	No eration			
No	No	No		No			
operation	operation	operation	ор	eration			
Example:	HERE ZERO NZERO	DCFSNZ TE : :	MP				
Before Instruc TEMP	=	?					
After Instruction TEMP If TEMP PC If TEMP PC	on = = = ≠ =	TEMP – ⁻ 0; Address 0; Address	(ZERO				

© 2006 Microchip Technology Inc.

GOTO	Unconditio	onal Bra	nch	
Syntax:	[label] G	iOTO k		
Operands:	$0 \le k \le 104$	8575		
Operation:	$k \rightarrow PC < 20$	):1>		
Status Affected:	None			
Encoding: 1st word (k<7:0>) 2nd word(k<19:8>)	1110 1111	1111 k ₁₉ kkk	k ₇ kkk kkkk	kkkk ₀ kkkk ₈
Description:		vithin enti 20-bit va	ire 2-Mb lue 'k' is	yte memory loaded into
Words:	2			
Cycles:	2			
Q Cycle Activity:				
Q1	Q2	Q	3	Q4
Decode	Read literal 'k'<7:0>	No operat	tion	Read literal 'k'<19:8>, Vrite to PC
No operation	No operation	No operat		No operation
<u>Example:</u> After Instructio PC =		RE HERE)		

_		Increment	1						
Synta	ax:	[label]	NCF f[	,d [,a]]					
Oper	rands:	$0 \le f \le 255$	$0 \le f \le 255$						
		d ∈ [0,1]							
		a ∈ [0,1]							
Oper	ration:	$(f) + 1 \rightarrow d$	est						
Statu	is Affected:	C, DC, N,	OV, Z						
Enco	oding:	0010	10da	fff	f	ffff			
		incremente placed in V placed bac is '0', the A overriding the bank w BSR value	V. If 'd' is ok in regis Access Ba the BSR v vill be sele	ʻ1', the sterʻf' ( ank wil value. ected a	e res (defa I be If 'a'	sult is ault). If 'a selected = 1, the			
Word	ds:	1							
		1 1							
Cycle		•							
Cycle	es:	•	Q			Q4			
Cycle	es: cycle Activity:	1 Q2 Read	Q	3		Vrite to			
Cycle	es: ycle Activity: Q1	1 Q2		3 ess					
Cycle Q C	es: ycle Activity: Q1 Decode	1 Q2 Read register 'f'	Proce Dat	3 ess		Vrite to			
Cycle	es: ycle Activity: Q1 Decode nple:	1 Q2 Read register 'f' INCF	Proce	3 ess		Vrite to			
Cycle Q C	es: ycle Activity: Q1 Decode nple: Before Instruc	1 Q2 Read register 'f' INCF	Proce Dat	3 ess		Vrite to			
Cycle Q C	es: ycle Activity: Q1 Decode nple: Before Instruc CNT Z	1 Q2 Read register 'f' INCF tion = 0xFF = 0	Proce Dat	3 ess		Vrite to			
Cycle Q C	es: ycle Activity: Q1 Decode nple: Before Instruc CNT Z C	1 Q2 Read register 'f' INCF tion = 0xFF = 0 = ?	Proce Dat	3 ess		Vrite to			
Cycle Q C <u>Exan</u>	es: ycle Activity: Q1 Decode nple: Before Instruc CNT Z C DC	1 Q2 Read register 'f' INCF tion = 0xFF = 0 = ? = ?	Proce Dat	3 ess		Vrite to			
Cycle Q C <u>Exan</u>	es: ycle Activity: Q1 Decode nple: Before Instruc CNT Z C	1 Q2 Read register 'f' INCF tion = 0xFF = 0 = ? = ?	Proce Dat	3 ess		Vrite to			
Cycle Q C <u>Exan</u>	es: ycle Activity: Q1 Decode nple: Before Instruct CNT Z C DC After Instruction	1 Q2 Read register 'f' INCF tion = 0xFF = 0 = ? = ? on	Proce Dat	3 ess		Vrite to			

	SZ	Increment	f, Skip if 0					
Synta	ax:	[label] IN	ICFSZ f[,d	[,a]]				
Oper	ands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	d ∈ [0,1]					
Oper	ation:	()	(f) + 1 $\rightarrow$ dest, skip if result = 0					
Statu	s Affected:	None						
Enco	ding:	0011	11da ff	ff ffff				
Desc	ription:	incremented placed in W placed back If the result which is alre and a NOP i it a two-cycl Access Ban overriding th	The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If the result is '0', the next instruction which is already fetched is discarded and a NOP is executed instead, making it a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the					
Word	le.	1	()					
Cycle	es:	1(2) <b>Note:</b> 3 cy	cles if skip ar 2-word instru					
QC	ycle Activity:	,						
	Q1	Q2	Q3	Q4				
	Decode	Read	Process	Write to				
lf als		register 'f'	Data	destination				
lf sk	ip: Q1	Q2	Q3	Q4				
I	No	No	No	No				
	operation	operation	operation	operation				
lfsk	ip and followe			oportation				
II OK	Q1	Q2	Q3	Q4				
l	No	No	No	No				
	operation	operation	operation	operation				
	No	No	No					
	110			No				
	operation	operation	operation	No operation				
<u>Exam</u>		operation HERE NZERO	operation					
		operation HERE NZERO ZERO	operation INCFSZ C :	operation				
	n <u>ple:</u> Before Instruc	operation HERE NZERO ZERO tion = Address	operation INCFSZ C : : s (HERE) 1	operation				

INFSNZ		Increment	f, Skip i	f not 0			
Syntax:		[label]	NFSNZ	f [,d [,	a]]		
Operands:		$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$					
Operation:		. ,	(f) + 1 $\rightarrow$ dest, skip if result $\neq 0$				
Status Affected	:	None					
Encoding:		0100	10da	fff	f ffff		
Description: The contents of register 'f' are incremented. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed back in register 'f' (default). If the result is not '0', the next instruction which is already fetched is discarded and a NOP is executed instead, making it a two-cycle instruction. If 'a' is '0', the Access Ban will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (defau					e result is e result is (default). next y fetched is ecuted ycle Access Bank y the BSR ank will be		
Words:		1					
Cycles:			cycles if s a 2-word		d followed ction.		
Q Cycle Activi	ty:						
Q1		Q2	Q	3	Q4		
Decode	)	Read register 'f'	Proce Dat		Write to destination		
If skip:		_					
Q1		Q2	Q	1	Q4		
No operatio		No operation	No opera	tion	No operation		
If skip and foll	owed	-					
Q1		Q2	Q	-	Q4		
No operatio	n	No operation	No opera		No operation		
No		No	No		No		
operatio	n	operation	opera		operation		
Example:		HERE ZERO NZERO	INFSNZ	REG			
Before Ins PC After Instr		= Addres	S (HER	E)			
REG If RE PC		= REG + ≠ 0; = Addres		RO)			
lf RE PC	G	= 0;	S (ZER				

© 2006 Microchip Technology Inc.

IORLW		Inclusive	OR Litera	al with W				
Syntax:		[label]	ORLW k	ζ				
Operand	s:	$0 \le k \le 25$	$0 \le k \le 255$					
Operatio	n:	(W) .OR. k	$x \rightarrow W$					
Status Af	ffected:	N, Z						
Encoding	g:	0000	1001	kkkk	kkkk			
Descripti	on:	The conter eight-bit lit W.						
Words:		1						
Cycles:		1						
Q Cycle	e Activity:	:						
	Q1	Q2	Q	3	Q4			
	Decode	Read literal 'k'	Proce Dat		rite to W			
Example	<u>:</u>	IORLW	0x35					
	Before Instructi W After Instruction							
Alle	W	= 0xBF						

IORWF	Inclusive O	R W with	n f			
Syntax:	[label] IC	RWF f	[,d [,a]]			
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	d ∈ [0,1]				
Operation:	eration: (W) .OR. (f) $\rightarrow$ dest					
Status Affected:	N, Z					
Encoding:	0001	00da	ffff	ffff		
	'0', the result is placed in W. If 'd' is the result is placed back in register (default). If 'a' is '0', the Access Ban will be selected, overriding the BSF value. If 'a' = 1, then the bank will b selected as per the BSR value (default)					
Words:	1					
Cycles:	1					
Q Cycle Activity:						
Q1	Q2	Q3		Q4		
Decode	Read register 'f'	Proces Data		Vrite to stination		
Example: IORWF RESULT, W Before Instruction RESULT = 0x13 W = 0x91						

0x13 0x93

After Instruction RESULT = W = 

LFSF	2	Load FSR					MOVF	Move f			
Synta	ax:	[label] Ll	FSR f,k			I	Syntax:	[label] M	OVF f[,d[,a	a]]	
Oper	ands:	$0 \le f \le 2$ $0 \le k \le 409$	5				Operands:	$\begin{array}{l} 0 \leq f \leq 255 \\ d \in \ [0,1] \end{array}$			
Oper	ation:	$k\toFSRf$						a ∈ [0,1]			
Statu	s Affected:	None					Operation:	$f \rightarrow \text{dest}$			
Enco	ding:	1110 1111			k ₁₁ kkk kkkk		Status Affected: Encoding:	N, Z	00da ff	ff	ffff
Desc	scription: The 12-bit literal 'k' is loaded into the file select register pointed to by 'f'.				Description:	a destinatio	s of register " n dependent	upon th	e		
Word	s:	2							. If 'd' is '0', th . If 'd' is '1', th		
Cycle	es:	2						•	. in register 'f'		
QC	cle Activity:								can be anywh		
	Q1	Q2	Q3	(	Q4				nk. If 'a' is '0' selected, ov	-	
	Decode	Read literal 'k' MSB	Process Data	liter MS	rite al 'k' B to RfH			BSR value.	If 'a' = 1, then as per the B	n the ba	ank will
	Decode	Read literal	Process	-	literal		Words:	1			
	Debbac	'k' LSB	Data		FSRfL		Cycles:	1			
							Q Cycle Activity:				
Exam	nple:	LFSR 2,	0x3AB				Q1	Q2	Q3	(	<b>Q</b> 4
	After Instructi FSR2H FSR2L	= 0x	:03 :AB				Decode	Read register 'f'	Process Data	Wri	te W
							Example:	MOVF R	EG, W		

Before Instruction REG W	=	0x22 0xFF
After Instruction		
REG W	= =	0x22 0x22

моу	FF	Move f to f	1			
Synta	ax:	[label] N	10VFF	f _s ,f _d		
Oper	ands:	$0 \le f_s \le 409$ $0 \le f_d \le 409$				
Oper	ation:	$(f_s) \to f_d$				
Statu	s Affected:	None				
	ding: ord (source) vord (destin.)	1100 1111	ffff ffff	fff fff		ffff _s ffff _d
Desc	ription:	The contents of source register ' $f_s$ ' are moved to destination register ' $f_d$ '. Location of source ' $f_s$ ' can be anywhere in the 4096-byte data space (000h to FFFh) and location of destination ' $f_d$ ' can also be anywhere from 000h to FFFh.				
		Either source or destination can be W (a useful special situation). MOVFF is particularly useful for transferring a data memory location to a peripheral register (such as the transmit buffer or an I/O port).				
		The MOVFF PCL, TOSU destination	J, TOSH			
		The MOVFF instruction should not be used to modify interrupt settings while any interrupt is enabled (see page 77).				
Word	ls:	2				
Cycle	es:	2 (3)				
QC	ycle Activity:					
	Q1	Q2	Q	3		Q4
	Decode	Read register 'f'	Proce Dat		ор	No eration

	register 'f' (src)	Data	operation
Decode	No operation No dummy read	No operation	Write register 'f' (dest)

Example:	MOVFF	REG1,	REG2	

Before Instruction		
REG1	=	0x33
REG2	=	0x11
After Instruction		
REG1	=	0x33
REG2	=	0x33

MOV	LB	Move Lite	ral to Lov	וממואו א	e in BSR			
Synta	IX:	[label]	NOVLB	k				
Opera	ands:	$0 \le k \le 255$	5					
Opera	ation:	$k \to BSR$						
Statu	s Affected:	None						
Enco	ding:	0000	0001	kkkł	k kkkk			
Desc	ription:	tion: The 8-bit literal 'k' is loaded into the Bank Select Register (BSR).						
Word	s:	1						
Cycles:		1	1					
QC	cle Activity:							
_	Q1	Q2	Q3	}	Q4			
	Decode	Read literal 'k'	Proce Data		Write literal 'k' to BSR			
Example: MOVLB 5 Before Instruction BSR register = 0x02 After Instruction BSR register = 0x05								

моу	'LW	Move Lite	Move Literal to W			
Synta	ax:	[ label ]	MOVLW	k		
Oper	ands:	$0 \le k \le 25$	5			
Oper	ation:	$k\toW$				
Statu	is Affected:	None				
Enco	oding:	0000	1110	kkk	k	kkkk
Desc	ription:	The eight-	bit literal '	k' is lo	ade	d into W.
Word	ls:	1				
Cycle	es:	1				
QC	ycle Activity:					
	Q1	Q2	Q	3		Q4
	Decode	Read literal 'k'		Process Data		ite to W
Exan	nple:	MOVLW	0x5A			
	After Instructio W	on = 0x5A				

Syntax:	[label] M	IOVWF	f [,a]	
Operands:	0 ≤ f ≤ 255 a ∈ [0,1]		. [,]	
Operation:	$(W) \to f$			
Status Affected:	None			
Encoding:	0110	111a	ffff	ffff
	Location 'f' can be anywhere in the 256-byte bank. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default).			
Words:	1			
- ·	1			
Cycles:				
Cycles: Q Cycle Activity:				
	Q2	Q3	}	Q4
Q Cycle Activity:	Q2 Read register 'f'	Q3 Proce Data	SS	Q4 Write egister 'f'

Bololo modia	011011	
W	=	0x4F
REG	=	0xFF
After Instruct	ion	
W	=	0x4F
REG	=	0x4F

 $[\]ensuremath{\textcircled{}^{\odot}}$  2006 Microchip Technology Inc.

MULLW	Multiply Literal v	with W	MULWF	Multiply W	with f	
Syntax:	[label] MULLW	/ k	Syntax:	[label] M	ULWF f[,a]	]
Operands:	$0 \leq k \leq 255$		Operands:	$0 \leq f \leq 255$		
Operation:	(W) x k $\rightarrow$ PROD	H:PRODL		a ∈ [0,1]		
Status Affected:	None		Operation:	(W) x (f) $\rightarrow$	PRODH:PRO	DL
Encoding:	0000 1101	l kkkk kkkk	Status Affected:	None		
Description:	An unsigned mult	iplication is carried out	Encoding:	0000	001a fff	f ffff
	literal 'k'. The 16- the PRODH:PRO PRODH contains unchanged. None of the statu Note that neither	the high byte. W is s flags are affected. Overflow nor Carry is peration. A Zero result	Description:	between the register file is stored in register pair byte. Both W and None of the Note that ne	e contents of N location 'f'. Th the PRODH:F r. PRODH con I 'f' are unchar status flags a either Overflow	e 16-bit result PRODL ntains the high nged. are affected. w nor Carry is
Words:	1			•	•	A Zero result
Cycles:	1			•	Bank will be s	ed. If 'a' is '0', selected.
Q Cycle Activity:				overriding th	he BSR value.	. If 'a'= 1, then
Q1	Q2	Q3 Q4		the bank wi BSR value	Il be selected	as per the
Decode		ocess Write	Words:	1	(deladit).	
	literal 'k' D	eata registers PRODH:	Cycles:	1		
		PRODL	Q Cycle Activity:	I		
			Q Cycle Activity.	Q2	Q3	Q4
Example:	MULLW 0xC4		Decode	Read	Process	Write
Before Instruc W PRODH PRODL	tion = 0xE2 = ? = ?			register 'f'	Data	registers PRODH: PRODL
After Instructi W PRODH PRODL	-		Example: Before Instruc W REG PRODH PRODL	ction = 0x = 0x	REG C4 B5	

After Instruction

W REG PRODH PRODL 0xC4 0xB5 0x8A 0x94

= = =

© 2006 Microchip Technology Inc.

NEGF	Negate f				
Syntax:	[label] NEGF f[,a]				
Operands:	0 ≤ f ≤ 255 a ∈ [0,1]				
Operation:	$(\overline{f}) + 1 \rightarrow f$				
Status Affected:	N, OV, C, DC, Z				
Encoding:	0110 110a ffff ffff				
Description:	Location 'f' is negated using two's complement. The result is placed in the data memory location 'f'. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value.				
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2 Q3 Q4				
Decode	ReadProcessWriteregister 'f'Dataregister 'f'				
Example: NEGF REG, 1					
Before Instruc REG After Instructio REG	= 0011 1010 [ <b>0x3A</b> ]				

NOP		No Operation				
Synta	ax:	[ label ]	NOP			
Oper	ands:	None				
Oper	ation:	No operati	on			
Status Affected: None						
Enco	ding:	0000	0000	000	0	0000
	1111 XXXX XXXX XXXX					XXXX
Desc	ription:	No operati	on.			
Word	ls:	1				
Cycle	es:	1				
QC	ycle Activity:					
	Q1	Q2	Q	3		Q4
	Decode	No	No			No
		operation	operat	tion	ор	eration

Example:

None.

 $[\]ensuremath{\textcircled{}^{\odot}}$  2006 Microchip Technology Inc.

POP Pop Top of Return Stack								
Synta	ax:	[label] P	[label] POP					
Oper	ands:	None	None					
Oper	ation:	(TOS) $\rightarrow$ bi	t bucket					
Statu	s Affected:	None						
Enco	ding:	0000	0000	000	0	0110		
Desc	ription:	stack and is then becom was pushed This instruc the user to	The TOS value is pulled off the return stack and is discarded. The TOS value then becomes the previous value that was pushed onto the return stack. This instruction is provided to enable the user to properly manage the return stack to incorporate a software stack.					
Word	ls:	1						
Cycle	es:	1						
QC	ycle Activity:							
	Q1	Q2	Q	3		Q4		
	Decode	No operation	POP T valu		ор	No eration		
Example:		POP GOTO	NEW					
Before Instruction TOS Stack (1 level down)				0x003 0x014				
	After Instructio TOS PC	on		0x014 NEW	332			

PUS	н	Push Top o	of Retur	n Stack		
Synt	ax:	[label] Pl	JSH			
Oper	rands:	None				
Oper	ration:	$(PC + 2) \rightarrow$	TOS			
Statu	is Affected:	None				
Enco	oding:	0000	0000	0000	0101	
Desc	pription:	the return st value is pus This instruct implement a modifying To	The PC + 2 is pushed onto the top of the return stack. The previous TOS value is pushed down on the stack. This instruction allows the user to implement a software stack by modifying TOS and then pushing it onto the return stack.			
Word	ds:	1				
Cycl	es:	1				
QC	ycle Activity:					
	Q1	Q2	Q	3	Q4	
	Decode	PUSH PC + 2 onto return stack	No opera		No operation	
<u>Exar</u>	nple: Before Instri	PUSH				
	TOS PC			0x00345 0x00012		
	After Instruc PC TOS Stack (	tion 1 level down)	=	0x00012 0x00012 0x00345	6	

RCA	LL	Relative Ca	Relative Call			
Synta	ax:	[label] RC	CALL n			
Oper	ands:	-1024 ≤ n ≤	1023			
Oper	ation:	(PC) + 2 → (PC) + 2 + 2	,	)		
Statu	is Affected:	None				
Enco	oding:	1101	1nnn	nnnr	n nnnn	
Desc	rription:	from the cu address (P stack. Ther number '2n have increr instruction, PC + 2 + 2	Subroutine call with a jump up to 1K from the current location. First, return address (PC + 2) is pushed onto the stack. Then, add the 2's complement number '2n' to the PC. Since the PC will have incremented to fetch the next instruction, the new address will be PC + 2 + 2n. This instruction is a two-cycle instruction.			
		•				
Cycle	es: ycle Activity:	2				
	Q1	Q2	C	23	Q4	
	Decode	Read literal 'n Push PC to stack		cess ata	Write to PC	
	No operation	No operation	N oper	-	No operation	

RES	ET	Reset		
Synta	ax:	[label] R	ESET	
Oper	ands:	None		
Oper	ation:		gisters and fla a MCLR Rese	0
Statu	s Affected:	All		
Enco	ding:	0000	0000 111	L1 1111
Desc	ription:		tion provides a MCLR Reset in	
Word	ls:	1		
Cycle	es:	1		
QC	ycle Activity:			
	Q1	Q2	Q3	Q4
	Decode	Start	No	No
		Reset	operation	operation

Example:

RESET After Instruction

Aller Instruction	
Registers =	Reset Value
Flags* =	Reset Value

Example:

HERE RCALL Jump

**Before Instruction** 

PC = Address (HERE)

After Instruction

PC = TOS = Address (Jump) Address (HERE + 2)

RETI	FIE	Return fro	m Interru	upt		
Synta	ax:	[ <i>label</i> ] F	RETFIE	[s]		
Oper	ands:	$s\in  [0,1]$				
Oper	ation:	$\begin{array}{l} 1 \rightarrow \text{GIE/G} \\ \text{if } \text{s} = 1 \\ (\text{WS}) \rightarrow \text{W} \\ (\text{STATUSS} \\ (\text{BSRS}) \rightarrow \end{array}$	$\begin{array}{l} (\text{TOS}) \rightarrow \text{PC}, \\ 1 \rightarrow \text{GIE/GIEH or PEIE/GIEL}, \\ \text{if } s = 1 \\ (\text{WS}) \rightarrow \text{W}, \\ (\text{STATUSS}) \rightarrow \text{Status}, \\ (\text{BSRS}) \rightarrow \text{BSR}, \\ \text{PCLATU, PCLATH are unchanged}. \end{array}$			
Statu	s Affected:	GIE/GIEH,	PEIE/GI	EL.		
Enco	ding:	0000	0000	0001	000s	
Desc	ription:	and Top-of- the PC. Int setting eith global inter contents of STATUSS their corres	Return from interrupt. Stack is popped and Top-of-Stack (TOS) is loaded into the PC. Interrupts are enabled by setting either the high or low priority global interrupt enable bit. If 's' = 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers W, Status and BSR. If 's' = 0, no update of these			
Word	ls:	1				
Cycle	es:	2				
QC	ycle Activity:					
	Q1	Q2	Q3		Q4	
	Decode	No operation	No operatio	on Set	PC from stack GIEH or GIEL	
	No	No	No		No	
	operation	operation	operatio	on op	eration	
<u>Exan</u>	After Interrupt	RETFIE 1	-	IOS		
	W BSR Status	PC = TOS W = WS BSR = BSRS			i	

RET	LW	Return Lit	eral to W	,	
Synta	ax:	[ <i>label</i> ] F	RETLW	k	
Oper	ands:	$0 \le k \le 255$	5		
Oper	ation:	k  ightarrow W, (TOS) $ ightarrow F$ PCLATU, F		are unchar	nged
Statu	Status Affected: None				
Enco	ding:	0000	1100	kkkk	kkkk
Desc	ription:	W is loaded with the eight-bit literal 'k'. The program counter is loaded from the top of the stack (the return address). The high address latch (PCLATH) remains unchanged.			
Word	ls:	1			
Cycle	es:	2			
QC	ycle Activity:				
	Q1	Q2	Q3		Q4
	Decode	Read literal 'k'	Proces Data	fron	op PC n stack, te to W
	No	No	No		No
	operation	operation	operation	on op	eration
<u>Exan</u>	CALL TABLE	E ; W conta ; offset ; W now H ; table v	value nas	ble	

: TABLE

ABI	LE					
	ADDWF	PCL	;	W =	off	Eset
	RETLW	k0	;	Begi	in t	able
	RETLW	k1	;			
	:					
	:					
	RETLW	kn	;	End	of	table
	Before	Instruct	ior	n		
	W		=	0x	07	

vv	-	0.01
After Instruct	tion	
W	=	value of kn

RET	JRN	Return from	m Subro	utine		
Synta	ax:	[label] R	ETURN	[s]		
Oper	ands:	$s \in [0,1]$				
Oper	ation:	$\begin{array}{l} (\text{TOS}) \rightarrow \text{PC},\\ \text{if } s = 1\\ (\text{WS}) \rightarrow \text{W},\\ (\text{STATUSS}) \rightarrow \text{Status},\\ (\text{BSRS}) \rightarrow \text{BSR},\\ \text{PCLATU, PCLATH are unchanged} \end{array}$				
Statu	s Affected:	None				
Enco	ding:	0000	0000	000	)1	001s
	ription:	popped and the top of the stack (TOS) is loaded into the program counter. If 's'= 1, the contents of the shadow registers WS, STATUSS and BSRS are loaded into their corresponding registers W, Status and BSR. If 's' = 0, no update of these registers occurs (default).				
Word	ls:	1				
Cycle	es:	2				
QC	ycle Activity:					
	Q1	Q2	Q3			Q4
	Decode	No operation	Proce Data			op PC m stack
	No	No	No			No
	operation	operation	operat	ion	ор	eration
<u>Exan</u>	nple: After Interrupt PC = TC	return DS				

RLCF	Rotate Left f through Carry
Syntax:	[ <i>label</i> ] RLCF f [,d [,a]]
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$
Operation:	$(f < n >) \rightarrow dest < n + 1 >,$ $(f < 7 >) \rightarrow C,$ $(C) \rightarrow dest < 0 >$
Status Affected:	C, N, Z
Encoding:	0011 01da ffff ffff
Description: Words:	The contents of register 'f' are rotated one bit to the left through the Carry flag. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' = 1, then the bank will be selected as per the BSR value (default). C register f
Cycles:	1
Q Cycle Activity: Q1	Q2 Q3 Q4
Decode	ReadProcessWrite toregister 'f'Datadestination
Example:	RLCF REG, W
Before Instruct REG C After Instruction REG W C	ction = 1110 0110 = 0

^{© 2006} Microchip Technology Inc.

RLNCF	Rotate Lef	Rotate Left f (no carry)					
Syntax:	[ label ]	RLNCF	f [,d [,a]	]			
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$						
Operation:	(f <n>)  o d (f&lt;7&gt;)  o d</n>		>,				
Status Affected:	N, Z	N, Z					
Encoding:	0100	01da	ffff	ffff			
Description:	The contents of register 'f' are rotated one bit to the left. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).						
		regi	ister f				
Words:	1						
Cycles:	1						
Q Cycle Activity:							
Q1	Q2	Q3	3	Q4			
Decode	Read register 'f'	Proce Data		Write to estination			
Example: RLNCF REG							
Before Instruction REG = 1010 1011 After Instruction							
REG	= 0101	0111					

RRCF	Rotate Rig	ht f thro	ugh Carr	у	
Syntax:	[label] R	RCF f	[,d [,a]]		
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$	d ∈ [0,1]			
Operation:	$(f<0>) \rightarrow C$	$\begin{array}{l} (f{<}n{>}) \rightarrow dest{<}n-1{>}, \\ (f{<}0{>}) \rightarrow C, \\ (C) \rightarrow dest{<}7{>} \end{array}$			
Status Affected:	C, N, Z				
Encoding:	0011 00da ff			ffff	
	flag. If 'd' is '0', the result is placed in W If 'd' is '1', the result is placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).				
		rog	istor f	7	
		reg	ster f		
Words:		reg	ster f	]_•	
Words: Cycles:		reg	ister f	<u>]</u> -•	
	1	► reg	ister f	]-•	
Cycles:	1	reg		 Q4	
Cycles: Q Cycle Activity:	1		ss V	Q4 Vrite to stination	
Cycles: Q Cycle Activity: Q1	1 1 Q2 Read register 'f'	Q3 Proce	ss V	Vrite to	
Cycles: Q Cycle Activity: Q1 Decode	1 1 Q2 Read register 'f' RRCF F	Q3 Proce Data	ss V	Vrite to	
Cycles: Q Cycle Activity: Q1 Decode Example: Before Instruc REG	1 1 Q2 Read register 'f' RRCF H tion = 1110 (	Q3 Proce Data REG, W	ss V	Vrite to	
Cycles: Q Cycle Activity: Q1 Decode Example: Before Instruc	1 1 2 Read register 'f' RRCF F tion = 1110 ( = 0	Q3 Proce Data REG, W	ss V	Vrite to	

DDNOF		0575	0-14			
RRNCF	Rotate Right f (no carry)	SETF	Set f			
Syntax:	[label] RRNCF f[,d[,a]]	Syntax:	[ label ] SET	if t[,a]		
Operands:	0 ≤ f ≤ 255 d ∈ [0,1]	Operands:	0 ≤ f ≤ 255 a ∈ [0,1]			
	a ∈ [0,1]	Quanting				
Operation:	$(f) \rightarrow dest,$	Operation:	$FFh \rightarrow f$			
oporanom	$(f<0>) \rightarrow dest<7>$	Status Affected:	None			
Status Affected:	N, Z	Encoding:	0110	100a ff:		
Encoding:	0100 00da ffff ffff	Description:		ts of the speci Fh. If 'a' is '0',		
Description:	The contents of register 'f' are rotated			e selected, ove		
	one bit to the right. If 'd' is '0', the result				en the bank will	
	is placed in W. If 'd' is '1', the result is		be selected as per the BSR value			
	placed back in register 'f' (default). If 'a' is '0', the Access Bank will be selected,		(default).			
	overriding the BSR value. If 'a' is '1',	Words:	1			
	then the bank will be selected as per	Cycles:	1			
	the BSR value (default).	Q Cycle Activity:	_	_	_	
	register f	Q1	Q2	Q3	Q4	
Words:	1	Decode	Read register 'f'	Process Data	Write register 'f'	
Cycles:	1		regiotor r	Dulu	regiotor r	
•	1	Example:	SETF H	REG		
Q Cycle Activity: Q1	Q2 Q3 Q4	Before Instruc	ction			
Decode	Read Process Write to	REG	= 0x	5A		
200040	register 'f' Data destination	After Instruction				
		REG	= 0x	FF		
Example 1:	RRNCF REG, 1, 0					
Before Instruc	tion					
REG	= 1101 0111					
After Instructio REG	on = 1110 1011					
Example 2:	RRNCF REG, W					
Before Instruc						
W	= ?					
REG	= 1101 0111					
After Instructio	on = 1110 1011					
REG	= 1101 0111					

SLE	EP	Enter Slee	ep Mode			SUBFWB	Subtract	f from W with	h Borrow
Synta	ax:	[ label ]	SLEEP			Syntax:	[ label ]	SUBFWB f	[,d [,a]]
Oper	rands:	None				Operands:	$0 \le f \le 25$	5	
Oper	ration:	$00h \rightarrow WI$					d ∈ [0,1] a ∈ [0,1]		
		$\begin{array}{c} 0 \rightarrow \underline{WDT} \\ 1 \rightarrow \overline{TO}, \end{array}$	postscaler,			Operation:		$-(\overline{C}) \rightarrow dest$	
		$1 \rightarrow \frac{10}{PD}$ , $0 \rightarrow PD$				•			
Statu	is Affected:	TO, PD				Status Affected:	N, OV, C,	г т <u>г</u>	
	oding:	0000	0000 00	00 0011	1	Encoding:	0101 Subtract		fff ffff
	cription:		r-Down status		1	Description:		register 'f' and from W (2's co	
		cleared. T	he Time-out s	tatus bit (TO)			method).	If 'd' is '0', the	result is stored
			tchdog Timer a rare cleared.	and its				' is '1', the res ' (default). If 'a	ult is stored in
		•	ssor is put inte	o Sleep mode				ank will be se	
			scillator stoppe					g the BSR valu	
Word	ds:	1						bank will be se value (default)	•
Cycle	es:	1				Words:	1		-
QC	ycle Activity:					Cycles:	1		
	Q1	Q2	Q3	Q4	ו	Q Cycle Activity:			
	Decode	No operation	Process Data	Go to Sleep		Q Oycle Activity. Q1	Q2	Q3	Q4
	<u></u>	operation	Dula	Сюбр	J	Decode	Read	Process	Write to
Exan	nple:	SLEEP					register 'f'	Data	destination
	Before Instruc	tion				Example 1:	SUBFWB	REG	
	$\overline{TO} =$	?				Before Instruc			
	PD = After Instruction	? חר				REG W	= 0x03 = 0x02		
	TO =	1†				С	= 0x01		
	PD =	0				After Instructio REG	on = 0xFF		
† If	WDT causes	wake-up, this I	bit is cleared.			W C	= 0x02 = 0x00		
						Z	= 0x00		
						N	= 0x01	; result is neg	-
						Example 2:	SUBFWB	REG, 0,	0
						Before Instruc REG	tion = 2		
						W	= 5		
						C After Instructio	= 1 on		
						REG	= 2		
						W C	= 3 = 1		
						Z N	= 0 = 0	; result is pos	itive
						Example 3:	SUBFWB	REG, 1,	
						Before Instruc		, -,	
						REG	= 1		
						W C	= 2 = 0		
						After Instructio			
						REG W	= 0 = 2		
						C Z	= 1 = 1	; result is zer	0
						N	= 0	, 100011 10 201	-

SUBLW	Subtract W fr	om Literal		SUBWF	Subtract	W from f	
Syntax:	[label] SUB	LW k		Syntax:	[label]	SUBWF f[,o	d [,a]]
Operands:	$0 \le k \le 255$			Operands:	0 ≤ f ≤ 255	5	
Operation:	$k-(W)\toW$				d ∈ [0,1]		
Status Affected:	N, OV, C, DC,	Z			a ∈ [0,1]		
Encoding:	0000 10		k kkkk	Operation:	(f) – (W) –		
Description:	W is subtracte	d from the	eight-bit	Status Affected:	N, OV, C,		
·	literal 'k'. The r			Encoding:	0101		ff ffff
Words:	1			Description:		N from registe ent method). I	
Cycles:	1					tored in W. If	
Q Cycle Activity:						tored back in	•
Q1	Q2	Q3	Q4			ected, overrid	Access Bank
Decode			Write to W				ne bank will be
	literal 'k'	Data				as per the BSI	R value
Example 1:	SUBLW 0x02	2			(default).		
Before Instruc				Words:	1		
W C	= 1 = ?			Cycles:	1		
After Instructi	on			Q Cycle Activity:			• ·
W C	= 1 = 1 ; result	is positive		Q1	Q2	Q3	Q4
Z	= 0			Decode	Read register 'f'	Process Data	Write to destination
N	= 0			Example 1:	•	1	
Example 2:	SUBLW 0x02	2			SUBWF R	EG	
Before Instruc W				Before Instruc REG	= 3		
č	= 2 = ?			W C	= 2 = ?		
After Instructi				After Instruction	-		
W C	= 0 = 1 ; result	is zero		REG W	= 1 = 2		
Z N	= 1 = 0			С	= 1	; result is po	sitive
Example 3:	SUBLW 0x02	>		Z	= 0 = 0		
Before Instruc		-		Example 2:	SUBWF R	EG W	
W	= 3			Before Instruc			
С	= ?			REG	= 2 = 2		
After Instructi W		omplement	)	W C	= 2 = ?		
C Z	= 0 ; result	is negative	,	After Instruction	on		
Z N	= 0 = 1			REG W	= 2 = 0		
				С	= 1	; result is zei	0
				Ž N	= 1 = 0		
				Example 3:	SUBWF R	EG	
				Before Instruc			
				REG	= 0x01		
				W C	= 0x02 = ?		
				After Instruction		(0)	
				REG W	= 0xFFh = 0x02	;(2's comple	ment)
				C Z	= 0x00	; result is neg	gative
				/	= 0x00		

SUBWFB	Subtract W	/ from f with	Borrow	
Syntax:	[label] S	UBWFB f[,	d [,a]]	
Operands:	$0 \le f \le 255$ $d \in [0,1]$ $a \in [0,1]$			
Operation:	(f) - (W) - (	$\overline{C}) \rightarrow dest$		
Status Affected:	N, OV, C, D	0C, Z		
Encoding:	0101	10da ff	ff ffff	
Description:	Subtract W and the Carry flag (borrow) from register 'f' (2's complement method). If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).			
Words:	1			
Cycles:	1			
Q Cycle Activity:				
Q1	Q2	Q3	Q4	
Decode	Read register 'f'	Process Data	Write to destination	
Example 1:	SUBWFB	REG, 1, 0		
Before Instruc				
REG W C	= 0x19 = 0x0D = 0x01	(0001 10 (0000 11	001) .01)	
After Instructic REG W C Z	= 0x0C = 0x0D = 0x01 = 0x00	(0000 10 (0000 11	.01)	
N	= 0x00	; result is p	ositive	
Example 2: Before Instruc	SUBWFB	REG, 0, 0		
REG W C After Instructio	= 0x1B = 0x1A = 0x00		11) 10)	
REG W C	= 0x1B = 0x00 = 0x01	(0001 10	11)	
ZN	= 0x01 = 0x00	; result is z	ero	
Example 3:	SUBWFB	REG, 1, 0		
Before Instruc REG ^W C After Instructic	= 0x03 = 0x0E = 0x01		11) 01)	
		(	\	
REG w	= 0xF5 = 0x0E	(1111 01 ; [2's comp (0000 11	<b>)</b>	

SWA	PF	Swap f			
Synta	ax:	[ label ]	SWAPF	f [,d [,a]]	
Oper	ands:	0 ≤ f ≤ 255 d ∈ [0,1] a ∈ [0,1]			
Oper	ation:	$(f<3:0>) \rightarrow dest<7:4>,$ $(f<7:4>) \rightarrow dest<3:0>$			
Status Affected: None					
Enco	ding:	0011	10da	ffff	ffff
		The upper and lower nibbles of register 'f' are exchanged. If 'd' is '0', the result is placed in W. If 'd' is '1', the result is placed in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).			
Word	ls:	1			
Cycle	es:	1			
QC	ycle Activity:				
	Q1	Q2	Q	3	Q4
	Decode	Read register 'f'	Proce Dat		Vrite to stination
<u>Exan</u>	nple:	SWAPF	REG		

Before Instru					
REG	=	0x53			
After Instruction					
REG	=	0x35			

TBL	RD	Table Read					
Synt	ax:	[ label ]	TBL	.RD ( *	; *+; *	-; +*)	
Ope	rands:	None					
Ope	ration:	if TBLRD *, (Prog Mem (TBLPTR)) → TABLAT; TBLPTR – No Change; if TBLRD *+, (Prog Mem (TBLPTR)) → TABLAT; (TBLPTR) + 1 → TBLPTR; if TBLRD *-, (Prog Mem (TBLPTR)) → TABLAT; (TBLPTR) - 1 → TBLPTR; if TBLRD +*, (TBLPTR) + 1 → TBLPTR; (Prog Mem (TBLPTR)) → TABLAT					
Statu	s Affected:	None					
Enco	oding:	0000	0	000	00	00	10nn nn=0 * =1 *+ =2 *- =3 +*
Desc	cription:	This instruct of Program Me Pointer (TBL The TBLPTF byte in the p 2-Mbyte add TBLPT TBLPT TBLPT TBLPTR a no chang post-incre post-decre	Mem mor PTF (a. rogr lress R[0] R[0] R[0] R[0] mer eme eme	hory (F y, a por R) is us 21-bit am me s range = 0: = 1: uction blows: nt	2.M.). inter of sed. pointe emory e. Leas Byte Merr Mos of Pr Word	To add called r) poin . TBLI of Pro of Pro nory W t Signi rogran	dress the Table nts to each PTR has a nificant ogram Vord fificant Byte n Memory
Word	ds:	1					
Cycl	es:	2					
•	ycle Activity	<i>r</i> :					
	Q1	Q2		Q	3		Q4
	Decode	No		N			No
	No	operation No operatio		opera No			eration operation
	operation	(Read Progra Memory)		opera		(	Write ABLAT)
<u>Exar</u>	nple 1:	TBLRD	*+	;			
Before Instruction TABLAT TBLPTR MEMORY(0x00A356) After Instruction TABLAT TBLPTR		56)	= = =	0x34	)A356 1		
Exar	<u>nple 2:</u>	TBLRD	+*	;			
	MEMC After Instru	AT FR DRY(0x01A35 DRY(0x01A35 ction		= = =	0x12 0x34	1A357 2 1	7
	TABLA TBLP			=	0x34 0x0	1 1 A 358	3

© 2006 Microchip Technology Inc.

TBLWT	Table Write					
Syntax:	[ label ]	TBLWT (	*; *+; *-; +*)			
Operands:	None	None				
Operation:	if TBLWT*, (TABLAT) $\rightarrow$ Holding Register; TBLPTR – No Change; if TBLWT*+, (TABLAT) $\rightarrow$ Holding Register; (TBLPTR) + 1 $\rightarrow$ TBLPTR; if TBLWT*-, (TABLAT) $\rightarrow$ Holding Register; (TBLPTR) – 1 $\rightarrow$ TBLPTR; if TBLWT+*, (TBLPTR) + 1 $\rightarrow$ TBLPTR; (TABLAT) $\rightarrow$ Holding Register;					
Status Affected	None					
Encoding:	0000	0000	0000	11nn nn=0 * =1 *+ =2 *- =3 +*		
Description:	This instructic determine wh TABLAT is wr used to progr Memory (P.M <b>Program Me</b> The TBLPTR byte in the pro 2-Mbyte addr TBLPTR sele memory locat TBLPTF TBLPTF TBLPTF	hich of the sitten to. The am the control of the sitten to. The am the control of the second state of the	8 holding re the holding re ntents of Pro o Section 6 additional d pointer) poin mory. TBLP . The LSb o byte of the p ess. Least Signi of Program Word Most Signif of Program Word	gisters the ogram <b>5.0 "Flash</b> letails.) tts to each TR has a f the brogram ficant Byte Memory icant Byte Memory		

- post-increment post-decrement
- pre-increment

#### **TBLWT Table Write (Continued)**

Word	s: 1

Cycles: 2

Q Cycle Activity:

Q1	Q2	Q3	Q4
Decode	No operation	No operation	No operation
	operation	operation	operation
	No operation		No operation
operation	(Read	operation	(Write to Holding
	TABLAT)		Register)

Example 1: TBLWT *+;

Before Instruction TABLAT	=	0x55		
TBLPTR HOLDING REGISTER	=	0x00A356		
(0x00A356)	=	0xFF		
After Instructions (table write	comp	completion)		
TABLAT	=	0x55		
TBLPTR	=	0x00A357		
HOLDING REGISTER (0x00A356)	=	0x55		
Example 2: TBLWT +	*;			
Before Instruction				
TABLAT	=	0x34		
TBLPTR	=	0x34 0x01389A		
TBLPTR HOLDING REGISTER (0x01389A)				
TBLPTR HOLDING REGISTER	=	0x01389A		
TBLPTR HOLDING REGISTER (0x01389A) HOLDING REGISTER (0x01389B)	= = =	0x01389A 0xFF 0xFF		
TBLPTR HOLDING REGISTER (0x01389A) HOLDING REGISTER	= = =	0x01389A 0xFF 0xFF		
TBLPTR HOLDING REGISTER (0x01389A) HOLDING REGISTER (0x01389B) After Instruction (table write of TABLAT TBLPTR	= = ompl	0x01389A 0xFF 0xFF etion)		
TBLPTR HOLDING REGISTER (0x01389A) HOLDING REGISTER (0x01389B) After Instruction (table write of TABLAT	= = ompl =	0x01389A 0xFF 0xFF etion) 0x34		

TST	FSZ	Test f, Skip	Test f, Skip if 0			
Synta	ax:	[label] T	STFSZ	f [,a]		
Oper	ands:	$0 \le f \le 255$				
		a ∈ [0,1]				
Oper	ation:	skip if $f = 0$				
Statu	is Affected:	None				
Enco	oding:	0110 011a ffff ffff			ffff	
Desc	ription:	If 'f' = 0, the next instruction fetched during the current instruction execution is discarded and a NOP is executed, making this a two-cycle instruction. If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).				
Word	ls:	1				
Cycle	es:	1(2) Note: 3 cycles if skip and followed by a 2-word instruction.				
00	volo Activity:			linea action		
Q Cycle Activity: Q1		Q2	Q3		Q4	
	Decode	Read register 'f'	Proce	ss	No	
lf sk	ip:	<u> </u>				
	Q1	Q2	Q3		Q4	
	No	No	No		No	
	operation	operation	operat	ion op	peration	
lf sk	ip and followe	,	struction	:		
	Q1	Q2	Q3		Q4	
	No	No	No		No	
	operation	operation No	operat No	ion op	peration No	
	No operation	operation	operat	ion op	peration	
Example: HERE TSTFSZ CNT NZERO : ZERO :						
Before Instruction PC = Address (HERE)						
After Instruction         If CNT         =         0x00,           PC         =         Address (ZERO)         If CNT         ≠         0x00,           PC         =         Address (NZERO)         ERO)         Address (NZERO)						

XORLW	Exclusive	Exclusive OR Literal with W			
Syntax:	[ label ]	XORLW I	K		
Operands:	$0 \le k \le 25$	$0 \le k \le 255$			
Operation:	(W) .XOR	(W) .XOR. $k \rightarrow W$			
Status Affected:	N, Z	N, Z			
Encoding:	0000	0000 1010 kkkk kk			
Description: Words:		ents of W a teral 'k'. Th			
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q3		Q4	
Decode	Read literal 'k'	Proces Data	s V	/rite to W	
Example: XORLW 0xAF					
Before Instruction					

Before Instruction W = 0xB5 After Instruction W = 0x1A

© 2006 Microchip Technology Inc.

XORWF	Exclusive	sive OR W with f			
Syntax:	[label]	XORWF	f [,d	[,a]]	
Operands:	0 ≤ f ≤ 255 d ∈ [0,1] a ∈ [0,1]				
Operation:	(W) .XOR.	(f) $\rightarrow$ des	t		
Status Affected:	N, Z				
Encoding:	0001	10da	fff	f	ffff
Description:	Exclusive OR the contents of W with register 'f'. If 'd' is '0', the result is stored in W. If 'd' is '1', the result is stored back in register 'f' (default). If 'a' is '0', the Access Bank will be selected, overriding the BSR value. If 'a' is '1', then the bank will be selected as per the BSR value (default).				
Words:	1				
Cycles:	1				
Q Cycle Activity:					
Q1	Q2	Q3			Q4
Decode	Read register 'f'	Proce Data			Irite to stination
Example:	XORWF	REG			
Before Instruc REG W After Instructi REG	= 0xAF = 0xB5				
W	= 0xB5				

# 26.0 DEVELOPMENT SUPPORT

The PICmicro $^{\ensuremath{\mathbb{B}}}$  microcontrollers are supported with a full range of hardware and software development tools:

- Integrated Development Environment
  - MPLAB® IDE Software
- Assemblers/Compilers/Linkers
  - MPASM[™] Assembler
  - MPLAB C17 and MPLAB C18 C Compilers
  - MPLINK[™] Object Linker/ MPLIB[™] Object Librarian
  - MPLAB C30 C Compiler
  - MPLAB ASM30 Assembler/Linker/Library
- Simulators
  - MPLAB SIM Software Simulator
  - MPLAB dsPIC30 Software Simulator
- Emulators
  - MPLAB ICE 2000 In-Circuit Emulator
  - MPLAB ICE 4000 In-Circuit Emulator
- In-Circuit Debugger
- MPLAB ICD 2
- Device Programmers
  - PRO MATE® II Universal Device Programmer
  - PICSTART® Plus Development Programmer
  - MPLAB PM3 Device Programmer
- Low-Cost Demonstration Boards
  - PICDEM[™] 1 Demonstration Board
  - PICDEM.net[™] Demonstration Board
  - PICDEM 2 Plus Demonstration Board
  - PICDEM 3 Demonstration Board
  - PICDEM 4 Demonstration Board
  - PICDEM 17 Demonstration Board
  - PICDEM 18R Demonstration Board
  - PICDEM LIN Demonstration Board
  - PICDEM USB Demonstration Board
- Evaluation Kits
  - KEELOQ[®] Evaluation and Programming Tools
  - PICDEM MSC
  - microID[®] Developer Kits
  - CAN
  - PowerSmart® Developer Kits
  - Analog

# 26.1 MPLAB Integrated Development Environment Software

The MPLAB IDE software brings an ease of software development previously unseen in the 8/16-bit microcontroller market. The MPLAB IDE is a Windows[®] based application that contains:

- · An interface to debugging tools
  - simulator
  - programmer (sold separately)
  - emulator (sold separately)
  - in-circuit debugger (sold separately)
- · A full-featured editor with color coded context
- A multiple project manager
- Customizable data windows with direct edit of contents
- High-level source code debugging
- Mouse over variable inspection
- Extensive on-line help

The MPLAB IDE allows you to:

- Edit your source files (either assembly or C)
- One touch assemble (or compile) and download to PICmicro emulator and simulator tools (automatically updates all project information)
- Debug using:
  - source files (assembly or C)
  - mixed assembly and C
  - machine code

MPLAB IDE supports multiple debugging tools in a single development paradigm, from the cost effective simulators, through low-cost in-circuit debuggers, to full-featured emulators. This eliminates the learning curve when upgrading to tools with increasing flexibility and power.

### 26.2 MPASM Assembler

The MPASM assembler is a full-featured, universal macro assembler for all PICmicro MCUs.

The MPASM assembler generates relocatable object files for the MPLINK object linker, Intel[®] standard HEX files, MAP files to detail memory usage and symbol reference, absolute LST files that contain source lines and generated machine code and COFF files for debugging.

The MPASM assembler features include:

- Integration into MPLAB IDE projects
- · User defined macros to streamline assembly code
- Conditional assembly for multi-purpose source files
- Directives that allow complete control over the assembly process

## 26.3 MPLAB C17 and MPLAB C18 C Compilers

The MPLAB C17 and MPLAB C18 Code Development Systems are complete ANSI C compilers for Microchip's PIC17CXXX and PIC18CXXX family of microcontrollers. These compilers provide powerful integration capabilities, superior code optimization and ease of use not found with other compilers.

For easy source level debugging, the compilers provide symbol information that is optimized to the MPLAB IDE debugger.

### 26.4 MPLINK Object Linker/ MPLIB Object Librarian

The MPLINK object linker combines relocatable objects created by the MPASM assembler and the MPLAB C17 and MPLAB C18 C compilers. It can link relocatable objects from precompiled libraries, using directives from a linker script.

The MPLIB object librarian manages the creation and modification of library files of precompiled code. When a routine from a library is called from a source file, only the modules that contain that routine will be linked in with the application. This allows large libraries to be used efficiently in many different applications.

The object linker/library features include:

- Efficient linking of single libraries instead of many smaller files
- Enhanced code maintainability by grouping related modules together
- Flexible creation of libraries with easy module listing, replacement, deletion and extraction

# 26.5 MPLAB C30 C Compiler

The MPLAB C30 C compiler is a full-featured, ANSI compliant, optimizing compiler that translates standard ANSI C programs into dsPIC30F assembly language source. The compiler also supports many command line options and language extensions to take full advantage of the dsPIC30F device hardware capabilities and afford fine control of the compiler code generator.

MPLAB C30 is distributed with a complete ANSI C standard library. All library functions have been validated and conform to the ANSI C library standard. The library includes functions for string manipulation, dynamic memory allocation, data conversion, timekeeping and math functions (trigonometric, exponential and hyperbolic). The compiler provides symbolic information for high-level source debugging with the MPLAB IDE.

# 26.6 MPLAB ASM30 Assembler, Linker and Librarian

MPLAB ASM30 assembler produces relocatable machine code from symbolic assembly language for dsPIC30F devices. MPLAB C30 compiler uses the assembler to produce it's object file. The assembler generates relocatable object files that can then be archived or linked with other relocatable object files and archives to create an executable file. Notable features of the assembler include:

- Support for the entire dsPIC30F instruction set
- Support for fixed-point and floating-point data
- · Command line interface
- Rich directive set
- Flexible macro language
- MPLAB IDE compatibility

### 26.7 MPLAB SIM Software Simulator

The MPLAB SIM software simulator allows code development in a PC hosted environment by simulating the PICmicro series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any pin. The execution can be performed in Single-Step, Execute Until Break or Trace mode.

The MPLAB SIM simulator fully supports symbolic debugging using the MPLAB C17 and MPLAB C18 C Compilers, as well as the MPASM assembler. The software simulator offers the flexibility to develop and debug code outside of the laboratory environment, making it an excellent, economical software development tool.

### 26.8 MPLAB SIM30 Software Simulator

The MPLAB SIM30 software simulator allows code development in a PC hosted environment by simulating the dsPIC30F series microcontrollers on an instruction level. On any given instruction, the data areas can be examined or modified and stimuli can be applied from a file, or user defined key press, to any of the pins.

The MPLAB SIM30 simulator fully supports symbolic debugging using the MPLAB C30 C Compiler and MPLAB ASM30 assembler. The simulator runs in either a Command Line mode for automated tasks, or from MPLAB IDE. This high-speed simulator is designed to debug, analyze and optimize time intensive DSP routines.

DS41159E-page 324

## 26.9 MPLAB ICE 2000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 2000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for PICmicro microcontrollers. Software control of the MPLAB ICE 2000 in-circuit emulator is advanced by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICE 2000 is a full-featured emulator system with enhanced trace, trigger and data monitoring features. Interchangeable processor modules allow the system to be easily reconfigured for emulation of different processors. The universal architecture of the MPLAB ICE in-circuit emulator allows expansion to support new PICmicro microcontrollers.

The MPLAB ICE 2000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft[®] Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

# 26.10 MPLAB ICE 4000 High-Performance Universal In-Circuit Emulator

The MPLAB ICE 4000 universal in-circuit emulator is intended to provide the product development engineer with a complete microcontroller design tool set for highend PICmicro microcontrollers. Software control of the MPLAB ICE in-circuit emulator is provided by the MPLAB Integrated Development Environment, which allows editing, building, downloading and source debugging from a single environment.

The MPLAB ICD 4000 is a premium emulator system, providing the features of MPLAB ICE 2000, but with increased emulation memory and high-speed performance for dsPIC30F and PIC18XXXX devices. Its advanced emulator features include complex triggering and timing, up to 2 Mb of emulation memory and the ability to view variables in real-time.

The MPLAB ICE 4000 in-circuit emulator system has been designed as a real-time emulation system with advanced features that are typically found on more expensive development tools. The PC platform and Microsoft Windows 32-bit operating system were chosen to best make these features available in a simple, unified application.

# 26.11 MPLAB ICD 2 In-Circuit Debugger

Microchip's In-Circuit Debugger, MPLAB ICD 2, is a powerful, low-cost, run-time development tool, connecting to the host PC via an RS-232 or high-speed USB interface. This tool is based on the Flash PICmicro MCUs and can be used to develop for these and other PICmicro microcontrollers. The MPLAB ICD 2 utilizes the in-circuit debugging capability built into the Flash devices. This feature, along with Microchip's In-Circuit Serial Programming[™] (ICSP[™]) protocol, offers cost effective in-circuit Flash debugging from the graphical user interface of the MPLAB Integrated Development Environment. This enables a designer to develop and debug source code by setting breakpoints, single-stepping and watching variables, CPU status and peripheral registers. Running at full speed enables testing hardware and applications in real-time. MPLAB ICD 2 also serves as a development programmer for selected PICmicro devices.

# 26.12 PRO MATE II Universal Device Programmer

The PRO MATE II is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features an LCD display for instructions and error messages and a modular detachable socket assembly to support various package types. In Stand-Alone mode, the PRO MATE II device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode.

# 26.13 MPLAB PM3 Device Programmer

The MPLAB PM3 is a universal, CE compliant device programmer with programmable voltage verification at VDDMIN and VDDMAX for maximum reliability. It features a large LCD display (128 x 64) for menus and error messages and a modular detachable socket assembly to support various package types. The ICSP™ cable assembly is included as a standard item. In Stand-Alone mode, the MPLAB PM3 device programmer can read, verify and program PICmicro devices without a PC connection. It can also set code protection in this mode. MPLAB PM3 connects to the host PC via an RS-232 or USB cable. MPLAB PM3 has high-speed communications and optimized algorithms for quick programming of large memory devices and incorporates an SD/MMC card for file storage and secure data applications.

^{© 2006} Microchip Technology Inc.

## 26.14 PICSTART Plus Development Programmer

The PICSTART Plus development programmer is an easy-to-use, low-cost, prototype programmer. It connects to the PC via a COM (RS-232) port. MPLAB Integrated Development Environment software makes using the programmer simple and efficient. The PICSTART Plus development programmer supports most PICmicro devices up to 40 pins. Larger pin count devices, such as the PIC16C92X and PIC17C76X, may be supported with an adapter socket. The PICSTART Plus development programmer is CE compliant.

### 26.15 PICDEM 1 PICmicro Demonstration Board

The PICDEM 1 demonstration board demonstrates the capabilities of the PIC16C5X (PIC16C54 to PIC16C58A), PIC16C61, PIC16C62X, PIC16C71, PIC16C8X, PIC17C42, PIC17C43 and PIC17C44. All necessary hardware and software is included to run basic demo programs. The sample microcontrollers provided with the PICDEM 1 demonstration board can be programmed with a PRO MATE II device programmer or a PICSTART Plus development programmer. The PICDEM 1 demonstration board can be connected to the MPLAB ICE in-circuit emulator for testing. A prototype area extends the circuitry for additional application components. Features include an RS-232 interface, a potentiometer for simulated analog input, push button switches and eight LEDs.

# 26.16 PICDEM.net Internet/Ethernet Demonstration Board

The PICDEM.net demonstration board is an Internet/ Ethernet demonstration board using the PIC18F452 microcontroller and TCP/IP firmware. The board supports any 40-pin DIP device that conforms to the standard pinout used by the PIC16F877 or PIC18C452. This kit features a user friendly TCP/IP stack, web server with HTML, a 24L256 Serial EEPROM for Xmodem download to web pages into Serial EEPROM, ICSP/MPLAB ICD 2 interface connector, an Ethernet interface, RS-232 interface and a 16 x 2 LCD display. Also included is the book and CD-ROM *"TCP/IP Lean, Web Servers for Embedded Systems,"* by Jeremy Bentham

# 26.17 PICDEM 2 Plus Demonstration Board

The PICDEM 2 Plus demonstration board supports many 18, 28 and 40-pin microcontrollers, including PIC16F87X and PIC18FXX2 devices. All the necessary hardware and software is included to run the demonstration programs. The sample microcontrollers provided with the PICDEM 2 demonstration board can be programmed with a PRO MATE II device programmer, PICSTART Plus development programmer, or MPLAB ICD 2 with a Universal Programmer Adapter. The MPLAB ICD 2 and MPLAB ICE in-circuit emulators may also be used with the PICDEM 2 demonstration board to test firmware. A prototype area extends the circuitry for additional application components. Some of the features include an RS-232 interface, a 2 x 16 LCD display, a piezo speaker, an on-board temperature sensor, four LEDs and sample PIC18F452 and PIC16F877 Flash microcontrollers.

# 26.18 PICDEM 3 PIC16C92X Demonstration Board

The PICDEM 3 demonstration board supports the PIC16C923 and PIC16C924 in the PLCC package. All the necessary hardware and software is included to run the demonstration programs.

# 26.19 PICDEM 4 8/14/18-Pin Demonstration Board

The PICDEM 4 can be used to demonstrate the capabilities of the 8, 14 and 18-pin PIC16XXXX and PIC18XXXX MCUs, including the PIC16F818/819, PIC16F87/88, PIC16F62XA and the PIC18F1320 family of microcontrollers. PICDEM 4 is intended to showcase the many features of these low pin count parts, including LIN and Motor Control using ECCP. Special provisions are made for low-power operation with the supercapacitor circuit and jumpers allow onboard hardware to be disabled to eliminate current draw in this mode. Included on the demo board are provisions for Crystal, RC or Canned Oscillator modes, a five volt regulator for use with a nine volt wall adapter or battery, DB-9 RS-232 interface, ICD connector for programming via ICSP and development with MPLAB ICD 2, 2 x 16 liquid crystal display, PCB footprints for H-Bridge motor driver, LIN transceiver and EEPROM. Also included are: header for expansion, eight LEDs, four potentiometers, three push buttons and a prototyping area. Included with the kit is a PIC16F627A and a PIC18F1320. Tutorial firmware is included along with the User's Guide.

DS41159E-page 326

## 26.20 PICDEM 17 Demonstration Board

The PICDEM 17 demonstration board is an evaluation board that demonstrates the capabilities of several Microchip microcontrollers, including PIC17C752, PIC17C756A, PIC17C762 and PIC17C766. A programmed sample is included. The PRO MATE II device programmer, or the PICSTART Plus development programmer, can be used to reprogram the device for user tailored application development. The PICDEM 17 demonstration board supports program download and execution from external on-board Flash memory. A generous prototype area is available for user hardware expansion.

### 26.21 PICDEM 18R PIC18C601/801 Demonstration Board

The PICDEM 18R demonstration board serves to assist development of the PIC18C601/801 family of Microchip microcontrollers. It provides hardware implementation of both 8-bit Multiplexed/Demultiplexed and 16-bit Memory modes. The board includes 2 Mb external Flash memory and 128 Kb SRAM memory, as well as serial EEPROM, allowing access to the wide range of memory types supported by the PIC18C601/801.

# 26.22 PICDEM LIN PIC16C43X Demonstration Board

The powerful LIN hardware and software kit includes a series of boards and three PICmicro microcontrollers. The small footprint PIC16C432 and PIC16C433 are used as slaves in the LIN communication and feature on-board LIN transceivers. A PIC16F874 Flash microcontroller serves as the master. All three micro-controllers are programmed with firmware to provide LIN bus communication.

# 26.23 PICkit[™] 1 Flash Starter Kit

A complete "development system in a box", the PICkit[™] Flash Starter Kit includes a convenient multi-section board for programming, evaluation and development of 8/14-pin Flash PIC[®] microcontrollers. Powered via USB, the board operates under a simple Windows GUI. The PICkit 1 Starter Kit includes the User's Guide (on CD ROM), PICkit 1 tutorial software and code for various applications. Also included are MPLAB[®] IDE (Integrated Development Environment) software, software and hardware "Tips 'n Tricks for 8-pin Flash PIC[®] Microcontrollers" Handbook and a USB interface cable. Supports all current 8/14-pin Flash PIC microcontrollers, as well as many future planned devices.

## 26.24 PICDEM USB PIC16C7X5 Demonstration Board

The PICDEM USB Demonstration Board shows off the capabilities of the PIC16C745 and PIC16C765 USB microcontrollers. This board provides the basis for future USB products.

# 26.25 Evaluation and Programming Tools

In addition to the PICDEM series of circuits, Microchip has a line of evaluation kits and demonstration software for these products.

- KEELOQ evaluation and programming tools for Microchip's HCS Secure Data Products
- CAN developers kit for automotive network applications
- Analog design boards and filter design software
- PowerSmart battery charging evaluation/ calibration kits
- IrDA[®] development kit
- microID development and rfLab[™] development software
- SEEVAL[®] designer kit for memory evaluation and endurance calculations
- PICDEM MSC demo boards for Switching mode power supply, high-power IR driver, delta sigma ADC and flow rate sensor

Check the Microchip web page and the latest Product Selector Guide for the complete list of demonstration and evaluation kits.

^{© 2006} Microchip Technology Inc.

# PIC18FXX8

NOTES:

DS41159E-page 328

# 27.0 ELECTRICAL CHARACTERISTICS

# Absolute Maximum Ratings^(†)

Ambient temperature under bias	40°C to +125°C
Storage temperature	65°C to +150°C
Voltage on any pin with respect to Vss (except VDD, MCLR and RA4)	0.3V to (VDD + 0.3V)
Voltage on VDD with respect to Vss	0.3V to +7.5V
Voltage on MCLR with respect to Vss (Note 2)	0V to +13.25V
Voltage on RA4 with respect to Vss	0V to +8.5V
Total power dissipation (Note 1)	1.0W
Maximum current out of Vss pin	
Maximum current into VDD pin	250 mA
Input clamp current, Iк (VI < 0 or VI > VDD)	±20 mA
Output clamp current, loк (Vo < 0 or Vo > VDD)	±20 mA
Maximum output current sunk by any I/O pin	25 mA
Maximum output current sourced by any I/O pin	25 mA
Maximum current sunk by all ports (combined)	200 mA
Maximum current sourced by all ports (combined)	200 mA
Note 1: Power dissipation is calculated as follows:	

 $Pdis = VDD x \{IDD - \sum IOH\} + \sum \{(VDD - VOH) x IOH\} + \sum (VOL x IOL)$ 


2: Voltage spikes below Vss at the MCLR/VPP pin, inducing currents greater than 80 mA, may cause latch-up. Thus, a series resistor of 50-100Ω should be used when applying a "low" level to the MCLR/VPP pin rather than pulling this pin directly to Vss.

**Note:** Stresses above those listed under "Absolute Maximum Ratings" may cause permanent damage to the device. This is a stress rating only and functional operation of the device at those or any other conditions above those indicated in the operation listings of this specification is not implied. Exposure to maximum rating conditions for extended periods may affect device reliability.


^{© 2006} Microchip Technology Inc.

# PIC18FXX8










DS41159E-page 330

© 2006 Microchip Technology Inc.

Downloaded from: http://www.datasheetcatalog.com/





^{© 2006} Microchip Technology Inc.

# 27.1 DC Characteristics

PIC18LI (Indus				lard O ating te			ditions (unless otherwise stated) -40°C $\leq$ TA $\leq$ +85°C for industrial		
PIC18FXX8 (Industrial, Extended)				Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended					
Param No.	Symbol	Characteristic/ Device	Min	Conditions					
	Vdd	Supply Voltage							
D001		PIC18LFXX8	2.0		5.5	V	HS, XT, RC and LP Oscillator modes		
D001		PIC18FXX8	4.2	_	5.5	V			
D002	Vdr	RAM Data Retention Voltage ⁽¹⁾	1.5	—	—	V			
D003	VPOR	VDD Start Voltage to ensure internal Power-on Reset signal		_	0.7	V	See section on Power-on Reset for details		
D004	Svdd	VDD Rise Rate to ensure internal Power-on Reset signal	0.05	—	—	V/ms	See section on Power-on Reset for details		
	VBOR	Brown-out Reset Voltag	е						
		PIC18LFXX8							
D005		BORV1:BORV0 = 11	1.96		2.16	V			
		BORV1:BORV0 = 10	2.64	—	2.92	V			
		BORV1:BORV0 = 01	4.07	—	4.59	V			
		BORV1:BORV0 = 00	4.36	—	4.92	V			
		PIC18FXX8							
D005		BORV1:BORV0 = 1x	N.A.	—	N.A.	V	Not in operating voltage range of device		
		BORV1:BORV0 = 01	4.07	—	4.59	V			
		BORV1:BORV0 = 00	4.36	—	4.92	V			

Legend: Rows are shaded for improved readability.

Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:

<u>OSC1</u> = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD MCLR = VDD; WDT enabled/disabled as specified.

- **3:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).
- 4: For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The △IBOR and △ILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

DS41159E-page 332

# 27.1 DC Characteristics (Continued)

PIC18LI (Indus			Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial						
PIC18FX (Indus	<b>(X8</b> trial, Exter	nded)	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended						
Param No.	Symbol	Characteristic/ Device	Min	Тур	Max	Units	Conditions		
	Idd	Supply Current ^(2,3,4)							
D010		PIC18LFXX8		.7 .7 1.7	2 2 4	mA mA mA	XT oscillator configuration $V_{DD} = 2.0V, +25^{\circ}C, Fosc = 4 MHz$ $V_{DD} = 2.0V, -40^{\circ}C to +85^{\circ}C, Fosc = 4 MHz$ $V_{DD} = 4.2V, -40^{\circ}C to +85^{\circ}C, Fosc = 4 MHz$ RC oscillator configuration		
			   	1 1 2.5	2.5 2.5 5	mA mA mA	VDD = $2.0V$ , $+25^{\circ}$ C, FOSC = $4$ MHz VDD = $2.0V$ , $-40^{\circ}$ C to $+85^{\circ}$ C, FOSC = $4$ MHz VDD = $4.2V$ , $-40^{\circ}$ C to $+85^{\circ}$ C, FOSC = $4$ MHz RCIO oscillator configuration		
				.7 .7 1.8	2.5 2.5 4	mA mA mA	$V_{DD} = 2.0V, +25^{\circ}C, Fosc = 4 \text{ MHz}$ $V_{DD} = 2.0V, -40^{\circ}C \text{ to } +85^{\circ}C, Fosc = 4 \text{ MHz}$ $V_{DD} = 4.2V, -40^{\circ}C \text{ to } +85^{\circ}C, Fosc = 4 \text{ MHz}$		
D010		PIC18FXX8		1.7 1.7 1.7	4 4 4	mA mA mA	XT oscillator configuration VDD = 4.2V, +25°C, Fosc = 4 MHz VDD = 4.2V, -40°C to +85°C, Fosc = 4 MHz VDD = 4.2V, -40°C to +125°C, Fosc = 4 MHz RC oscillator configuration		
			  _	2.5 2.5 2.5	5 5 6	mA mA mA	$V_{DD} = 4.2V, +25^{\circ}C, Fosc = 4 MHz$ $V_{DD} = 4.2V, -40^{\circ}C \text{ to } +85^{\circ}C, Fosc = 4 MHz$ $V_{DD} = 4.2V, -40^{\circ}C \text{ to } +125^{\circ}C, Fosc = 4 MHz$ RCIO oscillator configuration		
				1.8 1.8 1.8	4 5 5	mA mA mA	VDD = 4.2V, +25°C, Fosc = 4 MHz VDD = 4.2V, -40°C to +85°C, Fosc = 4 MHz VDD = 4.2V, -40°C to +125°C, Fosc = 4 MHz		
D010A		PIC18LFXX8	_	18	40	μA	LP oscillator, FOSC = 32 kHz, WDT disabled VDD = $2.0V$ , $-40^{\circ}C$ to $+85^{\circ}C$		
D010A		PIC18FXX8	_	60 60	150 180	μΑ μΑ	LP oscillator, FOSC = 32 kHz, WDT disabled VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C		

Legend: Rows are shaded for improved readability.

Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD  $\overline{MCLR}$  = VDD; WDT enabled/disabled as specified.

- **3:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and Vss and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).
- 4: For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.
- **5:** The LVD and BOR modules share a large portion of circuitry. The △IBOR and △ILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

© 2006 Microchip Technology Inc.

# 27.1 DC Characteristics (Continued)

PIC18LF (Indust				lard O ating te			ditions (unless otherwise stated) -40°C $\leq$ TA $\leq$ +85°C for industrial		
PIC18F) (Indust	<b>(X8</b> trial, Exter	nded)	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended						
Param No.	Symbol	Characteristic/ Device	Min	Тур	Max	Units	Conditions		
	Idd	Supply Current ^(2,3,4)							
D010C		PIC18LFXX8		21	28	mA	EC, ECIO oscillator configurations VDD = 4.2V, -40°C to +85°C		
D010C		PIC18FXX8	_	21	30	mA	EC, ECIO oscillator configurations VDD = 4.2V, -40°C to +125°C, Fosc = 25 MHz		
D013		PIC18LFXX8		1.3 18 28	3 28 40	mA mA mA	HS oscillator configurations Fosc = 6 MHz, $VDD = 2.0V$ Fosc = 25 MHz, $VDD = 5.5V$ HS + PLL osc configuration Fosc = 10 MHz, $VDD = 5.5V$		
D013		PIC18FXX8	_	18 28	28 40	mA mA	HS oscillator configurations Fosc = 25 MHz, VDD = 5.5V HS + PLL osc configuration Fosc = 10 MHz, VDD = 5.5V		
D014		PIC18LFXX8		32	65	μA	Timer1 oscillator configuration Fosc = 32 kHz, VDD = 2.0V		
D014		PIC18FXX8		62 62	250 310	μΑ μΑ	Timer1 oscillator configuration Fosc = 32 kHz, VDD = 4.2V, -40°C to +85°C Fosc = 32 kHz, VDD = 4.2V, -40°C to +125°C		
	IPD	Power-Down Current ⁽³⁾			•	•			
D020		PIC18LFXX8		0.3 2	4 10	μΑ μΑ	VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C		
D020 D021B		PIC18FXX8	_	2 6	10 40	μΑ μΑ	VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C		

Legend: Rows are shaded for improved readability.

Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are: OSC1 = external square wave, from rail-to-rail; all I/O pins tri-stated, pulled to VDD  $\overline{MCLR}$  = VDD; WDT enabled/disabled as specified.

- **3:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and VSs and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).
- 4: For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.
- 5: The LVD and BOR modules share a large portion of circuitry. The △IBOR and △ILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

DS41159E-page 334

# 27.1 DC Characteristics (Continued)

PIC18LI (Indus				lard O ating te			ditions (unless otherwise stated) -40°C $\leq$ TA $\leq$ +85°C for industrial	
PIC18F2 (Indus	<b>XX8</b> trial, Exter	nded)	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended					
Param No.	Symbol	Characteristic/ Device	Min	Тур	Max	Units	Conditions	
	ΔIWDT	Module Differential Cur	rent					
D022		Watchdog Timer PIC18LFXX8		0.75 0.8 7	1.5 8 25	μΑ μΑ μΑ	VDD = 2.5V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C	
D022		Watchdog Timer PIC18FXX8		7 7 7	25 25 45	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C	
D022A	ΔIBOR	Brown-out Reset ⁽⁵⁾ PIC18LFXX8		38 42 49	50 55 65	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C	
D022A		Brown-out Reset ⁽⁵⁾ PIC18FXX8		46 49 50	65 65 75	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C	
D022B	ΔILVD	Low-Voltage Detect ⁽⁵⁾ PIC18LFXX8		36 40 47	50 55 65	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C	
D022B		Low-Voltage Detect ⁽⁵⁾ PIC18FXX8		44 47 47	65 65 75	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C	
D025	∆ITMR1	Timer1 Oscillator PIC18LFXX8		6.2 6.2 7.5	40 45 55	μΑ μΑ μΑ	VDD = 2.0V, +25°C VDD = 2.0V, -40°C to +85°C VDD = 4.2V, -40°C to +85°C	
D025		Timer1 Oscillator PIC18FXX8		7.5 7.5 7.5	55 55 65	μΑ μΑ μΑ	VDD = 4.2V, +25°C VDD = 4.2V, -40°C to +85°C VDD = 4.2V, -40°C to +125°C	

Legend: Rows are shaded for improved readability.

Note 1: This is the limit to which VDD can be lowered in Sleep mode, or during a device Reset, without losing RAM data.

2: The supply current is mainly a function of the operating voltage and frequency. Other factors, such as I/O pin loading and switching rate, oscillator type, internal code execution pattern and temperature, also have an impact on the current consumption.

The test conditions for all IDD measurements in active operation mode are:  $\frac{OSC1}{MCLR} = \text{vbd}; \text{ WDT enabled/disabled as specified.}$ 

**3:** The power-down current in Sleep mode does not depend on the oscillator type. Power-down current is measured with the part in Sleep mode, with all I/O pins in high-impedance state and tied to VDD and VSS and all features that add delta current disabled (such as WDT, Timer1 Oscillator, BOR, ...).

4: For RC oscillator configuration, current through REXT is not included. The current through the resistor can be estimated by the formula Ir = VDD/2 REXT (mA) with REXT in kOhm.

**5:** The LVD and BOR modules share a large portion of circuitry. The △IBOR and △ILVD currents are not additive. Once one of these modules is enabled, the other may also be enabled without further penalty.

^{© 2006} Microchip Technology Inc.

# 27.2 DC Characteristics: PIC18FXX8 (Industrial, Extended) PIC18LFXX8 (Industrial)

DC CHARACTERISTICS			$\begin{array}{llllllllllllllllllllllllllllllllllll$						
Param No.	Symbol	Characteristic/ Device	Min	Мах	Units	Conditions			
	VIL	Input Low Voltage							
		I/O ports:							
D030		with TTL buffer	Vss	0.15 VDD	V	VDD < 4.5V			
D030A			_	0.8	V	$4.5V \le VDD \le 5.5V$			
D031		with Schmitt Trigger buffer RC3 and RC4	Vss Vss	0.2 Vdd 0.3 Vdd	V V				
D032		MCLR	Vss	0.2 Vdd	V				
D032A		OSC1 (in XT, HS and LP modes) and T1OSI	Vss	0.3 Vdd	V				
D033		OSC1 (in RC mode) ⁽¹⁾	Vss	0.2 Vdd	V				
	Viн	Input High Voltage							
		I/O ports:							
D040		with TTL buffer	0.25 VDD + 0.8V	Vdd	V	VDD < 4.5V			
D040A			2.0	Vdd	V	$4.5V \le VDD \le 5.5V$			
D041		with Schmitt Trigger buffer RC3 and RC4	0.8 Vdd 0.7 Vdd	Vdd Vdd	V V				
D042		MCLR	0.8 Vdd	Vdd	V				
D042A		OSC1 (in XT, HS and LP modes) and T1OSI	0.7 Vdd	Vdd	V				
D043		OSC1 (RC mode) ⁽¹⁾	0.9 Vdd	Vdd	V				
	lı∟	Input Leakage Current ^(2,3)							
D060		I/O ports	—	±1	μA	$Vss \le VPIN \le VDD,$ Pin at high-impedance			
D061		MCLR	—	±5	μA	$Vss \le VPIN \le VDD$			
D063		OSC1	—	±5	μΑ	$Vss \le VPIN \le VDD$			
	IPU	Weak Pull-up Current			1				
D070	IPURB	PORTB weak pull-up current	50	450	μA	VDD = 5V, VPIN = VSS			

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro[®] device be driven with an external clock while in RC mode.

2: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

3: Negative current is defined as current sourced by the pin.

# 27.2 DC Characteristics: PIC18FXX8 (Industrial, Extended) PIC18LFXX8 (Industrial) (Continued)

DC CHARACTERISTICS			Standard Operati Operating tempera	ature -40°C	$\leq TA \leq \cdot$	ess otherwise stated) +85°C for industrial +125°C for extended
Param No.	Symbol	Characteristic/ Device	Min	Max	Units	Conditions
	Vol	Output Low Voltage				
D080		I/O ports	—	0.6	V	IOL = 8.5 mA, VDD = 4.2V, -40°C to +85°C
D080A			—	0.6	V	IOL = 7.0 mA, VDD = 4.2V, -40°C to +125°C
D083		OSC2/CLKO (RC mode)	—	0.6	V	IOL = 1.6 mA, VDD = 4.2V, -40°C to +85°C
D083A			—	0.6	V	IOL = 1.2 mA, VDD = 4.2V, -40°C to +125°C
	Vон	Output High Voltage ⁽³⁾				
D090		I/O ports	VDD - 0.7	—	V	IOH = -3.0 mA, VDD = 4.2V, -40°C to +85°C
D090A			Vdd - 0.7	—	V	IOH = -2.5 mA, VDD = 4.2V, -40°C to +125°C
D092		OSC2/CLKO (RC mode)	Vdd - 0.7	—	V	IOH = -1.3 mA, VDD = 4.2V, -40°C to +85°C
D092A			Vdd - 0.7	—	V	IOH = -1.0 mA, VDD = 4.2V, -40°С to +125°С
D150	Vod	Open-Drain High Voltage	—	7.5	V	RA4 pin
		Capacitive Loading Specs on Output Pins				
D101	Сю	All I/O pins and OSC2 (in RC mode)	_	50	pF	To meet the AC Timing Specifications
D102	Св	SCL, SDA	—	400	pF	In I ² C™ mode

**Note 1:** In RC oscillator configuration, the OSC1/CLKI pin is a Schmitt Trigger input. It is not recommended that the PICmicro[®] device be driven with an external clock while in RC mode.


2: The leakage current on the MCLR pin is strongly dependent on the applied voltage level. The specified levels represent normal operating conditions. Higher leakage current may be measured at different input voltages.

**3:** Negative current is defined as current sourced by the pin.

^{© 2006} Microchip Technology Inc.

# PIC18FXX8





		$\begin{array}{l} \mbox{Standard Operating Conditions (unless otherwise stated)} \\ \mbox{Operating temperature} & -40^\circ C \leq TA \leq +85^\circ C \mbox{ for industrial} \\ & -40^\circ C \leq TA \ \leq +125^\circ C \mbox{ for extended} \end{array}$							
Param No.	Symbol	Characteristi	c	Min	Тур	Max	Units	Conditions	
D420	Vlvd	LVD Voltage	LVV = 0001	1.96	2.06	2.16	V	$T \ge 25^{\circ}C$	
			LVV = 0010	2.16	2.27	2.38	V	T ≥ 25°C	
			LVV = 0011	2.35	2.47	2.59	V	T ≥ 25°C	
			LVV = 0100	2.43	2.58	2.69	V		
			LVV = 0101	2.64	2.78	2.92	V		
			LVV = 0110	2.75	2.89	3.03	V		
			LVV = 0111	2.95	3.1	3.26	V		
			LVV = 1000	3.24	3.41	3.58	V		
			LVV = 1001	3.43	3.61	3.79	V		
			LVV = 1010	3.53	3.72	3.91	V		
			LVV = 1011	3.72	3.92	4.12	V		
			LVV = 1100	3.92	4.13	4.34	V		
			LVV = 1101	4.07	4.33	4.59	V		
			LVV = 1110	4.36	4.64	4.92	V		

### TABLE 27-1: LOW-VOLTAGE DETECT CHARACTERISTICS

DC Cha	racterist	tics	Standard Operating Conditions							
Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions			
		Internal Program Memory Programming Specifications								
D110	VPP	Voltage on MCLR/VPP pin	9.00	—	13.25	V				
D113	IDDP	Supply Current during Programming	—	—	10	mA				
		Data EEPROM Memory								
D120	ED	Cell Endurance	100K	1M	—	E/W	-40°C to +85°C			
D120A	ED	Byte Endurance	10K	100K	_	E/W	+85°C to +125°C			
D121	Vdrw	VDD for Read/Write	VMIN	—	5.5	V	Using EECON to read/write VMIN = Minimum operating voltage			
D122	TDEW	Erase/Write Cycle Time		4	—	ms				
D123	TRETD	Characteristic Retention	40	—	_	Year	Provided no other specifications are violated			
D124	TREF	Number of Total Erase/Write Cycles to Data EEPROM before Refresh*	1M	10M	_	Cycles	-40°C to +85°C			
D124A	TREF	Number of Total Erase/Write Cycles before Refresh*	100K	1M	—	Cycles	+85°C to +125°C			
		Program Flash Memory								
D130	Eр	Cell Endurance	10K	100K	—	E/W	-40°C to +85°C			
D130A	Eр	Cell Endurance	1000	10K	—	E/W	+85°C to +125°C			
D131	VPR	VDD for Read	VMIN	—	5.5	V	VMIN = Minimum operating voltage			
D132	VIE	VDD for Block Erase	4.5	—	5.5	V	Using ICSP™ port			
D132A	Viw	VDD for Externally Timed Erase or Write	4.5	—	5.5	V	Using ICSP port			
D132B	VPEW	VDD for Self-Timed Write	VMIN	—	5.5	V	VMIN = Minimum operating voltage			
D133	TIE	ICSP Erase Cycle Time	—	4	—	ms	$VDD \ge 4.5V$			
D133A	Tiw	ICSP Erase or Write Cycle Time (externally timed)	1	—	-	ms	$VDD \ge 4.5V$			
D133A	Tiw	Self-Timed Write Cycle Time	—	2	—	ms				
D134	TRETD	Characteristic Retention	40	—	-	Year	Provided no other specifications are violated			

#### TABLE 27-2: DC CHARACTERISTICS: EEPROM AND ENHANCED FLASH

† Data in "Typ" column is at 5.0V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

* See Section 5.8 "Using the Data EEPROM" for more information.

^{© 2006} Microchip Technology Inc.

## TABLE 27-3: COMPARATOR SPECIFICATIONS

<b>Operating Conditions:</b> VDD range as described in <b>Section 27.1 "DC Characteristics"</b> , -40°C < TA < +125°C							
Param No.	Sym	Characteristics	Min	Тур	Мах	Units	Comments
D300	VIOFF	Input Offset Voltage	_	±5.0	±10	mV	
D301	VICM	Input Common Mode Voltage	0	_	Vdd - 1.5	V	
D302	CMRR	CMRR	+55*	_	—	db	
D300	TRESP	Response Time ⁽¹⁾	—	300* 350*	400* 600*	ns ns	PIC18FXX8 PIC18LFXX8
D301	TMC20V	Comparator Mode Change to Output Valid	—		10*	μs	

These parameters are characterized but not tested.

Note 1: Response time measured with one comparator input at (VDD - 1.5)/2 while the other input transitions from Vss to VDD.

# TABLE 27-4: VOLTAGE REFERENCE SPECIFICATIONS

Operating 0	<b>Operating Conditions:</b> VDD range as described in <b>Section 27.1 "DC Characteristics"</b> , $-40^{\circ}C < TA < +125^{\circ}C$								
Param No.	Sym	Characteristics	Min	Тур	Max	Units	Comments		
D310	VRES	Resolution	Vdd/24	—	Vdd/32	LSB			
D311	Vraa	Absolute Accuracy	—	—	0.5	LSB			
D312	VRUR	Unit Resistor Value (R)	—	2K*	_	Ω			
D310	TSET	Settling Time ⁽¹⁾	—		10*	μs			

* These parameters are characterized but not tested.

**Note 1:** Settling time measured while CVRR = 1 and CVR<3:0> transitions from 0000 to 1111.

# 27.3 AC (Timing) Characteristics

#### 27.3.1 TIMING PARAMETER SYMBOLOGY

The timing parameter symbols have been created using one of the following formats:

1. TppS2pp	pS	3. Tcc:st	(I ² C specifications only)
2. TppS		4. Ts	(I ² C specifications only)
Т			
F	Frequency	Т	Time
Lowercase	e letters (pp) and their meanings:		
рр			
сс	CCP1	osc	OSC1
ck	CLKO	rd	RD
CS	CS	rw	RD or WR
di	SDI	SC	SCK
do	SDO	SS	SS
dt	Data in	tO	ТОСКІ
io	I/O port	t1	T1CKI
mc	MCLR	wr	WR
Uppercase	letters and their meanings:		
S			
F	Fall	Р	Period
н	High	R	Rise
1	Invalid (High-Impedance)	V	Valid
L	Low	Z	High-Impedance
I ² C only			
AA	output access	High	High
BUF	Bus free	Low	Low
TCC:ST (I ² C	Specifications only)		
CC			
HD	Hold	SU	Setup
ST			
DAT	DATA input hold	STO	Stop condition
STA	Start condition		

^{© 2006} Microchip Technology Inc.


### 27.3.2 TIMING CONDITIONS

The temperature and voltages specified in Table 27-5 apply to all timing specifications unless otherwise noted. Figure 27-5 specifies the load conditions for the timing specifications.

### TABLE 27-5: TEMPERATURE AND VOLTAGE SPECIFICATIONS – AC


Section 27.1 "DC Characteristics".	Standard Operating Conditions (unless otherwise stated)Operating temperature $-40^{\circ}C \le TA \le +85^{\circ}C$ for industrial $-40^{\circ}C \le TA \le +125^{\circ}C$ for extended
LF parts operate for industrial temperatures only.	Section 27.1 "DC Characteristics".

### FIGURE 27-5: LOAD CONDITIONS FOR DEVICE TIMING SPECIFICATIONS



DS41159E-page 342

### 27.3.3 TIMING DIAGRAMS AND SPECIFICATIONS



### TABLE 27-6: EXTERNAL CLOCK TIMING REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Мах	Units	Conditions
1A	Fosc	External CLKI Frequency ⁽¹⁾	DC	40	MHz	EC, ECIO oscillator, -40°C to +85°C
		Oscillator Frequency ⁽¹⁾	DC	25	MHz	EC, ECIO oscillator, +85°C to +125°C
			DC	4	MHz	RC oscillator
			0.1	4	MHz	XT oscillator
			4	25	MHz	HS oscillator, -40°C to +85°C
			4	25	MHz	HS oscillator, +85°C to +125°C
			4	10	MHz	HS + PLL oscillator, -40°C to +85°C
			4	6.25	MHz	HS + PLL oscillator, +85°C to +125°C
			DC	200	kHz	LP oscillator
1	Tosc	External CLKI Period ⁽¹⁾	25	_	ns	EC, ECIO oscillator, -40°C to +85°C
		Oscillator Period ⁽¹⁾	40	—	ns	EC, ECIO oscillator, +85°C to +125°C
			250	—	ns	RC oscillator
			250	10,000	ns	XT oscillator
			40	—	ns	HS oscillator, -40°C to +85°C
			40	—	ns	HS oscillator, +85°C to +125°C
			100	250	ns	HS + PLL oscillator, -40°C to +85°C
			160	250	ns	HS + PLL oscillator, +85°C to +125°C
			5	200	μs	LP oscillator
2	Тсү	Instruction Cycle Time ⁽¹⁾	100 160		ns ns	Tcy = 4/Fosc, -40°C to +85°C Tcy = 4/Fosc, +85°C to +125°C
3	TosL,	External Clock in (OSC1)	30	_	ns	XT oscillator
	TosH	High or Low Time	2.5	_	ns	LP oscillator
			10	—	μs	HS oscillator
4	TosR,	External Clock in (OSC1)		20	ns	XT oscillator
	TosF	Rise or Fall Time	_	50	ns	LP oscillator
			_	7.5	ns	HS oscillator

Note 1: Instruction cycle period (TcY) equals four times the input oscillator time base period. All specified values are based on characterization data for that particular oscillator type under standard operating conditions with the device executing code. Exceeding these specified limits may result in an unstable oscillator operation and/or higher than expected current consumption. All devices are tested to operate at "Min." values with an external clock applied to the OSC1/CLKI pin. When an external clock input is used, the "Max." cycle time limit is "DC" (no clock) for all devices.


© 2006 Microchip Technology Inc.

Param No.	Sym	Characteristic	Min	Тур†	Max	Units	Conditions
_	Fosc	Oscillator Frequency Range	4		10	MHz	HS mode only
—	Fsys	On-Chip VCO System Frequency	16		40	MHz	HS mode only
—	t _{rc}	PLL Start-up Time (Lock Time)	—		2	ms	
—	$\Delta CLK$	CLKO Stability (Jitter)	-2		+2	%	

### TABLE 27-7: PLL CLOCK TIMING SPECIFICATIONS (VDD = 4.2 TO 5.5V)

† Data in "Typ" column is at 5V, 25°C unless otherwise stated. These parameters are for design guidance only and are not tested.

### FIGURE 27-7: CLKO AND I/O TIMING



### TABLE 27-8: CLKO AND I/O TIMING REQUIREMENTS


Param No.	Symbol	Characteristic		Min	Тур	Max	Units	Conditions
10	TosH2ckL	OSC1 ↑ to CLKO ↓		_	75	200	ns	(1)
11	TosH2ckH	OSC1 ↑ to CLKO ↑		—	75	200	ns	(1)
12	TckR	CLKO Rise Time		_	35	100	ns	(1)
13	TckF	CLKO Fall Time		_	35	100	ns	(1)
14	TckL2ioV	CLKO↓ to Port Out Valid		_	—	0.5 TCY + 20	ns	(1)
15	TioV2ckH			0.25 Tcy + 25	—	_	ns	(1)
16	TckH2iol	Port In Hold after CLKO ↑		0	—	_	ns	(1)
17	TosH2ioV	OSC1 ↑ (Q1 cycle) to Port Out Valid		—	50	150	ns	
18	TosH2iol	OSC1 ↑ (Q2 cycle) to Port	PIC18FXX8	100	_	_	ns	
18A		Input Invalid (I/O in hold time) PIC18LFXX8		200	_	_	ns	
19	TioV2osH	Port Input Valid to OSC1 ↑ (I/O in setup time)		0	_	—	ns	
20	TIOR	Port Output Rise Time PIC18FXX8		—	10	25	ns	
20A		PIC18LFXX8		—	_	60	ns	
21	TIOF	Port Output Fall Time PIC18FXX8 PIC18LFXX8		—	10	25	ns	
21A				_	_	60	ns	
22†	TINP	INT pin High or Low Time		Тсү	_	—	ns	
23†	Trbp	RB7:RB4 Change INT High or Low Time		Тсү	_	—	ns	
24†	TRCP	RC7:RC4 Change INT High o	r Low Time	20	—	—	ns	

† These parameters are asynchronous events not related to any internal clock edges.


Note 1: Measurements are taken in RC mode where CLKO pin output is 4 x Tosc.

DS41159E-page 344





#### FIGURE 27-9: BROWN-OUT RESET AND LOW-VOLTAGE DETECT TIMING




# TABLE 27-9:RESET, WATCHDOG TIMER, OSCILLATOR START-UP TIMER, POWER-UP TIMER,<br/>BROWN-OUT RESET AND LOW-VOLTAGE DETECT REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Тур	Мах	Units	Conditions
30	TmcL	MCLR Pulse Width (low)	2	_	—	μs	
31	Twdt	Watchdog Timer Time-out Period (no prescaler)	7	18	33	ms	
32	Tost	Oscillation Start-up Timer Period	1024 Tosc	_	1024 Tosc	_	Tosc = OSC1 period
33	TPWRT	Power-up Timer Period	28	72	132	ms	
34	Tioz	I/O High-Impedance from MCLR Low or Watchdog Timer Reset	—	2	—	μs	
35	TBOR	Brown-out Reset Pulse Width	200		_	μs	For VDD $\leq$ BVDD (see D005)
36	TIRVST	Time for Internal Reference Voltage to become stable	—	20	50	μs	
37	TLVD	Low-Voltage Detect Pulse Width	200		—	μs	For VDD $\leq$ VLVD (see D420)

© 2006 Microchip Technology Inc.

### FIGURE 27-10: TIMER0 AND TIMER1 EXTERNAL CLOCK TIMINGS



Param No.	Symbol		Characteristic		Min	Max	Units	Conditions	
40	Tt0H	T0CKI High	Pulse Width No prescaler		0.5 TCY + 20	_	ns		
				With prescaler	10	_	ns		
41	TtOL	T0CKI Low F	Pulse Width	No prescaler	0.5 TCY + 20	_	ns		
				With prescaler	10	_	ns		
42	Tt0P	T0CKI Perio	d	No prescaler	Tcy + 10	—	ns		
				With prescaler	Greater of: 20 ns or <u>TCY + 40</u> N	_	ns	N = prescale value (1, 2, 4,, 256)	
45 Tt1H		T1CKI	Synchronous, r	no prescaler	0.5 TCY + 20		ns		
	High Time	High Time	High Time Synchronous	Synchronous,	PIC18FXX8	10		ns	
			with prescaler	PIC18LFXX8	25	_	ns		
			Asynchronous	PIC18FXX8	30	_	ns		
				PIC18LFXX8	50	_	ns		
46	Tt1L	T1CKI	Synchronous, r	Synchronous, no prescaler		_	ns		
		Low Time	Synchronous,	PIC18FXX8	10	_	ns		
			with prescaler	PIC18LFXX8	25	_	ns		
			Asynchronous	PIC18FXX8	30	—	ns		
				PIC18LFXX8	TBD	TBD	ns		
47	Tt1P	T1CKI Input Period	Synchronous		Greater of: 20 ns or <u>TCY + 40</u> N	_	ns	N = prescale value (1, 2, 4, 8)	
			Asynchronous		60		ns		
	Ft1	T1CKI Oscill	ator Input Frequency Range		DC	50	kHz		
48	Tcke2tmrl	Delay from E Timer Increm	External T1CKI C	lock Edge to	2 Tosc	7 Tosc			

**Legend:** TBD = To Be Determined

DS41159E-page 346






TABLE 27-11: CAPTURE/COMPARE/PWM REQUIREMENTS (CCP1 AND ECCP1)

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions	
50	TccL	CCPx Input Low Time	No prescal	No prescaler		_	ns	
			With	PIC18FXX8	10	_	ns	
			prescaler	PIC18LFXX8	20	_	ns	
51	ТссН	CCPx Input High Time	No prescaler		0.5 TCY + 20	_	ns	
			With	PIC18FXX8	10		ns	
			prescaler	PIC18LFXX8	20	_	ns	
52	TccP	CCPx Input Period			<u>3 Tcy + 40</u> N	_	ns	N = prescale value (1, 4 or 16)
53	TccR	CCPx Output Fall Time		PIC18FXX8	—	25	ns	
				PIC18LFXX8	—	45	ns	
54	TccF	CCPx Output Fall Time F		PIC18FXX8	—	25	ns	
				PIC18LFXX8	—	45	ns	

^{© 2006} Microchip Technology Inc.




FIGURE 27-12:	PARALLEL SLAVE PORT TIMING (PIC18F248 AND PIC18F458)	
	FARALLEL SLAVE FURI TIMING (FIG 10F240 AND FIG 10F430)	1

TARI E 27-12.	PARALLEL SLAVE PORT	<b>BEQUIREMENTS</b>	(PIC18F248 AND PIC18F458)
IADLL ZI-IZ.	FARALLEL SLAVE FURI		(FICTOLZ40 AND FICTOL430)

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
62	TdtV2wrH	Data-In Valid before $\overline{\text{WR}} \uparrow \text{ or } \overline{\text{CS}} \uparrow$ (setup time)		20 25	_	ns ns	Extended Temp. range
63	TwrH2dtl	$\overline{WR}$ $\uparrow$ or $\overline{CS}$ $\uparrow$ to Data-In Invalid	PIC18FXX8	20	_	ns	
		(hold time)	PIC18LFXX8	35	—	ns	
64	TrdL2dtV	$\overline{RD}\downarrow$ and $\overline{CS}\downarrow$ to Data-Out Valid		-	80 90	ns ns	Extended Temp. range
65	TrdH2dtl	$\overline{RD} \uparrow or  \overline{CS} \downarrow to  Data-Out Invalid$		10	30	ns	
66	TibfINH	Inhibit the IBF flag bit being cleared from $\overline{\text{WR}} \uparrow \text{or } \overline{\text{CS}} \uparrow$		—	3 Тсү	ns	






TABLE 27-13:	EXAMPLE SPI™ MODE REQUIREMENTS (	(MASTER MODE, $CKE = 0$ )

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	$\overline{SS} \downarrow$ to SCK $\downarrow$ or SCK $\uparrow$ Input		Тсү	—	ns	
71	TscH	SCK Input High Time	SCK Input High Time Continuous		_	ns	
71A		(Slave mode)	Single Byte	40		ns	(Note 1)
72	TscL	SCK Input Low Time	Continuous	1.25 TCY + 30	_	ns	
72A		(Slave mode)	Single Byte	40		ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup Time of SDI Data Input to SCK Edge		100	—	ns	
73A	Тв2в	Last Clock Edge of Byte 1 to th of Byte 2	e 1st Clock Edge	1.5 TCY + 40	—	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to	SCK Edge	100	—	ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8		25	ns	
			PIC18LFXX8	—	45	ns	
76	TdoF	SDO Data Output Fall Time		—	25	ns	
78	TscR	SCK Output Rise Time	PIC18FXX8	—	25	ns	
		(Master mode)	PIC18 <b>LF</b> XX8	—	45	ns	
79	TscF	SCK Output Fall Time (Master mode)			25	ns	
80	TscH2doV,	SDO Data Output Valid after	PIC18FXX8		50	ns	
	TscL2doV	SCK Edge	PIC18LFXX8		100	ns	


**Note 1:** Requires the use of parameter #73A.

2: Only if parameter #71A and #72A are used.

^{© 2006} Microchip Technology Inc.

# PIC18FXX8





# TABLE 27-14: EXAMPLE SPI™ MODE REQUIREMENTS (MASTER MODE, CKE = 1)


Param No.	Symbol	Characterist	ic	Min	Max	Units	Conditions
71	TscH	SCK Input High Time	Continuous	1.25 Tcy + 30	_	ns	
71A		(Slave mode)	Single Byte	40	—	ns	(Note 1)
72	TscL	SCK Input Low Time	SCK Input Low Time Continuous		_	ns	
72A		(Slave mode)	Single Byte	40	_	ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup Time of SDI Data Input	to SCK Edge	100	_	ns	
73A	Тв2в	Last Clock Edge of Byte 1 to the 1st Clock Edge of Byte 2		1.5 Tcy + 40		ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to	Hold Time of SDI Data Input to SCK Edge		_	ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8	—	25	ns	
			PIC18LFXX8	—	45	ns	
76	TdoF	SDO Data Output Fall Time	•	—	25	ns	
78	TscR	SCK Output Rise Time	PIC18FXX8	—	25	ns	
		(Master mode)	PIC18LFXX8	—	45	ns	
79	TscF	SCK Output Fall Time (Master	r mode)	—	25	ns	
80	TscH2doV,	SDO Data Output Valid after PIC18FXX8			50	ns	
	TscL2doV	SCK Edge PIC18LFXX8			100	ns	
81	TdoV2scH, TdoV2scL	SDO Data Output Setup to SC	CK Edge	Тсү	—	ns	

**Note 1:** Requires the use of parameter #73A.

**2:** Only if parameter #71A and #72A are used.

DS41159E-page 350






Param No.	Symbol	Characteristic	Characteristic		Max	Units	Conditions
70	TssL2scH, TssL2scL	$\overline{\mathrm{SS}}\downarrow$ to SCK $\downarrow$ or SCK $\uparrow$ Input	r SCK ↑ Input		—	ns	
71	TscH	SCK Input High Time (Slave mode)	Continuous	1.25 Tcy + 30	_	ns	
71A			Single Byte	40	_	ns	(Note 1)
72	TscL	SCK Input Low Time (Slave mode)	Continuous	1.25 Tcy + 30	_	ns	
72A			Single Byte	40		ns	(Note 1)
73	TdiV2scH, TdiV2scL	Setup Time of SDI Data Input to SCK I	e of SDI Data Input to SCK Edge		_	ns	
73A	Тв2в	Last Clock Edge of Byte 1 to the 1st Cloc	k Edge of Byte 1 to the 1st Clock Edge of Byte 2			ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to SCK Edge		100	_	ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8	_	25	ns	
			PIC18 <b>LF</b> XX8		45	ns	
76	TdoF	SDO Data Output Fall Time		_	25	ns	
77	TssH2doZ	$\overline{SS}$ $\uparrow$ to SDO Output High-Impedance		10	50	ns	
78	TscR	SCK Output Rise Time (Master mode)	PIC18FXX8	_	25	ns	
			PIC18LFXX8		45	ns	
79	TscF	SCK Output Fall Time (Master mode)	•	_	25	ns	
80	TscH2doV,	SDO Data Output Valid after SCK	PIC18FXX8	_	50	ns	
	TscL2doV	Edge	PIC18 <b>LF</b> XX8		100	ns	
83	TscH2ssH, TscL2ssH	SS ↑ after SCK Edge		1.5 Tcy + 40	—	ns	

**Note 1:** Requires the use of parameter #73A.

2: Only if parameter #71A and #72A are used.

© 2006 Microchip Technology Inc.



#### FIGURE 27-16: EXAMPLE SPI[™] SLAVE MODE TIMING (CKE = 1)

Param No.	Symbol	Characteristic		Min	Max	Units	Conditions
70	TssL2scH, TssL2scL	$\overline{SS} \downarrow$ to SCK $\downarrow$ or SCK $\uparrow$ Input	r SCK ↑ Input			ns	
71	TscH	SCK Input High Time	Continuous	1.25 TCY + 30		ns	
71A		(Slave mode)	Single Byte	40	—	ns	(Note 1)
72	TscL	SCK Input Low Time	Continuous	1.25 Tcy + 30		ns	
72A		(Slave mode)	Single Byte	40		ns	(Note 1)
73A	Тв2в	Last Clock Edge of Byte 1 to the 1st C	lock Edge of Byte 2	1.5 TCY + 40	_	ns	(Note 2)
74	TscH2diL, TscL2diL	Hold Time of SDI Data Input to SCK	Time of SDI Data Input to SCK Edge			ns	
75	TdoR	SDO Data Output Rise Time	PIC18FXX8	—	25	ns	
			PIC18LFXX8		45	ns	Ī
76	TdoF	SDO Data Output Fall Time	- -	—	25	ns	
77	TssH2doZ	SS ↑ to SDO Output High-Impedance	9	10	50	ns	
78	TscR	SCK Output Rise Time	PIC18FXX8		25	ns	
		(Master mode)	PIC18LFXX8	—	45	ns	Ī
79	TscF	SCK Output Fall Time (Master mode)		—	25	ns	
80	TscH2doV,	SDO Data Output Valid after SCK	PIC18FXX8	—	50	ns	
	TscL2doV	Edge	PIC18LFXX8	—	100	ns	
82	TssL2doV	SDO Data Output Valid after $\overline{ ext{SS}}\downarrow$	PIC18FXX8	_	50	ns	
		Edge	PIC18LFXX8	—	100	ns	
83	TscH2ssH, TscL2ssH	SS ↑ after SCK Edge	·	1.5 Tcy + 40	—	ns	

# TABLE 27-16: EXAMPLE SPI™ SLAVE MODE REQUIREMENTS (CKE = 1)

**Note 1:** Requires the use of parameter #73A.

2: Only if parameter #71A and #72A are used.







TABLE 27-17:	I ² C [™] BUS START/STOP BITS REQUIREMENTS (SLAVE MODE	:)
--------------	----------------------------------------------------------------------------	----

Param No.	Symbol	Character	ristic	Min	Max	Units	Conditions
90	TSU:STA	Start Condition	100 kHz mode	4700		ns	Only relevant for Repeated
		Setup Time	400 kHz mode	600			Start condition
91	THD:STA	Start Condition	100 kHz mode	4000		ns	After this period, the first
		Hold Time	400 kHz mode	600			clock pulse is generated
92	TSU:STO	Stop Condition	100 kHz mode	4700	—	ns	
		Setup Time	400 kHz mode	600			
93	THD:STO	Stop Condition	100 kHz mode	4000	_	ns	
		Hold Time	400 kHz mode	600			





^{© 2006} Microchip Technology Inc.

Param No.	Symbol	Charact	eristic	Min	Max	Units	Conditions
100	Тнідн	Clock High Time	100 kHz mode	4.0	-	μs	PIC18FXX8 must operate at a minimum of 1.5 MHz
			400 kHz mode	0.6	—	μs	PIC18FXX8 must operate at a minimum of 10 MHz
			SSP Module	1.5 TCY	—		
101	TLOW	Clock Low Time	100 kHz mode	4.7	—	μs	PIC18FXX8 must operate at a minimum of 1.5 MHz
			400 kHz mode	1.3	—	μs	PIC18FXX8 must operate at a minimum of 10 MHz
			SSP module	1.5 Tcy	_	ns	
102	TR	SDA and SCL Rise	100 kHz mode	—	1000	ns	
		Time	400 kHz mode	20 + 0.1 Св	300	ns	CB is specified to be from 10 to 400 pF
103	TF	SDA and SCL Fall	100 kHz mode		300	ns	
		Time	400 kHz mode	20 + 0.1 Cв	300	ns	CB is specified to be from 10 to 400 pF
90	TSU:STA	Start Condition	100 kHz mode	4.7	_	μs	Only relevant for Repeated
		Setup Time	400 kHz mode	0.6	—	μs	Start condition
91	THD:STA	Start Condition	100 kHz mode	4.0		μs	After this period the first
		Hold Time	400 kHz mode	0.6	—	μs	clock pulse is generated
106	THD:DAT	Data Input Hold	100 kHz mode	0	—	ns	
		Time	400 kHz mode	0	0.9	μs	
107	TSU:DAT	Data Input Setup	100 kHz mode	250	—	ns	(Note 2)
		Time	400 kHz mode	100	—	ns	
92	Tsu:sto	Stop Condition	100 kHz mode	4.7	—	μs	-
		Setup Time	400 kHz mode	0.6	—	μs	
109	ΤΑΑ	Output Valid from	100 kHz mode	—	3500	ns	(Note 1)
		Clock	400 kHz mode	—	—	ns	
110	TBUF	Bus Free Time	100 kHz mode	4.7		μs	Time the bus must be free
			400 kHz mode	1.3	_	μs	before a new transmission can start
D102	Св	Bus Capacitive Load	ding	—	400	pF	

## TABLE 27-18: I²C[™] BUS DATA REQUIREMENTS (SLAVE MODE)

**Note 1:** As a transmitter, the device must provide this internal minimum delay time to bridge the undefined region (min. 300 ns) of the falling edge of SCL to avoid unintended generation of Start or Stop conditions.

2: A Fast mode I²C[™] bus device can be used in a Standard mode I²C bus system, but the requirement TSU;DAT ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line.

Before the SCL line is released, TR max. + TSU:DAT = 1000 + 250 = 1250 ns (according to the Standard mode I²C bus specification).

# FIGURE 27-19: MASTER SSP I²C[™] BUS START/STOP BITS TIMING WAVEFORMS





TABLE 27-19:	MASTER SSP I ² C [™] BUS START/STOP BITS REQUIREMENTS
--------------	---------------------------------------------------------------------------

Param No.	Symbol	Characte	eristic	Min	Max	Units	Conditions
90	TSU:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)		ns	Only relevant for
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_		Repeated Start
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_		condition
91	THD:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)		ns	After this period, the
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)	_		first clock pulse is
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_		generated
92	Tsu:sto	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)		ns	
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_		
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_		
93	THD:STO	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)		ns	
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)		]	
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_		

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2C^{TM}$  pins.

# FIGURE 27-20: MASTER SSP I²C™ BUS DATA TIMING



© 2006 Microchip Technology Inc.

Param. No.	Symbol	Charac	teristic	Min	Max	Units	Conditions
100	Тнідн	Clock High Time	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			400 kHz mode	2(Tosc)(BRG + 1)		ms	
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_	ms	
101	TLOW	Clock Low Time	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			400 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_	ms	
102	TR	SDA and SCL	100 kHz mode	_	1000	ns	CB is specified to be
		Rise Time	400 kHz mode	20 + 0.1 Св	300	ns	from 10 to 400 pF
			1 MHz mode ⁽¹⁾		300	ns	
103	TF	SDA and SCL	100 kHz mode		300	ns	CB is specified to be
		Fall Time	400 kHz mode	20 + 0.1 Св	300	ns	from 10 to 400 pF
			1 MHz mode ⁽¹⁾		100	ns	
90	TSU:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	Only relevant for
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_	ms	Repeated Start
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_	ms	condition
91	THD:STA	Start Condition	100 kHz mode	2(Tosc)(BRG + 1)	_	ms	After this period, the
		Hold Time	400 kHz mode	2(Tosc)(BRG + 1)	_	ms	first clock pulse is
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_	ms	generated
106	THD:DAT	Data Input	100 kHz mode	0	_	ns	
		Hold Time	400 kHz mode	0	0.9	ms	
107	TSU:DAT	Data Input	100 kHz mode	250	_	ns	(Note 2)
		Setup Time	400 kHz mode	100	_	ns	
92	Tsu:sto	Stop Condition	100 kHz mode	2(Tosc)(BRG + 1)		ms	
		Setup Time	400 kHz mode	2(Tosc)(BRG + 1)	_	ms	
			1 MHz mode ⁽¹⁾	2(Tosc)(BRG + 1)	_	ms	
109	ΤΑΑ	Output Valid	100 kHz mode	—	3500	ns	
		from Clock	400 kHz mode	_	1000	ns	
			1 MHz mode ⁽¹⁾	—	—	ns	
110	TBUF	Bus Free Time	100 kHz mode	4.7	_	ms	Time the bus must be
			400 kHz mode	1.3	_	ms	free before a new transmission can star
D102	Св	Bus Capacitive Lo	pading	_	400	рF	


# TABLE 27-20: MASTER SSP I²C™ BUS DATA REQUIREMENTS

**Note 1:** Maximum pin capacitance = 10 pF for all  $I^2C^{TM}$  pins.

2: A Fast mode I²C bus device can be used in a Standard mode I²C bus system, but parameter #107 ≥ 250 ns must then be met. This will automatically be the case if the device does not stretch the low period of the SCL signal. If such a device does stretch the low period of the SCL signal, it must output the next data bit to the SDA line.

Before the SCL line is released, parameter #102 + parameter #107 = 1000 + 250 = 1250 ns (for 100 kHz mode).


### FIGURE 27-21: USART SYNCHRONOUS TRANSMISSION (MASTER/SLAVE) TIMING



#### TABLE 27-21: USART SYNCHRONOUS TRANSMISSION REQUIREMENTS

Param No.	Symbol	Characteristic		Min	Мах	Units	Conditions
120	TckH2dtV	<u>SYNC XMIT (Master &amp; Slave)</u> Clock High to Data-Out Valid	PIC18 <b>F</b> XX8	_	50	ns	
			PIC18LFXX8	_	150	ns	
121	Tckrf	Clock Out Rise Time and Fall Time	PIC18FXX8	_	25	ns	
		(Master mode)	PIC18LFXX8	_	60	ns	
122	Tdtrf	Data-Out Rise Time and Fall Time	PIC18FXX8	_	25	ns	
			PIC18LFXX8		60	ns	

#### FIGURE 27-22: USART SYNCHRONOUS RECEIVE (MASTER/SLAVE) TIMING



#### TABLE 27-22: USART SYNCHRONOUS RECEIVE REQUIREMENTS

Param No.	Symbol	Characteristic	Min	Max	Units	Conditions
125	TdtV2ckl	<u>SYNC RCV (Master &amp; Slave)</u> Data-Hold before CK ↓ (DT hold time)	10		ns	
126	TckL2dtl	Data-Hold after CK $\downarrow$ (DT hold time)	15	_	ns	

 $[\]ensuremath{\textcircled{}^{\odot}}$  2006 Microchip Technology Inc.

Symbol NR EIL EDL EFS EOFF	Character Resolution Integral Linearity Differential Linea Full Scale Error Offset Error Monotonicity ⁽³⁾	Error	Min — — — —	Typ — — —	Max 10 <±1 <±1 <±1	Units bit LSb LSb	ConditionsVREF = VDD $\geq 3.0V$ VREF = VDD $\geq 3.0V$ VREF = VDD $\geq 3.0V$
EIL EDL EFS EOFF	Integral Linearity Differential Linea Full Scale Error Offset Error		— — — —		<±1 <±1	LSb	$VREF=VDD\geq 3.0V$
Edl Efs Eoff	Differential Linea Full Scale Error Offset Error				<±1		
Efs Eoff —	Full Scale Error Offset Error	rity Error		_		LSb	$V_{BEE} = V_{DD} > 3.0V$
EOFF	Offset Error		—		<+1		
_					<±1	LSb	$VREF = VDD \ge 3.0V$
	Monotonicity ⁽³⁾		—	—	<±1.5	LSb	$VREF = VDD \ge 3.0V$
Voee		guaranteed				$VSS \le VAIN \le VREF$	
VREF	Reference Voltage		0V		_	V	
	(VREFH – VREFL)		ЗV	_	—	V	For 10-bit resolution
Vrefh	Reference Voltage High		Vss	_	VDD + 0.3V	V	
Vrefl	Reference Voltage Low		Vss - 0.3V	_	Vdd	V	
VAIN	Analog Input Voltage		Vss - 0.3V	_	VREF + 0.3V	V	
ZAIN	Recommended Impedance of Analog Voltage Source		—	_	10.0	kΩ	
IAD		PIC18FXX8	_	180	_	μA	Average current
		PIC18 <b>LF</b> XX8	—	90	—	μA consumption when A/D is on <b>(Note 1)</b>	
50 IREF VREF Input Current (Note 2)		0	_	5	μΑ μΑ	During VAIN acquisition. Based on differential of VHOLD to VAIN. To charge CHOLD. During A/D conversion	
	VREFL VAIN ZAIN AD	VREFH Reference Voltage VREFL Reference Voltage VAIN Analog Input Volt ZAIN Recommended In Analog Voltage S AD A/D Conversion Current (VDD)	VREFH       Reference Voltage High         VREFL       Reference Voltage Low         VAIN       Analog Input Voltage         ZAIN       Recommended Impedance of Analog Voltage Source         AD       A/D Conversion Current (VDD)	VREFH     Reference Voltage High     Vss       VREFL     Reference Voltage Low     Vss – 0.3V       VAIN     Analog Input Voltage     Vss – 0.3V       ZAIN     Recommended Impedance of Analog Voltage Source     —       AD     A/D Conversion Current (VDD)     PIC18FXX8     —	VREFH     Reference Voltage High     Vss       VREFL     Reference Voltage Low     Vss - 0.3V       VAIN     Analog Input Voltage     Vss - 0.3V       ZAIN     Recommended Impedance of Analog Voltage Source     -       AD     A/D Conversion Current (VDD)     PIC18FXX8     -     180	VREFH     Reference Voltage High     VSS      VDD + 0.3V       VREFL     Reference Voltage Low     VSS - 0.3V      VDD       VAIN     Analog Input Voltage     VSS - 0.3V      VREF + 0.3V       ZAIN     Recommended Impedance of Analog Voltage Source      10.0       AD     A/D Conversion Current (VDD)     PIC18FXX8      180        REF     VREF Input Current (Note 2)     0      5	VREFHReference Voltage HighVSS $-$ VDD + 0.3VVVREFLReference Voltage LowVSS - 0.3V $-$ VDDVVAINAnalog Input VoltageVSS - 0.3V $-$ VREF + 0.3VVZAINRecommended Impedance of Analog Voltage Source $ -$ 10.0k $\Omega$ ADA/D Conversion Current (VDD)PIC18FXX8 $-$ 180 $ \mu A$ REFVREF Input Current (Note 2)0 $-$ 5 $\mu A$


# TABLE 27-23: A/D CONVERTER CHARACTERISTICS: PIC18FXX8 (INDUSTRIAL, EXTENDED) PIC18LFXX8 (INDUSTRIAL)

Note 1: When A/D is off, it will not consume any current other than minor leakage current. The power-down current specification includes any such leakage from the A/D module. VREF current is from RA2/AN2/VREF- and RA3/AN3/VREF+ pins or VDD and VSS pins, whichever is selected as reference input.

**2:** VSS  $\leq$  VAIN  $\leq$  VREF

**3:** The A/D conversion result never decreases with an increase in the input voltage and has no missing codes.





Param No.	Symbol	Characte	Min	Max	Units	Conditions	
130	Tad	A/d Clock Period PIC18FXX8		1.6	20 ⁽⁵⁾	μs	Tosc based, VREF $\geq$ 3.0V
			PIC18LFXX8	3.0	20 ⁽⁵⁾	μs	TOSC based, VREF full range
			PIC18FXX8	2.0	6.0	μs	A/D RC mode
			PIC18LFXX8		9.0	μs	A/D RC mode
131	TCNV	Conversion Time (not including acquisition	11	12	Tad		
132	TACQ	Acquisition Time (Note 3)		15 10	_	μs μs	$-40^{\circ}C \le Temp \le +125^{\circ}C$ $0^{\circ}C \le Temp \le +125^{\circ}C$
135	Tswc	Switching Time from C	onvert $\rightarrow$ Sample	—	(Note 4)		
136	Тамр	Amplifier Settling Time (Note 2)		1	_	μs	This may be used if the "new" input voltage has not changed by more than 1 LSb (i.e., 5 mV @ 5.12V) from the last sampled voltage (as stated on CHOLD).

#### TABLE 27-24: A/D CONVERSION REQUIREMENTS

**Note 1:** ADRES register may be read on the following TCY cycle.

- 2: See Section 20.0 "Compatible 10-Bit Analog-to-Digital Converter (A/D) Module" for minimum conditions when input voltage has changed more than 1 LSb.
- **3:** The time for the holding capacitor to acquire the "New" input voltage when the voltage changes full scale after the conversion (AVDD to AVSS or AVSS to AVDD). The source impedance (*Rs*) on the input channels is 50Ω.
- 4: On the next Q4 cycle of the device clock.
- 5: The time of the A/D clock period is dependent on the device frequency and the TAD clock divider.

^{© 2006} Microchip Technology Inc.


NOTES:


DS41159E-page 360

### 28.0 DC AND AC CHARACTERISTICS GRAPHS AND TABLES


**Note:** The graphs and tables provided following this note are a statistical summary based on a limited number of samples and are provided for informational purposes only. The performance characteristics listed herein are not tested or guaranteed. In some graphs or tables, the data presented may be outside the specified operating range (e.g., outside specified power supply range) and therefore, outside the warranted range.


"Typical" represents the mean of the distribution at 25°C. "Maximum" or "minimum" represents (mean +  $3\sigma$ ) or (mean -  $3\sigma$ ) respectively, where  $\sigma$  is a standard deviation, over the whole temperature range.















#### FIGURE 28-3: TYPICAL IDD vs. Fosc OVER VDD (HS/PLL MODE)



















#### FIGURE 28-7: TYPICAL IDD vs. Fosc OVER VDD (LP MODE)
















#### FIGURE 28-11: TYPICAL AND MAXIMUM IDD vs. VDD (TIMER1 AS MAIN OSCILLATOR 32.768 kHz, C1 AND C2 = 47 pF)



#### FIGURE 28-12: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE, C = 20 pF, $+25^{\circ}$ C)



DS41159E-page 366






FIGURE 28-13: AVERAGE FOSC vs. VDD FOR VARIOUS VALUES OF R (RC MODE, C = 100 pF,  $+25^{\circ}$ C)











FIGURE 28-15: IPD vs. VDD, -40°C TO +125°C (SLEEP MODE, ALL PERIPHERALS DISABLED)







# FIGURE 28-17: TYPICAL AND MAXIMUM $\triangle$ ITMR1 vs. VDD OVER TEMPERATURE (-10°C TO +70°C, TIMER1 WITH OSCILLATOR, XTAL = 32 kHz, C1 AND C2 = 47 pF)










#### FIGURE 28-19: TYPICAL, MINIMUM AND MAXIMUM WDT PERIOD vs. VDD (-40°C TO +125°C)










FIGURE 28-21: TYPICAL, MINIMUM AND MAXIMUM VOH vs. IOH (VDD = 5V, -40°C TO +125°C)








#### FIGURE 28-23: TYPICAL AND MAXIMUM Vol vs. Iol (VDD = 5V, -40°C TO +125°C)





DS41159E-page 372







FIGURE 28-25: MINIMUM AND MAXIMUM VIN vs. VDD (ST INPUT, -40°C TO +125°C)









### FIGURE 28-27: MINIMUM AND MAXIMUM VIN vs. VDD (I²C™ INPUT, -40°C TO +125°C)







^{© 2006} Microchip Technology Inc.


NOTES:

DS41159E-page 376

### 29.0 PACKAGING INFORMATION

### 29.1 Package Marking Information

#### 28-Lead SPDIP



28-Lead SOIC



#### 40-Lead PDIP



Example



#### Example




#### Example




Legend	: XXX Y YY WW NNN @3 *	Customer-specific information Year code (last digit of calendar year) Year code (last 2 digits of calendar year) Week code (week of January 1 is week '01') Alphanumeric traceability code Pb-free JEDEC designator for Matte Tin (Sn) This package is Pb-free. The Pb-free JEDEC designator (e3) can be found on the outer packaging for this package.				
Note:	In the event the full Microchip part number cannot be marked on one line, it will be carried over to the next line, thus limiting the number of available characters for customer-specific information.					

### 29.1 Package Marking Information (Continued)


44-Lead PLCC



44-Lead TQFP



Example



Example




### 29.2 Package Details

The following sections give the technical details of the packages.

#### 28-Lead Skinny Plastic Dual In-line (SP) – 300 mil Body (PDIP)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units	Jnits INCHES*			М		
Dimer	ision Limits	MIN	NOM	MAX	MIN	NOM	MAX
Number of Pins	n		28			28	
Pitch	р		.100			2.54	
Top to Seating Plane	А	.140	.150	.160	3.56	3.81	4.06
Molded Package Thickness	A2	.125	.130	.135	3.18	3.30	3.43
Base to Seating Plane	A1	.015			0.38		
Shoulder to Shoulder Width	E	.300	.310	.325	7.62	7.87	8.26
Molded Package Width	E1	.275	.285	.295	6.99	7.24	7.49
Overall Length	D	1.345	1.365	1.385	34.16	34.67	35.18
Tip to Seating Plane	L	.125	.130	.135	3.18	3.30	3.43
Lead Thickness	С	.008	.012	.015	0.20	0.29	0.38
Upper Lead Width	B1	.040	.053	.065	1.02	1.33	1.65
Lower Lead Width	В	.016	.019	.022	0.41	0.48	0.56
Overall Row Spacing	<b>§</b> eB	.320	.350	.430	8.13	8.89	10.92
Mold Draft Angle Top	α	5	10	15	5	10	15
Mold Draft Angle Bottom	β	5	10	15	5	10	15

* Controlling Parameter § Significant Characteristic


Significant Notes:

Dimension D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MO-095

Drawing No. C04-070

### 28-Lead Plastic Small Outline (SO) – Wide, 300 mil Body (SOIC)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



sion Limits n p A A2	MIN .093	NOM 28 .050	MAX	MIN	NOM 28	MAX
p A	.093	-			28	
A	.093	.050				
	.093				1.27	
A2		.099	.104	2.36	2.50	2.64
7.4	.088	.091	.094	2.24	2.31	2.39
A1	.004	.008	.012	0.10	0.20	0.30
Е	.394	.407	.420	10.01	10.34	10.67
E1	.288	.295	.299	7.32	7.49	7.59
D	.695	.704	.712	17.65	17.87	18.08
h	.010	.020	.029	0.25	0.50	0.74
L	.016	.033	.050	0.41	0.84	1.27
φ	0	4	8	0	4	8
С	.009	.011	.013	0.23	0.28	0.33
В	.014	.017	.020	0.36	0.42	0.51
α	0	12	15	0	12	15
β	0	12	15	0	12	15
	E E1 D h L φ C B α	E         .394           E1         .288           D         .695           h         .010           L         .016           φ         0           c         .009           B         .014           α         0	E         .394         .407           E1         .288         .295           D         .695         .704           h         .010         .020           L         .016         .033 $\phi$ 0         4           c         .009         .011           B         .014         .017 $\alpha$ 0         12	E	E	$\begin{array}{c c c c c c c c c c c c c c c c c c c $

* Controlling Parameter

§ Significant Characteristic


Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MS-013

Drawing No. C04-052

### 40-Lead Plastic Dual In-line (P) – 600 mil Body (PDIP)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



				IVIIIN		WI/A/A
n		40			40	
р		.100			2.54	
Α	.160	.175	.190	4.06	4.45	4.83
A2	.140	.150	.160	3.56	3.81	4.06
A1	.015			0.38		
E	.595	.600	.625	15.11	15.24	15.88
E1	.530	.545	.560	13.46	13.84	14.22
D	2.045	2.058	2.065	51.94	52.26	52.45
L	.120	.130	.135	3.05	3.30	3.43
С	.008	.012	.015	0.20	0.29	0.38
B1	.030	.050	.070	0.76	1.27	1.78
В	.014	.018	.022	0.36	0.46	0.56
eB	.620	.650	.680	15.75	16.51	17.27
α	5	10	15	5	10	15
β	5	10	15	5	10	15
	n           p           A           A2           A1           E           D           L           c           B1           B           eB           α	n           p           A         .160           A2         .140           A1         .015           E         .595           E1         .530           D         2.045           L         .120           c         .008           B1         .030           B         .014           eB         .620           α         5	$\begin{array}{c c c c c c c c c c c c c c c c c c c $	$\begin{array}{c c c c c c c c c c c c c c c c c c c $	$\begin{array}{c c c c c c c c c c c c c c c c c c c $	$\begin{array}{c c c c c c c c c c c c c c c c c c c $

* Controlling Parameter § Significant Characteristic

Significar Notes:


Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MO-011

Drawing No. C04-016

^{© 2006} Microchip Technology Inc.

### 44-Lead Plastic Leaded Chip Carrier (L) – Square (PLCC)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



		INCHES*			MILLIMETERS			
Dimension	MIN	NOM	MAX	MIN	NOM	MAX		
Number of Pins	n		44			44		
Pitch	р		.050			1.27		
Pins per Side	n1		11			11		
Overall Height	А	.165	.173	.180	4.19	4.39	4.57	
Molded Package Thickness	A2	.145	.153	.160	3.68	3.87	4.06	
Standoff §	A1	.020	.028	.035	0.51	0.71	0.89	
Side 1 Chamfer Height	A3	.024	.029	.034	0.61	0.74	0.86	
Corner Chamfer 1	CH1	.040	.045	.050	1.02	1.14	1.27	
Corner Chamfer (others)	CH2	.000	.005	.010	0.00	0.13	0.25	
Overall Width	Е	.685	.690	.695	17.40	17.53	17.65	
Overall Length	D	.685	.690	.695	17.40	17.53	17.65	
Molded Package Width	E1	.650	.653	.656	16.51	16.59	16.66	
Molded Package Length	D1	.650	.653	.656	16.51	16.59	16.66	
Footprint Width	E2	.590	.620	.630	14.99	15.75	16.00	
Footprint Length	D2	.590	.620	.630	14.99	15.75	16.00	
Lead Thickness	С	.008	.011	.013	0.20	0.27	0.33	
Upper Lead Width	B1	.026	.029	.032	0.66	0.74	0.81	
Lower Lead Width	В	.013	.020	.021	0.33	0.51	0.53	
Mold Draft Angle Top	α	0	5	10	0	5	10	
Mold Draft Angle Bottom	β	0	5	10	0	5	10	

* Controlling Parameter

§ Significant Characteristic


Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. JEDEC Equivalent: MO-047

Drawing No. C04-048

#### 44-Lead Plastic Thin Quad Flatpack (PT) 10x10x1 mm Body, 1.0/0.10 mm Lead Form (TQFP)

**Note:** For the most current package drawings, please see the Microchip Packaging Specification located at http://www.microchip.com/packaging



	Units		INCHES		MILLIMETERS*			
Dimension	Limits	MIN	NOM	MAX	MIN	NOM	MAX	
Number of Pins	n		44			44		
Pitch	р		.031			0.8	0	
Pins per Side	n1		11			11		
Overall Height	Α	.039	.043	.047	1.00	1.10	1.20	
Molded Package Thickness	A2	.037	.039	.041	0.95	1.00	1.05	
Standoff	A1	.002	.004	.006	0.05	0.10	0.15	
Foot Length	L	.018	.024	.030	0.45	0.60	0.75	
Footprint (Reference)	F	.039 REF.				1.00 REF.		
Foot Angle	¢	0	3.5	7	0	3.5	7	
Overall Width	Е	.463	.472	.482	11.75	12.00	12.25	
Overall Length	D	.463	.472	.482	11.75	12.00	12.25	
Molded Package Width	E1	.390	.394	.398	9.90	10.00	10.10	
Molded Package Length	D1	.390	.394	.398	9.90	10.00	10.10	
Lead Thickness	С	.004	.006	.008	0.09	0.15	0.20	
Lead Width	В	.012	.015	.017	0.30	0.38	0.44	
Pin 1 Corner Chamfer	СН	.025	.035	.045	0.64	0.89	1.14	
Mold Draft Angle Top	α	5	10	15	5	10	15	
Mold Draft Angle Bottom	β	5	10	15	5	10	15	
* Controlling Parameter								

* Controlling Parameter

#### Notes:

Dimensions D and E1 do not include mold flash or protrusions. Mold flash or protrusions shall not exceed .010" (0.254mm) per side. REF: Reference Dimension, usually without tolerance, for information purposes only.

See ASME Y14.5M

JEDEC Equivalent: MS-026 Drawing No. C04-076

Revised 07-22-05

NOTES:

DS41159E-page 384

# APPENDIX A: DATA SHEET REVISION HISTORY

### Revision A (June 2001)

Original data sheet for the PIC18FXX8 family.

### Revision B (May 2002)

Updated information on CAN module, device memory and register maps, I/O ports and Enhanced CCP.

### **Revision C (January 2003)**

This revision includes the DC and AC Characteristics Graphs and Tables (see Section 28.0 "DC and AC Characteristics Graphs and Tables"), Section 27.0 "Electrical Characteristics" have been updated and CAN certification information has been added.

#### **Revision D (September 2004)**

Data Sheet Errata (DS80134 and DS80161) issues have been addressed and corrected along with minor corrections to the data sheet text.

#### **Revision E (October 2006)**

Packaging diagrams updated.

#### TABLE B-1: DEVICE DIFFERENCES

	Features	PIC18F248	PIC18F258	PIC18F448	PIC18F458
Internal	Bytes	16K		16K	32K
Program Memory	# of Single-Word Instructions	8192	16384	8192	16384
Data Memory (Bytes)		768	1536	768	1536
I/O Ports		Ports A, B, C	Ports A, B, C	Ports A, B, C, D, E	Ports A, B, C, D, E
Enhanced Capture/Compare/PWM Modules		-	—	1	1
Parallel Slave Port		No	No	Yes	Yes
10-bit Analog	g-to-Digital Converter	5 input channels	5 input channels	8 input channels	8 input channels
Analog Com	parators	No	No	2	2
Analog Comparators VREF Output		N/A	N/A	Yes	Yes
Packages		28-pin SPDIP 28-pin SOIC	28-pin SPDIP 28-pin SOIC	40-pin PDIP 44-pin PLCC 44-pin TQFP	40-pin PDIP 44-pin PLCC 44-pin TQFP

### APPENDIX B: DEVICE DIFFERENCES

The differences between the devices listed in this data sheet are shown in Table B-1.

# APPENDIX C: DEVICE MIGRATIONS

This section is intended to describe the functional and electrical specification differences when migrating between functionally similar devices (such as from a PIC16C74A to a PIC16C74B).

**Not Applicable** 

### APPENDIX D: MIGRATING FROM OTHER PICmicro® DEVICES

This discusses some of the issues in migrating from other PICmicro devices to the PIC18FXX8 family of devices.

### D.1 PIC16CXXX to PIC18FXX8

See Application Note AN716 "Migrating Designs from PIC16C74A/74B to PIC18C442" (DS00716).

### D.2 PIC17CXXX to PIC18FXX8

See Application Note AN726 "PIC17CXXX to PIC18CXXX Migration" (DS00726).

DS41159E-page 386

# INDEX

Α
A/D241
A/D Converter Flag (ADIF Bit)
A/D Converter Interrupt, Configuring
Acquisition Requirements
Acquisition Time
ADCON0 Register
ADCON1 Register241
ADRESH Register241
ADRESH/ADRESL Registers
ADRESL Register241
Analog Port Pins, Configuring246
Associated Registers Summary248
Calculating the Minimum Required
Acquisition Time245
Configuring the Module244
Conversion Clock (TAD)
Conversion Status (GO/DONE Bit)
Conversion TAD Cycles
Conversions
Minimum Charging Time
Result Registers247
Selecting the Conversion Clock
Special Event Trigger (CCP) 126
Special Event Trigger (ECCP) 133, 248
TAD vs. Device Operating Frequencies
(For Extended, LF Devices) (table)246
TAD vs. Device Operating
Frequencies (table)246
Use of the ECCP Trigger 248
Absolute Maximum Ratings
AC (Timing) Characteristics
Parameter Symbology 341
Access Bank
ACKSTAT
ACKSTAT Status Flag
ADCONO Register
GO/DONE Bit
ADCON1 Register
ADDLW
Addressable Universal Synchronous Asynchronous
Receiver Transmitter. See USART.
ADDWF
ADDWFC
ADRESH Register
ADRESH/ADRESL Register
Analog-to-Digital Converter. See A/D.
ANDLW
ANDUC 288 ANDWF
Assembler
MPASM Assembler
Associated Registers
В
Bank Select Register (BSR)54
Baud Rate Generator
BC
BCF
BF

Block Diagrams	
A/D	
Analog Input Model 244	, 253
Baud Rate Generator	
CAN Buffers and Protocol Engine	. 200
CAN Receive Buffer	. 230
CAN Transmit Buffer	. 227
Capture Mode Operation	. 125
Comparator I/O Operating Modes	
Comparator Output	
Comparator Voltage Reference	
Output Buffer Example	257
Compare (CCP Module) Mode Operation	
Enhanced PWM	
Interrupt Logic	
Low-Voltage Detect (LVD)	
Low-Voltage Detect with External Input	. 260
MSSP (I ² C Master Mode)	
MSSP (I ² C Mode)	. 152
MSSP (SPI Mode)	. 143
On-Chip Reset Circuit	25
OSC2/CLKO/RA6 Pin	94
PIC18F248/258 Architecture	8
PIC18F448/458 Architecture	9
PLL	
PORTC (Peripheral Output Override)	
PORTD and PORTE (Parallel Slave Port)	
PORTD in I/O Port Mode	
PWM (CCP Module)	. 128
RA3:RA0 and RA5 Pins	
RA4/T0CKI Pin	
RB1:RB0 Pins	-
RB2/CANTX/INT2 Pin	
RB3/CANRX Pin	98
RB7:RB4 Pins	97
Reads from Flash Program Memory	
Table Read Operation	65
Table Write Operation	
Table Writes to Flash Program Memory	
Timer0 in 16-bit Mode	
Timer0 in 8-bit Mode	
Timer1	
Timer1 (16-bit Read/Write Mode)	
Timer2	
	-
Timer3	
Timer3 (16-bit Read/Write Mode)	
USART Receive	
USART Transmit	
Voltage Reference	
Watchdog Timer	. 273
BN	. 290
BNC	. 291
BNN	. 291
BNOV	. 292
BNZ	. 292
BOR. See Brown-out Reset.	
BOV	. 295
BRA	
BRG. See Baud Rate Generator.	00
Brown-out Reset (BOR)	265
Drewn out neget (Dony	, 200

 $\ensuremath{\textcircled{}^\circ}$  2006 Microchip Technology Inc.

BF Status Flag ...... 173

BSF
BTFSC
BTFSS
BTG
BZ
С
C Compilers
MPLAB C17
MPLAB C18
MPLAB C30
CALL
CAN Module
Aborting Transmission228
Acknowledge Error237
Baud Rate Registers
Baud Rate Setting233
Bit Error
Bit Time Partitioning (diagram)233
Bit Timing Configuration Registers
BRGCON1
BRGCON2
BRGCON3
Calculating To, Nominal Bit Rate and
Nominal Bit Time234
Configuration Mode226
Control and Status Registers 201
Controller Register Map225
CRC Error
Disable Mode226
Error Detection
Error Modes and Error Counters
Error Modes State (diagram)238
Error Recognition Mode227
Error States237
Filter/Mask Truth (table)232
Form Error
Hard Synchronization
I/O Control Register
Information Processing Time
Initiating Transmission
Internal Message Reception Flowchart231
Internal Transmit Message
Flowchart
Interrupt Acknowledge
Interrupt Registers
Interrupts
Bus Activity Wake-up
Bus-Off
Code Bits
Error
Message Error
Receive
Receiver Bus Passive
Receiver Overflow
Receiver Warning239
Transmit
Transmitter Bus Passive
Transmitter Warning239
Lengthening a Bit Period
(diagram)235

Listen Only Mode	
Loopback Mode	227
Message Acceptance Filters	
and Masks 215,	232
Message Acceptance Mask and	
Filter Operation (diagram)	232
Message Reception	
Message Time-Stamping	
Message Transmission	
Modes of Operation	
Normal Mode	
Oscillator Tolerance	236
Overview	
Phase Buffer Segments	
Programming Time Segments	
Propagation Segment	
Receive Buffer Registers	210
Receive Buffers	
Receive Message Buffering	
Receive Priority	
Registers	
Resynchronization	
Sample Point	
Shortening a Bit Period (diagram)	
Stuff Bit Error	
Synchronization	
Synchronization Rules	
Synchronization Segment	234
Time Quanta	234
Transmit Buffer Registers	206
Transmit Buffers	227
Transmit Priority	227
Transmit/Receive Buffers	
Values for ICODE (table)	
Capture (CCP Module)	
CAN Message Time-Stamp	
CCP Pin Configuration	
CCP1 Prescaler	
CCPR1H:CCPR1L Registers	124
Software Interrupt	
Timer1/Timer3 Mode Selection	120
Capture (ECCP Module)	124
CAN Message Time-Stamp	
Capture/Compare/PWM (CCP)	123
Capture Mode. See Capture	
(CCP Module).	
CCP1 Module	
Timer Resources	
CCPR1H Register	
CCPR1L Register	124
Compare Mode. See Compare	
(CCP Module).	
Interaction of CCP1 and	
ECCP1 Modules	124
PWM Mode. See PWM (CCP Module).	
Ceramic Resonators	
Ranges Tested	17
Clocking Scheme	
CLRF	
CLRWDT	297

Code Examples
16 x 16 Signed Multiply Routine
16 x 16 Unsigned Multiply Routine76
8 x 8 Signed Multiply Routine
8 x 8 Unsigned Multiply Routine
Changing Between Capture Prescalers
Data EEPROM Read
Data EEPROM Write
Erasing a Flash Program Memory Row
Fast Register Stack
How to Clear RAM (Bank 1) Using
Indirect Addressing55
Initializing PORTA93
Initializing PORTB
Initializing PORTC
Initializing PORTD
Initializing PORTE104 Loading the SSPBUF Register146
Reading a Flash Program
Memory Word
Saving Status, WREG and BSR
Registers in RAM
WIN and ICODE Bits Usage in
Interrupt Service Routine to
Access TX/RX Buffers
Writing to Flash Program Memory72–73
Code Protection
COMF
Comparator Module
Analog Input Connection Considerations
Associated Registers
Configuration
Enerts of a Reset
Internal Reference Signal
Interrupts
Operation
Operation During Sleep
Outputs
Reference251
Response Time
Comparator Specifications
Comparator Voltage Reference Module
Accuracy/Error
Associated Registers
Connection Considerations
Effects of a Reset
Operation During Sleep
Compare (CCP Module) 126
CCP1 Pin Configuration126
CCPR1 and ECCPR1 Registers 126
Registers Associated with Capture,
Compare, Timer1 and Timer3127
Software Interrupt
Special Event Trigger
Compare (ECCP Module)
Registers Associated with Enhanced
Capture, Compare, Timer1 and Timer3
Special Event Trigger
Compatible 10-Bit Analog-to-Digital
Converter (A/D) Module. See A/D.
Configuration Mode (CAN Module)
CPFSEQ

CPFSGT
Capacitor Selection
D
Data EEPROM Memory 59
Associated Registers
EEADR Register
EECON1 Register
EECON2 Register
Operation During Code-Protect
Protection Against Spurious Writes
Reading
Usage
Write Verify
Writing to
Data Memory
General Purpose Registers
Special Function Registers
Data Memory Map
PIC18F248/448
PIC18F258/458
DAW
DC and AC Characteristics
Graphs and Tables
DC Characteristics
EEPROM and Enhanced Flash
PIC18FXX8 (Ind., Ext.) and
PIC18LFXX8 (Ind.)
DCFSNZ
DECF
DECFSZ
Demonstration Boards
PICDEM 1 326
PICDEM 17 327
PICDEM 18R 327
PICDEM 2 Plus 326
PICDEM 3 326
PICDEM 4
PICDEM LIN 327
PICDEM USB 327
PICDEM.net Internet/Ethernet
Development Support 323
Device Differences
Device Migrations 386
Device Overview7
Features7
Direct Addressing 56
Disable Mode (CAN Module) 226
E

Electrical Characteristics	329
Enhanced Capture/Compare/PWM (ECCP)	131
Auto-Shutdown	142
Capture Mode. See Capture	
(ECCP Module).	
Compare Mode. See Compare	
(ECCP Module).	
ECCPR1H Register	132
ECCPR1L Register	132
Interaction of CCP1 and	
ECCP1 Modules	132
Pin Assignments for Various Modes	132
PWM Mode. See PWM (ECCP Module).	
Timer Resources	132

Enhanced CCP Auto-Shutdown	142
Enhanced PWM Mode.	
See PWM (ECCP Module).	
Errata	5
Error Recognition Mode (CAN Module)	
Evaluation and Programming Tools	
External Clock Input	19

### F

•	
Firmware Instructions	
Flash Program Memory	65
Associated Registers	74
Control Registers	
Erase Sequence	70
Erasing	70
Operation During Code-Protect	73
Reading	
TABLAT (Table Latch) Register	68
Table Pointer	
Boundaries Based on Operation	68
Table Pointer Boundaries	
Table Reads and Table Writes	65
TBLPTR (Table Pointer) Register	68
Write Sequence	71
Writing to	71
Protection Against Spurious Writes	73
Unexpected Termination	73
Write Verify	73
G	
GOTO	
н	
••	
Hardware Multiplier	
Operation	
Performance Comparison (table)	
HS4 (PLL)	
I	
I/O Ports	93
I ² C Mode	
ACK Pulse	
Acknowledge Sequence Timing	
Baud Rate Generator	
Bus Collision During a	
Repeated Start Condition	180
Bus Collision During a Start Condition	
Bus Collision During a Start Condition	
Clock Arbitration	

Effect of a Reset ...... 177

General Call Address Support ...... 166

Master Mode ......167

Reception......173

Repeated Start Condition Timing......172

Start Condition Timing ......171

Transmission......173

and Bus Arbitration ......177

Multi-Master Mode ......177

Operation ......156

Read/Write Bit Information (R/W Bit) ...... 156, 157

Communication, Bus Collision

Sleep Operation	
Stop Condition Timing	176
ID Locations 265,	
INCF	
INCFSZ	
In-Circuit Debugger	
In-Circuit Serial Programming (ICSP)	
Indirect Addressing	
FSR Register INDF Register	
Operation	
INFSNZ	
Initialization Conditions for All Registers	
Instruction Cycle	
Instruction Flow/Pipelining	41
Instruction Format	
Instruction Set	281
ADDLW	287
ADDWF	287
ADDWFC	
ANDLW	
ANDWF	
BC	
BCF	
BN	
BNC	
BNN	
BNOV BNZ	
BOV	
BRA	
BSF	
BTFSC	
BTFSS	
BTG	
BZ	296
CALL	296
CLRF	297
CLRWDT	
COMF	
CPFSEQ	
CPFSGT	
CPFSLT	
DCFSNZ DECF	
DECF DECFSZ	
GOTO	
INCF	
INCFSZ	
INFSNZ	
IORLW	
IORWF	304
LFSR	
MOVF	
MOVFF	306
MOVLB	306
MOVLW	
MOVWF	
MULLW	
MULWF	308

Slave Mode..... 156 Addressing...... 156 Reception ...... 157 Transmission ...... 157

Serial Clock (RC3/SCK/SCL).....157

NEGF	
NOP	
POP	
PUSH	
RCALL	
RESET	
RETFIE	
RETLW	
RETURN	
RLCF	
RLNCF	
RRCF	
RRNCF	
SETF	
SLEEP	
SUBFWB	
SUBLW	
SUBWF	
SUBWFB	
SWAPF	
TBLRD	
TBLWT	
TSTFSZ	
XORLW	
XORWF	
Summary Table284	
INTCON Register	
RBIF Bit96	
Inter-Integrated Circuit. See I ² C.	
Interrupt Sources	
A/D Conversion Complete244	
CAN Module238	
Capture Complete (CCP) 125	
Compare Complete (CCP)126	
Interrupt-on-Change (RB7:RB4)96	
TMR0 Overflow111	
TMR1 Overflow 113, 115	
TMR2 to PR2 Match118	
TMR2 to PR2 Match (PWM) 117, 128	
TMR3 Overflow 119, 121	
Interrupt-on-Change (RB7:RB4) Flag	
(RBIF Bit)	
Interrupts77, 265	
Context Saving During92	
Enable Registers85	
Flag Registers82	
INT92	
PORTB Interrupt-on-Change92	
Priority Registers	
TMR0	
Interrupts, Flag Bits	
A/D Converter Flag (ADIF Bit)243	
CCP1 Flag (CCP1IF Bit) 124, 125, 126	
IORLW	
IORWF	
L	
-	

LFSR	305
Listen Only Mode (CAN Module)	
Look-up Tables	
Computed GOTO	
Table Reads/Table Writes	
Loopback Mode (CAN Module)	226

Low-Voltage Detect	259
Characteristics	338
Current Consumption	263
Effects of a Reset	263
Operation	262
Operation During Sleep	263
Reference Voltage Set Point	263
Typical Application	259
Low-Voltage ICSP Programming	279
LVD. See Low-Voltage Detect.	

#### Μ

Master Synchronous Serial Port (MSSP). See MSSP.	
Master Synchronous Serial Port. See MSSP.	
Memory Organization	. 37
Data Memory	. 44
Internal Program Memory Operation	. 37
Program Memory	
Migrating from other PICmicro Devices	
MÖVF	
MOVFF	306
MOVLB	306
MOVLW	307
MOVWF	307
MPLAB ASM30 Assembler,	
Linker, Librarian	324
MPLAB ICD 2 In-Circuit Debugger	325
MPLAB ICE 2000 High-Performance	
Universal In-Circuit Emulator	325
MPLAB ICE 4000 High-Performance	
Universal In-Circuit Emulator	325
MPLAB Integrated Development	
Environment Software	323
MPLAB PM3 Device Programmer	325
MPLINK Object Linker/	
MPLIB Object Librarian	324
MSSP	143
Control Registers	143
Enabling SPI I/O	147
Operation	146
Overview	-
SPI Master Mode	
SPI Master/Slave Connection	147
SPI Mode	143
SPI Slave Mode	
TMR2 Output for Clock Shift 117,	
Typical Connection	147
MSSP. See also I ² C Mode, SPI Mode.	
MULLW	
MULWF	308
Ν	

NEGF	309
NOP	309
Normal Operation Mode (CAN Module)	226

# 0

Opcode Field Descriptions	
Oscillator	
Effects of Sleep Mode	23
Power-up Delays	
Switching Feature	
System Clock Switch Bit	
Transitions	21
Oscillator Configurations	
Crystal Oscillator, Ceramic Resonators	
EC	
ECIO	
HS	
HS4	
LP	
RC	17. 18
RCIO	
ХТ	
Oscillator Selection	
Oscillator, Timer11	
Oscillator, WDT	

# Ρ

Packaging Information	
Details	
Marking	
Parallel Slave Port (PSP)	. 102, 107
Associated Registers	
PORTD	
PSP Mode Select (PSPMODE) Bit	
RE2/AN7/CS/C2OUT	
PIC18FXX8 Voltage-Frequency	
Graph (Industrial)	
PIC18LFXX8 Voltage-Frequency	
Graph (Industrial)	
PICkit 1 Flash Starter Kit	
PICSTART Plus Development	
Programmer	326
Pin Functions	
MCLR/VPP	10
OSC1/CLKI	
OSC2/CLKO/RA6	
RA0/AN0/CVREF	
RA1/AN1	
RA2/AN2/VREF	
RA3/AN3/VREF+	
RA4/T0CKI	
RA5/AN4/SS/LVDIN	
RA6	
RB0/INT0	
BB1/INT1	
RB2/CANTX/INT2	
RB3/CANRX	
RB4	
RB5/PGM	
RB6/PGC	
BB7/PGD	
RC0/T1OSO/T1CKI	
RC1/T10SI	
RC2/CCP1	
RC3/SCK/SCL	-
RC4/SDI/SDA	-
RC5/SDO	-
RC6/TX/CK	
RC7/RX/DT	

RD0/PSP0/C1IN+ 1	
RD1/PSP1/C1IN 1	
RD2/PSP2/C2IN+ 1	
RD3/PSP3/C2IN 1	
RD4/PSP4/ECCP1/P1A 1	
RD5/PSP5/P1B 1	
RD6/PSP6/P1C 1	14
RD7/PSP7/P1D 1	14
RE0/AN5/RD 1	15
RE1/AN6/WR/C1OUT 1	15
RE2/AN7/CS/C2OUT 1	15
Vdd 1	15
Vss 1	15
Pinout I/O Descriptions 1	0
Pointer, FSRn	55
POP	
POR. See Power-on Reset.	
PORTA	
Associated Register Summary9	<del>)</del> 5
Functions	<del>)</del> 5
LATA Register9	
PORTA Register	
TRISA Register9	
PORTB	
Associated Register Summary	99
Functions	
LATB Register	
PORTB Register	
RB7:RB4 Interrupt-on-Change	
Flag (RBIF Bit)	96
TRISB Register	
PORTC	,0
Associated Register Summary 10	1
Functions	
LATC Register	
PORTC Register	
RC3/SCK/SCL Pin	
RC7/RX/DT pin	
TRISC Register	
PORTD	50
Associated Register Summary 10	פו
Functions	
LATD Register	
Parallel Slave Port (PSP) Function	
PORTD Register	
TRISD Register	בי רי
PORTE	12
-	าค
Associated Register Summary	
LATE Register	
•	
PORTE Register	
PSP Mode Select (PSPMODE) Bit	
RE2/AN7/CS/C2OUT	
TRISE Register	)4
Power-Down Mode. See Sleep.	~-
Power-on Reset (POR)	
MCLR	
Oscillator Start-up Timer (OST)	
PLL Lock Time-out	20
Power-up Timer (PWRT)	
Time-out Sequence	27
Power-up Delays	
OSC1 and OSC2 Pin States	<u>م</u>
in Sleep Mode 2	<u>2</u> 3
Prescaler, Timer0 11	

Dresselar Timor 100
Prescaler, Timer2
Programmer
Program Counter
PCL Register
PCLATH Register
PCLATU Register
Program Memory
Fast Register Stack 40
Instructions41
Two-Word43
Map and Stack for PIC18F248/448
Map and Stack for PIC18F258/458
PUSH and POP Instructions
Return Address Stack
Stack Full/Underflow Resets
Top-of-Stack Access
Program Verification and
Code Protection
Associated Registers Summary
Configuration Register Protection
Data EEPROM Code Protection
Program Memory Code Protection
Programming, Device Instructions
PUSH
PWM (CCP Module)128
CCPR1H:CCPR1L Registers 128
Duty Cycle128
Example Frequencies/Resolutions
Period
Registers Associated with
PWM and Timer2
Setup for PWM Operation
PWM (ECCP Module)
Full-Bridge Application Example
Full-Bridge Mode
Direction Change
Half-Bridge Mode
Half-Bridge Output Mode
Applications Example
Output Configurations
Output Polarity Configuration140
Output Relationships Diagram135
Programmable Dead-Band Delay 140
Registers Associated with Enhanced PWM
and Timer2141
Setup for PWM Operation
Standard Mode
Start-up Considerations
Q
Q Clock
<b>D</b>
R
RAM. See Data Memory.
RCALL
RCON Register
Significance of Status Bits vs.
Initialization Condition
RCSTA Register 183

Register File Summary	49
Registers	
ADCON0 (A/D Control 0)	
ADCON1 (A/D Control 1) BRGCON1 (Baud Rate Control 1)	
BRGCON2 (Baud Rate Control 2)	
BRGCON3 (Baud Rate Control 3)	
CANCON (CAN Control)	
CANSTAT (CAN Status)	
CCP1CON (CCP1 Control)	
CIOCON (CAN I/O Control)	221
CMCON (Comparator Control)	249
COMSTAT (CAN	
Communication Status)	205
CONFIG1H (Configuration 1 High)	
CONFIG2H (Configuration 2 High)	
CONFIG2L (Configuration 2 Low)	
CONFIG4L (Configuration 4 Low)	
CONFIG5H (Configuration 5 High)	
CONFIG5L (Configuration 5 Low)	
CONFIG6H (Configuration 6 High)	
CONFIG6L (Configuration 6 Low)	
CONFIG7H (Configuration 7 High)	
CONFIG7L (Configuration 7 Low) CVRCON (Comparator Voltage	270
Reference Control)	255
DEVID1 (Device ID 1)	
DEVID2 (Device ID 2)	
ECCP1CON (ECCP1 Control)	131
ECCP1DEL (PWM Delay)	
ECCPAS (Enhanced Capture/Compare/PWM	
Auto-Shutdown Control)	142
EECON1 (EEPROM Control 1)	
INTCON (Interrupt Control)	60, 67 79
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2)	60, 67 79 80
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3)	60, 67 79 80 81
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1)	50, 67 79 80 81 88
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2)	60, 67 79 80 81 88 89
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2)	60, 67 79 80 81 88 89 0, 224
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	60, 67 79 80 81 88 89 0, 224 261 20
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 85 86 7, 223 82
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 85 86 7, 223 82
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223 82 82 83
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223 82 82 83 4, 222 58, 91
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223 82 83 4, 222 58, 91 184
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223 82 82 83 4, 222 58, 91 184 210
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223 82 82 83 4, 222 58, 91 184 210
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223 82 83 4, 222 58, 91 184 210 211
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 86 7, 223 82 83 4, 222 58, 91 184 210 211
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 85 86 7, 223 82 83 4, 222 58, 91 184 210 213
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 85 86 7, 223 82 83 4, 222 58, 91 184 210 213
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 85 86 7, 223 82 83 4, 222 58, 91 184 210 211 213 214
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 85 86 7, 223 82 83 4, 222 58, 91 184 210 211 213 214
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 85 86 7, 223 82 83 4, 222 58, 91 184 211 213 214 212
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 85 86 7, 223 82 83 4, 222 58, 91 184 211 213 214 212
INTCON (Interrupt Control) INTCON2 (Interrupt Control 2) INTCON3 (Interrupt Control 3) IPR1 (Peripheral Interrupt Priority 1) IPR2 (Peripheral Interrupt Priority 2) IPR3 (Peripheral Interrupt Priority 3)	50, 67 79 80 81 88 89 0, 224 261 20 85 85 86 7, 223 82 83 4, 222 58, 91 184 211 213 212 213

© 2006 Microchip Technology Inc.

RXBnSIDL (Receive Buffer n
Standard Identifier, Low Byte)
RXERRCNT (Receive Error Count)
RXFnEIDH (Receive Acceptance Filter n
Extended Identifier, High Byte)
RXFnEIDL (Receive Acceptance Filter n
Extended Identifier, Low Byte)
RXFnSIDH (Receive Acceptance Filter n
Standard Identifier Filter, High Byte)
RXFnSIDL (Receive Acceptance Filter n
Standard Identifier Filter, Low Byte)
RXMnEIDH (Receive Acceptance Mask n
Extended Identifier Mask, High Byte)
RXMnEIDL (Receive Acceptance Mask n
Extended Identifier Mask, Low Byte)
RXMnSIDH (Receive Acceptance Mask n
Standard Identifier Mask, High Byte)
RXMnSIDL (Receive Acceptance Mask n
Standard Identifier Mask, Low Byte)
SSPCON1 (MSSP Control 1, I ² C Mode)
SSPCON1 (MSSP Control 1, SPI Mode)
SSPCON2 (MSSP Control 2, I ² C Mode)
SSPSTAT (MSSP Status, I ² C Mode)
SSPSTAT (MSSP Status, PC Mode)
Status
STKPTR (Stack Pointer)
T0CON (Timer0 Control)
T2CON (Timer2 Control)
T3CON (Timer3 Control)
TRISE (PORTE Direction/PSP Control)
TXBnCON (Transmit Buffer n Control)
TXBnDLC (Transmit Buffer n
Data Length Code)209
TXBnDm (Transmit Buffer n
Data Field Byte m)
TXBnEIDH (Transmit Buffer n
Extended Identifier, High Byte)
TXBnEIDL (Transmit Buffer n
Extended Identifier, Low Byte)
TXBnSIDH (Transmit Buffer n
Standard Identifier, High Byte)
TXBnSIDL (Transmit Buffer n
Standard Identifier, Low Byte)
TXERRCNT (Transmit Error Count)
TXSTA (Transmit Status and Control)
WDTCON (Watchdog Timer Control)
RESET
Reset
MCLR Reset During Normal Operation25
MCLR Reset During Sleep25
Power-on Reset (POR)25
Programmable Brown-out Reset (PBOR)25
RESET Instruction25
Stack Full Reset
Stack Underflow Reset25
Watchdog Timer (WDT) Reset25
RETFIE
RETLW
RETURN
Revision History
DL OF
RLCF
RLNCF
RLNCF
RLNCF

### S

SCI. See USART.
SCK Pin 143
SDI Pin
SDO Pin
Serial Clock (SCK) Pin
Serial Communication Interface.
See USART.
Serial Peripheral Interface. See SPI.
SETF
Slave Select (SS) Pin
Slave Select, SS Pin
SLEEP
Sleep
Software Simulator (MPLAB SIM)
Software Simulator (MPLAB SIM3)
Special Event Trigger. <i>See</i> Compare.
Special Features of the CPU
Configuration Bits
Configuration Bits and
Device IDs 265
Configuration Registers 266–271
Special Function Register Map 47
Special Function Registers 44
SPI Mode
Associated Registers 151
Bus Mode Compatibility 151
Effects of a Reset 151
Master Mode
Master/Slave Connection
Registers
Serial Clock
Serial Data In (SDI) Pin 143
Serial Data Out (SDO) Pin
Slave Select
Slave Select Synchronization
Sleep Operation
SPI Clock
SSPBUF Register
SSPSR Register
SSPOV
SSPOV Status Flag 173
SSPSTAT Register
R/W Bit 156, 157
SUBFWB
SUBLW
SUBWF
SUBWFB
SWAPF
т
Table Pointer Operations (table)
TBLRD

Operation ...... 111

Overflow Interrupt ...... 111

Prescaler ...... 111

Switching Prescaler Assignment ...... 111

Prescaler. See Prescaler, Timer0.

Timer1	113
16-bit Read/Write Mode	115
Associated Registers	116
Operation	114
Oscillator	,
Overflow Interrupt	
Special Event Trigger (CCP)	
Special Event Trigger (ECCP)	
TMR1H Register	
TMR1L Register	
TMR3L Register	
Timer2 Associated Registers	
Operation	
Postscaler. See Postscaler, Timer2.	
PR2 Register	117 128
Prescaler. See Prescaler, Timer2.	
SSP Clock Shift	117. 118
TMR2 Register	
TMR2 to PR2 Match Interrupt1	
Timer3	119
Associated Registers	121
Operation	120
Oscillator	
Overflow Interrupt	
Special Event Trigger (CCP)	
TMR3H Register	
Timing Conditions	
Load Conditions for Device	0.40
Timing Specifications	
Temperature and Voltage Specifications – AC	240
Specifications – AC	
Timing Diagrams	
Timing Diagrams A/D Conversion	
A/D Conversion	
A/D Conversion Acknowledge Sequence	359 176
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration	359 176 170
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition	359 176 170
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1)	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated Start Condition (Case2)	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated Start Condition (Case2) Bus Collision During a Stop	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated Start Condition (Case 2) Bus Collision During a Stop Condition (Case 1)	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated Start Condition (Case2) Bus Collision During a Stop Condition (Case 1) Bus Collision During a Stop	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated Start Condition (Case2) Bus Collision During a Stop Condition (Case 1) Bus Collision During a Stop Condition (Case 2)	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated Start Condition (Case2) Bus Collision During a Stop Condition (Case 1) Bus Collision During a Stop Condition (Case 2) Bus Collision During a	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> </ul>	
A/D Conversion Acknowledge Sequence Baud Rate Generator with Clock Arbitration BRG Reset Due to SDA Arbitration During Start Condition Brown-out Reset (BOR) and Low-Voltage Detect Bus Collision During a Repeated Start Condition (Case 1) Bus Collision During a Repeated Start Condition (Case2) Bus Collision During a Stop Condition (Case 1) Bus Collision During a Stop Condition (Case 2) Bus Collision During a	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> <li>Capture/Compare/PWM</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> <li>Capture/Compare/PWM (CCP1 and ECCP1)</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> <li>Capture/Compare/PWM (CCP1 and ECCP1)</li> <li>CLKO and I/O</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> <li>Capture/Compare/PWM (CCP1 and ECCP1)</li> <li>CLKO and I/O</li> <li>Clock Synchronization</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> <li>Capture/Compare/PWM (CCP1 and ECCP1)</li> <li>CLKO and I/O</li> <li>Clock Synchronization</li> <li>Clock/Instruction Cycle</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> <li>Capture/Compare/PWM (CCP1 and ECCP1)</li> <li>CLKO and I/O</li> <li>Clock Synchronization</li> <li>Clock/Instruction Cycle</li> <li>External Clock.</li> </ul>	
<ul> <li>A/D Conversion</li> <li>Acknowledge Sequence</li> <li>Baud Rate Generator with Clock Arbitration</li> <li>BRG Reset Due to SDA Arbitration During Start Condition</li> <li>Brown-out Reset (BOR) and Low-Voltage Detect</li> <li>Bus Collision During a Repeated Start Condition (Case 1)</li> <li>Bus Collision During a Repeated Start Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 1)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During a Stop Condition (Case 2)</li> <li>Bus Collision During Start Condition (SCL = 0)</li> <li>Bus Collision During Start Condition (SDA Only)</li> <li>Bus Collision for Transmit and Acknowledge</li> <li>Capture/Compare/PWM (CCP1 and ECCP1)</li> <li>CLKO and I/O</li> <li>Clock Synchronization</li> <li>Clock/Instruction Cycle</li> </ul>	

Half-Bridge PWM Output	136
I ² C Bus Data	353
I ² C Bus Start/Stop Bits	353
I ² C Master Mode (Reception,	000
7-bit Address)	175
I ² C Master Mode (Transmission,	
7 or 10-bit Address)	174
I ² C Slave Mode (Transmission,	
10-bit Address)	101
	101
I ² C Slave Mode (Transmission,	
7-bit Address)	159
$I^2C$ Slave Mode with SEN = 0 (Reception,	
10-bit Address)	160
$I^2C$ Slave Mode with SEN = 0 (Reception,	100
7-bit Address)	158
I ² C Slave Mode with SEN = 1 (Reception,	
10-bit Address)	165
$I^2C$ Slave Mode with SEN = 1 (Reception,	
7-bit Address)	161
Low-Voltage Detect	262
Master SSP I ² C Bus Data	355
Master SSP I ² C Bus Start/Stop Bits	355
Parallel Slave Port (PIC18F248	
and PIC18F458)	210
Parallel Slave Port Read	
Parallel Slave Port Write	107
PWM Direction Change	139
PWM Direction Change at Near	
100% Duty Cycle	120
PWM Output	
Repeated Start Condition	170
	172
	172
Reset, Watchdog Timer (WDT),	172
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST),	
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT)	
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence	345
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode)	345 166
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization	345 166 149
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization	345 166 149
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD)	345 166 149 . 29
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode	345 166 149 . 29 148
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0)	345 166 149 . 29 148 349
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1)	345 166 149 . 29 148 349 350
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0)	345 166 149 . 29 148 349 350 150
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0)	345 166 149 . 29 148 349 350 150
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1)	345 166 149 . 29 148 349 350 150 150
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 1) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0)	345 166 149 . 29 148 349 350 150 150 351
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1)	345 166 149 . 29 148 349 350 150 150 351
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1)	345 166 149 . 29 148 349 350 150 150 351 352
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1)	345 166 149 . 29 148 349 350 150 150 351 352
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1)	345 166 149 . 29 148 349 350 150 150 351 352
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled	345 166 149 . 29 148 349 350 150 150 351 352 176
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD)	345 166 149 . 29 148 349 350 150 150 351 352 176
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-out Sequence on Power-up	345 166 149 . 29 148 349 350 150 150 351 352 176
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-out Sequence on Power-up (MCLR Not Tied to VDD)	345 166 149 . 29 148 349 350 150 351 352 176 . 29
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) STI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-out Sequence on Power-up (MCLR Not Tied to VDD) Case 1	345 166 149 .29 148 349 350 150 351 352 176 .29 .28
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-out Sequence on Power-up (MCLR Not Tied to VDD) Case 1 Case 2	345 166 149 .29 148 349 350 150 351 352 176 .29 .28
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Examp	345 166 149 . 29 148 349 350 150 351 352 176 . 29 . 28 . 28
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Examp	345 166 149 . 29 148 349 350 150 351 352 176 . 29 . 28 . 28
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-out Sequence on Power-up (MCLR Not Tied to VDD) Case 1 Case 2 Time-out Sequence on Power-up (MCLR Tied to VDD)	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE =	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 1) SPI Slave Mode (CKE = 1) SPI Slave Mode (CKE = 1) .	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28 346
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 0) SPI Slave Mode Example (CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-out Sequence on Power-up (MCLR Not Tied to VDD) Case 1 Case 2 Time-out Sequence on Power-up (MCLR Tied to VDD) Timer0 and Timer1 External Clock Transition Between Timer1 and OSC1 (HS with PLL)	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28 346
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-Out Sequence on Power-up (MCLR Tied to VDD) Case 1 Case 2 Time-Out Sequence on Power-up (MCLR Tied to VDD) Timer0 and Timer1 External Clock Transition Between Timer1 and OSC1 (HS with PLL) Transition Between Timer1 and	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28 346 .22
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-Out Sequence on Power-up (MCLR Tied to VDD) Case 1 Case 2 Time-Out Sequence on Power-up (MCLR Tied to VDD) Timer0 and Timer1 External Clock Transition Between Timer1 and OSC1 (HS with PLL) Transition Between Timer1 and	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28 346 .22
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-out Sequence on Power-up (MCLR Not Tied to VDD) Case 1 Case 2 Time-out Sequence on Power-up (MCLR Tied to VDD) Timer0 and Timer1 External Clock Transition Between Timer1 and OSC1 (HS with PLL) Transition Between Timer1 and OSC1 (HS, XT, LP)	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28 346 .22
Reset, Watchdog Timer (WDT), Oscillator Start-up Timer (OST), Power-up Timer (PWRT) Slave Mode General Call Address Sequence (7 or 10-bit Address Mode) Slave Synchronization Slow Rise Time (MCLR Tied to VDD) SPI Master Mode Example (CKE = 0) SPI Master Mode Example (CKE = 1) SPI Master Mode Example (CKE = 1) SPI Slave Mode (with CKE = 0) SPI Slave Mode (with CKE = 1) SPI Slave Mode Example (CKE = 1) Stop Condition Receive or Transmit Mode Time-out Sequence on POR w/PLL Enabled (MCLR Tied to VDD) Time-Out Sequence on Power-up (MCLR Tied to VDD) Case 1 Case 2 Time-Out Sequence on Power-up (MCLR Tied to VDD) Timer0 and Timer1 External Clock Transition Between Timer1 and OSC1 (HS with PLL) Transition Between Timer1 and	345 166 149 .29 148 349 350 150 351 352 176 .29 .28 .28 .28 346 .22 .21

Transition from OSC1 to
Timer1 Oscillator21
USART Asynchronous Reception 192
USART Asynchronous Transmission190
USART Asynchronous Transmission
(Back to Back)190
USART Synchronous Receive
(Master/Slave)357
USART Synchronous Reception
(Master Mode, SREN)195
USART Synchronous Transmission
USART Synchronous Transmission
(Master/Slave)357
USART Synchronous Transmission
(Through TXEN)194
Wake-up from Sleep via Interrupt275
Timing Diagrams and Specifications
A/D Conversion Requirements
A/D Converter Characteristics
Capture/Compare/PWM Requirements
(CCP1 and ECCP1)
CLKO and I/O Timing
Requirements344
Example SPI Mode Requirements
(Master Mode, CKE = 0)
Example SPI Mode Requirements
(Master Mode, CKE = 1)
Example SPI Mode Requirements
(Slave Mode, CKE = 0)
Example SPI Slave Mode
Requirements (CKE = 1)352
External Clock Timing Requirements
I ² C Bus Data Requirements
(Slave Mode)
I ² C Bus Start/Stop Bits Requirements
(Slave Mode)
Master SSP I ² C Bus Data
Requirements
Master SSP I ² C Bus Start/Stop Bits
Requirements
Parallel Slave Port Requirements
(PIC18F248 and PIC18F458)
PLL Clock
Reset, Watchdog Timer, Oscillator
Start-up Timer, Power-up Timer,
Brown-out Reset and Low-Voltage
Detect Requirements
Timer0 and Timer1 External
Clock Requirements
USART Synchronous Receive
Requirements
USART Synchronous Transmission
Requirements
TSTFSZ
TXSTA Register
BRGH Bit 185

#### U

USART	183
Asynchronous Mode	
Reception	
Setting Up 9-Bit Mode with	
Address Detect	191
Transmission	189
Asynchronous Reception	192
Asynchronous Transmission	
Associated Registers	190
Baud Rate Generator (BRG)	
Associated Registers	
Baud Rate Error, Calculating	185
Baud Rate Formula	
Baud Rates for Asynchronous Mode	
(BRGH = 0)	187
Baud Rates for Asynchronous Mode	-
(BRGH = 1)	188
Baud Rates for Synchronous Mode	186
High Baud Rate Select (BRGH Bit)	
Sampling	
Serial Port Enable (SPEN) Bit	
Synchronous Master Mode	
Reception	
Transmission	
Synchronous Master Reception	
Associated Registers	195
Synchronous Master Transmission	
Associated Registers	193
Synchronous Slave Mode	
Reception	
Transmission	
Synchronous Slave Reception	
Synchronous Slave Transmission	
Associated Registers	197
·	-
V	
Voltage Reference Specifications	340
W	
Wake-up from Sleep	<u>2</u> 74
Using Interrupts	
Watchdog Timer (WDT) 265, 2	
Associated Registers	
Control Register	
Postscaler	273
Programming Considerations	272

WWW, On-Line Support ......5

WDT. See Watchdog Timer.

Х

# THE MICROCHIP WEB SITE

Microchip provides online support via our WWW site at www.microchip.com. This web site is used as a means to make files and information easily available to customers. Accessible by using your favorite Internet browser, the web site contains the following information:

- **Product Support** Data sheets and errata, application notes and sample programs, design resources, user's guides and hardware support documents, latest software releases and archived software
- General Technical Support Frequently Asked Questions (FAQ), technical support requests, online discussion groups, Microchip consultant program member listing
- Business of Microchip Product selector and ordering guides, latest Microchip press releases, listing of seminars and events, listings of Microchip sales offices, distributors and factory representatives

# CUSTOMER CHANGE NOTIFICATION SERVICE

Microchip's customer notification service helps keep customers current on Microchip products. Subscribers will receive e-mail notification whenever there are changes, updates, revisions or errata related to a specified product family or development tool of interest.

To register, access the Microchip web site at www.microchip.com, click on Customer Change Notification and follow the registration instructions.

## **CUSTOMER SUPPORT**

Users of Microchip products can receive assistance through several channels:

- Distributor or Representative
- Local Sales Office
- Field Application Engineer (FAE)
- Technical Support
- Development Systems Information Line

Customers should contact their distributor, representative or field application engineer (FAE) for support. Local sales offices are also available to help customers. A listing of sales offices and locations is included in the back of this document.

Technical support is available through the web site at: http://support.microchip.com

# **READER RESPONSE**

It is our intention to provide you with the best documentation possible to ensure successful use of your Microchip product. If you wish to provide your comments on organization, clarity, subject matter, and ways in which our documentation can better serve you, please FAX your comments to the Technical Publications Manager at (480) 792-4150.

Please list the following information, and use this outline to provide us with your comments about this document.

To:	Technical Publications Manager	Total Pages Sent
RE:	Reader Response	
Fror	n: Name	
	Company	
٨٥٩	lelephone: () lication (optional):	FAX: ()
	uld you like a reply?YN	
Dev	ice: PIC18FXX8	Literature Number: DS41159E
Que	estions:	
1.	What are the best features of this do	cument?
2.	How does this document meet your	hardware and software development needs?
3.	Do you find the organization of this c	locument easy to follow? If not, why?
4.	What additions to the document do y	you think would enhance the structure and subject?
5.	What deletions from the document of	ould be made without affecting the overall usefulness?
5.		ouid be made without anecting the overall dserdiness:
6.	Is there any incorrect or misleading i	nformation (what and where)?
0.		
7.	How would you improve this docume	ent?

### PIC18FXX8 PRODUCT IDENTIFICATION SYSTEM

To order or obtain information, e.g., on pricing or delivery, refer to the factory or the listed sales office.

PART NO.	X <u>/XX XXX</u> Temperature Package Pattern Range	<ul> <li>Examples:</li> <li>a) PIC18LF258-I/L 301 = Industrial temp., PLCC package, Extended VDD limits, QTP pattern #301.</li> <li>b) PIC18LF458-I/PT = Industrial temp., TQFP</li> </ul>
Device	PIC18F248/258 ⁽¹⁾ , PIC18F448/458 ⁽¹⁾ , PIC18F248/258T ⁽²⁾ , PIC18F448/458T ⁽²⁾ ; VDD range 4.2V to 5.5V PIC18LF248/258 ⁽¹⁾ , PIC18LF448/458 ⁽¹⁾ , PIC18LF248/258T ⁽²⁾ , PIC18LF448/458T ⁽²⁾ ; VDD range 2.0V to 5.5V	<ul> <li>package, Extended VDD limits.</li> <li>c) PIC18F258-E/L = Extended temp., PLCC package, normal VDD limits.</li> </ul>
Temperature Range	$ \begin{array}{rcl} I & = & -40^{\circ}C \text{ to } +85^{\circ}C & (Industrial) \\ E & = & -40^{\circ}C \text{ to } +125^{\circ}C & (Extended) \end{array} $	Note 1: F = Standard Voltage Range LF = Wide Voltage Range
Package	PT = TQFP (Thin Quad Flatpack) L = PLCC SO = SOIC SP = Skinny Plastic DIP P = PDIP	2: T = in tape and reel PLCC and TQFP packages only.
Pattern	QTP, SQTP, Code or Special Requirements (blank otherwise)	

^{© 2006} Microchip Technology Inc.



# WORLDWIDE SALES AND SERVICE

#### AMERICAS

Corporate Office 2355 West Chandler Blvd. Chandler, AZ 85224-6199 Tel: 480-792-7200 Fax: 480-792-7277 Technical Support: http://support.microchip.com Web Address: www.microchip.com

Atlanta Alpharetta, GA Tel: 770-640-0034 Fax: 770-640-0307

Boston Westborough, MA Tel: 774-760-0087 Fax: 774-760-0088

**Chicago** Itasca, IL Tel: 630-285-0071 Fax: 630-285-0075

**Dallas** Addison, TX Tel: 972-818-7423 Fax: 972-818-2924

Detroit Farmington Hills, MI Tel: 248-538-2250 Fax: 248-538-2260

**Kokomo** Kokomo, IN Tel: 765-864-8360 Fax: 765-864-8387

Los Angeles Mission Viejo, CA Tel: 949-462-9523 Fax: 949-462-9608

Santa Clara Santa Clara, CA Tel: 408-961-6444 Fax: 408-961-6445

Toronto Mississauga, Ontario, Canada Tel: 905-673-0699 Fax: 905-673-6509

#### ASIA/PACIFIC

Asia Pacific Office Suites 3707-14, 37th Floor Tower 6, The Gateway Habour City, Kowloon Hong Kong Tel: 852-2401-1200 Fax: 852-2401-3431

Australia - Sydney Tel: 61-2-9868-6733 Fax: 61-2-9868-6755

**China - Beijing** Tel: 86-10-8528-2100 Fax: 86-10-8528-2104

**China - Chengdu** Tel: 86-28-8665-5511 Fax: 86-28-8665-7889

**China - Fuzhou** Tel: 86-591-8750-3506 Fax: 86-591-8750-3521

**China - Hong Kong SAR** Tel: 852-2401-1200 Fax: 852-2401-3431

**China - Qingdao** Tel: 86-532-8502-7355 Fax: 86-532-8502-7205

**China - Shanghai** Tel: 86-21-5407-5533 Fax: 86-21-5407-5066

**China - Shenyang** Tel: 86-24-2334-2829 Fax: 86-24-2334-2393

**China - Shenzhen** Tel: 86-755-8203-2660 Fax: 86-755-8203-1760

**China - Shunde** Tel: 86-757-2839-5507 Fax: 86-757-2839-5571

**China - Wuhan** Tel: 86-27-5980-5300 Fax: 86-27-5980-5118

**China - Xian** Tel: 86-29-8833-7250 Fax: 86-29-8833-7256

#### ASIA/PACIFIC

India - Bangalore Tel: 91-80-4182-8400 Fax: 91-80-4182-8422

India - New Delhi Tel: 91-11-4160-8631 Fax: 91-11-4160-8632

India - Pune Tel: 91-20-2566-1512 Fax: 91-20-2566-1513

**Japan - Yokohama** Tel: 81-45-471- 6166 Fax: 81-45-471-6122

**Korea - Gumi** Tel: 82-54-473-4301 Fax: 82-54-473-4302

Korea - Seoul Tel: 82-2-554-7200 Fax: 82-2-558-5932 or 82-2-558-5934

**Malaysia - Penang** Tel: 60-4-646-8870 Fax: 60-4-646-5086

Philippines - Manila Tel: 63-2-634-9065

Fax: 63-2-634-9069 Singapore Tel: 65-6334-8870 Fax: 65-6334-8850

**Taiwan - Hsin Chu** Tel: 886-3-572-9526 Fax: 886-3-572-6459

**Taiwan - Kaohsiung** Tel: 886-7-536-4818 Fax: 886-7-536-4803

**Taiwan - Taipei** Tel: 886-2-2500-6610 Fax: 886-2-2508-0102

**Thailand - Bangkok** Tel: 66-2-694-1351 Fax: 66-2-694-1350

#### EUROPE

Austria - Wels Tel: 43-7242-2244-3910 Fax: 43-7242-2244-393

**Denmark - Copenhagen** Tel: 45-4450-2828 Fax: 45-4485-2829

France - Paris Tel: 33-1-69-53-63-20 Fax: 33-1-69-30-90-79

**Germany - Munich** Tel: 49-89-627-144-0 Fax: 49-89-627-144-44

**Italy - Milan** Tel: 39-0331-742611 Fax: 39-0331-466781

Netherlands - Drunen Tel: 31-416-690399 Fax: 31-416-690340

**Spain - Madrid** Tel: 34-91-708-08-90 Fax: 34-91-708-08-91

**UK - Wokingham** Tel: 44-118-921-5869 Fax: 44-118-921-5820